




Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## **CERTIFICATE**

**CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-  
3924-32 DATED 27-07-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.**

  
**Executive Engineer,  
Baijnath Division,  
HP.PWD, Baijnath.**



**Office of**  
**Executive Engineer Baijnath Division HP.PWD, Baijnath**  
**Himachal Pradesh Public works Department Baijnath-176125**  
**Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **14.08.2024 up to 11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **13.08.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **12.08.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Restoration of rain damages on Lot to Karot Raod (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)	Rs.44,000/-	Rs.9,00/-	Rs.350/-	Two Months
2	C/O Road from Purani Palam to Jigari Ram House (SH: P/L Kharanja Stone Soling & C.C Pavement at RD 0/069 to 0/171) & C/O 0.60 Mtr Span RCC slab Culvert at RD 0/155)	Rs.4,92,234/-	Rs.9,900/-	Rs.350/-	Two Months
3	R/D Upper Thehad to Chadhiar via Bakshi Partap Singh House Km 0/00 to 2/060 (SH: P/L C.C. Pavement & WBM G-II at Km 0/00 to 0/100 and 0/210 to 0/260)	Rs.4,91,660/-	Rs.9,900/-	Rs.350/-	Two Months
4	C/O Upper Story Building work (Samudayak Bhawan Simbal) (SH: P/L Brick work, 1:2:4, wood work and steel work etc.) (Deposit work)	Rs.4,99,133/-	Rs.10,000/-	Rs.350/-	Two Months
5	Restoration of Rain Damages on Various roads under Baijnath Division Sub-Division (Chobin Section) (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debries and C/O road side Katcha drains)	Rs.99,000/-	Rs.2,000/-	Rs.350/-	Two Months
6	Community Bhawan Kukaina (SH: P/L Kharanja Stone Soling, 1:2:4 and cement plaster) (Deposit Works)	Rs.49,945/-	Rs.1,000/-	Rs.350/-	One Month
7	C/O Shed of Samshan Ghat of Ward No.3 Trehal (SH: P/F G.I Sheet Roofing and 1:2:4) (Deposit work)	Rs.99,422/-	Rs.2,000/-	Rs.350/-	Two Months
8	Comp. under construction Road (Aram Ghar) (SH: P/L C.C. Pavement at Km 0/00 to 0/060) (Deposit Work)	Rs.98,558/-	Rs.2,000/-	Rs.350/-	Two Months
9	C/O Road from Main road to Smt. Indu Bala House-5 Mahal Patt (SH: P/L C.C Pavement & Kharnja Soling at Km 0/00 to 0/084) (Deposit Work)	Rs.99,300/-	Rs.2,000/-	Rs.350/-	One Month
10	Construction B.P.S Govt. Sr. Sec. School Chadhiar (SH: P/F G.I Sheet Roofing, Kharnja Stone Soling and 1:2:4) (Deposit work)	Rs.98,039/-	Rs.2,000/-	Rs.350/-	Two Months
11	Samudayak Bhawan Ward No.5 Near GPS Nauri (SH:P/F G.I Sheet Roofing, Kharnja Stone Soling and 1:2:4) (Deposit Work)	Rs.2,99,490/-	Rs.6,000/-	Rs.350/-	Two Months
12	C/O Pulli in Village Lehal (SH: C/O 1.00 mtr. Span R.C.C. Slab culvert at RD 0/230) (Deposit Work)	Rs.1,95,515/-	Rs.4,000/-	Rs.350/-	Two Months
13	C/O Pulli in Village Lehal (SH: C/O 0.60 mtr. Span R.C.C. Slab culvert at RD 0/750) (Deposit Work)	Rs.1,43,096/-	Rs.2,900/-	Rs.350/-	Two Months
14	C/O Shed Near Mela Ground kandral (SH: P/F G.I Sheet Roofing and 1:2:4) (Deposit Work)	Rs.79,736/-	Rs.1,600/-	Rs.350/-	Two Months
15	C/O Stage in GSSS Jandpur (SH: P/L Tile work, Kharnja Stone Soling and 1:3:6) (Deposit Work)	Rs.97,989/-	Rs.2,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.

**E.E.**

8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Bajnath Division.,  
H.P.PWD..Bajnath.

For & On behalf of the governor of H.P.

**Dated:- 27.07.2024**

**NO:-PWD/BD/TA/NIT/2024-25/-**

**3924-32**

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

~~Executive Engineer,  
Bajnath Division.,  
H.P.PWD..Bajnath.~~

①

# DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 44,000.00

Earnest Money:- 9,00.00



Time Limit:- Two Months

Name of work:- Restoration of rain damages on Lot to Karol Road

(SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges P.O. charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator.	40.00 Hours			Per Hour	

Total

  
H.P.R.M.D., Daljnath  




(2) (a)

**D.N.I.T/ SCHEDULE OF QUANTITY**

Name of work :- C/O Road From Purani Palam to Jigari Ram House.

(Deposit)

(SH:- P/I

Estimated Cost

492234.00

Kharanja Stone Soling &amp; C.C pavement at RD 0/069 to 0/171) &amp; C/O 0.60 Mtr Span RCC Culvert at RD 0/155).

Earnest Money

9900.00


Time limit

Two Months

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and laying hard stone soling properly hand packed intersects with kharanja stone and consolidating with power hand road roller to the requested gradient and camber including spreading watering and rolling of binding morrum or earth etc Complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and entire satisfaction. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	41.31	Per Cubic Meter			
2	Providing and laying damp proof course 40 mm (forty millimetre) thick with cement concrete 1:2:4 (one cement isto two sand isto four aggregate) graded crushed stone aggregate 12.5mm (tewelve decimal five millimeter) nominal size mechanically mixed and curing complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	44.06	Per Cubic Meter			
3	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	12.22	Per Cubic Meter			
4	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 M-10 The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	2.59	Per Cubic Meter			
5	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	9.93	Per Cubic Meter			

(2) (6)

6	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	1.68	Per Cubic Meter			
7	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	170.00	Per Kilogram			


  
Engineer  
Division  
Bijainth  
2

**DNIT/DRAFT SCHEDULE OF QUANTITY**

(3)

<b>Name of Work :</b> <del>200</del> Upper Thehad to Chadhiar via Bakshi Partap Singh House km 0/00 to 2/060 . <b>(SH:-P/L C. C Pavement &amp; W B M G-II at km 0/00 to 0/100 and 0/210 to 0/260 )</b>	<b>Estimate Cost:</b> 4,91,660.00/- <b>Earnest Money:</b> 9,900.00/- <b>Time Limit :</b> Two Months
---	---

Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
						Words	
1		Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template. hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax. Sale Tax or other taxes imposed by the government.	8.09	Per Cubic Metre			
2		Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	67.42	Per Cubic metre			
			Total				

  
**Executive Engineer**  
**Bajnath Division,**  
**H.P.P.W.D. Bajjnath (H.P.)**

(4) (a)

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O Upper Story Building work (Samudayak Bhawan Simbal ) **(Deposit work)**  
 (SH: P/L Brick work ,1:2:4 , wood work and steel work etc )



Estimate Cost: 4,99,133.00  
 Earnest Money: 10,000.00  
 Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi. royalty. GST. toll tax. Sale Tax or other taxes imposed by the government.	23.64	Per cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi. royalty. Malkana. tolltax. Sale Tax or other taxes imposed by the government.	4.59	Per cubic metre			
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi. royalty. Malkana. tolltax. Sale Tax or other taxes imposed by the government	459.00	Pkg			
4	Providing woodwork of second class deodar wood in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	0.39	Per cubic metre			
5	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm (zero point sixty centimetre) cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.50mm (two point five millimetre) the main crest with at top zinc waiting top coat with regular modified polyester coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	14.00	Per running metre			



④⑥


6	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists, channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like work including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2090 00	Per Kg			

  
Executive Engineer  
Bajnath Division,  
H.P.P.W.D. Bajnath (H.P.) 

5

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Various roads under Baijnath Division Sub Division (Chobin Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains)				Estimate Cost: 99,000.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of Hydraulic Excavator cum loader having 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk.shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive all taxes including GST levy by the government time to time.	90.00	Per working hour			
	<b>Total</b>					

  
 Engineer in Charge  
 Baijnath Division  
 H.R.P.W.D., Bikaner  
 18/9

6

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Community Bhawan Kukaina (SH: P/L Kharanja Stone Soling , 1:2:4 and cement plaster . ) ( Deposit Works )				Estimate Cost:49,945.00 Earnest Money:1,000.00 Time Limit : One Month		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	7.36	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	4.90	Per cubic metre			
3	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises.internal rounded angles.chamfers and or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (1Cement:6 Sand) . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	19.13	Per square metre			

Executive Engineer  
Bajnath Division,  
H.P.P.W.D. Bajjnath (H.P.)

7

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O Shed Of Samshan Ghat of Ward No. 3 Trehal  
(SH: P/F G.I sheet Roofing and 1:2:4 . )

(Depend work)

Estimate Cost:99,422.00  
Earnest Money:2,000.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	0.41	Per Cum				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.41	Per Cubic metre				
3	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty milimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six milimetre) . 28mm (twenty eight milimetre) crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one milimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	26.25	Per square metre				
4	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins, connected to common rafters and the like work including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	446.25	Per Kg				

Executive Engineer  
Bajinath Division,  
H.P.P.W.D. Bajinath (H.P.)

## DNIT/DRAFT SCHEDULE OF QUANTITY

8

Name of Work : Comp . Under Construction Road ( Aram Ghar ) . *(Repair work)*  
 (SH:-P/L C. C Pavement at km 0/00 to 0/060 . )

Estimate Cost: 98,558.00/-  
 Earnest Money: 2,000.00/-  
 Time Limit :Two Months

## SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
					Words	Rs.	P
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	14.18	Per Cubic metre				
	Total						

*Executive Engineer*  
 Bajinath Division,  
 H.P.P.W.D. Bajinath (H.P.)



**DNIT/DRAFT SCHEDULE OF QUANTITY**

9

**Name of work :- C/O Road From Main road to Smt Indu Bala House -5 Mahal Patt . (Deposit work)**  
**(SH:-P/L. C. C Pavement & Kharnja Soling at km 0/00 to 0/084 )**

Estimate Cost: 99,300.00/-  
 Earnest Money:2,000.00/-  
 Time Limit :One Month

**SCHEDULE OF WORKS**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.97	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	13.23	Per Cubic metre			
<b>Total</b>						

**Executive Engineer**  
**Bajnath Division,**  
**H.P.P.W.D. Bajjnath (H.P.)**

Name of Work : Construction B.P.S Govt Sr. Sec School Chadhiar  
(SI) : P.F.C.I sheet Roofing , Kharnja Stone Soling and 1:2:4 )

BNI/DRAFT SCHEDULE OF QUANTITY  
(Deposit work)

Estimate Cost: 98,039.00  
Earnest Money: 2,000.00  
Time Limit : Two Months

Time Limit : Two Months		Rate		AMOUNT	
Sr.no	Description of work	No. or Qty.	Unit	Figures	Words
1	Providing and fixing eight millimeter (thick anti skid water proof slant and impervious waterproofing tiles 150 mm x 75 mm (Six hundred into six hundred) in slanting roof, manufactured of approved shade and colour in flooring, treads of steps and landings and over 200 mm thick cement concrete 1:3 for cement and three sand) pointed with cement slurry mixed with 10% fine aggregate and 1% shade of red oxide iron pigment. The rates are inclusive cost and carriage of materials and labour, leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer in Charge. The rates include provision, royalty, GST, and tax, Sale tax or other taxes imposed by the government.	66.70	Per square metre		
2	Providing and fixing white glazed tiles 6 mm (Six millimeter) thick in skirting, riser, nosing and dado 200 x 150 mm (Two hundred into one hundred fifty millimeter) size laid on bed of 25 mm thick cement concrete 1:3 for cement and three sand finished with flush pointing of white cement concrete as per PWD specification. The rates are inclusive cost and carriage of materials and labour, leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer in Charge. The rates include provision, royalty, GST, and tax, Sale tax or other taxes imposed by the government.	7.35	Per square metre		

Executive Engineer  
Bajinath Division,  
H.P.P.W.D. Bajinath (H.P.)

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Samudayak Bhawan Ward No.5 Near GPS Nauri (Deposit work)				Estimate Cost:2,99,490.00 Earnest Money:6,000.00 Time Limit : Two Months		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty millimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six millimetre) . 28mm (twenty eight millimetre) crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one millimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	125.80	Per square metre			
2	Providing and laying hard stone Soling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	10.54	Per Cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement 2 coarse sand) 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	10.54	Per cubic metre			
4	Providing and fixing 15cm(fifteen centimetre) wide 45cm (forty five millimetre) over all semicircular plain G.I sheet gutter with iron brackets 40x3mm size bolts and nuts and washers etc including making necessary connections with rain water pipe complete as per design 0.63mm thick sheet as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	30.00	Per running metre			

Executive Engineer  
Bajnath Division  
H.P.P.W.D. Bajnath (H.P.)

**DNIT/DRAFT SCHEDULE OF QUANTITY**

(12) (a)



<b>Name of Work : C/O Pulli in Village Lehal (Deposited work)</b> <b>(SH:- C/O 1.00 mtr Span R C C Slab culvert at RD 0/230 . )</b>				<b>Estimate Cost: 1,95,515.00/-</b> <b>Earnest Money: 4,000.00/-</b> <b>Time Limit : Two Months</b>		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	29.69	Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm( forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, or other taxes imposed by the government	3.25	Cum			

3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.97	Cum			
4	Providing and laying plain /Reinforced Cement Concrete Bedding Complete as per Drawings and Technical Specifications clause 1303 to 1204 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.93	Cum			
5	Providing and laying mechanically mixed vibrated reinforced cement concrete in substructure using concrete grade M-20 ( M twenty ) design Mix with cement contents not less then 330 kg (three hundred and thirty kilogram ) per cubic meter as per drawing and M.O.R.D. technical specification section 800, 900,1200. Including the cost of form work in bed block and dirt wall etc excluding the cost of reinforcement for reinforced concrete work but including curing complete as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.84	Cum			
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause ,800 and 1206.3 RCC M-25 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.69	Cum			
7	Supplying, fitting, and placing HYSD bar reinforcement in sub structure complete as per drawing and technical specifications Clauses 1002, 1005,1010 and 1202 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	84.00	KG			



(12) (C)

8	Supplying, fitting, and placing HYSD bar reinforcement in super structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	236.000	KG			

  
 Executive Engineer  
 Baijnath Division,  
 H.P.P.W.D. Baijnath (H.P.)  


# **DNIT/DRAFT SCHEDULE OF QUANTITY**

(13) (a)


**Name of Work : C/O Pulli in Village Lehal . (Deposit Work)**  
**(SH:-C/O 0.60 mtr Span RCC slab culvert at RD 0/750 )**

**Estimate Cost: 1,43,096.00/-**  
**Earnest Money: 2,900.00/-**  
**Time Limit : Two Months**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.24	Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm( forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana. or other taxes	2.59	Cum			
3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.62	Cum			

(13)(b)

4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause ,800 and 1206.3 RCC M-25 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.56	Cum			
5	Supplying, fitting, and placing HYSD bar reinforcement in sub and super structure complete as per drawing and technical specifications Clauses 1002, 1005,1010 and 1202 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	170.00	Kg			

  
 Executive Engineer  
 Baijnath Division,  
 H.P.P.W.D. Baijnath (H.P.)

Name of Work : - C/O Shed Near Mela Ground Kandral  
(Srl: P/F G.I sheet Roofing and 1:2:4 . )

DNIT/DRAFT SCHEDULE OF QUANTITY

(14) (9)

Estimate Cost: 79,736.00  
Earnest Money: 1,600.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty millimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six millimetre) , 28mm (twenty eight millimetre) crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one millimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	21.00	Per square metre				
2	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists, channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like work including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Including carriage of materials within all leads and lifts and other incidental rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	357.00	Per Kg				
3	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	0.36	Per Cum				

(K)(b)

4	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.36	Per Cubic metre			

Executive Engineer  
 Baijnath Division,  
 H.P.P.W.D. Baijnath (H.P.)



DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O Stage in GSSS Jandpur (Deposit works)  
(SH: P/L Tile work , Kharnja Stone Soling and 1:3:6.)

Estimate Cost:97,989.00  
Earnest Money:2,000.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre in width or 10 sqm ( Ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m ( Fifty metre ).All kinds of soil. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.61	Cum				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.70	Per cubic metre				
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.38	Per Cum				
4	Providing and laying hard stone Soling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.13	Per Cubic metre				
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.75	Per cubic metre				
6	Providing and fixing 10mm(ten milimeter) thick anti skid water proof stain and impect resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundred into six hundred into ten milimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	37.16	Per square metre				

(15) (b)

7	Providing and laying white glazed tiles 6 mm (Six millimetrt) thick in skirting, riser, steps and dedo 200x150 mm (Two hundred into one hundred fifty millimetre) size laid on bed of 12 mm (Twelve millimetre) thick cement mortor 1:3 (one cement : three sand ) finished with flush pointing in white cement complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	12.36	Per square metre			

~~Executive Engineer~~  
Bajjnath Division,  
H.P.P.W.D. Bajjnath (H.P.)

