



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

SHORT TERM NOTICE INVITING TENDERS

HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **14/08/2024** up to 11.00 AM and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **13/08/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **12/08/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Hmirpur Sujanpur Thural Maranda road Km. 30/0 to 59/775 (SW:- C/o PCC R/Wall at Rd 47/110 to 47/120)	1,44,425/-	2900	Two Months	350/-
2	C/o Devi to Malehar road Km. 0/00 to 1/00 (SW:- C/o U-shape drain in Km. 0/800 to 0/915)	1,47,930/-	3000/-	One Month	350/-
3	C/o Tin Shed at Malahu Tehsil Palampur Distt. Kangra (SW:- C/o Tin Shed) (Deposit Work)	1,00,642/-	2000/-	Three Months	350/-
4	C/o Galu Ghanetta Baba Kripa road Km. 0/0 to 5/00 (SW:- C/o R/Wall at Rd 2/300 to 2/314)	3,16,505/-	6300/-	Three Months	350/-
5	C/o link road from Bhagolu Da Ghatta Umri via Mohrian Km. 0/00 to 4/00 (SW:- P/L Wearing in Km. 1/500 to 2/250)	3,59,100/-	7100/-	Three Months	350/-
6	C/o Ambulance road from FPO Building to ITI Link road Km. 0/0 to 0/160 (SW:- P/L CC work in Km. 0/0 to 0/068 (DC Deposit)	2,00,872/-	4000/-	Two Months	350/-
7	C/o Bhagolu da Ghatta to Umri via Mohrian Km. 0/0 to 4/00 (SW:- Formation cutting in Km. 1/500 to 2/500)	3,56,678/-	7200/-	One Month	350/-
8	C/o link road Pharer to Manjha via Band Km. 0/00 to 1/150 (SW:- C/o Khul Crossing at Rd 0/490, 0/590 & 0/645 & L CC Pavement in Km. 0/410 to 0/520) (under SCSP)	4,98,120/-	9900/-	Three Months	350/-
9	Geotechnical Investigation for C/o 30mtr span bridge over Sukad Khad on Hamirpur Sujanpur Thural Maranda road at Rd 33/300	2,40,000/-	5000/-	30 days	350/-
10	C/o Health Sub Centre at Chambi Tehsil Dheera Distt. Kangra (HP) (SW:- C/o B/Wall (length 90.00 mtr) P/L Paver block in Court Yard, C/o Boundary wall & Gate)	4,37,377/-	8700/-	Three Months	350/-
11	C/o link road from Henja to Bhawarna Khas via Garla Dei upto Swargjan (SW:- C/o U-shape Drain between Km. 0/330 to 0/500, P/L CC Pavement in Km. 0/330 to 0/425)	4,51,418/-	9000/-	Three Months	350/-
12	Restoration of rain damages on Dehan Kasoti Road Km 0/0 to 2/00. (SH:- C/o B/Wall in Km. 0/605 to 0/613).	88,140/-	1800/-	One Month	350/-
13	C/o 19.75 metre span RCC T-Beam over Rian Khad on Sullah Majhakra Harbaral road at Rd 0/360 (SW:- C/o approaches Harbaral Side from Rd 0/353 to 0/358.50)	4,85,627/-	9700/-	Two Month	350/-
14	Geotechnical Investigation for C/o 40mtr span Double lane bridge Up gradation of Gallu Bhoda Shivnagar road at Rd 3/870 under PMGSY-III	1,80,000/-	3600/-	One Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

No. PWD/BWD/Tender/NIT/2024-25/-

5167-5226

(On behalf of Governor of Himachal Pradesh)
Dated:- 6/8/2024

Copy to following for information and necessary action:-

1. The Principal Secy (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer (Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of work:- Restoration of rain damages on Hamirpur Sujjanpur Thural Maranda road Km 30/0 to 59/775. (SH:- Construction of PCC R/wall at RD 47/110 to 47/120).

Estimated Cost :- Rs. 1,44,425/-
Earnest Money :- Rs. 2900/-
Time Limit :- Two Month

S No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.70			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.00			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- C/o Devi to Malehar road Km 0/00 to 1/00 (SH:- C/o U-shape drain in Km 0/800 to 0/915).

Estimate Cost :- Rs. 1,47,930/-
Earnest Money :- 3000/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	48.30			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	30.19			Per Cubic metre	
Total:-						


Executive Engineer
Bhawerna Division
HP PWD Bhawerna

Schedule of Quantity

Name of Work :- Construction of Tin Shed at Malahu Tehsil Palampur Distt. Kangra. (SH:- C/o Tin Shed) (Deposit work).

Estimated Cost :- Rs. 1,00,642/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, malkana, toll tax, GST and other taxes imposed by the government.	1.01			Per Cubic metre	
2	Providing and laying cement concrete 1:3:6 (one cement isto three sand isto six graded, crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	0.14			Per Cubic metre	
3	Providing and laying cement concrete work of grade M-20 (M-twenty) design mix to obtain the minimum compressive strength 20N/mm ² (Twenty newton per square millimeter) with cement content not less than 320 kg/cum (Three hundred twenty Kilogram per cubic metre) and curing complete and mechanically mixed and vibrated as per approved specification, drawing and design, excluding cost of form work and reinforcement for reinforced concrete work in suspended floor roofs, landing and shelves and their supports balconies, beams, girder, bressumers and cantiliver upto any floor level including cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.48			Per Cubic metre	
4	Storage-filling tightly dry hand packed under flooring including ramming and consolidation complete as per the direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sales tax or other taxes imposed by the government.	1.75			Per Cubic Metre	

5	Providing and laying cement concrete 1:4:8 (one cement isto four sand isto eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.31			Per Cubic metre
6	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in beams joints, channels angles tees flats with connections plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	539.28			Per Kilogram
7	Providing corrugated G.I 0.63 mm thick (zero decimal six three millimetre) sheet roofing fixed with galvanised iron J or L hooks bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers filled with white lead complete excluding the cost of purlins rafters and trusses The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	17.20			Per Square metre
8	Providing ridges or hips 0.63 mm thick (zero decimal six three millimetre) over all in plain G.I.sheet with galvanised iron J or L hooks. bolts and nuts 8mm dia G.I. Limpet and bitumen washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In- Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.40			Per Running metre
9	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	43.58			Per Square metre
10	40 (forty) millimetre thick cement concrete flooring 1:2:4 (one cement: two sand: three graded crushed stone aggregate 20 mm (twenty millimeter) nominal size laid in one layer finished with a floating coat of neat cement. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8.75			Per Square metre
Total :-					

Murphy
Executive Engineer
Bhawana Division
HP PWD Bhawana

Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of work:- Construction of Galu Ghanetta Baba Kripa Road Km. 0/00 to 5/000 (SH.-C/O R/Wall at Rd. 2/300 to 2/314).

Estimate Cost :- Rs. 3,16,505/-

Earnest Money :- Rs. 6300/-

Time Limit :- Three Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	23.94			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	75.88			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28			Each	
Total:-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Bhagolu Da Ghatta Umri Via Mohrian Km 0/00 to 4/00. (SH:-P/L Wearing in Km. 1/500 to 2/500).

Estimate Cost :-Rs. 3,59,100/-
Earnest Money :-7100/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	189.00			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of work:- C/O Ambulance road from FPO Building to ITI link road Km 0/0 to 0/160 (SH:- P/L CC work in Km 0/0 to 0/068) (DC Deposit)

Estimate Cost :- Rs. 2,00,872/-
Earnest Money :- 4000/-
Time Limit :- Two Months

S.No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.04			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated reinforced concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.80			Per Cubic metre	
Total:-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Bhagolu da Ghatta to Umri via Mohrian Km 0/0 to 4/00 (SH:- Formation cutting in Km 1/500 to 2/500)

Estimate Cost :- Rs. 3,56,678/-

Earnest Money :- Rs. 7200/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil soft Rock, Hard rock, chisseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line ,grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302,1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unuseful material for filling in road way, camber , embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials , tools equipments and safety measures and incidentals necessary to complete the 73.29 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases .	2443.00			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- C/o Link road Pharer to Manjha via Band Km 0/00 to 1/150 (SW:- C/O Khul Crossing at RD 0/490, 0/590 & 0/645 & P/L CC Pavement in Km 0/410 to 0/520). (Under SCSP)

Estimate Cost :-Rs. 4,98,120/-
Earnest Money :- Rs. 9900/-
Time Limit :- Three Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	187.65			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.26			Per Cubic metre	
3	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in grating framed guard bares ladders railing brackets and similar work etcetra. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1143.82			Per Quintal	
4	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	30.80			Per Cubic Metre	

5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38.50		Per Cubic metre	
Total :-					


 Executive Engineer,
 Bhawana Division,
 HP PWD Bhawana

DRAFT SCHEDULE OF QUANTITY						
NAME OF WORK:- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF 30 MTR SPAN BRIDGE OVER SUKAD KHAD ON HAMIRPUR SUJANPUR THURAL MARANDA ROAD at rd 33/300						
				Estimated Cost : Rs	0.00	240000.00
				Earnest Money : Rs	5000.00	
				Time Limit :	30 DAYS	
S.No	Description of Item	Quantity	In fig.	Rate	Unit	Amount
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia h for investigation of soil rock conditions at site of work including mobilization and demobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	40.00	62001-	SIX THOUSAND TWO HUNDRED ONLY/-	Per running meter	
Total:-						


 Executive Engineer,
 Bhawana Division,
 H.P. PWD Bhawana


 M/s ARS CONSULTANTS
 Prop. PRAVEER SHARMA
 R/o Rajveer Villa, Shyamnagar
 District Kangra (H.P.) - 176215
 HP-SEV-(C)-0081

Schedule of Quantity

Name of work:- Construction of Health Sub Centre at Chambhi Tehsil Dheera Distt Kangra (HP) (SH:- C/o B/wall (length 90.00 mtr), P/L Paver block in Court Yard, C/o Boundary wall & Gate).

Estimated Cost :- Rs. 4,37,377/-
Earnest Money :- Rs. 8700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government	43.39			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana. toll tax, sale tax or other taxes imposed by the Government	21.06			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P V C pipe weep holes in brick masonry/ stone masonry plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax. GST or other taxes imposed by the Government	8.00			Each	
4	Providing laying Soling 90 to 45mm (Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with three wheel 80-100 Kn Static roller in stages to proper grade and camber applying and brooming stone screening/ binding materials to fill-up the interslices of coarse aggregate watering and compacting to the required density grading * as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government	6.00			Per Cubic metre	

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.01			Per Cubic metre
6	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.23			Per Cubic metre
7	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm (Sixty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	55.29			Per Square metre
8	Random rubble masonry with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement isto six sand isto Twelve graded stone aggregate) 20 mm (Twenty millimetre nominal size) at plinth level in cement mortar 1:6 (one cement isto six sand) including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax. GST and any other taxes imposed by the government.	12.15			Per Cubic metre
9	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etcetra, with wooden battens and balties for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation. Footings bases of columns and mass concrete. The rate is inclusive of cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax. GST and any other taxes imposed by the government.	11.40			Per Square metre

10	Providing and laying cement concrete work of grade M-20 (M-Twenty) design mix to obtain the minimum compressive strength of 20N/mm ² (twenty newton per square millimetre) with cement content not less than 320 kg/cubic meter mechanically mixed and vibrated including curing complete as per PWD specification, drawing and design excluding cost of form work and reinforcement for reinforced concrete work in coulmn, pillars posts and struts upto any floor level including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1.68			Per Cubic metre
11	Providing and laying cement concrete grade M-25 (M-Twenty five) design mix with minimum compressive strength 25N/mm ² (twenty five newton per millimetre square) with cement contents not less than 360 Kg (Three hundred sixty kilogram) per Cubic metre mechanically mixed and vibrated including curing complete as per PWD specification, drawing and design excluding the cost of form work and reinforcement for reinforcement cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc upto any floor level including carriage of materials with in all leads, lifts and other incidentals and further as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of Royalty, Malkana, sale tax, toll tax, GST and any other taxes imposed by the government.	0.05			Per Cubic metre
12	Providing and laying tor steel of TataTISCO, SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arrisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	252.00			Per Kilogram
13	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure upto all floor levels as per PWD specification, drawing and design and curing complete including scaffolding and cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1.98			Per Cubic metre
14	Second class half brick work using common burnt clay building bricks with hoop iron in cement mortar 1:4 (one cement isto four sand) in super structure as per PWD specification, drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	60.89			Per Square metre

15	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in In gratings framed guard bars,ladders,railing,brackets and similar works. and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	168.94			Per Kilogram
16	Providing and fixing 300x16mm (Three hundred into sixteen millimeter) size coloured / anodized aluminum sliding door bolt, anodized transparent or dyed to required colour and shade with bolts and nuts, screws etcetra complete. The rate is inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.00			Each
17	Providing and fixing 125mm (one hundred twenty five millimetre) size coloured / anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.00			Each
18	15mm (fifteen millimeters) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeters) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification including cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	141.03			Per Square metre
19	Wall painting (two coats) with premium emulsion paint of Asian paint / Nerolac Suraksha paint/ Berger paint / Dulux paint approved shade on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including cost and carriage of materials with in all leads, lifts and other incidentals as per specifications, approved drawing, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax toll tax, GST and any other taxes imposed by the government	141.03			Per Square metre

20	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5 40			Per Square metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of work:- C/o Link Road From Henja to Bhawarna khas via Garla Dei upto Swargjan. (SW:-C/O U-Shape Drain between Km. 0/330 to 0/500., P/L CC Pavement in Km. 0/330 to 0/425).

Estimate Cost :- Rs. 4,51,418/-
Earnest Money :- Rs. 9000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise but during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	57.75			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	34.20			Per Cubic metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density/grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	10.00			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.18			Per Cubic metre	
Total:-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dehan Kasoti Road Km 0/0 to 2/00. (SH:- C/o B/Wall in Km. 0/605 to 0/613).

Estimate Cost :- Rs. 88,140/-

Earnest Money :- Rs. 1800/-

Time Limit :- One Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes.	9.20			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.96			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8			Each	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of 19.75 metre span RCC T-Beam Bridge over Rain Khad on Sullah Majhakra Harbaral road at RD 0/360. (SH:- Clo approaches Harbaral Side from RD 0/353 to 0/358.50).

Estimate Cost :- Rs. 4,85,627/-
Earnest Money :- Rs. 9700/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	49.50			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	111.38			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.76			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

(Signature)
Executive Engineer
Bhawarna Division
HP PWD Bhawarna


Schedule of Quantity

NAME OF WORK:- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF 40.00 mtr span Double lane Bridge on Up-gradation of Gallu Bhoda Shrivnagar road at RD 3/870 under PMGSY-III.

Estimate Cost :- Rs. 1,80,000/-
Earnest Money :- 3600/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia h for investigation of soil rock conditions at site of work including mobilization and de-mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as per rthe direction of Engineer-in Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.00			Per Running metre	
Total:-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana