

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

E-Mail id-ee-bil2-hp@nic.in
Phone No.01978-222550

NOTICE INVITING TENDERS

Sealed percentage rates tender for the following works are hereby invited by the Executive Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriate class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 09.08.2024 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on any working day upto 02.00 PM. On dated 08.08.2024. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No.etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.


S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages Deoth Lagghat Jamli road Km.0/00 to 13/180(SH:-C/o B/Wall at RD.7/745 to 7/760)	Rs.2,16,244/-	Rs.4,400/-	Rs.350/-	Three Months
2	Restoration of Rain damages on link road Kothipura Rajpura Prohi Deoth road Km.0/00 to 8/785(SH:-C/o R/Wall at RD.4/820 to 4/835).	Rs.3,00,200/-	Rs.6,100/-	Rs.350/-	Three Months
3	A/R & M/O HP.PWD, Rest House Namhol, Distt. Bilaspur, HP(SH:- Providing and laying Painting work).	Rs.1,47,923/-	Rs.3,000/-	Rs.350/-	Three Months
4	Repair & Maintenance on Navgoun Beri road Km.4/350 to 23/700(SH:-C/o Rain Shelter at Bassi RD.20/00)	Rs.2,76,556/-	Rs.5,600/-	Rs.350/-	Three Months
5	Restoration of Rain Damages on Brampukhar to Shelli road Km.0/00 to 11/300(SH:-C/o R/Wall at RD.1/345 to 1/353).	Rs.3,96,974/-	Rs.8,000/-	Rs.350/-	Three Months
6	Restoration of Rain Damages on link road to Village Malothi Km.0/00 to 2/270 (SH:-C/o R/Wall at RD.1/820 to 1/827).	Rs.1,45,611/-	Rs.3,000/-	Rs.350/-	Three Months
7	Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road Km.0/00 to 18/690(SH:-C/o R/Wall at RD.10/985 to 10/995).	Rs.2,65,244/-	Rs.5,400/-	Rs.350/-	Three Months
8	Restoration of rain damages on Deoth Dabbar road Km.0/00 to 10/980(SH:-C/o R/Wall at RD.3/450 to 3/465).	Rs.3,19,732/-	Rs.6,400/-	Rs.350/-	Three Months
9	Restoration of rain damages on link road to Harizan Bazsti Tiun Khas road Km.0/00 to 3/135(SH:-C/o R/Wall at RD.1/240 to 1/252.30 and 1/870 to 1/883).	Rs.4,61,669/-	Rs.9,300/-	Rs.350/-	Three Months
10	Restoration of Rain Damages on Rajpura Chilla Charanmore Road Km.0/00 to 4/405(SH:-C/o R/Wall at RD.3/765 to 3/781)	Rs.4,86,640/-	Rs.9,800/-	Rs.350/-	Three Months

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.

5. The contractor/ Firms are requested to insert the rate of each item both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.


No.PW/NBT/CB/Tender-State/EA-1/2024-

3102-3111

Dated:- 30/07/2024

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HP.PWD., Hamirpur.
3. The Superintending Engineers, 10th Circle, HP. PWD., Bilaspur.
4. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through email-eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/ Notice Board.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,16,244/-Only.						
Earnest Money :- Rs.4,400/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages Deoth Lagghat Jamli road km 0/00 to 13/180 (SH:- C/o Bl/wall at RD 7/745 to 7/760)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.450 cubic metre	327.00	Rs. Three Hundred Twenty Seven only.	Per cubic metre	4071.00
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m (Twenty meter) as per Technical Specification Clause 1603.1 including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.75 Cubic metre.	150.00	Rs. one hundred Fifty only.	Per Cubic Metre	3713.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.25 Cubic metre	4222.00	Rs. Four Thousand Two Hundred Twenty Two only.	Per Cubic metre	199490.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00 Nos.	345.00	Rs. Three Hundred Forty Five only.	Each	8970.00
Total:-		(+/-) %				
Quoted Rate in Figures (%)						
Quoted Rate in Words(%)						
						216244.00

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,00,200/-Only.

Earnest Money :- Rs.6,100/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road Kothipura Rajpura Prohi Deoth road km 0/00 to 8/785 (SH:- C/o R/wall at RD 4/820 to 4/835)

Description of items.

Sr No.	Quantity	Rates in		Unit	Amount
		Figure.	Words.		
1	3	4	5	6	7
1	26 18	327.00	Rs. Three Hundred Twenty Seven only.	Per cubic metre	8561.00
2	62.25	4203.00	Rs. Four Thousand Two Hundred Three only.	Per Cubic metre	261637.00
3	14 40	1221.00	Rs. One Thousand Two hundred Twenty One only.	Per Cubic Metre	17582.00
4	36 00	345.00	Rs. Three Hundred Forty Five only.	Each	12420.00
Total:-					300200
Quoted Rate in Figures (%)					
Quoted Rate in Words(%)					

(+/-) %

**Executive Engineer
Bilaspur Division No.
HP PWD, Bilaspur**

Estimated cost:- Rs.1,47,923/-Only.

Earnest Money :- Rs.3,000/-

Time:- Three Months.

Executive Engineer
Bilaspur Division
M.P. PYD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,76,556/-Only.

Earnest Money :- Rs.5,600/-

Time:- Three Months.

NAME OF WORK:- Repair& Maintenance on Navygoan Beri road km 4/350 to 23/700 (SH:- C/o Rain Shelter at Bassi Rd 20/00)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.33	cubic metre	Rs.Two hundred thirty Six only.	Per cubic metre	786.00
2	Providing and laying cement concrete, 1:6:12 (One cement : six Sand : twelve graded crushed stone aggregate , 40mm (Forty milimetres) nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.57	cubic metre	Rs.Five thousand Three hundred Sixty only.	Per cubic metre	3055.00
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.80	Cubic Metre	Rs. Eight thousand Two hundred Thirty Four only	Per Cubic Metre	6587.00
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:4 (one cement : Four coarse sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.08	Cubic Metre	Rs. One Thousand One Hundred One only	Per Cubic Metre	28714.00
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including Carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, , royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.35	Cubic Metre	Rs. Four thousand Three hundred Sixty Four only	Per Cubic Metre	10255.00

6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.92	Cubic metre.	4721.00	Rs. Four Thousand Seven Hundred Twenty One only.	Per Cubic Metre	13785.00
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.980	Cubic metre.	5421.00	Rs. Five Thousand Four hundred Twenty One only.	Per Cubic Metre	70365.00
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	602.38	Kilogram	132.00	Rs. One Hundred Thirty Two only.	Per Kilogram.	79514.00
9	Providing and fixing M.S.B.P sheet 1.66 mm to 2mm (One point sixty six millimeter to two millimeter) thick in leaves board/facia/sofits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the direction of the Engineer-in-Charge (base member of steel work shall be measured and paid for separately), including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.08	Square metre.	1673.00	Rs. One thousand Six hundred Seventy Three only.	Per Square metre	6826.00
10	Providing and fixing 0.60 mm thick pre-painted Steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 (Twenty)microns over 5 microns primer coating to back coat of polyester of 5 microns over primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm dia. metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of engineer-in-Charge including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.72	Square Meter	1508.00	Rs. One Thousand Five hundred Eight Only.	Per Square metre	28230.00
11	Centering and shuttering including strutting, propping etc. and removal of form for including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.						0.00

i)	Suspended floors, roofs, landings, balconies and access platform	3.17	Square Meter	390.00	Rs. Three hundred Ninety only.	Per Square metre	1236.00
12	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.03	Kilogram	90.00	Rs. Ninety only.	Per Kilogram.	1623.00
13	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone masonry for interior plastering including arrises internal rounded angles, chamfers, and/ or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth: cement mortar 1:6 (One cement Six sand) including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.73	Square metre.	318.00	Rs. Three Hundred Eighteen only.	Per Square metre.	14542.00
14	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on steel work including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.22	Square metre.	167.00	Rs. One Hundred Sixty Seven only.	Per Square metre.	3544.00
15	Lettering with black Japan paint of approved brand and manufacture including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	300	Per letter Per CM	4.00	Rs. Four only.	Per letter Per CM	1200
16	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.73	Square metre.	102.00	Rs. One Hundred Two only.	Per Square metre.	4664.00
17	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.73	Cubic metre.	942.00	Rs. Nine Hundred Forty Two only.	Per Cubic Metre	1630.00
	Quoted Rate in Figures (%)						
	Quoted Rate in Words(%)						

(+/-) %

276556.00

Executive Engineer
Bilaspur Division
HP PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,96,974/- Only.
Earnest Money :- Rs.8,000/-
Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Brampukhar to Shelli Road km 0/00 to 11/300 (SH:- C/o R/wall at RD 1/345 to 1/353)

Description of items.

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.00	327.00	Rs. Three Hundred Twenty Seven only.	Per cubic metre	15042.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.44	4014.00	Rs. Four Thousand & Fourteen only.	Per Cubic metre	359012.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.12	1221.00	Rs. One Thousand Two hundred Twenty One only	Per Cubic Metre	16020.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	345.00	Rs. Three Hundred Forty Five only	Each	6900.00
Total:-						
Quoted Rate in Figures (%)						
Quoted Rate in Words(%)						

(+/-) %

396974.00

EXECUTIVE ENGINEER
Bilaspur Division No
HP PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,45,611/-Only.

Earnest Money :- Rs.3,000/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road to village Malothi km 0/00 to 2/270 (SH:- C/o R/wall at RD 1/820 to 1/827)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.30	cubic metre	171.00	Rs One Hundred Seventy One only.	Per cubic metre	2274.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.12	Cubic metre	4480.00	Rs. Four Thousand Four Hundred Eighty only.	Per Cubic metre	130458.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.72	Cubic metre.	1209.00	Rs. One Thousand Two hundred Nine only.	Per Cubic Metre	8124.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos	317.00	Rs. Three Hundred Seventeen only.	Each	4755.00
Total:-							145611.00
Quoted Rate in Figures (%)							
Quoted Rate in Words(%)							

Executive Engineer!
Bilaspur Division No
HP PWD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,65,244/-Only.

Earnest Money :- Rs.5,400/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- C/o R/wall at RD 10/985 to 10/995)

Description of items.		Quantity	Rates in		Unit	Amount	
Sr No.			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.20	171.00	Rs. One Hundred Seventy One only.	Per cubic metre	4309.00	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C. C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.90	4552.00	Rs. Four Thousand Five Hundred Fifty Two only.	Per Cubic metre	240801.00	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.20	1221.00	Rs. One Thousand Two hundred Twenty One only.	Per Cubic Metre	12454.00	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos	320.00	Rs. Three Hundred Twenty only.	Each	7680.00
Total:-							
Quoted Rate in Figures (%)						265244.	
Quoted Rate in Words(%)							

(+/-) %

265244.

EXECUTIVE ENGINEER
Bilaspur Division
HP PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,19,732-Only.

Earnest Money :- Rs.6,400/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Deeth Dabber Road km 0/00 to 10/980 (SH:- C/o R/wall at RD 3/450 to 3/465)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3		4 327.00	5 Rs. Three Hundred Twenty Seven only.	6 Per cubic metre	7 9663.0
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.25	Cubic metre	4502.00	Rs. Four Thousand Five Hundred Two only.	Per Cubic metre	280250.
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.25	Cubic metre.	1221.00	Rs. One Thousand Two hundred Twenty One only.	Per Cubic Metre	17399.
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.00	Nos.	345.00	Rs. Three Hundred Forty Five only.	Each	12420.
Total:-							
Quoted Rate in Figures (%)		(+) %					
Quoted Rate in Words (%)							

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,61,669/-Only.

Earnest Money :- Rs.9,300/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road to Harizan Basti Tuin Khas road km 0/00 to 3/135 (SH:- C/O R/wall at RD 1/240 to 1/252.30 and 1/870 to 1/883)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	37.50	Rs. One Hundred Seventy One only.	Per cubic metre	6413.00	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	92.69	Cubic metre	4338.00	Rs. Four Thousand Three Hundred Thirty Eight only.	Per Cubic metre	402089.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.44	Cubic metre.	1221.00	Rs. One Thousand Two hundred Twenty One only.	Per Cubic Metre	37167.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00	Nos.	320.00	Rs. Three Hundred Twenty only.	Each	16000.00
Total:-							
Quoted Rate in Figures (%)						461669.	
Quoted Rate in Words(%)							

(+/-) %

Executive Engineer
Bilaspur Division
HP PWD., Bilaspur

SCHEDULE OF QUANTITY.						
NAME OF WORK:- Restoration of Rain Damages on Rajpura Chilla Charnmore Road km 0/00 to 4/405 (SH:- C/o R/wall at RD 3/765 to 3/781)						
Estimated cost:- Rs.4,86,640/-Only.						
Earnest Money :- Rs.9,800/-						
Time:- Three Months.						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax , building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	42.56	Rs. Three hundred Eleven only.	Per cubic metre	13236.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	104.96	4131.00	Rs. Four Thousand One Hundred Thirty One only.	Per Cubic metre	433590.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.92	1176.00	Rs. One Thousand one hundred Seventy Six only.	Per Cubic metre	25778.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax , building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	44.00	Nos. 319.00	Rs. Three Hundred Nineteen only.	Each	14036.00
Total:-						
Quoted Rate in Figures (%)						486640.00
Quoted Rate in Words(%)						(+/-) %