

**Himachal Pradesh
Public works Department**

Notice inviting Tender

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **11-09-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **10-09-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 09-09-2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1.	RRD on Bhagwanpur Katlog road km. 0/00 to 3/300 (SH:- C/o P.C.C R/wall at RD 1/115 to 1/122)	1,36,191/-	2800	Two Months
2.	RRD on Bhagwanpur Katlog road km. 0/00 to 3/300 (SH:- C/o P.C.C R/wall with toe wall at RD 0/320 to /326.50)	1,93,099/-	3900	Two Months
3.	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- C/o R/wall at RD 126/750 to 126/755)	1,41,816/-	2900	Two Months
4.	RRD on Jachh Mashogal road km 0/00 to 10/250 (SH:- C/o R/wall at RD 6/850 to 6/859.70)	3,80,995/-	7700	Two Months
5.	RRD on Kathala Burahata road km. 0/00 to 6/080 (SH:- C/o PCC B/wall at RD 1/675 to 1/755) to Protect the private land (St. Leela Devi Court Case)	4,75,597/-	9600	Two Months
6.	C/o Sukkibain to sarogi road via Chhibba Killing Dahal or upto Dhahad km 0/00 to 4/500 (SH:- P/L stone solling, CC Pavement and V-shape drain at RD 0/900 to 0/970) under SCDP	2,81,991/-	5700	Two Months
7.	RRD on Sainj Kasan road km 0/00 to 5/00 (SH:- Repair of Abutments of 6.00 mtr. Span RCC Slab culvert at RD 1/780)	2,22,483/-	4500	Two Months
8.	RRD on Shaheed Tej Singh Jatta ra Nallah to Hallah to Harizan Basti Salon, Kafflon road km 0/00 to 2/250 (SH:- C/o PCC R/wall at RD 0/500 to 0/523) under SCSP	4,29,028/-	8600	Two Months
9.	RRD on link road Pali Anupali Brihmani road km. 0/00 to 5/00 (SH:- C/o PCC R/wall at RD 4/175 (SH:- C/o PCC R/wall at RD 4/175 to 4/189)	2,13,605/-	4300	Two Months
10.	RRD on link road Kattal Nattal Dharmdawara road km 0/00 to 13/00 (SH:- C/o PCC B/wall at RD 5/960 to 5/990)	3,76,763/-	7600	Two Months
11.	RRD on Hafwana to Panyas road km 0/00 to 17/500 km , 0/00 to 2/500km (SH:- C/o PCC R/wall Between RD 4/986 to 4/994.50)	4,93,463/-	9900	Two Months
12.	C/o link road Dugrain to Samih km 0/00 to 2/500 (SH:- C/o PCC R/wall at RD 0/215 to 0/230) under OTMNP	2,60,745/-	5300	Two Months

13.	C/o link road Dugrain to Samih km 0/00 to 2/500 (SH:- C/o PCC R/wall at RD 0/235 to 0/243) under OTMNP	2,20,516/-	4500	Two Months
14.	RRD on Dhanotu Rohangloo road km 13/00 to 32/400 (SH:- C/o PCC toe wall on Existing Toe wall at RD 13/00 to 13/016)	3,30,075/-	6700	Two Months
15.	RRD on Maloh to Katru road km 6/00 to 14/250 (SH:- C/o PCC R/wall for protection of road at RD 13/385 to 13/394)	3,90,312/-	7900	Two Months
16.	RRD on Chunahan to Malhanu road km 0/00 to 5/00 (SH:- C/o B/wall at RD 3/960 to 3/978)	1,52,003/-	3100	Two Months
17.	RRD on Gohar Kandha road km 0/00 to 2/600 (SH:- C/o R/wall at RD 1/060 to 1/072	2,76,332/-	5600	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated 27-08-2024

No. PW-GHR-Tender/NIT/2024

4866-84

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1st Circle, HP.PWD Mandi.
4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

Executive Engineer,
Gohar Division (B&R),
HPPWD.,Gohar.

Name of work :- RRD on Bhagwanpur Katlog road km 0/00 to 3/300 (SH:- Construction of PCC R/Wall at RD 1/115 to 1/122)

BILL OF QUANTITY

to 1/122)					Kangwanpur Katlog road km 0/00 to 3/300 (SH:- Construction of PCC R/Wall at RD 1/115		Estimated cost	1,36,191.00
							Earnest Money cost Rs. 2800.00	
							Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	10.99	Per Cubic meter					
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	25.73	Per Cubic meter					
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	5.00	Per Cubic meter					
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	7.00	Each					
Total:-								
Quoted rate in figure								
Quoted rate in words								

Name of work :- RRD on Bhagwanpur Katlog road km 0/00 to 3/300 (SH:- Construction of R/Wall with toe wall at RD 0/320 to 0/326.50)

BILL OF QUANTITY

Estimated cost 1,93,099.00

Earnest Money cost Rs. -3900.00

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.46	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	37.24	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	5.85	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	9.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

3

BILL OF QUANTITY

ame of work :- RRD on Shimla Mandi via Tattapani road km 115/00 to 135/00 (SH:- Construction of R/Wall at RD 126/750 to 126/755)

Estimated cost 1,41,816.00
Earnest Money cost Rs. 2900.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	17.63	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	26.99	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.35	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	6.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

BILL OF QUANTITY

me of work :- RRD on Jachh Mashogal road km 0/00 to 10/250 (SH:- Construction of R/Wall at RD 6/850 to /859.70)

Estimated cost 3,80,995.00

Earnest Money cost Rs. 7700.00

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer in Charge.	28.80	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals : as per direction of Engineer -in -Charge completer in all respect.	73.90	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	9.12	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	14.00	Each			
Total:-						
Quoted rate in figure						
Quoted rate in words						

5

NAME OF WORK :- RRD on Kathla Burahata road Km 0/00 to 6/080 (SH:- Construction of PCC B/Wall at RD 1/675 to 1/755) to Protect the private land (Smt. Leela Devi Court Case)

BILL OF QUANTITY

Estimated cost 4,75,597.00

Earnest Money cost Rs. 9600.00

Time - Two Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	38.40	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	86.40	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	51.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

BILL OF QUANTITY						
Name of work :- C/o Sukkibain to sarogi road via Chhibba Killing Dahal or upto Dhahad km 0/0 to 4/500 (SH:- Providing and laying Stone soling, CC Pavement and V-Shape drain at Rd 0/900 to 0/970) Under SCDP					Estimated cost	2,81,991.00
					Earnest Money cost Rs.	5700.00
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	34.18	Per Cubic meter			
2	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) :4 graded stone aggregate 20 mm nominal size) with in all leads .lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	27.56	Per Cubic meter			
3	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	5.80	Per Cubic meter			
4	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	5.42	Per Cubic meter			
Total:-						
Quoted rate in figure						
Quoted rate in words						

Name of Work:- RRD on Sainj Kasan road km. 0/00 to 5/00 (SH:- Repair of Abutments of 6.00 mtr. Span RCC Slab Culvert at RD. 1/780)) .					BILL OF QUANTITY	
					Estimated cost Rs. - 222483.00	
					Earnest Money cost Rs. - 4500.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.24	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 (one cement: three sand : six graded stone aggregated) P.C.C grade M 10 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.71	Per Cubic metre			
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.50	Per cubic metre			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

ne of work :- RRD on Shaheed Tej Singh Jatta ra Nallah to Harizan Basti Salon, Kafflon road km 0/00 to 2/250
(SH:- Construction of PCC R/Wall at RD 0/500 to 0/523) Under SCSP

Estimated cost 4,29,028.00
Earnest Money cost Rs. 8600.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	25.30	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	84.18	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	21.00	Each			
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	6.90	Per Cubic meter			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

92/9

Name of work :- RRD on link road Pali Anupali Brikhmani road km 0/00 to 5/00 (SH:- Construction of PCC R/Wall at RD 4/175 to 4/189)

BILL OF QUANTITY

Estimated cost 2,13,605.00
Earnest Money cost Rs. 4300.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	9.45	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	40.95	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	23.00	Each			
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.92	Per Cubic meter			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (B&R)
H.P.W.D Gohar.

BILL OF QUANTITY

me of work :- RRD on link road Kattal Nattal Dharmdawara road km 0/00 to 13/00 (SH:- Construction of PCC /Wall at RD 5/960 to 5/990)

Estimated cost 3,76,763.00

Earnest Money cost Rs. 7600.00

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	28.88	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	75.00	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	20.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

me of work :- RRD on Hafwana to Panyas road Km 0/00 to 17/500 km 0/00 to 2/500 (SH:- Construction of PCC
A/Wall Between RD 4/986 to 4/994.50)

Estimated cost 4,93,463.00
Earnest Money cost Rs. 9900.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	41.99	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	94.95	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	10.46	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	28.00	Each			
Total:-						
Quoted rate in figure						
Quoted rate in words						

BILL OF QUANTITY

Name of work :- Construction of link road Dugrain to Samih km 0/00 to 2/500 (SH:- Construction of PCC R/Wall at RD 0/215 to 0/230) Under OTMNP

Estimated cost 2,60,745.00
Earnest Money cost Rs. 5300.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.63	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	49.87	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	25.00	Each			
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	4.65	Per Cubic meter			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

BILL OF QUANTITY

Name of work :- Construction of link road Dugrain to Samih km 0/00 to 2/500 (SH:- Construction of PCC R/Wall at RD 0/235 to 0/243) Under OTMNP

Estimated cost 2,20,516.00
Earnest Money cost Rs. 4500.00
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.68	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	42.72	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	17.00	Each			
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.50	Per Cubic meter			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

106 19

Name of work :- RRD on Dhanotu Rohangalooroad Km 13/00 to 32/400 (SH:- Construction of PCC toe wall on Existing Toe wall at RD 13/00 to 13/016)

BILL OF QUANTITY

Estimated cost Rs. - 3,30,075/-

Earnest Money cost Rs. 6700/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	67.20	Per Cubic meter			
2	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	20.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (B&R)
H.P.PWD Gohar.

BILL OF QUANTITY

Name of work :- RRD on Maloh to Katru road Km 6/00 to 14/250 (SH:- Construction of PCC R/Wall for protection of road at RD 13/385 to 13/394)

Estimated cost Rs. - 3,90,312/-

Earnest Money cost Rs. 7900/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	22.95	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	75.60	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	9.63	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	20.00	Each			
Total:-						
Quoted rate in figure						
Quoted rate in words						

BILL OF QUANTITY

Name of work :- RRD on Chunahan to Malhanu road Km 0/00 to 5/00 (SH:- Construction of B/Wall at RD 3/960 to 3/978)

Estimated cost Rs. - 1,52,003/-

Earnest Money cost Rs. 3100/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	19.44	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	29.16	Per Cubic meter			
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	15.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

me of work :- RRD on Gohar Kandha road km 0/00 to 2/600 (SH:- Construction of R/Wall at RD 1/060 to 1/072)

Estimated cost 2,76,332.00

Earnest Money cost Rs. -5600.00

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths as per direction of Engineer -in -Charge complete in all respect.	33.90	Per Cubic meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	51.82	Per Cubic meter			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	8.46	Per Cubic meter			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	15.00	Each			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					