



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 04-09-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 02-09-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 03-09-2024 from 2.00 P.M. to 5.00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost tender form	Eligible Class of Contractor	Time
1	Construction of Bridge over River Beas in G.P. Tullah near Tuline Bharari Temple in Joginder Nagar Constituency to connect the Dharampur Constituency (SH:- Formation cutting of approach road to Bridge km. 0/0 to 0/435).	Rs.4,90,787/-	Rs.8,800/-	Rs.350/-	Class "D"	Three Months
2	Construction & M/T on Khai Dhar to Patyur road km. 0/0 to 2/0 (SH:- Providing and laying Cement Concrete Pavement at km. 0/00 to 0/50)	Rs.1,37,222 /-	Rs.2,700/-	Rs.350/-	Class "D"	Three Months
3	A/R & M/O Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashat Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli rod km. 0/00 to 80/00(MDR-57) (SH:- Clearing and grubbing of road land at km. 50/00 to 53/00).	Rs.98,555/-	Rs.1,900/-	Rs.350/-	Class "D"	Two Months
4	Restoration of rain damages on Sandha Makan road km. 0/00 to 3/00 (SH:- Construction of Retaining wall in km. 1/076 to 1/089).	Rs. 4,69,702/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
5	Restoration of rain damages on various roads under Joginder Nagar Sub Division HP PWD, Joginder Nagar (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side Katcha Drains etc).	Rs. 99,060/-	Rs.2000/-	Rs.350/-	Class "D"	One Month
6	Construction of Link rod from Sajehar to Galmatha Under BASP (SH):- Removal of Formation Deficiency between km. 7/705 to 7/795)	Rs.1,88,938 /-	Rs.3,800/-	Rs.350/-	Class "D"	Three Months
7	Special Repair to Sub Judge office Building at Joginder Nagar Distt. Mandi (SH:- Construction of Gents Toilet).	Rs.87,088/-	Rs.1,700/-	Rs.350/-	Class "D"	Two Months
8	Restoration of Rain Damages on Machhyal Bhararu Bihun road km. 0/00 to 12/00 (SH:- Construction of Retaining wall at km. 8/915 to 8/930)	Rs.2,82,190/-	Rs.5,600/-	Rs.350/-	Class "D"	Three Months
9	Restoration of Rain Damages on Baljnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Construction Retaining wall at km. 8/170 to 8/185).	Rs.1,87,435/-	Rs.3,700/-	Rs.350/-	Class "D"	Three Months
10	A/R & M/O to Various Non Residential Buildings Under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Providing and fixing Unic Stone 12mm thick in 2 nd floor outer side at Divisional office HP PWD, Joginder Nagar).	Rs.3,27,098/-	Rs.6,500/-	Rs.350/-	Class "D"	Three Months
11	Construction of link rod from Bhujru Nallah to Harizan Basti Bhalyandra GP Ner Gharwasra km. 0/00 to 1/500 under SCSP (SH:- Construction of Breast wall to protect existing house at km. 0/310 to 0/325).	Rs. 1,85,306/-	Rs.3,700/-	Rs.350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.

5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures falling which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW/JND-B&R-EA-I/NIT/Press/2023-24- 7263-7312

Dated:- 29/07/2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD,
Joginder Nagar.

SCHEDULE OF QUANTITY

Name of Work: Construction of Bridge over river Beas in GP Tullah near Tuine Bharari Temple in Joginder Nagar Constituency to connect the Dharampur Constituency (Sub Head:- Formation cutting of Approach road to Bridge km 0/0 to 0/435)				Estimate Cost: 4,90,787.00 Earnest Money: 9,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 114.85 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2296.94	Per cubic metre			
			Total			

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar.

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on Khai Dhar to Patyur road 0/0 to 2/0 (SH: Providing and Laying Cement Concrete Pavement at km 0/00 to 0/050)					Estimate Cost: Earnest Money: Time Limit :			1,37,222.00 2,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P			
				Figures	Words				
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.69	Per Cubic metre						
Total									


 Executive Engineer
 R & R Division HP, PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O Sandapattao Bharol Bagora Bagla Hard Ropari Kolang Triambli Boshan Druibdal
 Chironji Banwar Kun Ka Far Mandokhar Bhargoan Kotli Road km 0/00 to 80/00 (MDR-57) (SH: Clearing and
 grubbing of road land at km 50/00 to 53/00)

Estimate Cost: 96,555.00
 Earnest Money: 1,900.00
 Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Cleaning and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier and disposal of unseizable materials and stacking of seizable material to be used or auctioned, upto a lead of 1000m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	12300.00	Per square metre			
Total						


 Engineer
 B & R Division HP, PWD,
 Angul, Odisha

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Sandha Makan road km 0/00 to 3/00

(SfH: Construction of Retaining wall in km 1/076 to 1/089)

Sr. No.		Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	Amount
					Figures	Words		
1		Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiselling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.08	Per cubic metre				4,89,702.00
2		Providing and laying cement concrete 1:2:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	85.67	Per cubic metre				9,800.00

Three Months

Rs. P

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.83	Per cubic metre				
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R. Technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	48.00	Each				
	Total						


 Engineer
 B & R Division HP, PWD,
 Jalandhar

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:- Restoration of rain damages on various roads under Joginder Nagar sub Division, HPPWD, Joginder Nagar (Makriri Section)
 Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within 20 loads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
				Total:-		

Executive Engineer,
 B&R Division, HPPWD,
 Joginder Nagar

(6)

SCHEDULE OF QUANTITY

Name of Work: Construction of Link road from Sajehar to Galmatha User BASP (SH: Removal of Formation Deficiency between km 7/705 to 7/795)			Estimate Cost: Earnest Money: Time Limit :			1,88,938.00 3,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 72.30 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	851.11	Per cubic metre		-		
	Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of work : Special Repair to Sub Judge office Building at Joginder Nagar Distt. Mandi
(SH: Construction of Gents Toilet)

Name of work : Special Repair to Sub Judge office Building at Joginder NagarDistt. Mandi (SH: Construction of Gents Toilet)							Estimate Cost: Earnest Money: Time Limit :	87,068.00 1,700.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Demolishing brick work in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 (fifty) metres lead as per direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.52	Per Cubic metre					
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level Cement mortar 1:4 (one cement into four coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.25	Per Square Meter					
3	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm. thirty five by thirty five by five millimeter joints mitered and welded by angle iron 35x35x5 mm. thirty five by thirty five by five millimeter) or 35x 5 mm (thirty five by five millimeter) flat pieces to the existing iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.30	Per Kilogramme					
4	Providing and fixing 35 mm (thirty five millimetre) panelled or panelled and glazed shutters with Kiln seasoned and chemically treated hollock wood for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.20	Per Square Metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	15mm (Fifteen millimeter) cement plaster in single coat on the Rough side in cement mortar 1:6 (one Cement : six Sand), of brick/concrete/stone walls for plastering upto floor two level including arises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.50	Per Square Metre			
6	Distempering with oil bound washable distemper of approved brand and manufacture on New work (two or more coats) over and including water thinnable priming coat with cement primer to give an even shade complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.50	Per Square Meter			
7	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.78	Per Square Meter			
8	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 lit/10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @0.75 lit/10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture complete in all respect including building of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.78	Per Square Metre			
9	Providing and laying vitrified floor tiles of size 600X600 mm (six hundred millimeter) (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved brand, in all colours and shades, laid on 20mm (twenty millimeter) thick cement mortar 1:4 (one cement to four coarse sand), jointing with grey cement slurry @ 3.5 kg (three point three kilogramme per square meter) including grouting the joints with white cement and marbling pigments etc., complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.02	Per Square Metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
10	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% (Zero point zero eight percentage) and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints. (Payment for grouting of joints to be made separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.07	Per Square Metre			
11	Providing and fixing 250x16mm (two hundred fifty by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc, complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
12	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 200x10mm (Two hundred into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
13	Providing and fixing anodized aluminum handle anodized transparent or dyed to required shade and colour with necessary screws etcetra complete, 125mm (one hundred twenty five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
14	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and bid, in the low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.P. bracket, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof covering of approved municipal design complete, including painting of fittings and brackets, cutting & making good the walls and floors wherever required W.C. pan with ISI marked water proofing, seat and lid as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
15	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimeter) C.P. brass pillar taps, 32 mm (thirty two millimeter) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 550x400mm (five hundred fifty by four hundred millimeter) with a pair of 15 mm (fifteen millimeter) C.P. brass pillar taps as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
16	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 400x260x350 mm (four hundred thirty by two hundred sixty by three hundred fifty millimeter) and 400x410x265 mm (three hundred forty by four hundred ten by two hundred sixty five millimeter) sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required One urinal basin with 5 litre white P.V.C. automatic flushing cistern as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
17	Providing and fixing Division Plate for Vitreous China 300 mm (six hundred by three hundred millimeter) Vitreous China as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
18	Providing and fixing 8 mm (eight millimeter) in C.P. S.S. Jet with flexible tube upto 1 cm (one centimeter) long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
19	Providing and fixing PVC connection of 15 mm (fifteen millimeter) nominal size with 15 mm (fifteen millimeter) nominal size PVC accessories as required as per the direction and entire satisfaction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
10	Providing and fixing 32mm dia (thirty two millimeters) PVC waste for wash basin or sink including PVC fittings. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each			
11	Providing and fixing 15 mm (fifteen millimeter) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety grammes). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
12	Providing and fixing 15 mm (fifteen millimeter) nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
13	Providing and fixing 600x450 mm (six hundred by four hundred fifty millimeter) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimeter) thick lead board and ground fixed to wooden cleats with C.P. brass screws and washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
14	Providing and fixing PTMT soap Dish Holder having length of 138mm, (one hundred thirty eight millimeter) breadth 102mm, (one hundred two millimeter) height of 75mm (seventy five millimeter) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six grammes) complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
25	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm (six hundred millimeter) long towel rail with total length of 645 mm (six hundred forty five millimeter), width 78 mm (seventy eight millimeter) and effective height of 88 mm, (eighty eight millimeter) weighing not less than 190 gms. (one hundred ninety millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
26	Providing and fixing CP Brass toilet paper holder. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
27	Providing and fixing PVC floor trap 100 mm X 75 mm (one hundred ten by seventy five millimeter) ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
28	Providing and fixing PTMT grating circular type 100 mm (one hundred millimeter) nominal dia of approved quality and colour complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
29	Providing and fixing rigid PVC rain water pipe 100 mm (one hundred millimeter) seven five millimeter diameter) diameter conforming to IS : 13592 Type A, including cutting with seal ring conforming to IS : 8532, leaving 10 mm (ten millimeter) gap for thermal expansion, (i) Single socketed pipes. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.85	Per running metre			

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
30 Providing and fixing on wall face unplasticised - PVC moulded fittings accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 110x110x110 mm (one hundred ten by one hundred ten by one hundred ten millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
31 Providing and fixing on wall face unplasticised - PVC moulded fittings accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 75x75x75 mm (Seventy five by Seventy five by Seventy five millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each			
32 Providing and fixing on wall face unplasticised - PVC moulded fittings accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (Actual 87.5 x 75 mm (Twenty five millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each			
33 Providing and fixing on wall face unplasticised - Polyvinyl Chloride (PVC) rain water pipes nominal outer dia 110 mm (four inch) thermal stability for hot & cold water apply including all CPVC plain & basic moulded fittings including fixing the pipe with clamp and 100 mm spacing. This includes jointing of pipes with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-In-Charge. Internal work - Exposed in wall. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
34	Providing and fixing one piece construction white vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. P.V.C flush pipe for back and front flush with standard spreader pipes with fittings, G.I clamps and C.P. brass coupling complete, including painting of fittings and cutting and making good the walls and floors etc, wherever required Single squatting plate with 5 (five) litre P.V.C. automatic flushing cistern. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
Total						


 Executive Engineer
 B & R Division, H.P.W.D.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Machhwal Bhararu Bihun road km 0/00 to 12/00
(SH: Construction of Retaining wall at km 8/915 to 8/930)

Name of work : Restoration of Ram Damages on Machhyal Bhararu Bihun road km 0/00 to 12/00 (SH: Construction of Retaining wall at km 8/915 to 8/930)										Estimate Cost: 2,82,190.00 Earnest Money: 5,600.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P					
				Figures	Words						
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.20	Per cubic metre								
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) 3 plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.36	Per cubic metre								

S. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.70	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD.
Jalandhar Nagar

SCHEDULE OF QUANTITY

Reim

Name of Work: Restoration of Damages ~~on~~ on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Construction of Retaining wall at km 8/170 to 8/185)

Sl. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	1,87,435.00 3,700.00 Three Months
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R. Technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.30	Per cubic metre				
2	Providing and laying cement concrete (1:5:10) one cement, five standard graded crushed broken stone aggregate 40 mm (four millimeters) nominal size 1 plants and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.75	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.60	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
Total						


 Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to Various Non Residential Buildings Under Joginder Nagar Division HP.PWD Joginder Nagar (S.H. : Providing and fixing Unic Stone 12mm thick in 2nd floor outer Side at Divisional Office HP.PWD Joginder Nagar)				Estimate Cost: Earnest Money: Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing Unic Stone 12.5mm.(twelve point five millimeter) cladding on R.C.C. (reinforced cement concrete) surface side as on faces of Arch masonry walls etc.on 12mm.(twelve millimeter) Thick cement plaster 1:3 (one cement into three sand) and jointed with cement slurry i/c scaffolding etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	153.56	Per square metre			
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Bhujru Nallah to Harizan Basti Bhalyandra GP Ner Ghaswasra km 0.00 to 1/500 Under SCSP (SH: Construction of Breast wall to protect existing house at km 0/310 to 0/325)				Estimate Cost: 1,85,306.00 Earnest Money: 3,700.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT Rs. P
				Figures Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.13	Per cubic metre		
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.25	Per cubic metre		

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.40	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar