

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **19.08.2024** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **17.08.2024** up to **4:00 P.M.** and the application for issue of tender form shall be received on **16.08.2024** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road to village Dehru in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement in Km 0/500 to 0/600)	293063/-	5900/-	Two months
2	Construction of link road to Than Mata Mandir in Distt Kangra (HP) (SH:-Construction of 900mm dia RCC Hume pipe culvert at RD 0/430 and C/o Retaining wall at RD 0/450 to 0/558).	499459/-	10000/-	Two months
3	Construction of Trangari (Bridge)at Ustehar in Gram Panchayat Ustehar in Distt Kangra (HP) (Deposit work) (SH:-Construction of both side abutment of 8.00 mtrs span RCC slab culvert at RD 0/450).	382201/-	7650/-	Four months
4	Restoration of rain damages on link road from Kalizan to Balol road Km 0/000 to 8/000 in Distt Kangra (HP) (SH:-Construction of retaining wall at RD 0/450 to 0/460(Length 10.00 mtr Ht 3.65 mtrs)	195356/-	3950/-	Two months
5	Special repair to T.B. Sanatorium Building in Dr R.P. Govt. Medical College Kangra at Tanda in Distt Kangra (HP) Deposit work (SH:-Providing and laying paver block etc; in left side, Right Side and front side).	499990/-	10000/-	Two months
6	Construction of link road NH-88 to Gujjar Basti in G.P. in G.P. Balugaloa Tehsil Baroh Distt Kangra (HP) (SH:-Construction of retaining wall at RD 0/032 to 0/047).	394067/-	7890/-	Three months
7	Construction of Sport Complex in Maharana Partap International School at Dharamgiri in Distt Kangra (HP) (Deposit work) (SH:-Construction of Play Ground etc;)	434616/-	8700/-	Two months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

No.PW/NBD/TA/Tender/NIT/2023-24-

Copy to the following for information and necessary action:-

- The Principal Secy. (PW) to the Govt. of H.P. Shimla.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Director, Information & Publications Department, H.P. Shimla
- The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Principal, Dr. RPGMC, Tanda.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- The Block Development Office Nagrota Bagwan
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- The Contractors concerned.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)
Dated/ 8-8-2024

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST :- ₹ 293063.00
 EARNEST MONEY :- ₹ 5900.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road to village Dehru in Distt. Kangra (H.P.).

SUB HEAD :- Providing and laying cement concrete pavement in Km 0/500 to 0/600

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two milimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	8.75 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size) complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	48.00 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 499459.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road to Than Mata Mandir in Distt. Kangra (H.P.)

SUB HEAD :- Construction of 900mm dia RCC Hume Pipe culvert at RD 0/430 and C/O Retaining wall at RD 0/540 to 0/558

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	68.68 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	1.27 Cubic metres			Per cubic metre	
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 in 1:2.5:5 (One cement : Two and half sand : five graded) broken/crushed stone aggregate 20mm (Twenty millimeters) nominal size PCC grade M-15 (M-Fifteen), as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	10.50 Cubic metres			Per cubic metre	
4	Providing and laying non-pressure NP2 class R.C.C. hume pipes 900mm (Nine hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	7.50 Running metre			Per running metre	
5	Filling available excavated earth (excluding rock) intrtrenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer-in - charge as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	6.18 Cubic metres			Per cubic metre	
6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	92.23 Cubic metres			Per cubic metre	

7	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	57.60 Running metres			Per running metre
8	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	29.59 Cubic metres			Per cubic metre
TOTAL :-					


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 382201.00
 EARNEST MONEY :- ₹ 7650.00
 TIME LIMIT : FOUR MONTHS

NAME OF WORK :- Construction of Trangari (Bridge) at Ustehar in Gram Panchayat Ustehar in Distt. Kangra (H.P.) DEPOSIT WORK
SUB HEAD :- Construction of both side abutment of 8.00 mtrs span RCC slab culvert at RD 0/450

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of bridge structure in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty milimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental.	58.15 Cubic meters			Per cubic metre	
2	Providing and laying plain/reinforced cement concrete in sub structure as per drawing and technical specifications Clauses 802, 804, 805, 806, 807, 1202 and 1204 and 1205.5 PCC grade M-15 (M-Fifteen) in cement mortar 1:2.5:5 (One cement: Two and half sand Five graded crushed /broken stone aggregate 20mm) (Twenty millimeters nominal size), as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	72.15 Cubic meters			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- ₹ 195356.00
 EARNEST MONEY :- ₹ 3950.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road from Kalizan to Balol road Km 0/000 to 8/000 in Distt Kangra (HP).

SUB HEAD :- Construction of Retaining wall at RD 0/450 to 0/460 (Length 10.00 mtrs Ht. 3.65 mtrs)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	17.38 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	46.70 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	25.00 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	14.25 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagla Bagawan.

Schedule of Quantity

ESTIMATED COST :- ₹ 499990.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Special repair to T.B. Sanatorium Building in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt Kangra (HP), DEPOSIT WORK
SUB HEAD :- Providing and laying paver block etc; in Left side, Right Side and Front Side.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
		3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	22.90 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	28.20 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	7.90 Cubic metres			Per cubic metre	
4	Providing and laying 60mm thick cement concrete paver block of M-35 grade with approved colour, design and pattern factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	235.20 Square metre			Per square metre	
5	15mm (Fifteen millimetre) thick cement plasters in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm in girth and finished even and smooth with cement mortar 1:6 (One cement : Six sand) above plinth level to floor all level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	185.05 Square metres			Per square metre	
TOTAL :-						


Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - 394067.00
 EARNEST MONEY :- 7890.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road NH-88 to Gujjar Basti in G.P. Balugaloa Tehsil Baroh in District Kangra, (H.P.).
SUB-HEAD :- Construction of Retaining wall at RD 0/032 to 0/047.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	16.50 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	99.50 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	37.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	12.66 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- ₹ 434616.00
 EARNEST MONEY :- ₹ 8700.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Sports Complex in Maharana Partap International School at Dharamgiri in Distt. Kangra (H.P.) (Deposit work)
SUB HEAD :- Construction of Play Ground etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	95.52 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagnita Bagwan.