

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

No:-PW-NCD-E-Tender-NIT/2024-25:- 3494-3501

Dated:- 09.08.2024

To

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.


**DA: - Notice Inviting Tender.**  
**(79 No. Works)**

**Copy forwarded to for information:-**

Copy forwarded to the Superintending Engineer, 1<sup>st</sup> Circle, HP.PWD.,  
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.  
Copy to Account Branch in this office.  
Copy to Drawing Branch in this office.  
Notice Board.

  
**Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk**

  
**Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk**

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDER"**

Engineer, Nerchowk, H.P.PWD. Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **21.08.2024 upto 01.30 P.M.** and will be opened on the same day at **3.30 P.M.** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 19.08.2024** and tender form will be issued on dated **21.08.2024 upto 12:30 PM.** The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tender's and the tender's received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **90 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Eligible Class of Contractor
1	Restoration of rain damages on Ratti Kalkhar road km 10/000 to 13/500. (SH:- Construction of Retaining wall at RD 10/890 to 10/905).	474897	9500	350	Two Months	"D"
2	Construction of road from Kuppulu Thina to DPF Baglu km 0/0 to 5/000. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 2/395 alongwith both side wing walls). Under OTMNP.	252347	5100	350	Two Months	"D"
3	Improvement and widening of curve on Kalkhar Galu to Noundhar Upper Dibhri Lower Dibhri Bhout Sidhyani road km 0/000 to 5/000. (SH:- Construction of Breast wall at RD 1/490 to 1/505).	286667	5800	350	Two Months	"D"
4	Construction of Kalkhar Galu to Noundhar upper Dibhri lower Dibhri Bhout Sidhyani road km 0/0 to 4/600. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 2/240 alongwith both side wing walls).	253213	5100	350	Two Months	"D"
5	Restoration of rain damages on Kalkhar Leda Sundenagar road km 0/000 to 13/000. (SH:- Construction of Breast wall at RD 7/510 to 7/520).	192581	3900	350	One Month	"D"
6	Construction of Sardhar Bharedka Nalu road km 0/000 to 1/750. (SH:- Construction of Breast wall at RD 1/660 to 1/680). Under OTMNP	406371	8200	350	Two Months	"D"
7	Restoration of rain damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Removal of formation deficiency/ widening of curves in km 13/900 to 14/150).	376664	7600	350	One Month	"D"
8	Restoration of rain damages on Mandi Gagai Chailchowk Janjehli Chhatni Rana-Ka-Bag Nagan road km 0/0 to 16/190. (SH:- C/O PCC Retaining wall at RD 0/611 to 0/624).	469813	9400	350	Two Months	"D"
9	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar. (Rewalsar Section). (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris and dressing of berms etcetra). Job No.III.	220500	4500	350	210 Hrs.	"D"
10	Annual repair & maintenance of various road in Rewalsar Sub-Division HPPWD Rewalsar. (SH:- Manufacturing and supplying of retro-reflecotrised jurisdiction/ place identification guide sign board).	256234	5200	350	Two Months	"D"
11	Restoration of rain damages on Reur Durgapur road km 0/000 to 4/000. (SH:- Construction of U-Shape drain in PCC 1:3:6 at RD 1/400 to 1/600).	227626	4600	350	Two Months	"D"
12	Construction of Kalkhar Galu to Noundhar Upper Dibhri Lower Dibhri Bhout Sidhyani road km 0/000 to 4/500. (SH:- Construction of unlined drain in essential portion from km 0/000 to 4/500).	205200	4100	350	Two Months	"D"
13	Restoration of rain damages on Leda Ghangnoo road km 0/000 to 12/000. (SH:- Construction of Retaining wall at RD 8/370 to 8/385).	326409	6600	350	Two Months	"D"

14	Restoration of rain damages on Manjhyali Panyali Samloun Chalehar Sapru road km 0/000 to 9/500. (SH:- Construction of Retaining wall at RD 1/470 to 1/482).	481102	9700	350	Two Months	"D"
15	Restoration of rain damages on Halyatar Tryambha Gushali road km 0/000 to 8/000. (SH:- Construction of Retaining wall at RD 4/395 to 4/410).	259991	5200	350	Two Months	"D"
16	Restoration of rain damages on Leda Ghangnoo road km 0/000 to 12/000. (SH:- Construction of Retaining wall at RD 7/690 to 7/705).	349754	7000	350	Two Months	"D"
17	Construction of link road from Sarkidhar to Baba Balak Nath Temple km 0/0 to 2/000. (SH:- Construction of 900 mm dia RCC Hume pipe culvert at RD 1/525 alongwith both side wing walls).	228625	4600	350	Two Months	"D"
18	Construction of link road from Rewalsar Grauru Mode to Harizan Basti Chhir GP Lower Rewalsar km 0/000 to 0/500. (SH:- Construction of V-Shape drain from km 0/000 to 0/500). Under SCDP.	184600	3700	350	Two Months	"D"
19	Restoration of rain damages on Manjhyali Ghour Sardhwar upto village Batahan road km 0/000 to 13/000. (SH:- Construction of Retaining wall at RD 1/520 to 1/530).	217647	4400	350	Two Months	"D"
20	Restoration of rain damages on Rewalsar Dhiundhar road km 0/000 to 6/00. (SH:- Construction of Breast wall at RD 3/950 to 3/962).	244652	4900	350	One Month	"D"
21	Construction of link road from Suka Reur to Bagla Bari Gehri km 0/0 to 2/165. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 0/500 alongwith both side wing walls). Under OTMNP.	228984	4600	350	Two Months	"D"
22	Construction of link road from Gas Godawn to Chhukrahan Gram Panchayat lower Rewalsar km 0/0 to 1/700. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 0/250 alongwith both side wing walls). Under OTMNP.	229244	4900	350	Two Months	"D"
23	Improvement of Black spot on Talyahar Pingla Thona Sarkaghat road km 11/000 to 22/645. (SH:- Removal of formation deficiency/ widening of curves at RD 11/525 to 11/585 & 11/690 to 11/735).	194530	3900	350	One Month	"D"
24	Restoration of rain damages on Reur Durgapur road km 0/000 to 4/000. (SH:- Construction of Retaining wall at RD 2/759 to 2/773.35).	494407	9900	350	Two Months	"D"
25	Construction of link road Ridhu to Nalu Saryad km 0/000 to 1/000. (SH:- Construction of Retaining wall at RD 0/340 to 0/353). Under OTMNP.	436222	8800	350	Two Months	"D"
26	RRD on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD 0/630 to 0/645).	475453	9600	350	Two Months	"D"
27	Construction of link road from Damka Samloun Galma Pargipul Bag Sidhkothe Beri Samlehar Badhkari Tarwai km 0/00 to 2/600. (SH:- Construction of 900 mm dia RCC Hume pipe culvert at RD 1/990, with wing walls both side). Under OTMNP. Against Working Program.	372634	7500	350	Two Months	"D"
28	Restoration of road damages on Ratti to Randhara road km 0/0 to 9/00. (SH:- Construction of PCC Retaining wall at RD 6/550 to 6/562).	465127	9400	350	Two Months	"D"
29	RRD on Galma Nalwari road km 0/00 to 3/00. (SH:- Construction of PCC Retaining wall at RD 0/075 to 0/085 and at RD 0/600 to 0/614).	488340	9800	350	Two Months	"D"
30	Restoration of road damages caused due to laying of optical fiber cable on Ratti Kalkhar road km 0/0 to 10/00. (SH:- Extended 900 mm RCC hume pipe culvert at RD 5/0 with wing wall).	221030	4500	350	Two Months	"D"
31	RRD on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD 0/645 to 0/660).	474635	9500	350	Two Months	"D"
32	Restoration of rain damages on Manjhyali Ghour Sardhwar upto village Batahan road km 0/0 to 13/000. (SH:- Construction of Retaining wall at RD 4/755 to 4/765).	340676	6900	350	Two Months	"D"
33	Restoration of road damages on Sidhyani Khetri road km 0/0 to 5/200. (SH:- Construction of PCC Retaining wall at RD 1/620 to 1/632).	193386	3900	350	Two Months	"D"



34	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Trimming of grass and weeds and maintenance of drain from various roads under Nerchowk Section).	99700	2000	350	One Month	"D"
35	Restoration of rain damages on Manjhyali Samloun Patha via Chalehar Safu road km 0/000 to 9/945. (SH:- Construction of wire crated Retaining wall at RD 1/350 to 1/368).	326682	6600	350	Two Months	"D"
36	Restoration of road damages due to laying of optical fiber cable on Ratti Dharwan Grencha road km 0/00 to 6/00. (SH:- Providing and laying cement concrete paver blocks at RD 1/190 to 1/264).	493237	9900	350	Two Months	"D"
37	A/R & M/O Ratti to Kalkhar road km 0/0 to 10/00. (SH:- Repair of pot holes in km 0/0 to 1/00).	402012	8100	350	One Month	"D"
38	Construction of Debrī Ambe ka Ghar to Gajrehra Rathol km 0/0 to 0/500. (SH:- C/O PCC Retaining wall at RD 0/115 & 0/140). Under SCSP.	398102	8000	350	Two Months	"D"
39	Construction of Football play Ground for Govt. Senior Secondary School Gagal Tehsil Balh Distt Mandi HP. (SH:- C/O football play ground) Deposit Work Job No. I.	494301	10000	350	One Month	"D"
40	Restoration of rain damages on Galma Manjhyali road km 0/0 to 9/00. (SH:- Construction of Breast wall at RD 7/615 to 7/630).	218534	4400	350	Two Months	"D"
41	A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km 184/600 to 198/050. (SH:- Repair and chanalisation of culvert at RD 192/510).	497487	10000	350	Two Months	"D"
42	Restoration of road damages on Ratti Dharwan Grencha road km 0/0 to 6/00. (SH:- Construction of Retaining wall at RD 1/090 to 1/108).	101645	2100	350	Two Months	"D"
43	Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD 4/475 to 4/485).	161619	3300	350	Two Months	"D"
44	Construction of Football play Ground for Govt. Senior Secondary School Gagal Tehsil Balh Distt Mandi HP. (SH:- C/O football play ground) Deposit Work Job No. II.	494159	10000	350	One Month	"D"
45	RRD on Gutkar Behna Tikkar Malwana Badhyal road km 0/00 to 5/510. (SH:- Construction of PCC Retaining wall at RD 1/775 to 1/785).	287415	5800	350	Two Months	"D"
46	Construction of open air Stadium for play ground at Govt. Sen. Sec. School Pairi Tehsil Balh Distt Mandi HP. Deposit work	475101	9600	350	Two Months	"D"
47	Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD 7/071.50 to 7/083).	239573	4800	350	Two Months	"D"
48	Restoration of rain damages on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Breast wall at RD 3/700 to 3/712).	96545	2000	350	Two Months	"D"
49	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Nerchowk Section. (SH:- Hiring of Tractor with trolley for carriage of muck/ debris and shifting of materials etc).	74250	1500	350	Two Months	"D"
50	Construction of 6.00 mtr span RCC slab culvert at RD 2/135 on Galma Nalwari road km 0/0 to 3/0. (SH:- Construction of Nalwari side approaches at RD 0/0 to 0/004 U/S). Both side. (Under SCDP).	288334	5800	350	Two Months	"D"
51	Construction of road from Kothi Thapla Bhout Sarharka Lagda Hawanoo Dahanoo Bag and C/O culvert on Gamoulti Khad portion Kothi Thapla Bhout km 0/0 to 3/500. Under SCSP. (SH:- Construction of 900 mm dia hume pipe culvert at RD 1/350, with wing wall).	196601	4000	350	Two Months	"D"
52	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section). (SH:- Hiring of JCB clearing of debris and dressing of berms etc).	252000	5100	350	One Month	"D"
53	A/R & M/O old NH-21 Chandigarh Mandi Manali road km 184/650 to 198/00. (SH:- Construction of PCC U-Shape drain at RD. 186/800 to 186/980).	495230	10000	350	Two Months	"D"

54	A/R & M/O various bridge work under Chakkar Sub Division HPPWD Nerchowk. (SH:- Preparation of detailed working estimate for C/O 25.00 mtr span RCC box girder at Soyra Kalon Nalwari Galma Khad under OTMNP, C/O 75.00 mtr span precast bridge over Suketi Khad at Gutkar & Behna on Gutkar Behna road at km 0/300, preparation of hydraulic data for 25.00 mtr bridge on C/O road from Kothi Thapla Bhout Sararka Leda Hawanu Dhangu Bag road at RD 2/675 on Damodhi Khad bridge).	235000	5000	350	One Month	"D"
55	Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/00 to 14/580. (SH:- Construction of PCC Retaining wall at RD 7/060 to 7/071.50).	238982	4800	350	Two Months	"D"
56	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section). (SH:- Hiring of tractor with trolley for carriage of muck/debris and shifting of materials etc).	99000	2000	350	Two Months	"D"
57	RRD on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD 6/940 to 6/955).	311453	6300	350	Two Months	"D"
58	Construction of road from Chholi to Sanehra vill. Chawari km 0/0 to 3/00. (SH:- Providing and laying WBM G-I & G-II in km 1/500 to 1/900). Under SCDP.	429825	8600	350	Two Months	"D"
59	Restoration of road damages caused due to laying of optical fiber cable on Ratti to Kalkhar road km 0/00 to 10/00. (SH:- Construction of Retaining wall at RD 3/525 to 3/540).	253591	5100	350	Two Months	"D"
60	Construction of drain from the house of Smt. Pushpa Guleria to the house of Sh. Manish Kumar S/O Lt. Sh. Mohan Lal and Sh. Vijay Kumar house at village Lunapani Ward No. 3 (Old NH-21). (SH:- C/O PCC drain at RD 188/197 to 188/234). Deposti Work.	94909	2000	350	Two Months	"D"
61	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc). Gagal Section.	105000	2100	350	One Month	"D"
62	Restoration of rain damages on Kapahi to Jhor road km 0/00 to 2/500. (SH:- Construction of wire crate wall for protection of abutment for Balley bridge at RD 1/430 Jhor side).	466151	9400	350	One Month	"D"
63	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Preparation of DPR/ Detailed estimate for I> Upgradation of Mandi Gagal Chailchowk Chattari Rana Ka Bag road km 0/0 to 16/190 under CRF, II> Upgradation of Nerchowk Ratti Kalkhar road km 0/0 to 13/300 under NABARD, III> C/O Lakhwan Dahanu Hawanu Bhansot Rathol Andreta Meramasit road km 0/0 to 5/600 Under NABARD).	148500	3000	350	One Month	"D"
64	Restoration of rain damages on Ratti to Behal road km 0/00 to 8/00. (SH:- Construction of PCC retaining wall at RD 7/775 to 7/787).	313856	6300	350	Two Months	"D"
65	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti Section). (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	273000	5460	350	Two Months	"D"
66	Restoration of rain damages on Chahari School to Trambli Dehraloo Shil Kuntbhyo Gadwahan Doh road km 0/0 to 2/150. (SH:- Repair of various span RCC slab culverts at 0/435, 1/060 & 1/370).	424280	8500	350	Two Months	"D"
67	Restoration of rain damages on RPTD road km 0/00 to 10/00. (SH:- Construction of retaining wall at RD 0/985 to 1/00).	326250	6600	350	Two Months	"D"
68	Restoration of road damages caused by laying of optical fiber cable of Ratti Kalkhar road km 0/0 to 10/0. (SH:- Providing and laying WBM G-II, G-III and tarring in road side edges in km 0/0 to 0/837).	473318	9500	350	One Month	"D"
69	Construction of Pedestal for installation of statue of Martyar Sh. Tek Singh Mastana at village- Sayanh PO Lohara Tehsil Balh Distt Mandi HP.	133909	2700	350	Two Months	"D"




70	A/R & M/O various roads in under Chakkar Sub Division HPPWD Nerchowk. (SH:- Providing & fixing dual directional retro reflective cat-eyes studs). Gagal Section.	217350	4400	350	15 Days	"D"
71	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar, Leda Section. (SH:- Hiring of earth cutting/ Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra).	231000	4700	350	220 Hrs	"D"
72	A/R & M/O various road in under Chakkar Sub Division HPPWD Nerchowk. (SH:- Providing & fixing dual directional cat-eyes studs). Gagal Section.	217350	4400	350	15 Days	"D"
73	Annual Repair & maintenance of RPTD road km 0/0 to 10/0. (SH:- Providing and fixing dual directional retro reflective cat-eye studs).	248400	5000	350	One Month	"D"
74	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section). (SH:- Hiring of tractor with trolley for carriage of muck/debris and shifting of materials etc).	99000	2000	350	Two Months	"D"
75	RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk Section). (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	276150	5600	350	Two Months	"D"
76	Restoration of rain damages on Kalkhar Leda Sundemagar road km 0/000 to 13/600. (SH:- Construction of Retaining wall at RD 6/650 to 6/658).	401691	8100	350	Two Months	"D"
77	Restoration of rain damages on Rewalsar Sararidhar road km 0/000 to 6/800. (SH:- Construction of Retaining wall at RD 4/980 to 4/988).	268718	5400	350	Two Months	"D"
78	Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sihal Trambi road at RD 0/085. (SH:- Construction of wing wall at RD 0/10 to 0/24 U/S Chandyal side).	485102	9800	350	Two Months	"D"
79	Restoration of rain damages on Bhangrotu Nauru Tikkari road km 0/00 to 4/400. (SH:- Construction of PCC retaining wall at RD 0/110 to 0/160).	384312	7700	350	Two Months	"D"

It is certified that the above tenders are very "urgent nature", so may be uploaded on department website in public interest.

**Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).**

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.

  
Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk

①  
DNIT S.NO. (62) for the year 2024-25

**Draft Schedule of Quantity**

Estimated Cost:- Rs. 474897.00  
Earnest Money:- Rs. 9500.00  
Time:- Two Months

**Name of work:-** Restoration of rain damages on Ratti Kalkhar road Km. 10/000 to 13/500  
**Sub Head:-** Construction of Retaining wall at R.D. 10/890 to 10/905.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	30.45 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	8739.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	102.90 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	436296.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.60 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	19530.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	36.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	10332.00
					<b>Total</b>	<b>474897.00</b>

Draft schedule of quantity checked and approved for Rs 474897/- (Rupees four lac seventy four thousand eight hundred ninety seven) only.

Executive Engineer,  
H.P.R.W.D. Division,  
Narchowk



DNIT S.NO. (61) for the year 2024-25

### Draft Schedule of Quantity

Estimated Cost:- Rs. 252347.00  
Earnest Money:- Rs. 5100.00  
Time:- Two Months

Name of work:- Construction of road from Kuppala Thina to DPF Baglu Km. 0/0 to 5/000

Sub Head:- Construction of 900mm dia. R.C.C. Hume pipe culvert at RD. 2/395 alongwith both side wing walls.Under OTMNP

Sr. No	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	59.08 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	16956.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.02 Cubic metre	3090.00	Rupees three thousand ninety and paise nil only.	Per cubic metre	15512.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	4.74 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	20894.00
4	Stone masonry in cement mortar in sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Coursed rubble masonry (2nd (Second sort) in cement mortar 1:6 (one cement : six sand) and curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	11.46 Cubic metre	4500.00	Rupees four thousand five hundred and paise nil only	Per cubic metre	51570.00
5	Stone masonry in cement mortar in sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) and curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	20.92 Cubic metre	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	76358.00
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00



2

Sr. No.	Description of item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
7	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.96 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	4070.00
8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	15.16 Cubic metre	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	31836.00
9	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.81 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10301.00
					Total:-	252347.00

*Graft schedule of quantity checked and approved for Rs. 252347/- (Rupees two lac fifty two thousand three hundred forty seven) only.*

*[Signature]*  
Executive Engineer,  
HP PWD Division,  
Jalandhar

(3)

DNIT S.No. (35) for the year 2023-24

## Draft Schedule of Quantity

Estimated Cost:- 286667.00  
 Earnest Money:-Rs. 5800.00  
 Time:- Two Months

Name of work:- Improvement and widening of curve on Kalkhar Galu to Noundhar Upper Dibhri Lower Dibhri Bhout Sidhyani road Km. 0/000 to 5/000.  
 Sub Head:- Construction of Breast wall at R.D. 1/490 to 1/505.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	39.00 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	6708.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.15 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	3487.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	70.32 Cum.	3850.00	Rupees three thousand eight hundred fifty and paise nil only	Per cubic metre	270732.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	20.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	5740.00
					Total	286667.00

Draft Schedule of quantity checked and approved for Rs 286667/- (Rupees two lac eighty six thousand six hundred sixty seven) only.

Executive Engineer,  
 H.P.P.W.D. Division,  
 Narehwa

DNIT S.NO. (60) for the year 2024-25

### Draft Schedule of Quantity

Estimated Cost:- Rs. 253213.00  
Earnest Money:- Rs. 5100.00  
Time:- Two Months

**Name of work:-** Construction of Kaikhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road Km. 0/0 to 4/600.

**Sub Head:-** Construction of 900mm dia. R.C.C. Hume pipe culvert at RD. 2/240 alongwith both side wing walls.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	59.76 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	17151.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	7.90 Cubic metre	3040.00	Rupees three thousand forty and paise nil only.	Per cubic metre	24016.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	4.74 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	20894.00
4	Stone masonry in cement mortar in sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) and curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	32.38 Cubic metre	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	118187.00
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
6	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	1.41 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	5978.00



(4)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
7	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	15.16 Cubic metre	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	31836.00
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.81 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10301.00
					Total:-	253213.00

Draft schedule of quantity checked and approved for Rs. 253213/- (Rupees two lac fifty three thousand two hundred thirteen) only.

Executive Engineer,  
HP PWD Division,  
Nero Chowk

(5)

DNIT S.NO. (59) for the year 2024-25  
Draft Schedule of Quantity

Estimated Cost:- 192581.00  
Earnest Money:-Rs. 3900.00  
Time:- One Month

Name of work:- Restoration of rain damages on Kalkhar Leda Sundernagar road Km. 0/000 to 13/000.  
Sub Head:- Construction of Breast wall at R.D. 7/510 to 7/520.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	16.00 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	2752.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.80 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	2813.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	43.16 Cum.	4240.00	Rupees thousand four hundred forty and paise nil only	Per cubic metre	182998.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4018.00
					Total	192581.00

Draft schedule of quantity checked and approved for Rs. 192581/- (Rupees one lac ninety two thousand five hundred eighty one) only.

Executive Engineer,  
H.P.P.W.D. Division,  
Nerchowk

6

DNIT S.No. 65 for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- 406371.00  
 Earnest Money:-Rs. 8200.00  
 Time:- Two Months

Name of work:- Construction of Sardhwar Bharedka Nalu road Km. 0/000 to 1/750.  
 Sub Head:- Construction of Breast wall at R.D. 1/660 to 1/680. (Under OTMNP)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	54.00 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	9288.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	16.20 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	4649.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	90.66 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	384398.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	28.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	8036.00
					Total	406371.00

Draft schedule of quantity checked and approved for Rs. 4,06,371/- (Rupees four lac six thousand three hundred seventy one) only.

Executive Engineer,  
 H.P.P.W.D. Division,  
 Nalagarh



7

DAI.P.S.No? 102

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Removal of formation deficiency/ widening of curves in km. 13/900 to 14/150)

Estimated Cost:- 376664.00

Earnest Money :- 7600.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 100.15 cum. @ 300/- per cubic metre amounting to Rs.30,045/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.	2003.00	188.05	Rupees One hundred eighty eight and paise zero five only.	Per cubic Metre	376664.00
Total						376664.00

Draft schedule of quantity approved for 23,76,664/-

Executive Engineer,  
HPPWD Division  
Nerchowk

(8)

DNI FS-ND 106

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Mandi Gagai Chailchowk Janjehli Chhatti Rana-Ka-Bag Nagan road  
Km. 0/0 to 16/190. (SH:- C/O P.C.C. Retaining wall at RD. 0/611 to 0/624)

Estimated Cost:- 469813.00

Earnest Money :- 9400.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.71	287.00	Rupees Two hundred eighty seven and paise zero only	Per Cubic Metre	12258.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	103.16	4240.00	Rupees Four thousand two hundred forty and paise only.	Per Cubic Metre	437398.00
3	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm (Six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads, lifts/depths or as per the entire satisfaction and direction of Engineer-in-Charge.	12.09	1050.00	Rupees One thousand fifty and paise zero only	Per Cubic Metre	12695.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	26.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	7462.00
					Total	469813.00

*Draft schedule of quantity approved for 24,69,813/-*

Executive Engineer  
HPPWD Division,  
HPPWD Noida

(9)

DNIT S.No. (39) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 220500.00

Earnest Money:-Rs 4500.00

Time:- 210 Hrs

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Rewalsar Section)

Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.III)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

## Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees two lac twenty thousand five hundred) only.

Assistant Engineer,  
Rewalsar Sub-Division,  
HP.PWD. Rewalsar.

Executive Engineer  
H.P.P.W.D. Division  
Nagrohwa-175008



(10)

DNIT S.NO. (37) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- 256234.00  
 Earnest Money:- Rs. 5200.00  
 Time:- Two Months

Name of work:- Annual repair & Maintenance of various road in Rewalsar Sub Division HP.PWD. Rewalsar.  
 Sub Head:- Manufacturing and Supplying of retro-reflectorised jurisdiction/ place identification guide sign board).

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Manufacturing and supplying of jurisdiction or place identification guide of retro reflectorised sign board having size 1.22m x 0.915m (one point twenty two metre into zero point nine hundred fifteen metre) as per IRC-67 specification made of encapsuled leacs type retro reflective sheeting vide clause 1701.2.3 fixed over aluminium composite panel sheeting of 3mm (three millimetre) thick with area exceeding 0.9sqm. (zero point nine squaremetre) supporting in a square metre pipe frame of 25mm (twenty five millimetre) fixed with aluminium rivets 200mm (two hundred millimetre) centre with two post of G.I. pipe of 50 (fifty) NB 3m (three metre) long by means of properly design and drawing complete as per direction and entire satisfaction of the Engineer-in-charge with all leads and lifts.	16.00 Nos.	16014.60	Rupees sixteen thousand fourteen and paise sixty only	Each	256234.00
				Total:-		256234.00

Draft Schedule of quantity approved for Rs 256234/-  
 (Rupees two lac fifty six thousand two hundred thirty four) only.

Assistant Engineer  
 Rewalsar Sub-Division  
 HPPWD Rewalsar

Executive Engineer  
 H.P.P.W.D. Division  
 Noida-175008

(11)

DNIT NO. (57) FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 227626.00

Earnest Money:- Rs. 4600.00

Time:- Two Months

Name of work:- Restoration of rain damages on Reur Durgapur road Km. 0/000 to 4/000.

Sub Head:- Construction of U-shape drain in P.C.C. 1:3:6 at RD 1/400 to 1/600.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	124.00 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	21328.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	54.00 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	15498.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 20mm twenty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	40.00 Cum.	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	190800.00
					Total:-	227626.00

Draft schedule of quantity approved for Rs. 2,27,626/- only.

  
 Executive Engineer,  
 HP PWD Division,  
 Noida.

(12)

DNIT NO. (56) FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 205200.00

Earnest Money:- 4100.00

Time:- Two Months

Name of work:- Construction of Kalkhar Galu to Noundhar Upper Dibhri Lower Dibhri Bhout Sidhyani road Km. 0/000 to 4/500.

Sub Head:- Construction of unlined drain in essential portion from Km. 0/000 to 4/500

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point forty squaremetre) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical specification clause 307 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	2700.00 Rmt.	76.00	Rupees seventy six and paise nil only	Per running metre	205200.00
					Total:-	205200.00

Draft schedule of quantity approved for Rs. 2,05,200/- only.

Executive Engineer,  
HP PWD Division,  
Nerchowk.



(13)

DNIT NO. (54) FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 326409.00

Earnest Money:- Rs. 6600.00

Time:- Two Months

Name of work:- Restoration of rain damages on Leda Ghangnoo road Km. 0/000 to 12/000.

Sub Head:- Construction of Retaining wall at R.D. 8/370 to 8/385.

Sr. No.	Description of item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	42.90 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	12312.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	70.01 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	296842.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.60 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10080.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	25.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	7175.00
					Total	326409.00

Draft schedule of quantity approved for Rs. 3,26,409/- only.

Executive Engineer,  
H.P.P.W.D. Division,  
Narchowk

(14)

DNIT NO. 53 FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 481102.00

Earnest Money:- Rs. 9700 00

Time:- Two Months

Name of work:- Restoration of rain damages on Manjhyali Panyali Samioun Chalehar Sapru road Km. 0/000 to 9/500.  
Sub Head:- Construction of Retaining wall at R.D. 1/470 to 1/482.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	44.64 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	12812.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	104.76 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	444182.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.76 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	15498.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	30.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	8610.00
					Total	481102.00

Draft schedule of quantity approved for Rs. 4,81,102/- only.

Executive Engineer,  
H.P.P.W.D. Division,  
Narchowk



(15)

DNIT NO. (51) FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 259991.00  
 Earnest Money:- Rs. 5200.00  
 Time:- Two Months

Name of work:- Restoration of rain damages on Halyatar Tryambha Ghushali road Km. 0/000 to 8/000.  
 Sub Head:- Construction of Retaining wall at R.D. 4/395 to 4/410.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	33.45 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	9600.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	56.11 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	237906.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	6.15 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	6458.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	21.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	6027.00
					Total	259991.00

Draft Schedule of Quantity approved for Rs. 2,59,991/- Only .

Executive Engineer,  
 H.P.R.W.D. Division,  
 Nerchowk



(16)

DNIT NO. 50 FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 349754.00

Earnest Money:- Rs. 7000.00

Time:- Two Months

Name of work:- Restoration of rain damages on Leda Ghangnoo road Km. 0/000 to 12/000.

Sub Head:- Construction of Retaining wall at R.D. 7/690 to 7/705.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	55.80 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	16015.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.80 Cum	3090.00	Rupees three thousand ninety and paise nil only	Per cubic metre	33372.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	42.18 Cum	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	153957.00
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 25mm (twenty five millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	6.60 Cum	4408.00	Rupees four thousand four hundred eight and paise nil only	Per cubic metre	29093.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidentals.	47.99 Cum	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	100779.00
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	15.75 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	16538.00
					Total	349754.00

Draft schedule of quantity approved for Rs. 3,49,754/- Only.

  
 Executive Engineer,  
 H.P.P.W.D. Division,  
 Narchowk.

(17)

DNIT NO. 48 FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 228625.00

Earnest Money:-Rs. 4600.00

Time:- Two Months

Name of work:- Construction of link road from Sarkidhar to Baba Balak Nath Temple Km. 0/0 to 2/000.

Sub Head:- Construction of 900mm dia. R.C.C. Hume pipe culvert at RD. 1/525 alongwith both side wing walls.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	46.69 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13400.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3.19 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	14062.00
3	Providing and laying concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.05 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	43169.00
4	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.68 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	125843.00

(17)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	7.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	2009.00
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.04 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	5292.00
					Total:-	228625.00

Draft schedule of quantity approved for Rs. 2,28,625/- only.

Executive Engineer,  
HP.PWD.Division,  
Nerchowk



(18)

DNIT S.No. (46) for the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- 184600.00

Earnest Money:- 3700.00

Time:- Two Months

Name of work:- Construction of link road from Rewalsar Grauru More to Harizan Basti Chhir GP Lower Rewalsar Km.0/000 to 0/500.

Sub Head:- Construction of V-shape drain from Km. 0/000 to 0/500. (Under SCDP)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Providing and laying V-Shape drain mechanically mixed and vibrated with plain cement concrete M-10 grade with 20mm (twenty millimetre) nominal size with thickness of concrete as 10cm (ten centimetre) of size 45x25cm (forty five into twenty five centimetre) and curing complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	500.00 Rmt	369.20	Rupees three hundred sixty nine and paise twenty only	Per Running metre	184600.00
					Total:-	184600.00

Draft schedule of quantity checked and approved for Rs. 184600/-  
(Rupees one lac eighty four thousand six hundred) only.

Executive Engineer,  
HP PWD Division,  
Nagchowk

(19)

DNIT S.NO. (45) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 217647.00

Earnest Money:- Rs. 4400.00

Time:-

Two Months

Name of work:- Restoration of rain damages on Manjhyali Ghour Sardhar upto village Batahan road Km. 0/000 to 13/000.

Sub Head:- Construction of Retaining wall at R.D. 1/520 to 1/530.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	30.10 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	8639.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	46.67 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	197881.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	5.95 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	6248.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	17.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4879.00
					Total	217647.00

Draft schedule of quantity checked and approved for Rs. 217647/-  
(Rupees two lac seventeen thousand six hundred forty seven) only.

Executive Engineer,  
H.P.P.W.D. Division,  
Nellore

(20)

**DNIT S.NO. (44) For the Year 2024-25**  
**Draft Schedule of Quantity**

Estimated Cost:- Rs. 244652.00  
 Earnest Money:- Rs. 4900.00  
 Time:- One Month

Name of work:- Restoration of rain damages on Rewalsar Dhiundhar road Km. 0/000 to 6/00  
 Sub Head:- Construction of Breast wall at R.D. 3/950 to 3/962.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	38.70 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	6656.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.72 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	2790.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	54.39 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	230614.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4592.00
					<b>Total</b>	<b>244652.00</b>

*Draft schedule of quantity checked and approved for Rs 244652/- (Rupees two lac forty four thousand six hundred fifty two) only.*

*[Signature]*  
 Executive Engineer,  
 H.P.P.W.D. Division,  
 Narechowk.



(21)

DNIT S.NO. (42) for the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 228984.00

Earnest Money:-Rs. 4600.00

Time:- Two Months

Name of work:- Construction of link road from Suka Riur to Bagla Bari Gehri Km. 0/0 to 2/165

Sub Head:- Construction of 900mm dia R.C.C. Hume pipe culvert at RD. 0/500 alongwith both side wing walls Under OTMNP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	47.94 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13759.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3.19 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	14062.00
3	Providing and laying concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.05 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	43169.00
4	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.68 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	125843.00

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V.20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	7.00 Nos.	287 00	Rupees two hundred eighty seven and paise nil only	Each	2009.00
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.04 Cubic metre	1050 00	Rupees one thousand fifty and paise nil only	Per cubic metre	5292.00
					Total:-	228984.00

*Draft schedule of quantity checked and approved for Rs 228984/- (Rupees two lac twenty eight thousand nine hundred eighty four) only.*

*[Signature]*  
Executive Engineer,  
HP PWD Division,  
Noida

(22)

DNIT S.NO. (41) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 229244.00

Earnest Money:-Rs. 4900.00

Time:- Two Months

Name of work:- Construction of link road from Gas Godawn to Chhukrahan Gram Panchayat lower Rewalsar Km. 0/0 to 1/700.

Sub Head:- Construction of 900mm dia. R.C.C. Hume pipe culvert at RD 0/250 alongwith both side wing walls. Under OTMNP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	47.16 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13535.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3.30 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	14546.00
3	Providing and laying concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.05 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	43169.00
4	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.68 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	125843.00



Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge	7.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	2009.00
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.04 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	5292.00
					Total:-	229244.00

*Draft schedule of quantity checked and approved for Rs 229244/- (Rupees two lac twenty nine thousand two hundred forty four) only.*

*[Signature]*  
Executive Engineer,  
HP PWD Division,  
Narchowk

(23)

DNIT S.NO. (29) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- 194530.00  
 Earnest Money:- 3900.00  
 Time:- One month.

Name of work:- Improvement of Black spot on Talyahar Pingla Thona Sarkaghat road km. 11/000 to 22/645.  
 Sub Head:- Removal of formation deficiency/widening of curves at RD. 11/525 to 11/585 & 11/690 to 11/735.

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways. embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries. materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 51.72 cum. ( fifty one point seventy two) cubic metre) @ (at the rate of) Rs. 300/- (three hundred only) per cubic metre amounting to Rs.15516/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.	1034.46 Cum	188.05	Rupees one hundred eighty eight and paise five only	Per cubic metre	194530.00
				Total:-		194530.00

Draft schedule of quantity checked and approved for Rs 194530/- (Rupees one lakh ninety four thousand five hundred thirty) only.

Executive Engineer,  
 H.P.P.W.D. Division,  
 Nashik

(24)

DNIT S.No. (31) for the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 494407.00

Earnest Money:- Rs. 9900.00

Time:- Two Months

Name of work:- Restoration of rain damages on Reur Durgapur road Km. 0/000 to 4/000.

Sub Head:- Construction of Retaining wall at R.D. 2/759 to 2/773.35.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	46.78 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13426.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	109.75 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	465340.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	8.61 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	9040.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	23.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	6601.00
					Total	494407.00

Sd/- schedule of quantity checked and approved  
for Rs. 494407/- (Rupees four lac ninety four thousand  
four hundred seven) only.

Executive Engineer,  
H.P.R.W.D. Division,  
Nagpur



(25)

DNIT S.NO. (34) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 436222.00

Earnest Money:- Rs. 8800.00

Time:- Two Months

Name of work:- Construction of link road Ridhu to Nalu Saryad Km. 0/000 to 1/000.

Sub Head:- Construction of Retaining wall at R.D. 0/340 to 0/353. Under OTMNP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	63.44 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	18207.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	94.06 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	398814.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.18 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	11739.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	26.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	7462.00
					Total	436222.00

Draft schedule of quantity checked and approved for Rs. 436222/- (Rupees four lac thirty six thousand two hundred twenty two) only.

Executive Engineer,  
Nerchowk Division,

H.P. P.W.D. Nerchowk

(26)

DNI P.S. NO. 40

## DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD. 0/630 to 0/645)

Estimated Cost:- 475453.00

Earnest Money :- 9600.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	48.75	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	13991.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	144.56	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	416333.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.98	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	45129.00
					Total	475453.00

Draft schedule of quantity approved for 24.75453/b

Executive Engineer,  
HPPWD Division,  
HPPWD-Nerchowki



D NIT. S.No 374 for the year 2023-24.

### DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of link road from Damka-Samloun-Galma-Pargi-Pul-Bag-Sidhkothi-Beri-Samiehar-Badhkari-Tarwai Km. 0/00 to 600. (SH)- Construction of 900mm dia RCC Hume Pipe Culvert at RD. 1/990, with wing walls both side (Under OTMNP) Against Working programme

Estimated Cost:- 372634.00

Earnest Money :- 7500.00

Time : Two Months

S N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	84.87	287.00	Rupees Two hundred eighty seven and paise only	Per Cubic Metre	24386.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:6:12 (one cement: six sand : Twelve graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	9.93	3650.00	Rupees Three thousand six hundred fifty and paise zero only	Per Cubic Metre	36245.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704, 1202 & 1204 random rubble masonry second sort in cement mortar 1:4 (one cement : four sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	10.47	4500.00	Rupees Four thousand five hundred and paise zero only	Per Cubic Metre	47115.00
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 Rubble stone laid in cement mortar 1:3. (one cement : three sand) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	0.45	5233.00	Rupees Five thousand two hundred thirty three and paise zero only.	Per Cubic Metre	2355.00
5	Providing and laying 900 mm (Nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials and as per the entire satisfaction and direction of Engineer-in-Charge	7.00	3580.00	Rupees Three thousand five hundred fifty and paise zero only	Per Running metre	24850.00
6	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704, 1202 & 1204 random rubble masonry second sort in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	29.57	4200.00	Rupees Four thousand two hundred and paise zero only	Per Cubic Metre	124194.00
7	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	3.00	4408.00	Rupees Four thousand four hundred eight and paise zero only	Per Cubic Metre	13224.00
8	Construction of dry rubble stone masonry as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	42.77	2100.00	Rupees Two thousand one hundred and paise zero only	Per Cubic Metre	89817.00
9	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	9.95	1050.00	Rupees One thousand fifty and paise zero only	Per Cubic Metre	10448.00
					<b>Total</b>	<b>372634.00</b>

Draft schedule of quantity approved for 372,634/-

Executive Engineer,  
HPPWD Division,  
Nerohowk



(28)

DMPS-NO (22) for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages on Ratti to Randhara road km. 0/0 to 9/00, (SH:- Construction of PCC Retaining wall at RD. 6/550 to 6/562)

Estimated Cost:- 465127.00

Earnest Money :- 9400.00

Time :- Two Months

S.N o		Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
Rs. P.							
In figure	In word						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8610.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	101.28	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	429427.00	
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.96	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	16758.00	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 814,709,1204,3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	36.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	10332.00	
						Total	465127.00

Draft schedule of quantity approved for 4,65,127/-

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk

(29)

DNIP 3ND1- 391 for the year 2023-24.

## DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Gaima Nalwari road km. 0/00 to 3/00. (SH:- Construction of PCC Retaining wall at RD. 0/075 to 0/085 and at RD. 0/600 to 0/614)

Estimated Cost:- 488340.00

Earnest Money :- 9800.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	46.96	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	13478.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	104.72	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	444013.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	42.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	12054.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	17.90	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	18795.00
					Total	488340.00

Draft schedule of quantity approved 224,88,340/-

Executive Engineer,  
HPPWD Division,  
HPPWD, Noida



DMFS NO (519)

# DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Kalkhar road km. 0/0 to 10/00. (SH:- Extended 900mm dia RCC Hume Pipe Culvert at RD. 5/0, with wing wall)

Estimated Cost:- 221030.00

Earnest Money :- 4500.00

Time : Two Months

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.19	287.00	Rupees Two hundred eighty seven and paise only.	Per Cubic Metre	8378.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:6:12 (one cement: six sand : Twelve graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.11	3090.00	Rupees Three thousand ninety and paise zero only.	Per Cubic Metre	18880.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 random rubble masonry second sort in cement mortar 1:5 (one cement: five sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	2.54	4134.00	Rupees Four thousand one hundred thirty four and paise zero only.	Per Cubic Metre	10500.00
4	Providing and laying 900 mm (Nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials and as per the entire satisfaction and direction of Engineer-in-Charge.	2.50	3550.00	Rupees Three thousand five hundred fifty and paise zero only.	Per Running metre	8875.00
5	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 random rubble masonry second sort in cement mortar 1:6 (one cement: six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	27.71	4200.00	Rupees Four thousand two hundred and paise zero only	Per Cubic Metre	116382.00
6	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.08	4018.00	Rupees Four thousand eighteen and paise zero only.	Per Cubic Metre	16393.00
7	Construction of dry rubble stone masonry as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.84	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	35384.00
8	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 in Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.98	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	6258.00
					Total	221030.00

Draft schedule of quantity approved for 221,030/-

Executive Engineer,  
HPPWD Division,  
Nerchowk.



(31)

DM P.S. NO (42)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD. 0/645 to 0/660)


Estimated Cost:- 474635.00

Earnest Money :- 9500.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	45.90	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	13173.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	144.56	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	416333.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.98	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	45129.00
					Total	474635.00

Draft schedule of quantity approved for 2,47,4635/-

  
 Executive Engineer,  
 HPPWD Division,  
 HPPWD Nerchowk

(32)

DNIT S.NO. (35) for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 340676.00

Earnest Money:- Rs. 6900.00

Time:- Two Months

Name of work:- Restoration of rain damages on Manjhyali Ghour Sardhwar upto village Batahan road Km. 0/0 to 13/000.  
 Sub Head:- Construction of Retaining wall at R.D. 4/755 to 4/765.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	15.80 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	4535.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	75.28 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	319187.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.50 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	12075.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	17.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4879.00
					Total	340676.00

Draft schedule of quantity checked and approved for  
 Rs. 340676/- (Rupees three lac forty thousand six hundred  
 seventy six) only.

Executive Engineer,  
 Nerchowk Division,  
 H.P.W.D. Nerchowk



## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages on Sidhyani Khetari road km. 0/0 to 5/200. (SH:- Construction of PCC Retaining wall at RD. 1/620 to 1/632)

Estimated Cost:- 193386.00

Earnest Money :- 3900.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	20.28	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	5820.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	41.16	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	174518.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.96	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	7308.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
Total						193386.00

Draft schedule of quantity approved for Rs. 1,93,386/-

Executive Engineer,  
HPPWD Division,  
HPPWD Noida



(34)

DNI P.S. NO (417) for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R &amp; M/O Various roads under Chakkar Subdivision HPPWD Nerchowk.

(SH:- Trimming of grass and weeds and maintenance of drain from various roads under Nerchowk section.

Estimated Cost Rs. 99700.00

Earnest Money Rs. 2000.00

Time Limit One month

S.No.	Description of items	Qty	Rate in		Unit	Total Amount Inclusive of all Taxes
			In Figures	In Words		
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 complete including carriage of materials with in all leads and lifts and complete in all respect.	17000.00	Three rupees and fifty paise only	3.50	per square metre	59500.00
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 complete including carriage of material	12000.00	Three rupees and twenty paise only	3.35	RMT	40200.00
Total:						99700.00

Draft schedule of quantity approved for 99,700/- P



Assistant Engineer,  
B&R Subdivision,  
HPPWD Chakkar.

Executive Engineer,  
Division Nerchowk,  
HPPWD

(35)

## Draft Schedule of Quantity

Estimated Cost:- 326682.00  
 Earnest Money:-Rs. 6600.00  
 Time:- Two Months

Name of work:- Restoration of rain damages on Manjhyali Samloun Patha via Chalehar Safru road Km. 0/000 to 9/945.

Sub Head:- Construction of wire crated Retaining wall at RD.1/350 to 1/368.

Sr. No.	Description of item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	26.73 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	7672.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre) into one hundred millimetre mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	103.68 Cum.	2880.00	Rupees two thousand eight hundred eighty and paise nil only.	Per cubic metre	298598.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	19.44 Cum.	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	20412.00
				Total:-		326682.00

Draft schedule of quantity approved for Rs 326682/-  
 (Rupees three lac twenty six thousand six hundred eighty two) only.

Executive Engineer,  
 H.P.W.D. Division,  
 Noida

(36)

DMFS.No (98)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages due to laying of optical fibre cable on Ratti Dharwan Grenchia road km. 0/00 to 6/00. (SH:- Providing and laying cement concrete paver blocks at RD. 1/190 to 1/264)

Estimated Cost:- 493237.00

Earnest Money :- 9900.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.803.1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	4.44	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	25796.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentals and as per the entire satisfaction and direction of Engineer-in-Charge	22.79	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per cubic Metre	100458.00
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm ( fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (eighty millimetre) thick cement concrete paver block of M-30 (thirty) grade with approved colour, design pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	227.94	1610.00	Rupees One thousand six hundred ten and paise zero only	Per square Metre	366983.00
					Total	493237.00

Draft schedule of quantity approved for 4,93,237/-

Executive Engineer,  
HPPWD Division  
Nerchowk



(37)

DMP S.No. - (97)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R &amp; M/O Ratti to Kalkhar road km. 0/0 to 10/00. (SH:- Repair of Pot Holes in km. 0/0 to 1/00)

Estimated Cost:- 402012.00

Earnest Money :- 8100.00

Time :- One Month

S.N o	Description of item	Quantity	Time :- One Month		Unit	Amount
			Rate with all taxes including GST in			
			Rs.	P.		
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 63-45mm (Sixty three to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	39.54	2240.00	Rupees Two thousand two hundred forty and paise zero only.	Per Cubic Metre	88570.00
2	Providing, laying, spreading and compacting stone aggregate of sizes 53mm to 22.40mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	39.54	2290.00	Rupees Two thousand two hundred ninety and paise zero only	Per Cubic Metre	90547.00
3	Providing and applying a primer coat with bitumen emulsion (SS-I) on prepared surface of granular base cleaned of dust and extraneous material with hydraulic broom or any other approved equipment and spraying primer at the rate of 0.70-1.00 Kg./Sqm. (zero point seven zero to one point zero zero kilogram per square metre) using mechanical means as per technical specification clause 502 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	527.25	60.00	Rupees Sixty and paise zero only.	Per Square Metre	31635.00
4	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg./sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm.(One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	527.25	362.75	Rupees Three hundred sixty two and paise seventy five only.	Per Square Metre	191260.00
					Total	402012.00

Draft schedule of quantity approved for ₹ 4,02,012/-

Executive Engineer,  
RPPWD Division  
Nashik

(38)

D.M.P.S. NO. - 96

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Debari Ambe ka Ghar to Gajrehra Rathol km. 0/0 to 0/500. (SH:- C/O PCC Retaining wall at RD. 0/115 & 0/140) Under SCSP

Estimated Cost:- 398102.00

Earnest Money :- 8000.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	37.75	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	10834.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	85.75	4240.00	Rupees Four thousand two hundred forty and paise only.	Per Cubic Metre	363580.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.00	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	16800.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	24.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6888.00
					<b>Total</b>	<b>398102.00</b>

*Draft schedule of quantity approved for 2398102/P*

Executive Engineer,  
HPPWD Division  
HPPWD Narehok



(39)

DMP S.No. 99

## DRAFT SCHEDULE OF QUANTITY

Work of work:- Construction of Football Play Ground for Govt. Senior Secondary School Gagal Tehsil Baih District Mandi H.P. (SH:- C/O  
Football Play Ground) (Deposit work) Job No. 1

Estimated Cost:- 494301.00

Earnest Money :- 10000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.80	287.00	Rupees Two hundred eighty seven and paise zero only.	Per cubic Metre	8266.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm (Twenty millimetre) nominal size) including curing, form work, carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	19.84	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per cubic Metre	94637.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates, ramps and similar works within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	2290.00	120.00	Rupees One hundred twenty and paise zero only.	Per Kilogram	274800.00
4	Providing and fixing G.I. round pipe for Goal post complete within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	24.80	1388.70	Rupees One thousand three hundred eighty eight and paise seventy only.	Per Running metre	34440.00
5	Providing and fixing Spartan tournament football goal post net of superior quality complete within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	1.00	5800.00 MIR	Rupees Five thousand eight hundred and paise only.	Per Pair	5800.00
6	Laying 300mm (Three hundred millimetre) diameter Reinforced cement concrete pipe NP2/prestressed concrete pipe for drain but excluding excavation, protection works, back filling, concrete and masonry works in head walls and parapets with in all leads and lifts of Materials, carriage complete as per entire satisfaction and direction of Engineer-in-charge.	40.00	1334.60	Rupees One thousand three hundred thirty four and paise sixty only.	Per Running metre	53384.00
7	Earth filling of local earth (including royalty) by mechanical transport up to a lead of 5 km, including ramming and watering of the earth in layer not exceeding 20cm in trenches, plinth sides of foundation etc.	42.00	547.00	Rupees Five hundred forty seven and paise zero only.	Per cubic Metre	22974.00
					<b>Total</b>	<b>494301.00</b>

Draft schedule of quantity approved for Rs 4,94,301/- up

Executive Engineer  
HPPWD Division  
Narchowk



(40)

DNI F.S.M. (89)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Galma Manjhyali road km. 0/0 to 9/00. (SH:- Construction of Breast wall at RD. 7/615 to 7/630)

Estimated Cost:- 218534.00

Earnest Money :- 4400.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.80	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	4822.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	49.05	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	207972.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
					Total	218534.00

*Draft schedule of quantity approved for 2,18,534/-*

Executive Engineer,  
HPPWD Division,  
HPPWD Natchok

DMPS-NO (91)

# DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km. 184/600 to 198/050. (SH:- Repair and  
channelisation of culvert at RD. 192/510)

Estimated Cost:- 497487.00

Earnest Money :- 10000.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.50	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	13059.00
2	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	93.75	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	447188.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.00	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	31500.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical (to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
					Total	497487.00

Draft schedule of quantity approved for 24.97.437/60

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowak

(42)

DNI PS-NO (92)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages on Ratti Dharwan Grencha road km. 0/0 to 6/00.  
(Srl:- Construction of Retaining wall at RD. 1/090 to 1/108)

Estimated Cost:- 101645.00

Earnest Money :- 2100.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.34	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3255.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	20.25	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	85850.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.56	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	7938.00
4	Providing weep hole in brick masonry/ stone masonry / Plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	16.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	4592.00
Total						101645.00

*Draft schedule of quantity approved for 1,01,645/-*

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowki



(43)

DNI P S.No. 87

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD. 4/475 to 4/485)

Estimated Cost:- 161619.00

Earnest Money :- 3300.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	12.40	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3559.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.30	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	145432.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.20	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	8610.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	14.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	4018.00
					Total	161619.00

Draft schedule of quantity approved for 21.6.1919

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk

(44)

DM P.S. NO. 101

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Football Play Ground for Govt. Senior Secondary School Gagal Tehsil Balh District  
Mandi H.P. (SH:- C/O Football Play Ground) (Deposit work) Job No. 2

Estimated Cost:- 494159.00

Earnest Money :- 10000.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.80	287.00	Rupees Two hundred eighty seven and paise zero only.	Per cubic Metre	8266.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm (Twenty millimetre) nominal size) including curing, form work, carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	19.84	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per cubic Metre	94637.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates, ramps and similar works within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	2476.76	120.00	Rupees One hundred twenty and paise zero only.	Per Kilogram	297211.00
4	Providing and fixing G.I. round pipe for Goal post complete within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	29.28	1388.70	Rupees One thousand three hundred eighty eight and paise seventy only.	Per Running metre	40661.00
5	Laying 300mm (Three hundred millimetre) diameter Reinforced cement concrete pipe NP2/prestressed concrete pipe for drain but excluding excavation, protection works, back filling, concrete and masonry works in head walls and parapets with in all leads and lifts of Materials, carriage complete as per entire satisfaction and direction of Engineer-in-charge.	40.00	1334.60	Rupees One thousand three hundred thirty four and paise sixty only.	Per Running metre	53384.00
					Total	494159.00

Draft schedule of quantity approved for 4,94,159/-

Executive Engineer,  
HPPWD Division  
Nerchowk

# **DRAFT SCHEDULE OF QUANTITY**

Name of work:- RRD on Gutkar Behna Tikkar Malwana Badhyal road km. 0/00 to 5/510. (SH:- Construction of P.C.C. Retaining wall at RD. 1/775 to 1/785)

Estimated Cost:- 287415.00

Earnest Money :- 5800.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.90	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8294.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	62.90	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	266596.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	9.10	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	9555.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	10.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2870.00
					<b>Total</b>	<b>287415.00</b>

*Draft schedule of quantity approved for 22,87,415/-*

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk



DNIP S.No. 82

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Open Air Stadium for play ground at Govt. Sen. Sec. School Pairi, Tehsil Balh, Distt. Mandi (H.P.). Deposit work

Estimated Cost:- 475101.00

Earnest Money :- 9600.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in foundation trenches etc in earth work in all kinds of soil, such as pick work, pick jumper work, jumper blasting work, chiseling wedging out rocks including pumping or bailing out water upto all lifts, stacking the excavated soil not more than three metres clear from the edge of excavation and then returning the stacked soil in 15 cm (fifteen centimetres) layers when required in to plinth sides of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as desired with including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.80	287.00	Rupees Two hundred eighty seven and paise only.	Per Cubic Metre	8266.00
2	Providing and laying in position cement concrete 1:5:10 (one cement : five coarse sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding the cost of centering and shuttering all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.83	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	45919.00
3	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth as per the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.55	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per Cubic Metre	37688.00
4	Providing and laying in position plain cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 40 mm (forty millimetre) nominal size), including the cost of centering, shuttering, finishing and reinforcement all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	56.43	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	327858.00
5	Back filling with granular material behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.6 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.07	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	30524.00
6	Providing and laying Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor in all shapes and sizes in : Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.90	8165.00	Rupees Eight thousand one hundred sixty five and paise zero only.	Per Running Metre	7349.00
7	15 mm (Fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (One cement : Six sand) complete including carriage of material with in all leads and lift and as per the direction of the Engineer-in-charge.	191.33	91.45	Rupees Ninety one and paise forty five only.	Per Square Metre	17497.00
					Total	475101.00

Draft schedule of quantity approved for ₹ 4,75,101/-

Executive Engineer,  
HPPWD Division  
Nerchow

(47)

DN/P9-NO/- (85)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD. 7/071.50 to 7/083)

Estimated Cost:- 239573.00

Earnest Money :- 4800.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	20.36	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	5843.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	51.52	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	218445.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	9.09	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	9545.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
					Total	239573.00

*Draft schedule of quantity approved for 22,39,573/-*

Executive Engineer,  
HPPWD Division,  
HPPWD Nerkowk



48

DNIP S.No (90) for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti Meramasit Leda road km 0/0 to 14/580  
(SH:- Construction of PCC Breast wall at RD. 3/700 to 3/712)

Estimated Cost:- 96545.00

Earnest Money :- 2000.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	9.24	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1589.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	9.84	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2824.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	21.12	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	89549.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 814,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	9.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2583.00
					Total	96545.00

Draft schedule of quantity approved for 296,545/-

Executive Engineer,  
HPPWD Division,  
HPPWD Northward





50

DWP S.NO. 82

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 6.00 mtr span RCC slab culvert at RD. 2/135 on Galma Nalwari road km. 0/0 to 3/0. (Sub Head:- Construction of Nalwari side approaches at RD. 0/0 to 0/004 U/S). Both side (Under SCDP)

Estimated Cost:- Rs. 288334.00  
 Earnest Money :- Rs. 5800.00  
 Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	24.16	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	6934.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	55.92	4240.00	Rupees Four thousand two hundred forty and paise zero only	Per Cubic Metre	237101.00
3	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications 1204.3.8 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	25.92	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	27216.00
4	Construction of subgrade and earthen shoulders with approved materials obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m (one thousand meter) as per Technical Specification Clause 303.1, complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	42.34	267.90	Rupees Two hundred sixty seven and paise seventy only.	Per Cubic Metre	11343.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
					Total	288334.00

Draft schedule of quantity approved for Rs. 2,88,334/-

Executive Engineer,  
 HPPWD Division,  
 Nerchowk




(51)

D.N.F.S.NO! - (58)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of road from Kothi Thapla Bhout Sarharka Lagda Hawanoo Dhanoo Bag end C/O culvert on Gamoulti Khad Portion Kothi Thapla Bhout Km. 0/0 to 3/500 Under SCSP (SH:- Construction of 900mm dia Hume pipe culvert at RD. 1/350, with wing wall)							Estimated Cost:- 196601.00		Earnest Money :- 4000.00		
							Time : Two Months				
S N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount					
			Rs.	P.			In figure	In word			
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	37.63	287.00		Rupees Two hundred eighty seven and paise only.	Per Cubic Metre	10800.00				
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:6:12 (one cement : six sand : Twelve graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.75	3090.00		Rupees Three thousand ninety and paise zero only.	Per Cubic Metre	17768.00				
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry second sort in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	7.80	4134.00		Rupees Four thousand one hundred thirty four and paise zero only.	Per Cubic Metre	32245.00				
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 Rubble stone laid in cement mortar 1:3. (one cement : three sand) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	0.45	5110.00		Rupees Five thousand one hundred ten and paise zero only.	Per Cubic Metre	2300.00				
5	Providing and laying 900 mm (Nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excavation protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials and as per the entire satisfaction and direction of Engineer-in-Charge.	7.00	3550.00		Rupees Three thousand five hundred fifty and paise zero only.	Per Running metre	24850.00				
6	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704, 1202 & 1204 random rubble masonry second sort in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	15.52	3650.00		Rupees Three thousand six hundred fifty and paise zero only	Per Cubic Metre	56648.00				
7	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	1.08	4408.00		Rupees Four thousand four hundred eight and paise zero only.	Per Cubic Metre	4761.00				
8	Construction of dry rubble stone masonry as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.38	2100.00		Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	42798.00				
9	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 in Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	4.22	1050.00		Rupees One thousand fifty and paise zero only	Per Cubic Metre	4431.00				
						Total	196601.00				

Draft schedule of quantity approved for 2,96,601/-

  
Executive Engineer,  
HPPWD Division,  
Nerchowk.

Draft schedule of quantity approved for 2,19,66,601/-

Executive Engineer,  
HPPWD Division,  
Nerchowki.



(52)

DNI P.S. NO. (557)

DRAFT SCHEDULE OF QUANTITY

Name of work: A/R &amp; M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gaga) section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 252000/-

Earnest Money Rs. 5100/-

Time: -One Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240 hours	1050.00	Rupees one Thousand fifty only	Per hours	252000.00
Total:-						252000.00

Draft schedule of quantity approved for Rs 2,52,000/-

Assistant Engineer,  
Chakkar Sub Division,  
HPPWD Nerchowk.

Executive Engineer,  
Nerchowk Division,  
HPPWD Nerchowk.

53

DNIT S.No. 184 for the year 2023/24.

①

## DRAFT SCHEDULE OF QUANTITY

Major work:- A/R & M/O old NH-21 Chandigarh Mandi Manali road Km. 184/550 to 198/00. (SH:- Construction of PCC U-Shape drain at RD. 186/800 to 186/980)

Estimated Cost:- 495230.00

Earnest Money :- 10000.00

Time :- Two Months

S.No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	187.20	287.00	Rs. Two hundred eighty seven and paise zero only	Per cubic Metre	53726.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation/ Drain complete as per drawing and technical specification in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm (Twenty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	100.80	4380.00	Rs. Four thousand three hundred eighty and paise zero only	Per cubic Metre	441504.00
					<b>Total</b>	<b>495230.00</b>

Draft schedule of quantity approved for 2,49,523/-

Executive Engineer,  
HPPWD Division  
Nerchowk

(54)

DNI/8.ND/555

## DRAFT SCHEDULE OF QUANTITIES

Estimated Cost Rs. : 2,35,000/-only

Earnest Money Rs. : 5000/- only

Time: One month

Name of work:- A/R &amp; M/O various Bridge work under Chakkar Sub Division HPPWD Nerchowk

(SH:- Preparation of detailed working estimate for C/O 25.00 mtr span RCC Box Girder Bridge at Soyra Katon Nalwari Galma Khad under C/O 75.00 mtr span pretreed bridge over Suketi khad at Gutkar &amp; Behna on Gutkar Behna Road at Km. 0/300, Preparation of Hydraulic data for 25.00 mtr bridge on C/O road from Kothi Thapla Bhout Sararka Leda Hawanu Dhangu Bag road at RD 2/675 on Damodhi Khad Bridge)

Sr.No.	Description	Qty.	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In words		
1	Preparation of detailed working estimate of C/O 25.00 mtr span RCC Box Girder Bridge at Soyra Katon Nalwari Galma Khad and its approval from competent authority and checking of whole estimate manuscript / fair copy approved from the Circle Office & Chief office as per direction of engineer-in-charge.	1.000	60000.00	Rupees Sixty Thousand only	Job	60000.00
2	Preparation of detailed working estimate of C/O 75.00 mtr span pretreed bridge over Suketi khad at Gutkar & Behna on Gutkar Behna Road at Km. 0/300 and its approval from competent authority and checking of whole estimate manuscript / fair copy approved from the Circle Office & Chief office as per direction of engineer-in-charge.	1.000	60000.00	Rupees Sixty Thousand only	Job	60000.00
3	Site survey using total station for Preparation of Hydraulic data for 25.00 mtr bridge on C/O road from Kothi Thapla Bhout Sararka Leda Hawanu Dhangu Bag road at RD 2/675 on Damodhi Khad including Site survey using total station of proposed bridge site, cross section of the proposed bridge, cross section of 150m D/S and 150m U/S, Contour survey of bridge site for a required area, required length of approaches on each side, hydraulic particulars such as HFL, LWL, HTL, LTL, and discharge calculation with bridge alignment proposal. 3 sets of DPR containing the above detail shall be delivered on completion of work, as per direction of engineer-in-charge.	1.000	115000.00	Rupees One Lakh Fifteen Thousand only	Job	115000.00
					Total	235000.00

Draft schedule of quantity approved for 2,35,000/-

Executive Engineer  
 HP.PWD Division  
 Nerchowk-175008



(53)

DNIT B.ND <sup>23</sup> for the year 2024-25.

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road  
Km. 0/00 to 14/580. (SH:- Construction of PCC Retaining wall at RD. 7/060 to 7/071.50)

Estimated Cost:- 238982.00

Earnest Money :- 4800.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	23.36	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	6701.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	51.52	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	218445.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.71	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	8096.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
					Total	238982.00

*Draft schedule of quantity approved for 2,38,982/-*

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk

(56)

DRT SNO (76)

for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division, HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of Tractor with trolley for carriage of much debris and shifting of materials etc.)

Estimated Cost:- 99000.00

Earnest Money:- 2000.00

Time:- Two Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60.00	1650.00	Rupees One thousand six hundred fifty only.	Per day	99000.00
					Total:-	99000.00

Assistant Engineer,  
Chakkar Sub-Division  
H.P.W.D. Ner Chowk

Executive Engineer  
HPPWD Division  
Nerchowk

Amir  
IE

(57)

DNI P.S. No. 54

## DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Moramasit Leda road km. 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD. 6/940 to 6/955)

Estimated Cost:- 311453.00

Earnest Money :- 6300.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	31.65	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	9084.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	67.20	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	284928.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.05	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	10553.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	24.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6888.00
					Total	311453.00

Draft schedule of quantity approved for ₹3,11,453/-

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk



(58)

D.M.P.S.NO (64) for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of road from Chhol to Sanehra vill. Chawari km. 0/0 to 3/00. (SH:- Providing and laying WBM G-I &amp; G-III in Km. 1/500 to 1/900) Under SCDP


Estimated Cost:- 429825.00

Earnest Money :- 8600.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 90-45mm (Ninety to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	110.00	2190.00	Rupees Two thousand one hundred ninety and paise zero only.	Per Cubic Metre	240900.00
2	Providing, laying, spreading and compacting stone aggregate of sizes 53-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	82.50	2290.00	Rupees Two thousand two hundred ninety and paise zero only.	Per Cubic Metre	188925.00
					Total	429825.00

Draft schedule of quantity approved for 429,825/-

  
 Executive Engineer,  
 HPPWD Division  
 Nerchowk

(59)

DNIT S.No. (51) for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fibre cable on Ratti to Kalkhar road km. 0/00 to 10/00.  
(SH:- Construction of Retaining wall at RD. 3/525 to 3/540)


Estimated Cost:- 253591.00

Earnest Money :- 5100.00

Time :- Two Months

S.N o	Description of item	Quantity	Time :-Two Months		Unit	Amount
			Rate with all taxes including GST in			
			Rs. P.			
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.80	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8266.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:6:12 (one cement: six sand : twelve graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.35	3090.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	22712.00
3	Stone masonry in cement mortar in substructure complete as per drawing & technical specification clause 702,704,1202 and 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	27.21	3650.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	99317.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.00	4408.00	Rupees Four thousand four hundred eight and paise zero only	Per Cubic Metre	13224.00
5	Construction of dry rubble stone masonry for retaining and Breast walls as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.14	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	94794.00
6	Back filling with granular material behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	14.55	1050.00	Rupees One thousand fifty and paise zero only	Per Cubic Metre	15278.00
					Total	253591.00

Draft Schedule of quantity approved for ₹ 2,53,591/- only

  
 Executive Engineer,  
 HPPWD Division,  
 HPPWD, Nerkhwa

(60)

DNI 8-NO: 70 for the year 2024-25.

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of drain from the house of Smt. Pushpa Guleria to the house of Sh. Manish Kumar S/O Lt. Sh. Mohan Lal and Sh. Vijay Kumar house at Village Lunapani Ward No. 3. (Old NH -21)  
(SH:- C/O P.C.C drain at RD. 188 /197 to 188/234) Deposit work

Estimated Cost:- 94909.00

Earnest Money :- 2000.00

Time :- Two Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation of foundation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	35.52	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	10194.00
2	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:3:6 (One cement; three sand six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	17.76	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	84715.00
					Total	94909.00

Draft schedule of quantity approved for 94,909/-

Executive Engineer,  
HPPWD Division,  
HPPWD Nerkhwa



(61)

DNIF S.No. (74) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY							
Name of work:- RRD on various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Gagal Section)					Estimated Cost:-		105000.00
					Earnest Money:-		2100.00
					Time:- One month		
S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount	
			Figure	Words			
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	100.00	1050.00	Rupees One thousand fifty only.	Per hour	105000.00	
					Total	105000.00	
Draft schedule of quantity approved for 1,05,000/-							
Assistant Engineer Sub Division Chakkar HPPWD Nerchowk.			Executive Engineer HPPWD Division Nerchowk.				

(62)

DNIT S.NO. 70 for the year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- 466151.00

Earnest Money:-Rs. 9400.00

Time:- One Month

Name of work:- Restoration of rain damages on Kapahi to Jhor road Km. 0/000 to 2/500.

Sub Head:- Construction of wire crate wall for protection of abutment for valley bridge at RD 1/430 Jhor side.

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	15.30 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	4391.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	156.25 Cum.	2880.00	Rupees two thousand eight hundred eighty and paise nil only	Per cubic metre	450000.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.20 Cum.	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	11760.00
				Total:-		466151.00

Draft schedule of quantity checked and approved for  
Rs. 466151/- (Rupees four lac sixty six thousand one  
hundred fifty one) only

Executive Engineer,  
H.P.P.W.D. Division,  
Nerchowk

(63)

DNIPS NO (483)

**DRAFT SCHEDULE OF QUANTITY**

Name of work :- A/R and M/O various roads under Chakkar sub division HPPWD Nerchowk.

Estimated cost Rs. 1,48,500/-

Earnest Money Rs. 3,000/-

Time:- one month.

(SP) - Preparation of DPR/Detailed estimate for I>upgradation of Mandi Gagai Chailchowk Chattari Rana ka bag road km 0/0 to 16/190 under C&C, II>upgradation of Nerchowk Ratti Kalkhar road km 0/0 to 13/300 under NABARD, III> C/o Lakhwan Dahanu -Hawamu-Bhansot-Rathol-Andreta -Meramsit road km 0/0 to 5/600 under NABARD).

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Job work for preparation of revised DPR i/c computer typing and other necessary provision taken in estimate (four set computerized along with binding) and submission of the same to higher office for approval if any correction/amendments has desired by the head office, the same may be corrected as desired as per direction of Executive engineer Nerchowk Division, HPPWD Nerchowk.	3 No's	49,500.00	Rupees Forty Nine Thousand Five Hundred Only	Per Job	1,48,500.00
Total						1,48,500.00

*Draft schedule of quantity approved for 1,48,500/-*

Assistant Engineer,  
Chakkar Sub-Division  
H.P.P.W.D. Ner Chowk

Executive Engineer,  
Nerchowk Division  
H.P.P.W.D. Nerchowk



(64)

DRI/S.No] - 108

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti to Behal road km. 0/00 to 8/00. (SH:- Construction of P.C.C.  
Retaining wall at RD. 7/775 to 7/787)

Estimated Cost:- 313856.00

Earnest Money :- 6300.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	24.48	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	7026.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	68.04	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	288490.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	12.00	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	12600.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
Total						313856.00

Draft schedule of quantity approved for Rs 3,13,856/-

Executive Engineer,  
HPPWD Division,  
HPPWD Nerchowk

(65)

D.N.T. (115) For 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti Section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 273000/-  
Earnest Money Rs. 5460/-  
Time: - Two Month.

Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	260 hours	1050.00	Rupees one Thousand fifty only	Per hours	273000.00
					<b>Total:-</b>	273000.00

Assistant Engineer,  
Chakkar Sub Division,  
HPPWD Nerchowk.

Draft schedule of quantity checked & approved  
for Rs - 2,73,000/- only

Executive Engineer,  
Nerchowk Division,  
HPPWD Nerchowk.

(66)

DNIT S.NO. (66) For the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 424280.00

Earnest Money:- Rs. 8500.00

Time:- Two Months

Name of work:- Restoration of rain damages on Chahari School to Trambli Dehrigaloo Shil Kuntbhyo Gadwahan Doh road Km. 0/0 to 2/150.  
 Sub Head:- Repair of various Span R.C.C. slab culverts at RD. 0/435, 1/060 & 1/370.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : four graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	81.99 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only	Per cubic metre	391092.00
2	Providing and laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing walls, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204.3.8 complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	26.55 Cubic metre	1250.00	Rupees one thousand two hundred fifty and paise nil only.	Per cubic metre	33188.00
					Total:-	424280.00

Draft schedule of quantity checked and approved for Rs. 424280/- (Rupees four lac twenty four thousand two hundred eighty) only.

Executive Engineer,  
 HP PWD Division,  
 Nerchowk



67

DNIT S. No. (68) FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Name of work:- Restoration of rain damages on R.P.T.D. road Km. 0/000 to 10/000.  
Sub Head:- Construction of Retaining wall at R.D. 0/985 to 1/000.

Estimated Cost:- Rs. 326250.00  
Earnest Money:- Rs. 6600.00  
Time:- Two Months

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	38.55 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	11064.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	70.00 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	296800.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.95 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	11498.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	6888.00
					Total	326250.00

Draft schedule of quantity checked and approved  
for Rs. 326250/- (Rupees Three Lac Twenty Six Thousand  
Two Hundred Fifty) only.

Executive Engineer,  
H.P.P.W.D. Division,  
Nerchowk

(68)

DNIT NO. (118) FOR THE YEAR 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused by laying of optical fibre cable on Ratti Kalkhar road Km. 0/0 to 10/0. (SH:- Providing and laying WBM G-II, G-III and tarring in road side edges in km. 0/0 to 0/837)

Estimated Cost:- 473318.00

Earnest Money :- 9500.00

Time :- One Month

		Estimated Cost :- 473318.00				
		Earnest Money :- 9500.00				
		Time :- One Month				
S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	94.16	287.00	Rupees Two hundred eighty seven and paise zero only.	Per cubic metre	27024.00
2	Providing, laying, spreading and compacting stone aggregate of sizes 63-45mm (Sixty three to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	47.08	2240.00	Rupees Two thousand two hundred forty and paise zero only.	Per Cubic Metre	105456.00
3	Providing, laying, spreading and compacting stone aggregate of sizes 63-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	47.08	2290.00	Rupees Two thousand two hundred ninety and paise zero only.	Per Cubic Metre	107813.00
4	Providing and applying a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base created of dust and extraneous material with hydraulic broom or any other approved equipment and spraying primer at the rate of 0.70-1.00 Kg./Sq.m. (zero point seven zero to one point zero zero kilogram per square metre) using mechanical means as per technical specification clause 502 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	627.75	62.00	Rupees Sixty two and paise zero only.	Per Square Metre	38921.00
5	Providing and applying tack coat with bitumen emulsion (RS-1) on prepared dry and hungry bitumen surface cleaned of dust and extraneous material with Hydraulic brooms or any other approved equipment and spraying priming at the rate of 0.25 to 0.30 kg. (zero point two five to zero point three zero kilogram) per square metre with emulsion pressure distributor equipped for spraying uniformly complete as per technical specification clause 503 with in all leads lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	627.75	17.00	Rupees Seventeen and paise zero only.	Per Square Metre	10672.00
6	Providing, laying and rolling by mechanical means with bitumen (VG-10/S-90) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.0mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per Technical Specification Clause 508 including carriage of material within all leads, lifts and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	627.75	216.00	Rupees Two hundred sixteen and paise zero only.	Per Square Metre	135564.00
7	Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (VG-10/S-90) as per Technical Specification Clause 510 including carriage of material within all leads, lifts and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	627.75	76.20	Rupees Seventy six and paise twenty only.	Per Square Metre	47835.00
					Total	473318.00

Draft schedule of quantity checked & approved for  
Rs- 4,73,318.00/- onlyExecutive Engineer,  
HPPWD Division  
Noida



(69)

DNIT at Sr No 120 for the Year 2024-25,

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Pedestal for installation of statue of Martyar Sh. Tek Singh Mastana at Village- Sayanh,  
P.O.- Lohara Tehsil- Baih Distt. Mandi H.P.

Estimated Cost:- 133909.00

Earnest Money :- 2700.00

Time :- Two Months

			Earnest Money :- 2700.00			
			Time :- Two Months			
S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.00	192.20	Rupees One hundred ninety two and paise zero only.	Per Cubic Metre	577.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	0.60	5308.45	Rupees Five thousand three hundred eight and paise zero only.	Per Cubic Metre	3185.00
3	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802.803, 1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand: six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	3.17	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	15121.00
4	Boulder filling of selected hard dry stone hand packed tightly under floor as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts complete in all respect.	1.44	1309.40	Rupees One thousand three hundred and paise forty only.	Per Cubic Metre	1873.00
5	Brick work with common burnt clay F.P.S. Non modular bricks of class designation 7.5 (Seven point five) in foundation, plinth and super structure in all shapes and sizes in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.40	8886.30	Rupees Eight thousand eight hundred sixty six and paise thirty only.	Per cubic metre	30145.00
6	Providing and laying in position in concrete of specified grade excluding the cost of centering and shuttering all work to plinth level 1:2:4 (One cement : two coarse sand: four graded stone aggregate 20mm (Twenty millimetre) nominal size including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.87	7701.55	Rupees Seven thousand seven hundred one and paise fifty five only.	Per cubic metre	6700.00
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete including cost of binding wire upto all floor level. Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	50.00	88.25	Rupees Eighty eight and paise twenty five only.	Per Kilogram	4413.00
8	6mm (Six millimetre) cement plaster of mix 1:3 (one cement : three fine sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.25	223.40	Rupees Two hundred twenty three and paise forty only.	Per square metre	1622.00



9	Steel work welded in built up section/ framed work including cutting, holsting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. in grating frames, guard bar, ladder railing, brackets, gates and similar work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	77.44	106.10	Rupees One hundred six and paise ten only.	Per Kilogram me	8216.00
10	Providing and fixing 0.60mm ( Zero point sixty millimeter) thick pre-painted steel sheet of TATA/ DUROSHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 ( Twenty ) micron over 5 ( Five ) microns primer coating to back coat of polyester of 5 ( Five ) microns over 5 ( Five ) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts, 6mm diameter with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00	1448.85	Rupees One thousand four hundred forty eight and paise eighty five only.	Per square metre	7244.00
11	Providing and laying Galvanized chain 6mm (six millimetre) thick round the pedestal as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts complete in all respect.	37.20	126.20	Rupees One hundred twenty six and paise twenty only.	Per Running metre	4695.00
12	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (Eighteen millimetre) thick stone slab over 20 mm (Twenty millimetre) (average) thick base of cement mortar 1:4 (one cement : four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.41	3350.75	Rupees Three thousand three hundred fifty and paise seventy five only.	Per square metre	48264.00
13	Providing and laying 60mm (Sixty millimetre) thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (Fifty millimetre) thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete including carriage of material within all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	1.21	1280.00	Rupees One thousand two hundred eighty and paise zero only.	Per square Metre	1549.00
14	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.80 ltr/ 10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eight zero litre per ten square metre) of approved brand and manufacture including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.00	95.00	Rupees Ninety five and paise zero only.	Per square metre	285.00
					Total	133909.00

draft schedule of quantity checked &  
 Approved for Rs-133909.00/- (Rupees - one lakh  
 Thirty three thousand Nine hundred Nine) only.

Executive Engineer,  
 HPPWD Division,  
 HPPWD Nerchowk

(70)

D.N.I.T. No. 122 for the year 2024-25

Draft Schedule of Quantity

Name of Work: - A/R & M/O Various road in under Chakkar Sub Division HPPWD Nerchowk  
(SH: - Providing & fixing dual directional retro reflective cat-eyes studs) (Gagal Section)

Estimated Cost:- 217350/-  
Earnest Money:-4400/-  
Time: - 15 days

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			Figure	Words		
1	Providing & fixing dual directional retro reflective cat-eyes studs made from high quality colour less retro reflective mini board embedded to 6mm high (Six millimeter impact plastic eyes of dia. 16mm (16 millimeter) containing 7(seven) beads to each thus making a total of 42(forty two) beads housed on both sides in a strong aluminum casted stud size 10x10 cm (ten x ten centimeter) provided with a mild steel zinc plated nail of dia 12mm (twelve millimeter ) for fixing to roads by hammering made green/lite only including carriage of material within all leads and lifts complete including entire satisfaction of Engineer-in-charge.	630	345	Rupees Three Hundred & Forty Five only	Each	217350.00
					<b>Total:-</b>	<b>217350.00</b>

*Draft schedule of quantity checked &  
Approved for Rs. 2,17,350/- only*

*[Signature]*  
Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk

(71)

DNIT S.NO. (75) for the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:-Rs. 231000.00

Earnest Money:-Rs 4700.00

Time:- 220 Hrs

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar, (Leda Section)  
 Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor. Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	220.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	231000.00
				Total:-		231000.00

## Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 231000/- (Rupees two lac thirty one thousand) only.

Assistant Engineer,  
 Rewalsar Sub-Division,  
 HP.PWD. Rewalsar.

Executive Engineer  
 H.P.W.D. Division  
 Narehok-175008



(72)

D.N.I.T. No. (123) for the year 2024-25

Draft Schedule of Quantity

Name of Work: - A/R & M/O Various road in under Chakkar Sub Division HPPWD Nerchowk  
 (SH: - Providing & fixing dual directional retro reflective cat-eyes studs) (Gagal Section)

Estimated Cost:- 217350/-  
 Earnest Money:-4400/-  
 Time: - 15 days

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			Figure	Words		
1	Providing & fixing dual directional retro reflective cat-eyes studs made from high quality colour less retro reflective mini board embedded to 6mm high (Six millimeter impact plastic eyes of dia. 16mm (16 millimeter) containing 7(seven) beads to each thus making a total of 42(forty two) beads housed on both sides in a strong aluminum casted stud size 10x10 cm (ten x ten centimeter) provided with a mild steel zinc pladed nail of dia 12mm (twelve millimeter ) for fixing to roads by hammering made green/lite only including carriage of material within all leads and lifts complete including entire satisfaction of Engineer-in-charge.	630	345	Rupees Three Hundred & Forty Five only	Each	217350.00
					<b>Total:-</b>	<b>217350.00</b>

*Draft schedule of quantity checked & approved  
 for ₹- 2,17,350.00/- only*

Executive Engineer  
 Nerchowk Division  
 HPPWD Nerchowk

73

DNIT S.NO. (76) for the Year 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 248400.00

Earnest Money:- Rs. 5000.00

Time:- One month

Name of work:- Annual repair and maintenance of R.P.T.D. road Km. 0/0 to 10/0.

Sub Head:- Providing and fixing dual directional retro reflective cat-eyes studs.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing dual directional retro reflective cat eyes studs made from high quality colour less retro reflective mini board embedded to 6mm (six millimetre) high impact plastic eyes of diameter 16mm (sixteen millimetre) containing 7 (seven) beads to each thus making a total of 42 (forty two) beads housed on both sides in a strong aluminium casted stud size 10 x10cm (ten into ten centimetre) provided with a mild steel zinc plated nail of diameter 12mm (twelve millimetre) for fixing to roads by hammering made green/lite only including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.	720.00 Nos.	345.00	Rupees three hundred forty five and paise nil only	Each	248400.00
				Total:-		248400.00

Draft schedule of quantity checked and approved for Rs. 248400/- (Rupees two lac forty eight thousand four hundred) only.

Assistant Engineer  
Rewalsar Sub-Division  
HPPWD Rewalsar

Executive Engineer,  
Nerchowk Division,  
HP.PWD. Nerchowk

(74)

DNIT NO. FOR THE YEAR 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work: - RRD on various roads under Chakkar Sub Division, H.P.PWD, Nerchowk (Gagal Section)

(SH:- Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.

Estimated Cost Rs.99000/-  
Earnest Money Rs.2000 /-  
Time: -Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily, any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60 days	1650.00	Rupees one thousand Six Hundred Fifty only	Per Days	99000.00
					Total -	99000.00

Assistant Engineer,  
Chakkar Sub Division,  
HPPWD Nerchowk.Draft Schedule of quantity checked & approved  
for Rs. 99,000/- Only.Executive Engineer  
Nerchowk Division,  
HPPWD Nerchowk



(75)

DNIT S.No.

for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 276150/- ✓

Earnest Money Rs. 5600/- ✓

Time: -Two Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	263 hours	1050.00	Rupees one Thousand fifty only	Per hours	276150.00
Total:-						276150.00

Assistant Engineer,  
Chakkar Sub Division,  
HPPWD Nerchowk.

Draft schedule of quantity checked and approved for  
Rs. 276150/- (Rupees two lac seventy six thousand one  
hundred fifty) only

Executive Engineer,  
Nerchowk Division,  
HPPWD Nerchowk.

(76)

DNIT NO 37 FOR THE YEAR 2024-25

## Draft Schedule of Quantity

Estimated Cost:- Rs. 401691.00  
 Earnest Money:- Rs. 8100.00  
 Time:- Two Months

Name of work:- Restoration of rain damages on Kalkhar Leda Sundemagar road Km. 0/000 to 13/600.  
 Sub Head:- Construction of Retaining wall at R.D. 6/650 to 6/658.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	28.98 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	8317.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203, Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	87.19 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	369686.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.26 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10773.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	45.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	12915.00
					Total	401691.00

Draft schedule of quantity approved for  
 Rs. 4,01,691/- (Rupees Four Lac One Thousand  
 Six Hundred Ninety One) only.

Executive Engineer,  
 H.P.P.W.D. Division,  
 Nerchowk



(77)

DNIT S.NO. (168) for the year 2023-24

## Draft Schedule of Quantity

Estimated Cost:- Rs. 268718.00  
 Earnest Money:- Rs. 5400.00  
 Time:- Two Months

Name of work:- Restoration of rain damages on Rewalsar Sararidhar road Km. 0/000 to 6/800.  
 Sub Head:- Construction of Retaining wall at R.D. 4/980 to 4/988

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	39.04 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	11204.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	57.88 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	245411.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	6.88 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	7224.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	17.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4879.00
					Total	268718.00

Draft schedule of quantity approved for Rs. 268718/-  
 (Rupees two lac sixty eight thousand seven hundred eighteen) only.

Executive Engineer,  
 H.P.P.W.D. Division,  
 Nalchawki, D.D.



78

DNIF SNO

104

for the year 2024-25

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sishal Trambi road at RD. 0/085. (Sub Head:- Construction of wing wall at RD. 0/10 to 0/24 U/S Chandyal side).

Estimated Cost:- Rs. 485102.00

Earnest Money :- Rs. 9800.00

Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	37.52	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	10768.00
2	Providing and laying concrete Mechanically mixed and vibrated 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material with in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	102.20	4240.00	Rupees Four thousand two hundred forty and paise zero only	Per Cubic Metre	433328.00
3	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications 1204.3.8 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-In Charge.	33.04	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	34692.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	22.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6314.00
					Total	485102.00

Draft schedule of quantity approved for 24,85,102/-

Executive Engineer,  
HPPWD Division,  
Nerchowk

79

D.M.P.S. No. (111)

## DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhangrotu Nauru Tikari road km. 0/00 to 4/400. (SH:- Construction of P.C.C. Retaining wall at RD. 0/110 to 0/160)

Estimated Cost:- 384312.00

Earnest Money :- 7700.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In figure In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	41.50	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	11914.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	82.00	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	347680.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	14.25	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	14963.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	34.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	9758.00
Total						384312.00

*Draft schedule of quantity approved for 23,84,312/-*

Executive Engineer,  
HPRWD Division,  
HPRWD Nerchowk