

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2024-25-

6499-6501 Dated:- 26/7/24

To


The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 21.08.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 17.08.2024 upto 1.00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Padhar Nahuli road Km 0/0 to 14/500. (SH:- Construction of Retaining wall at R.D. 8/590 to 8/602)	4,22,113.79	8,400/-	350/-	One month
2	Working estimate for the Construction of Govt. Senior Secondary School Building at Baggi Distt. Mandi (H.P.) (SH:- Preparation of Working estimate for C/O Building portion with W.S. & S.I. , Septic Tank, RWHT & Site Development etc.)	1,29,500.00	2,600/-	350/-	One month
3	Working estimate for the Construction of Govt. Senior Secondary School Building at Gharan Distt. Mandi (H.P.) (SH:- Preparation of Working estimate for C/O Building portion with W.S. & S.I. , Septic Tank, RWHT & Site Development and Approach road etc.)	1,73,900.00	3,500/-	350/-	One month
4	Restoration of rain damages on Shegali Prasher road in Km 0/00 to 22/510. (SH:- Construction of C.C. Retaining wall over wire crate Retaining wall at R.D. 12/080 to 12/084)	3,98,745.56	8,000/-	350/-	One month
5	Restoration of rain damages on Shegali Prasher road in Km 0/00 to 22/510. (SH:- Construction of C.C. Retaining wall over wire crate Retaining wall at R.D. 12/084 to 12/088)	3,98,745.56	8,000/-	350/-	One month
6	Restoration of rain damages on Nandal Arnehar road at Km 0/00 to 11/510. (SH:- Construction of Retaining wall at R.D. 8/096 to 8/104)	1,78,688.45	3,600/-	350/-	One month
7	Restoration of rain damages on Link road from NH-154 to Bazir Ka Baag in Km 0/00 to 2/00. (SH:- Construction of Breast wall at R.D. 0/165 to 0/169)	2,48,640.96	5,000/-	350/-	One month
8	Restoration of rain damages on Junction Point of Uhl Valley road an Upper Bhiuli to Lower Bhiuli road in Km 0/0 to 10/00. (SH:- Construction of Retaining wall at RDs from 0/480 to 0/492)	2,54,049.19	5,100/-	350/-	One month

9	Restoration of rain damages on Ghatasani Jhatingri Tikkan Barot road in Km 0/0 to 25/00. (SH:- Construction of Retaining wall at R.D. 22/540 to 22/546)	1,99,572.85	4,000/-	350/-	One month
10	Restoration of Rain damages on Baragoun Bah Padwahan road Km 11/0 to 26/00. (SH:- Repair of pot holes in Km 11/00 to 19/00).	1,85,150.23	3,700/-	350/-	One month
11	Annual repair and maintenance of Padhar Nauhali road Km 0/0 to 14/500. (SH:- Providing and Laying G-III for correction and premix carpet and premix carpet at R.D. 11/500 to 13/500)	4,19,399.28	8,400/-	350/-	One month
12	Annual repair and maintenance of Padhar Nauhali road Km 0/0 to 14/500. (SH:- Providing and Laying G-III for correction and premix carpet and premix carpet at R.D. 13/500 to 14/500)	4,21,456.89	8,400/-	350/-	One month
13	Construction of Urla Kotropi Chukku Khajari road in Km 0/0 to 9/00. (SH:- Construction of Retaining wall at RD's from 11/326.65 to 11/333.80)	3,50,438.47	7,000/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD., at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 422113.79
 Earnest Money Rs:- 8400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of work :- Restoration of rain damages on Padhar Nahuli road Km. 0/0 to 14/500. (Sub Head:- Construction of Retaining wall at R.D. 8/590 to 8/602).
Contract No. :
Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	32.76	Per cubic metre	491.80	16111.37	Rupees Sixteen Thousand One Hundred Eleven and Paise Thirty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	80.09	Per cubic metre	4782.20	383006.40	Rupees Three Lakh Eighty Three Thousand Six and Paise Forty Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.60	Per cubic metre	1472.70	18556.02	Rupees Eighteen Thousand Five Hundred Fifty Six and Paise Two Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	277.50	4440.00	Rupees Four Thousand Four Hundred Forty Only
Total in figure :					422113.79	Rupees Four Lakh Twenty Two Thousand One Hundred and Paise Seventy Nine Only
Total in Words :		Rupees Four Lakh Twenty Two Thousand One Hundred and Paise Seventy Nine Only				


 Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

Percentage Rate Bill of Quantity

Estimated Cost:- 129500.00
 Earnest Money:- 2600.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.					
Name of work:- Working Estimate for the Construction of Govt. Senior Secondary School Building at Baggi, Distt. Mandi (H.P.). (Sub Head: Preparation of Working estimate for C/O Building portion with W.S.& S.I, Septic Tank, RWHT & Site Development etc.)					
Contact No. :					
Bidder Name:					
SCHEDULE OF WORKS					
Sr. No.	Description of item	Qty.	Rate in Figure	Excluding GST Rs. P. in Words	Units Amount
1	Preparation of Working estimate of whole project as per Architectural Drawing for the Construction of Govt. Senior Secondary School Building at Baggi, Distt. Mandi (H.P.) including Building portion with W.S.& S.I, Septic Tank, RWHT & Site Development etc... The Job shall also include supplying detailed estimate as per analysis of rates based on HPSR 2020/market rates for all the items appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office/Circle office/CE office (MZ) Mandi complete as per directions of Engineer-in-charge.	1.00	129500.00	Rupees One Lakh Twenty Nine Thousand Five Hundred Only	Per Job 129500.00
Total In figure :					Total 129500.00
Total In Words :			Rupees One Lakh Twenty Nine Thousand Five Hundred Only		

Executive Engineer
 Mandi Division no 1
 HPPWD at Padhar

Percentage Rate Bill of Quantity

Estimated Cost:- 173900.00
 Earnest Money:- 3500.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.

Name of work: - Working Estimate for the Construction of Govt. Senior Secondary School Building at Ghran, Distt. Mandi (H.P.) (Sub Head: Preparation of Working estimate for C/O Building portion with W.S.& S.I, Septic Tank, RWHT, Site Development and Approach road etc.).

Contact No. :

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Description of item	Qty.	Rate Excluding GST Rs. P.		Units	Amount
			in Figure	in Words		
1	reparation of Working estimate of whole project as per Architectural Drawing for the Construction of Govt. Senior Secondary School Building at Gharan, Distt. Mandi (H.P.) including Building portion with W.S.& S.I, Septic Tank, RWHT, Site Development and Approach road etc.. The Job shall also include supplying detailed estimate as per analysis of rates based on HPSR 2020/market rates for all the items. appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office / Circle office/CE office (MZ) Mandi complete as per directions of Engineer-in-charge.	1.00	173900.00	Rupees One Lakh Seventy Three Thousand Nine Hundred Only	Per Job	173900.00
Total In figure :					Total	173900.00

Total In Words :

Rupees One Lakh Seventy Three Thousand Nine Hundred Only

Executive Engineer
 Mandi Division no I
 HPPWD at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 398745.56
Earnest Money Rs:- 8000.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on Shegali Prasher road in Km. 0/00 to 22/510. (Sub Head: - Construction of C.C Retaining wall over wire crate Retaining wall at R.D. 12/080 to 12/084).						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.68	Per cubic metre	491.80	9678.62	Rupees Nine Thousand Six Hundred Seventy Eight and Paise Sixty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.20	Per cubic metre	4593.40	239775.48	Rupees Two Lakh Thirty Nine Thousand Seven Hundred Seventy Five and Paise Forty Eight
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.68	Per cubic metre	1472.70	11310.34	Rupees Eleven Thousand Three Hundred Ten and Paise Thirty Four Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	274.00	2192.00	Rupees Two Thousand One Hundred Ninety Two Only
	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	57.60	Per cubic metre	2357.45	135789.12	Rupees One Lakh Thirty Five Thousand Seven Hundred Eighty Nine and Paise Twelve Only
Total in figure :					398745.56	Rupees Three Lakh Ninety Eight Thousand Seven Hundred Forty Five and Paise Fifty Six Only
Total in Words :		Rupees Three Lakh Ninety Eight Thousand Seven Hundred Forty Five and Paise Fifty Six Only				


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 398745.56
 Earnest Money Rs:- 8000.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain Damages on Shegali Prasher road in Km. 0/00 to 22/510. (Sub Head: - Construction of C.C Retaining wall over wire crate Retaining wall at R.D. 12/084 to 12/088).

Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.68	Per cubic metre	491.80	9678.62	Rupees Nine Thousand Six Hundred Seventy Eight and Paise Sixty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.20	Per cubic metre	4593.40	239775.48	Rupees Two Lakh Thirty Nine Thousand Seven Hundred Seventy Five and Paise Forty Eight
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.68	Per cubic metre	1472.70	11310.34	Rupees Eleven Thousand Three Hundred Ten and Paise Thirty Four Only
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	274.00	2192.00	Rupees Two Thousand One Hundred Ninety Two Only
5	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	57.60	Per cubic metre	2357.45	135789.12	Rupees One Lakh Thirty Five Thousand Seven Hundred Eighty Nine and Paise Twelve Only
Total in figure :					398745.56	Rupees Three Lakh Ninety Eight Thousand Seven Hundred Forty Five and Paise Fifty Six Only
Total in Words :		Rupees Three Lakh Ninety Eight Thousand Seven Hundred Forty Five and Paise Fifty Six Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 178688.45
Earnest Money Rs:- 3600.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain Damages on Nandal Arnehar road at Km. 0/00 to 11/510. (Sub Head: - Construction of Retaining wall at R.D. 8/096 to 8/104).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.56	Per cubic metre	491.80	12078.61	Rupees Twelve Thousand Seventy Eight and Paise Sixty One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.07	Per cubic metre	4529.80	154330.29	Rupees One Lakh Fifty Four Thousand Three Hundred Thirty and Paise Twenty Nine Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.76	Per cubic metre	1472.70	8482.75	Rupees Eight Thousand Four Hundred Eighty Two and Paise Seventy Five Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.00	Each	271.20	3796.80	Rupees Three Thousand Seven Hundred Ninety Six and Paise Eighty Only
Total in figure :					178688.45	Rupees One Lakh Seventy Eight Thousand Six Hundred Eighty Eight and Paise Forty Five Only
Total in Words :					Rupees One Lakh Seventy Eight Thousand Six Hundred Eighty Eight and Paise Forty Five Only	

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 248640.96
Earnest Money Rs:- 3600.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on Link road from NH-154 to Bazir ka Baag in Km. 0/00 to 2/00. (Sub Head:- Construction of Breast wall at R.D. 0/165 to 0/169).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	39.60	Per cubic metre	491.80	19475.28	Rupees Nineteen Thousand Four Hundred Seventy Five and Paise Twenty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	49.44	Per cubic metre	4537.00	224309.28	Rupees Two Lakh Twenty Four Thousand Three Hundred Nine and Paise Twenty Eight Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	269.80	4856.40	Rupees Four Thousand Eight Hundred Fifty Six and Paise Forty Only
Total in figure :					248640.96	Rupees Two Lakh Forty Eight Thousand Six Hundred Forty and Paise Six Only
Total in Words :					Rupees Two Lakh Forty Eight Thousand Six Hundred Forty and Paise Ninety Six Only	


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 254049.19
Earnest Money Rs:- 5100.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP PWD, at Padhar.						
Name of work :- Restoration of rain Damages on Junction Point of Uhl Valley road and Upper Bhiuli to Lower Bhiuli road in Km. 0/00 to 10/00. (Sub Head: - Construction of Retaining wall at RD's from 0/480 to 0/492).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.04	Per cubic metre	491.80	14281.87	Rupees Fourteen Thousand Two Hundred Eighty One and Paise Eighty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	48.13	Per cubic metre	4561.70	219554.62	Rupees Two Lakh Nineteen Thousand Five Hundred Fifty Four and Paise Sixty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	270.60	3247.20	Rupees Three Thousand Two Hundred Forty Seven and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.52	Per cubic metre	1472.70	16965.50	Rupees Sixteen Thousand Nine Hundred Sixty Five and Paise Fifty Only
Total in figure :					254049.19	Rupees Two Lakh Fifty Four Thousand Forty Nine and Paise Nineteen Only
Total in Words :		Rupees Two Lakh Fifty Four Thousand Forty Nine and Paise Nineteen Only				

Executive Engineer,
Mandi Division No. I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 199572.85
Earnest Money Rs:- 4000.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on Ghatasani Jhatingri Tikkan Barot road in Km. 0/00 to 25/00. (Sub Head: - Construction of Retaining wall at R.D. 22/540 to 22/546).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.04	Per cubic metre	491.80	6413.07	Rupees Six Thousand Four Hundred Thirteen and Paise Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.33	Per cubic metre	5015.60	182216.75	Rupees One Lakh Eighty Two Thousand Two Hundred Sixteen and Paise Seventy Five Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.64	Per cubic metre	1472.70	8306.03	Rupees Eight Thousand Three Hundred Six and Paise Three Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	Each	293.00	2637.00	Rupees Two Thousand Six Hundred Thirty Seven Only
Total in figure :					199572.85	Rupees One Lakh Ninety Nine Thousand Five Hundred Seventy Two and Paise Eighty Five Only
Total in Words :					Rupees One Lakh Ninety Nine Thousand Five Hundred Seventy Two and Paise Eighty Five Only	


Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 185150.23
 Earnest Money Rs:- 3700.00
 Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of Rain Damages on Baragoun Bah Padwahan road Km. 11/00 to 26/00. (Sub Head:- Repair of pot holes in km. 11/00 to 19/00.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	12.50	Per cubic metre	2403.90	30048.75	Rupees Thirty Thousand Forty Eight and Paise Seventy Five Only
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	479.30	Per square metre	323.60	155101.48	Rupees One Lakh Fifty Thousand One Hundred and Paise Forty Eight Only
Total in figure :					185150.23	Rupees One Lakh Eighty Five Thousand One Hundred Fifty and Paise Twenty Three Only
Total in Words :		Rupees One Lakh Eighty Five Thousand One Hundred Fifty and Paise Twenty Three Only				

Executive Engineer,
 Mandi Division No. I
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 419399.28
Earnest Money Rs:- ~~84~~ 00.00
Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Annual repair and maintenance of Padhar Nauhali road Km. 0/0 to 14/500. (Sub Head:- Providing and Laying G-III for correction and premix carpet at R.D. 11/500 to 13/500).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing, laying, spreading and compacting stone aggregates by mechanical/ manual means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	14.99	Per cubic metre	2739.20	41060.61	Rupees Forty Thousand Sixty and Paise Sixty One Only
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Note:- Bitumen will be procured by the department.)	1225.19	Per square metre	308.80	378338.67	Rupees Three Lakh Seventy Eight Thousand Three Hundred Thirty Eight and Paise Sixty Seven Only
Total in figure :					419399.28	Rupees Four Lakh Nineteen Thousand Three Hundred Ninety Nine and Paise Eight Only
Total in Words :		Rupees Four Lakh Nineteen Thousand Three Hundred Ninety Nine and Paise Twenty Eight Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 421456.89
Earnest Money Rs:- 8400.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP. PWD. at Padhar.						
Name of work :- Annual repair and maintenance of Padhar Nauhali road Km. 0/0 to 14/500. (Sub Head:- Providing and Laying G-III for correction and premix carpet at R.D. 13/500 to 14/500).						
SCHEDULE OF WORKS						
Contract No. :						
Bidder Name :						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing, laying, spreading and compacting stone aggregates by mechanical/ manual means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	20.28	Per cubic metre	2720.20	55165.66	Rupees Fifty Thousand One Hundred Sixty Five and Paise Sixty Six Only
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Note:- Bitumen will be procured by the department.)	1188.10	Per square metre	308.30	366291.23	Rupees Three Lakh Sixty Six Thousand Two Hundred Ninety One and Paise Twenty Three Only
Total in figure :					421456.89	Rupees Four Lakh Twenty One Thousand Four Hundred Fifty Six and Paise Eighty Nine Only
Total in Words :		Rupees Four Lakh Twenty One Thousand Four Hundred Fifty Six and Paise Eighty Nine Only				


Executive Engineer,
Mandi Division No-1,
HP. PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 350438.47
 Earnest Money Rs:- 7000.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.						
Name of work :- Construction of Urla Kotropi Chukku Khajari road in Km. 0/00 to 9/00. (Sub Head: - Construction of Retaining wall at RD's from 11/326.65 to 11/333.30).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.79	Per cubic metre	491.80	14158.92	Rupees Fourteen Thousand One Hundred Fifty Eight and Paise Ninety Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.24	Per cubic metre	5150.00	320536.00	Rupees Three Lakh Twenty Thousand Five Hundred Thirty Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.00	Each	285.10	3991.40	Rupees Three Thousand Nine Hundred Ninety One and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.98	Per cubic metre	1472.70	11752.15	Rupees Eleven Thousand Seven Hundred Fifty Two and Paise Fifteen Only
Total in figure :					350438.47	Rupees Three Lakh Fifty Thousand Four Hundred Thirty Eight and Paise Forty Seven Only
Total in Words :					Rupees Three Lakh Fifty Thousand Four Hundred Thirty Eight and Paise Forty Seven Only	


 Executive Engineer,
 Mandi Division No. I,
 HP, PWD, at Padhar