

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed item rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP, for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **24.08.2024 up to 11.00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **23.08.2024 up to 4.00 P.M.** and the application for issue of tender form shall be received on **22.08.2024 up to 4.00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time Allowed
	2	3	4	5	6	
1	R/R damages on Forest coloney to chikhar pump house road km 0/0 to 6/400(SH:-C/o B/wall at RD 2/651.60 to 2/661.50 2/641.20 to 2/651.60 and 2/240 to 2/255)	Theog	4,68,980/-	9,400/-	350/-	One Month
2	R/R of rain damages on Powach to Dharmai road km 0/0 to 8/400 (SH:-C/o R/wall at RD 2/970 to 2/990) Balance work.	Theog	2,63,361/-	5,300/-	350/-	One Month
3	R/R of rain damages on Forest Coloney to Chikhar pump house road Km/Rd 0/0 to 6/400 (SH:-C/o R/wall at RD 5/697.50 to 5/708.20)	Theog	4,90,646/-	9,900/-	350/-	One Month
4	A/R & M/O on various roads under Sainj Sub-Division (SH:- Providing and Laying WBM G-III in various roads (Patch work)	Theog	2,00,440/-	4,050/-	350/-	One Month
5	R/R of rain damages on various roads under Theog Sub-Division (SH:-Hiring of JCB for removal of slips in various roads.)	Theog	99,750/-	2,000/-	350/-	One Month
6	R/R of rain damages on various roads under Theog Sub-Division (SH:-Hiring of JCB for removal of slips in various roads.)	Theog	96,600/-	2,000/-	350/-	One Month

7	Repair and maintenance of rest house at Sainj (SH:- Repair of bath/W.C with tile work and sanitary fitting etc.)	Theog	1,34,371/-	2,700/-	350/-	One Month
8	R/R damages on Thanola Nallaha to Kiri road Km 0/0 to 2/500 (SH:-C/o PCC R/wall at RD 0/315 to 0/323.)	Theog	4,93,489/-	9,900/-	350/-	One Month
9	R/R of rain damages on Sarion to Gowai via Bhalech Jadeog road Km 0/0 to 5/0 (SH:- Widening of sharp/blind curve at Km/Rd 1/705 to 1/740 0/705 to 0/735 and edging at Km/Rd 0/850 to 0/875)	Theog	2,48,071/-	5,000/-	350/-	One Month
10	R/R of rain damages on Devgarh Jarai Manlog road Km 0/0 to 6/500 (SH:- C/o PCC R/wall at RD 1/750 to 1/762 and 1/770 to 1/775.)	Theog	4,08,708/-	8,200/-	350/-	One Month
11	A/R & M/o on Chhailla Shalowa road km 0/0 to 6/500 (SH:-C/o PCC R/wall at RD 5/510 to 5/525.)	Theog	4,95,296/-	10,000/-	350/-	One Month
12	C/o approach road to PHC building at Ghorna (SH:-C/o PCC R/wall at RD 0/045 to 0/060.)	Theog	4,24,237/-	8,500/-	350/-	One Month
13	R/R of rain damages on Ghorna to Deothi road km 0/0 to 5/435 (SH:- C/O PCC R/wall at RD 5/180 to 5/194.)	Theog	4,93,412/-	9,900/-	350/-	One Month
14	Construction of link road from Forest coloney Theog to Bharana Km 0/0 to 1/199 (SH:- FCA online on the parivash portal version-2 i/c preparation of digital ap, KML files etc.)	Theog	95,000/-	1,900/-	350/-	One Month
15	A/R & M/o on approach road at rest house Sainj (SH:- C/o PCC edging R/wall at RD 0/050 to 0/065 & C/o V-shape drain Back side of Rest house.)	Theog	3,50,015/-	7,000/-	350/-	One Month
16	A/R & M/o on Chhailla Ghoond road Km 0/0 to 16/0 (SH:- C/o PCC R/wall at RD 2/447 to 2/460.)	Theog	2,82,457/-	5,700/-	350/-	One Month
17	Repair and maintenance of Rest house at Sainj (SH:-Repair of bath/W.C with tile work & sanitary fitting etc.)	Theog	4,99,589/-	10,000/-	350/-	One Month
18	C/o Litigant shad at Theog (SH:-C/o building portion,W.S & S.I etc balance work thereof.)	Theog	4,68,144/-	9,400/-	350/-	One Month
19	Repair and maintenance of Police station building at Deha Sub-Tehsil Deha District Shimla (HP) (SH:- Painting and distempering work and repair of flooring etc.)	Theog,	2,60,876/-	5,300/-	350/-	One Month
20	R/R damages on Ghorna to Deothi road Km 0/0 to 5/435 (SH:-C/o RCC 900mm dia hume pipe culvert at RD 5/250 i/c both side wing walls.)	Theog,	1,90,145/-	3,850/-	350/-	One Month


21	R/R of rain damages on Chhaila Ghoond Banari road Km 0/0 to 20/615 (SH:- C/o B/wall at RD 13/550 to 13/556.)	Theog	4,58,457/-	9,200/-	350/-	One Month
22	A/R & M/O on Balghar to Tihanadhar Kalna road Km 0/0 to 24/00 (SH:- C/o wire crates R/wall at Km/Rd 22/180 to 22/195.)	Theog	2,28,658/-	4,600/-	350/-	One Month
23	A/R & M/O on Balghar to Tihanadhar Kalna road Km 0/0 to 24/00 (SH:- C/o PCC R/wall at Km/RD 22/300 to 22/315.)	Theog	4,07,713/-	8,200/-	350/-	One Month
24	A/R & M/O on Balghar to Tihanadhar Kalna road Km 0/0 to 24/00 (SH:- C/o PCC B/wall at Km/RD 22/800 to 22/840.)	Theog	3,13,485/-	6,300/-	350/-	One Month
25	R/R damages on Dhamandri to Jais road km 0/0 to 6/500 (SH:- C/o R/wall ar RD 1/075 to 1/087.)	Theog	2,12,678/-	4,300/-	350/-	One Month
26	R/R damages on Dhamandri to Jais road km 0/0 to 6/500 (SH:- C/o wire crates for protection house at Km/RD 3/370 to 3/386.)	Theog	2,85,535/-	5,750	350/-	One Month
27	A/R & M/O on various roads under Theog Sub-Division (SH:- C/o unlined surface drain in various roads)	Theog	96,000/-	2,000/-	350/-	One Month
28	R/R damages on Kuthar Kunch Kanauri road km 0/0 to 11/075 (SH;- C/o RCC hume pipe culvert 900 mm dia i/c both wing walls at RD 6/450.)	Theog	1,94,327/-	3,900/-	350/-	One Month
29	R/R damages on Matiana Mahori road Km 16/00 to 24/00 (SH:- C/o PCC B/wall at RD 21/075 to 21/093.)	Theog	2,63,191/-	5,300/-	350/-	One Month
30	R/R damages on approach road on PHC building at Ghorna (SH;- C/o PCC R/wall at Rd 0/00 to 0/012 protection of building)	Theog	4,83,075/-	9,700/-	350/-	One Month
31	A/R & M/O on various roads under HPPWD Division Theog District Shimla 1. Road from Rail Nalla to Mundu Km 0/0 to 7/300 2.Balla to Kishore road Km 0/0 to 8/00 3. Road from Thouth to Noli Km 0/0 to 2/405 (SH:- Preparation of digital Map, Topo sheet of project and CA site with collection data from site under HPPWD Division Theog for with preparation of FCA case.)	Theog	4,66,100/-	9,350/-	350/-	One Month
32	A/R & M/O on various roads under HPPWD Division Theog District Shimla 1. Road from link Kashna to Kailash in GP Mundu 0/0 to 9/500 2. Road from Salana to Badlaog via Bagna road in GP Basadhar 0/0 to 10/300 (SH:- Preparation of digital Map, Topo sheet of project and CA site with collection data from site under HPPWD Division Theog for with preparation of FCA case.)	Theog,	4,95,600/-	10,000/-	350/-	One Month
33	A/R & M/O on various roads under HPPWD	Theog	3,48,100/-	7,000/-	350/-	One Month

	Division Theog District Shimla 1. Fagu Cheog Dhamandri Thenari Saini road Km 0/0 to 28/000 (SH:- Preparation of digital Map, Topo sheet of project and CA site with collection data from site under HPPWD Division Theog for with preparation of FCA case.)					
34	A/R & M/O on various roads under HPPWD Division Theog District Shimla 1. Fagu Cheog Dhamandri Thenari Saini road Km 0/0 to 28/000 (SH:- Preparation of digital Map, Topo sheet of project and CA site with collection data from site under HPPWD Division Theog for with preparation of FCA case.)	Theog	4,95,600/-	10,000/-	350/-	One Month
35	R/R of rain damages on Dhamandri to Jais road Km 0/0 to 7/00 (SH:- C/O PCC B/wall at RD 1/260 to 1/272 & 1/282 to 1/292)	Theog	2,52,212/-	5,100/-	350/-	One Month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Following documents should accompany the application for tenders: -

- (1) The contractors are required to produce a copy of their PAN No.GST. NO and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 ,G.S.T. shall not be paid extra.
- (5) Contractors are allowed to bid only two works, if he bids for more than two works only the first two works in sequence will be considered.


Executive Engineer,
(B&R) Division Theog

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2024-25 4017-28 dt. 14.8.24 are of emergent nature in exigency of public interest.

Dated 14th August 2024

Place Theog,


Executive Engineer,
Theog Division, B&R,
H.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.468980
Earnest Money:9400/

Time: One months

Name of Work : R/R damages on Forest Colony to Chikhar Pump House road km at RD 0/0 to 6/400 (SH:- C/O B/wall at RD2/651.60 to 2/651.60 and 2/240 to 2/255.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopess and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	59.95	84.95	Rupees Eighty Four and Paise Ninety Five Only	Per cubic meter	5093
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	35.37	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	7573
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	100.68	4378.40	Rupees Four Thousand Three Hundred Eighty and Paise Forty Only	Per cubic meter	440817
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in -Charge.	64.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Per running meter	15498
						468980
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

②

Earnest Money:5300/

Time: one Month

Wall at RD 2/970 to 2/990) Balance work.

Quoted rate in figer +/- (%.....)

Quoted rate in words

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.490646

Earnest Money:9900/-

Time: One months

Name of Work : R/R damages on Forest Colony to Chikhar Pump House road km at RD 0/0 to 6/400 (SH:- C/O R/wall at RD in km 5/697.50 to 5/708.20.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	60.99	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	13058
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	103.57	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	453471
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	30.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	7265
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	16.05	1050.00	Rupees One Thousand Fifty	Per cubic meter	16853
						490646
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP_PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost 200440

Earnest Money: 4009.00

Time: One Months

Name of work:- A/R & M/O Various Road under Sainj Sub-Division (SH:- Providing & Laying WBM G-III in Various road
(Patch - works)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	WBM Grading - III Providing laying spreading and compacting stone aggregates of specific sizes to water bond macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone, screening and compacting to the required density Grading - 3 As per Technical Specification clauses 405. (a) Manual Means. (53 to 22.4 mm size)	91.25	2196.60	Rupees Two Thousand One Hundred Ninety Six and Paise Sixty Only	P/Cum	200440.00
Total						200440.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 99750
Earnest Money: 2000.00
Time: One Months

Name of work:- R/R Damages on Various Roads in Theog Sub-Division (SH:- Hiring of J.C.B for removal of slips in Various Road)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (Excavator -Cum-Loader) including P.O.L charges. Shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of snow shall have to be neatly stacked along road side on road burms. Minimum 20 cubic meter of snow work shall be done by machine in one hour, other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads	95.00	1050.00	Rupees One Thousand Fifty Only	Per /Hour	99750.00
Total						99750.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 96600
Earnest Money: 2000.00
Time: One Months

Name of work:- R/R Damages on Various Roads in Theog Sub-Division (SH:- Hiring of J.C.B for removal of slips in Various Road)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (Excavator -Cum-Loader) including P.O.L charges. Shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of snow shall have to be neatly stacked along road side on road burms. Minimum 20 cubic meter of snow work shall be done by machine in one hour, other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads	92.00	1050.00	Rupees One Thousand Fifty Only	Per /Hour	96600.00
Total						96600.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 134371/

Earnest Money:2700/

Time: One months

f Work : Repair and maintenance of Rest house at Sainj (Repair and Bath/W.C with tile work & sanitary fittings etc.)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	32.17	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	6888
	Providing and fixing acrylic shelf complete fixed to wooden plugs with CP. Brass screws fitting complete including carriges of materials in all leads and lifts as per direction of Engineer-in-Charge	4.00	480.00	Rupees Four Hundred Eighty Only	Each	1920
	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangeent and making necessary holes for inlet , outlet and overflow pipes but without fittings and the base support for tank (Capacity 1000 litre)	2.00	8000.00	Rupees Eight Thousand Only	Each	16000
	Providing and fixing ball valve (Brass) of approved quality , high or low pressure , with plastic floats complete including carriges of material within all leads and lifts :- (i) 12 mm nominal bore	2.00	895.00	Rupees Eight Hundred Ninety Five Only	Each	1790
	Providing and fixing 20 mm nominal bore gun metal gate valve with C.I whee of approved quality (Screwed end) complete including carriges of materials within all leads and lifts.	8.00	525.00	Rupees Five Hundred Twenty Five Only	P/cum	4200
	Providing and Fixing PVC Finolex Degree bend 45 ISI marked including fixing with approved adhesive etc. complete including carriges of materials with in all leads and lifts :- (i) 100 mm nominal size.					
	110 mm nominal size	12.00	350.00	Rupees Three Hundred Fifty Only	Each	4200
	Providing and Fixing PVCFinolex plain bend ISI marked including fixing with approved adhesive etc. complete including carriges of materials within all leads and lifts :- (i) 110 mm nominal size	3.00	300.00	Rupees Three Hundred Only		900
	75 mm nominal dia	4.00	225.00	Rupees Two Hundred Five Only	Each	900

8	Providing and Fixing high pressure PVC (Finolex) type-B spigot and socket, waste and ventilating pipes including collar and clamps ISI marked including fixing with approved adhesive etc. complete including carriage of materials with in all leads and lifts:- 110mm dia.	62.00	650.00	Rupees Hundred Fifty Only	Six Fifty Only	Rmt	40300
8.01	75 mm dia	65.00	550.00	Rupees Hundred Fifty Only	Five Fifty Only	Rmt	35750
9	Providing and fixing PVC floor traps (finolex) ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts:- 110 mm nominal	2.00	270.00	Rupees Hundred Only	Two Seventy	Each	540.00
9	75 mm nominal						
10	Providing and fixing PVC (finolex) door band with oval access door, insertion rubber washer 3mm thick bolts and nuts ISI marked complete including fixing with approved adhesive complete including carriage of materials within all leads an lifts :- 110 mm dia (one hundred millimetre dia)	6.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	2100.00
10	75mm dia	4.00	250.00	Rupees Hundred Fifty Only	Two Fifty Only	each	1000.00
11	Providing and fixing PVC (finolex) plain tee ISI marked including fixing with approved adhesive complete including carriage of materials within all leads an lifts :- 110 mm dia one hundred millimetre dia	4.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	1400
11.01	75 mm dia Seventy five millimetre dia	4.00	250.00	Rupees Hundred Fifty Only	Two Fifty Only	each	1000
12	Providing and fixing PVC (finolex) door tee ISI marked including fixing with approved adhesive complete including carriage of materials within all leads an lifts :- 110 mm dia one hundred millimetre dia	3.00	450.00	Rupees Hundred Fifty Only	Four Fifty Only	each	1350
12.01	75 mm dia Seventy five millimetre dia	3.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	1050
13	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint, including all leads and lifts as per direction of the Engineer-in-Charge.						
	In gratings framed guard bars, ladders, railing, brackets and similar works	121.76	107.45	Rupees Hundred Seven and Paise Forty Five Only	One Seven and Paise Forty Five	Per kilo gram	13083
							134371
		Quoted rate in figer +/- (%.....)					
		Quoted rate in words					

Executive Engineer
H.P.W.D. (B & R)
Division Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 493489/

Earnest Money:9900/

Time: One months

Work : R/R damages on Thonala Nallah to kiri road km 0/0 to 2/500 (SH:- C/O PCC R/ wall at RD0/315 to 0/323)

No.	Description of item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	28.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	5995
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	73.92	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise	Per cubic meter	323651
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301including all leads and lifts as per direction of the Engineer-in-Charge.	46.88	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per cubic meter	138296
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	20.64	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	21672
5	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	16.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	3874
						493489
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.248071
Earnest Money:5000/

Time: One months
Name of Work : R/R Damages on Sarion to Gawai via Bhalech Jadeog road km 0/0 to 5/0 passed upto 3/330 (SH:- Winding of sharp /blind curve m 1/705, to 1/840 ,0/705 to 0/735 and edging at km 0/850 to 0/875.)

S. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	197.24	84.90	Rupees Eighty Four and Paise Ninety Only	Per cubic meter	16746
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	31.25	4378.40	Rupees Four Thousand Hundred Eighty and Paise Forty Only	Per cubic meter	136825
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	90.00	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	94500
						248071
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 408708

Earnest Money: 8200/

Time: One months

Work : R/R damages on Devgarh Jarai Manlog road km 0/0 to 6/500 (SH:- C/O (SH:- C/O PCC R/ wall at RD 1/750 to 1/762, and 1/770 to 5)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	81.00	214.10	Rupees Two Hundred and Paise Fourteen Only	Per cubic meter	17342
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:6:12)	6.12	3503.65	Rupees Three Thousand Five Hundred Three and Paise Sixty Five Only	Per cubic meter	21442
	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge.)	103.87	3365.50	Rupees Three Thousand Hundred Sixty Five and Paise Fifty Only	Per cubic meter	349574
	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	19.38	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	20349
						408708
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.495296

Earnest Money:10000/

Time: One months

of Work : A/R and M/O on Chhailla -Shalowa road km at RD 0/0 to 6/500 (SH:- C/O PCC R/wall at RD in km 5/510 to 5/525.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	53.40	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	11433
	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	107.99	4178.50	Rupees Four Thousand One Hundred Seventy Eight and Paise Fifty Only	Per cubic meter	451267
	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	9444
	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	22.05	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	23153
						495296
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.424237

Earnest Money:8500/

Time: One months

Work : C/O approach road to PHC at Ghorna (SH:- C/O PCC R/wall at RD in km 0/045 to 0/060)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	30.75	214.10	Rupees Hundred and Paise Ten Only	Per cubic meter	6584
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	88.80	4378.40	Rupees Thousand Hundred Eight and Paise Forty Only	Per cubic meter	388802
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	45.00	242.15	Rupees Hundred Forty Two and Paise Fifteen Only	each	10897
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	17.10	1050.00	Rupees Thousand Fifty Only	Per cubic meter	17955
						424237
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.493412

Earnest Money: 10000/-

Time: One months

of Work : R/R Damages on Ghorna to Deothi road km 0/0 to 5/435 (SH:- C/O PCC R/wall at RD 5/180 to 5/194.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	52.50	214.10	Rupees Hundred and Paise Ten Only	Per cubic meter	11240
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	109.20	4178.40	Rupees Thousand Hundred Eight and Paise Forty Only	Per cubic meter	456281
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	28.00	242.15	Rupees Hundred Forty Two and Paise Fifteen Only	each	6780
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	18.20	1050.00	Rupees Thousand Fifty Only	Per cubic meter	19110
						493412
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 95000

Earnest Money 2000.00

Time: One Months

Name of work:- Construction of link Road from forest coloney Theog to Bhariana Km 0/0 to 1/199 (SH:- FCA online on the parivash portal version-2 i/c preparation of digital ,ap, KML files i/c etc.)					
Sr. No.	Description of Item	QTY	Rate		Unit
			Rate in fig.	Rate in words	
1	Preparing of Geo Referenced Digital map, and collection of the Data for proposed site including field visit , preparation of KML files with Geo Coordinates along with marking of villages to be benefited by proposed site, marking the alignment in soft copy and submission of hard copy, caarriage of all equipment with in all leads & lifts and incidentals complete in all respect as per the direction and complete satisfaction of user agency and forest Department. Processing the case for preparation of forest diversion under Forest conservation Act, 1980 i/c preparation of revenue papers for land required in the project & collection of other filed data all relevant document/ formats mandatory required to be attached with the case as per the latest requirement of Ministry of Environment and Forest Conservation , Govt of India after getting the joint inspection of site including computer typing of 6 nos/ copies of the case binding complete and getting it through from DFO	1.199	95000.00	Rupees Ninety Five Thousand Only	P/Job
	Total				
			Quoted rate in figer+/- (-----)		
			Quoted rate in words		
					95000.00


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 350418/

Earnest Money: 7000/

Time: One months

of Work : A/R & M/O Approaches road Rest House at Sainj (SH:- C/O PCC Edging R/wall at RD 0/50 to 0/65 C/O V-shape drain Back Side of house)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	40.42	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	8654
	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	67.32	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	294754
	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge (1:3:6) 40 mm	4.50	5293.90	Rupees Five Thousand Two Hundred Ninety Three and Paise Ninety Only	Per cubic meter	23823
	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	38.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9202
	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	13.32	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	13986
						350418
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,

Estimated Cost Rs.282457
Earnest Money: 5800/
Time: One months

Name of Work

A/R and M/O on Chhalla, C.E. et al.

road km 0/0 to 16/0 (SH)- C/O PCC R/wall at RD 2/247

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of (Soil)	31.46	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	6736
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	60.71	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	253671
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts as per direction of the Engineer -in -Charge.	33.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	7991
4	Stone filling behind the retaining wall B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	13.39	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	14060
			Quoted rate in figer +/- (%.....)			282457
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.P.W.D. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 499589/

Earnest Money: 10000/

Time: One months

Work : Repair and maintenance of Rest house at Sainj (Repair and Bath/W.C with tile work & sanitary fittings etc.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Demolition cement concrete manually /by mechanical means including disposal of materials within 50 metres lead material including all leads and lifts as per direction of the Engineer-in-Charge. Nominal concrete 1:3:6 or leaner mix (i/c equivalent design Mix)	5.61	1150.00	Rupees One Thousand One Hundred Fifty Only	Per cubic meter	6452
2	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead (wooden/concrete joists to be measured and paid for separately including all leads and lifts as per direction of the Engineer-in-Charge For thickness of tiles above 25mm and upto 40mm	82.22	40.00	Rupees Forty Only	Per square meter	3289
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground with in 50 mtr leads including all leads and lifts as per direction of the Engineer-in-Charge	82.22	30.00	Rupees Thirty Only	Per square meter	2467
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 1:5:10 (One cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal Size	3.74	3350.00	Rupees Three Thousand Three Hundred Fifty Only	Per cubic meter	12529
5	Providing and laying in position cement concrete excluding of specified grade including the cost of centering and shuttering - All work up to all level : In retaining wall etc. 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 20 mm nominal size) upto all floor levels complete including carriage of material in all leads and lifts as per direction of the Engineer - in - Charge.	1.40	5500.00	Rupees Five Thousand Five Hundred Only	Per cubic meter	7700

17

	Providing and laying spartic ceramic tiles 12mm.thick in flooring (300x450mm. size)treads of steps laid on a bed of 12mm. thick cement mortar 1:3(1cement: 3 sand) finished with flush pointing in white cement including carriage of material in all leads and lifts as per direction of the Engineer - in - Charge.	85.22	1150.00	Rupees Thousand Hundred Fifty Only	One One Hundred Fifty Only	Per square meter	98003
	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete	18.71	1130.00	Rupees Thousand Hundred Thirty Only	One One Hundred Thirty Only	Per square meter	21142
	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) up to all floor levels complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	85.22	270.00	Rupees Hundred Only	Two Seventy Only	Per square meter	23009
	Providing and fixing PVC floor traps (finolex) ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts:- 110 mm x 75 mm	2.00	270.00	Rupees Hundred Only	Two Seventy Only	Each	540.00
	Providing and fixing High pressure PVC (finolex)spigot and socked , waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads an lifts :- 110mm dia	45.00	650.00	Rupees Hundred Fifty Only	Six Hundred Fifty Only	Per running meter	29250.00
1	75mm dia	40.00	550.00	Rupees Hundred Fifty Only	Five Hundred Fifty Only	Per running meter	22000.00
	Providing and fixing PVC (finolex) plain bend ISI marked including fixing with approved adhesive complete including carriage of materials within all leads an lifts :- 110 mm dia	20.00	300.00	Rupees Hundred Only	Three Hundred Only	each	6000.00
1	75mm dia	24.00	225.00	Rupees Hundred Five Only	Two Twenty Only	each	5400.00

2	Providing and fixing PVC (finolex) door band with oval access door, insertion rubber washer 3mm thick bolts and nuts ISI marked complete including fixing with approved adhesive complete including carriage of materials within all lifts :- 110 mm dia (one hundred millimetre dia)	8.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	2800.00
01	75mm dia	6.00	250.00	Rupees Hundred Fifty Only	Two Fifty Only	each	1500.00
3	Providing and fixing PVC (finolex) collars ISI marked including fixing with approved adhesive complete including carriage of materials within all lifts an lifts :- 110 mm dia one hundred millimetre dia	24.00	275.00	Rupees Hundred Five Only	Two Seventy	each	6600.00
01	75 mm dia Seventy five millimetre dia	20.00	185.00	Rupees Hundred Eighty Five Only	One Eighty Five	each	3700.00
4	Providing and fixing PVC (finolex) plain tee ISI marked including fixing with approved adhesive complete including carriage of materials within all lifts an lifts :- 110 mm dia one hundred millimetre dia	15.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	5250.00
01	75 mm dia Seventy five millimetre dia	15.00	250.00	Rupees Hundred Fifty Only	Two Fifty Only	each	3750.00
5	Providing and fixing PVC (finolex) door tee ISI marked including fixing with approved adhesive complete including carriage of materials within all lifts an lifts :- 110 mm dia one hundred millimetre dia	4.00	450.00	Rupees Hundred Fifty Only	Four Fifty Only	each	1800.00
01	75 mm dia Seventy five millimetre dia	6.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	2100.00
6	Providing and fixing PVC (finolex) degree bend 45 ISI marked including fixing with approved adhesive complete including carriage of materials within all lifts an lifts :- 110 mm dia one hundred millimetre dia	6.00	350.00	Rupees Hundred Fifty Only	Three Fifty Only	each	2100.00
01	75 mm dia Seventy five millimetre dia	6.00	250.00	Rupees Hundred Fifty Only	Two Fifty Only	each	1500.00
7	Providing and fixing chlorinated polyvinyl chloride (CPVC) Pipe, having thermal stability for hot and cold water supply, including all CPVC Plain and brass threaded fittings, i/c fixing the pipe with clamps at 1.00 mm spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting and making good the same including testing of joints complete as per direction of Engineer -in -Charge 15 mm nominal outer dia pipe	130.00	325.00	Rupees Hundred Five Only	Three Twenty	Per running meter	42250.00

18	Providing and fixing ceramic vitreous china pedestal type wash down water closet (European type W.C. pan) one piece with integral P or S trap including cestern seat and cover jointing the trap with soil pipe in cement mortar 1:1 No 20004 of HINDWARE with 100 mm sand cast (1 cement :1 sand) including carriage of material in all leads and lifts as per direction of the Engineer in Charge. Cat no. rim less wallhung duraplast soft closet seat cover	4.00	16088.00	Rupees Thousand Eight Only	Sixteen Eighty	each	64352
19	Providing and fixing health faucet for water closet including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	1144.00	Rupees Thousand Hundred Forty Four Only	One One Hundred Forty Four	each	4576
20	Providing and fixing 15 mm (fifteen millimetre) nominal bore angle cock of ESS catalogue No f2014201 or equivalent of approved quality and colour with flange including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	38.00	1358.00	Rupees Thousand Hundred Fifty Eight Only	One Three Fifty Eight	each	51604
21	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require. including carriage of material in all leads and lifts as per direction of the Engineer in Charge. White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	4.00	4841.00	Rupees Thousand Hundred Forty One Only	Four Eight Hundred Forty One	each	19364
22	Providing and fixing C.P. brass extension nipple (size 1 inch) of approved including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	26.00	80.00	Rupees Eighty Only		each	2080
23	Providing and fixing C.P. brass extension nipple (size 1 inch x 1/2 inch) of approved including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	26.00	95.00	Rupees Ninety Five Only		each	2470
24	Providing & fixing 100mm diaviking make . grating for floor or nahani / gully / floor trap including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	16.00	95.00	Rupees Ninety Five Only		each	1520
25	Providing & fixing 15mm nominal bore over head shower of cera make of approved quilty and colour including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	1898.00	Rupees Thousand Hundred Eighty Only	One Eight Ninety	each	7592
26	Providing & fixing 15mm nominal bore Ess-Ess basin mixer vor cera make of approved quilty and colour with flage including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	3565.00	Rupees Thousand Hundred Sixty Five Only	Three Five Sixty Five	each	14260

17	Providing and fixing soap dish with ESS-ESSmake of approved quality and colour with flange and screws including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	480.00	Rupees Hundred Only	Four Eighty	each	1920
18	Providing and fixing 600mm X 20mm size towel rail ESS-ESSmake of approved quality and colour with flange. Screws including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	750.00	Rupees Hundred Fifty Only	Seven	each	3000
19	Providing and fixing towel ring ESS-ESSmake of approved quality and colour with flange. Screws including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	475.00	Rupees Hundred Five Only	Four Seventy	each	1900
20	Providing and fixing toilet paper holder ESS-ESSmake of approved quality and colour with flange. Screws including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	620.00	Rupees Hundred Only	Six Twenty	each	2480
21	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	1265.00	Rupees Thousand Hundred Sixty Five Only	One Two Hundred Sixty Five	each	5060
22	Providing and fixing 45 cm length uplasticised PVC connection pipe with brass unions including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 15 mm nominal bore	32.00	170.00	Rupees Hundred Only	One Seventy	each	5440
23	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	210.00	Rupees Hundred Ten Only	Two	each	840
							499589
		Quoted rate in figer +/- (%).....)					
		Quoted rate in words					

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.468144
Earnest Money 9400/
Time: One months

Work : C/O Litigant shed at Theog (SH:- C/O Building Portion , WS & SI etc , Balance work thereof)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Providing & fixing fixed shutter for windows instead of openable shutter including all leads and lifts as per direction of the Engineer-in-Charge.	42.62	4450.00	Rupees Four Thousand Four Hundred Fifty Only	Per square metre	189659
	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting, including all leads and lifts as per direction of the Engineer-in-Charge. Readymixed paint brushing wood primer pink.	42.62	54.20	Rupees Fifty Four and Paise Twenty Only	Per square metre	2310
	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping.including all leads and lifts as per direction of the Engineer-in-Charge. With enamel paint other than white	42.62	93.35	Rupees Ninety Three and Paise Thirty Five Only	Per square metre	3979
	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204including all leads and lifts as per direction of the Engineer-in-Charge (1:6:12)	5.14	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic meter	19275
	Brick work using common burnt clay building bricks in foundation and plinth in cement mortar 1:6 (one cement : six sand) second class bricks complete including all leads and lifts as per direction of the Engineer-in-Charge	5.60	7910.30	Rupees Seven Thousand Nine Hundred Ten and Paise Thirty Only	Per cubic meter	44298
	Providing form work with steel plates 3.15mm (Three point one five millimetre) thick welded with angle iron in frame 30x30x5mm (Thirty into thirty into five millimetre) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in including all leads and lifts as per direction of the Engineer-in-Charge					

18

01	Flat surface such as soffits of suspended floors, roofs, landings and the like upto any thickness complete in all respect floor etc upto 200 mm thickness	7.03	420.00	Rupees Hundred Only	Four Twenty	Per square meter	2953
	Providing and laying Cement Concrete 1:1.5:3 (1 cement :1.5 Sand : 3 graded stone aggregate 20 mm nominal size) and Curing complete excluding Cost of form work and reinforcement for reinforced Concrete work in :-						
01	Suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level including curing complete in all respect.	1.22	7905.50	Rupees Thousand Hundred Five and Paise Fifty Only	Seven Nine Five and Paise Only	Per cubic meter	9645
	Constructing Course rubble hammer dressed 'U' shape open surface drain with side wall. 15x22 cm in cement mortar 1:6 (1 Cement : 6 Sand) and inside plastering with cement plaster 1:3 (1 Cement:3 Sand) including earth work and laying 10 cm cement concrete in 1:5:10 (1 Cement : 5 Sand : 10 graded stone aggregate) of 40 mm nominal size) and 7.5 cm cement concrete 1:2:4 (1 Cement : 2 Sand : 4 Graded stone aggregate of 20 mm nominal size) and finished with a floating coat of neat cement complete as per standard design.	35.20	695.00	Rupees Hundred Only	Six Ninety Five	Per running meter	24464
	40mm (forty millimeter) thick cement concrete flooring 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 20mm (twenty millimeter) nominal size) laid in one layer finished with a floating coat of neat complete including carriage of materials within all leads, lifts and other incidental charges.	56.73	392.10	Rupees Hundred Ninety Two and Paise Ten Only	Three	Per square meter	22244
0	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior /exterior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 30cm in girth and finished even and smooth including. Cement mortar 1:6 (1 cement : 6 sand)including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	30.99	288.30	Rupees Two Hundred Eighty Eight and Paise Thirty Only		Per square metre	8934

Excavation in foundation, trenches, etcetra in earth work in all kinds of classification, of soils such as pick work, jumper work blasting work saturated soils including chiseling or any other mixed variety of soils, dewatering and / or removal of slush and other incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth to the disposal point complete in all respect including all leads and lifts as per direction of the Engineer-in-Charge	51.57	355.60	Rupees Three Hundred Fifty Five and Paise Sixty Only	Per cubic meter	18338
Half Brick masonry in 2nd class common burnt clay building bricks in cement mortar 1: 4 (one cement : four sand) complete including all leads and lifts as per direction of the Engineer-in-Charge	4.93	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Square meter	6064
Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	21.00	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic meter	112350
Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	15.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	3632
					468144
	Quoted rate in figer +/- (%.....)				
	Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 260876/

Earnest Money:5300/

Time: One months

Work : Repair and maintenance of Police Station Building at Deha sub- tehsil Theog Distt. Shimla (HP) (SH:- Painting and distempering work repair of flooring etc.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and fixing 10mm thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including all leads and lifts as per direction of the Engineer-in-Charge.)	68.46	1688.35	Rupees Thousand Hundred Eight and Thirty Five Only	Per square meter	115584
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface .complete including all leads and lifts as per direction of the Engineer-in-Charge	388.22	86.40	Rupees Eighty Six and Paise Forty Only	Per square meter	33542
3	Applying priming coat on new concrete/masonry/asbestos cement/plastered surfaces after and including preparing the surface by thoroughly cleaning oil,grease,dirt and other foreign matter and sand papering as required with complete including all leads and lifts as per direction of the Engineer-in-Charge	388.22	41.50	Rupees Forty One and Paise Fifty Only	Per square meter	16111
4	Applying one coat of Acrylic Washable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth complete including all leads and lifts as per direction of the Engineer-in-Charge	388.22	130.55	Rupees One Hundred Thirty and Paise Fifty Five Only	Per square meter	50682
5	Removing old paint or polish from wood and wood based surfaces withpaint remover of approved brands and manufacture and making the surface even with including all leads and lifts as per direction of the Engineer-in-Charge.	206.22	80.10	Rupees Eighty and Paise Ten Only	Per square meter	16518

3	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including all leads and lifts as per direction of the Engineer-in-Charge.	206.22	48.80	Rupees Forty Eight and Paise Eighty Only	Per square meter	10064
4	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping. including all leads and lifts as per direction of the Engineer-in-Charge.	206.22	88.10	Rupees Eighty Nine and Paise Ten Only	Per square meter	18374
						260876
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.190145
Earnest Money:3800/

Time: One months

of Work : R/R Damages on Ghorna Deothi road km 0/0 to 5/435 (SH:- C/O RCC hume pipe culvert at Rd 5/250 including both side wing wall .)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	34.50	214.10	Rupees Hundred and Paise Ten Only	Per cubic meter	7386
	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	9.27	5293.90	Rupees Thousand Hundred Three and Ninety Only	Per cubic meter	49074
	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including all leads and lifts as per direction of the Engineer-in-Charge. Nominal mix 1: 6 :12)	1.49	3503.65	Rupees Thousand Hundred Three and Paise Sixty Five Only	Per cubic meter	5220
	Providing laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm dia including all leads and lifts as per direction of the Engineer-in-Charge.	7.50	4437.00	Rupees Thousand Hundred Seven Only	Per running meter	33278
	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 20 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	20.46	4178.40	Rupees Thousand Hundred Eight and Forty Only	Per cubic meter	85490
	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	16.64	242.15	Rupees Hundred Forty Two and Paise Fifteen Only	each	4029

Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	5.40	1050.00	Rupees Thousand Fifty Only	One Per cubic meter	5670
					190148
	Quoted rate in figer +/- (%.....)				
	Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.458457

Earnest Money:9200/-

Time: One months

Work : R/R Damages on Chhaila Ghoond Banari road km 0/0 to 20/615 (SH:- C/O R/wall at Rd 13/550 to 13/566.)

Description of Item	QTY	Rate		Unit	Amount
		Rate in fig.	Rate in words		
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	46.72	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	10003
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:4:8 40 mm N.S including all leads and lifts as per direction of the Engineer-in-Charge.	94.72	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	414722
Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	42.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	10170
Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	18.72	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five	Per cubic meter	23562
					458457
	Quoted rate in figer +/- (%.....)				
	Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

22

Name of Work : A/R and M/O on Balghar Tihanadhar Kalna

Executive Engineer,
Theog Division,
HP.PWD. Theog.

Estimated Cost Rs.411375
Earnest Money: 8300/
Time: One months
to 22/3/15)

Estimated Cost Rs.411375

Earnest Money: 8300/

Time: One months

Name of Work : A/R and M/O on Balghar Tihanadhar Kalna road

111

Executive Engineer,
Theog Division
HP.PWD, Theog

SCHEDULE OF QUANTITY

Name of Work : A/R and M/O on Balghar Tihanadhar Kalha road km 0/0 to 24/0 (SH- C/O PCC B/wall at RD 22/800 to 22/840)

Estimated Cost Rs.313485

Earnest Money: 6300/

Time: One months

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of (Soil)	113.60	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	24322
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 20 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	64.80	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	Per cubic meter	270760
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	76.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	18403
			Quoted rate in figer +/- (%.....)			313485
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD Theog

25

SCHEDULE OF QUANTITY

Estimated Cost Rs.212678

Earnest Money: 4300/

Time: One months

Work : R/R damages on Dhamandri Jais road km 0/0 to 6/500 (SH- C/O R/wall at RD 1/075 to 1/087.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	25.44	214.10	Rupees Hundred and Paise Ten Only	Per cubic meter	5447
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	41.40	4500.00	Rupees Thousand Hundred Only	Per cubic meter	186300
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer-in -Charge.	24.00	242.15	Rupees Hundred Forty Two and Paise Fifteen Only	Each	5812
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in -Charge.	14.40	1050.00	Rupees Thousand Fifty Only	Per cubic meter	15120
						212678
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.285535

Earnest Money: 5800/

Time: One months

Work : R/R damages on Dhamandri Jais road to 6/150 (SH- C/O B/wall wire crate for protection house at km 3/370 to 3/386.)

Description of Item	QTY	Rate		Unit	Amount
		Rate in fig.	Rate in words		
Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	60.80	200.10	Rupees Hundred and Paise Ten Only	Per cubic meter	12166
Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size. Mesh Type 10x12 (D=100 mm with tolerance of $\pm 2\%$) Zinc coated, Mesh wire diameter 3.0 mm, mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge	91.00	3004.05	Rupees Thousand Four and Paise Five Only	Per cubic meter	273369
					285535
Quoted rate in words		Quoted rate in figer +/- (%.....)			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

5

Earnest Money: 2000/

Time: One month

Line of Work : A/R and M/O on Various road under Theog Sub-Division km at RD 0/0 to 6/500 (SH:- C/Ounlined surface drain in Km various & road.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including all leads and lifts as per direction of the Engineer-in-Charge.	6000.00	16.00	Rupees Only Sixteen	Per running meter	96000
						96000
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.194327

Earnest Money:4000/

Time: one month

Work : R/R damages on Kuthar Koonch Kanowri road Km 0/0 to 11/075 (SH:- C/O RCC hume pipe culvert 900 mm i/c both side wing walls
(450)

QTY	Description of Item	Rate		Unit	Amount
		Rate in fig.	Rate in words		
34.50	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	7386
9.27	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge (1:3:6) 40 mm	5293.90	Rupees Five Thousand Hundred Three and Paise Ninety Only	Per cubic meter	49074
1.49	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:6:12)	3503.65	Rupees Three Thousand Five Hundred Three and Paise Sixty Five Only	Per cubic meter	5220
7.50	Providing laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 900mm dia including all leads and lifts as per direction of the Engineer-in-Charge.	4437.00	Rupees Four Thousand Four Hundred Thirty Seven Only	Per running meter	33278
20.46	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8 graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	89582
17.00	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	4117

Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	5.40	1050.00	Rupees Thousand Fifty Only	One Only	Per cubic meter	5670
						194327
	Quoted rate in figer +/- (%.....)					
	Quoted rate in words					


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 263191
Earnest Money: 5300.00
Time: one Months

Damages on R/R Damages on Matiana Mohari Guthan road km16/00 to 24/00 (SH:- C/O B/wall at RD Km 21/075 to 21/093)						
Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
			Rate in words			
Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of excavated earth with in lift upto 1.5 mtr. and a lead upto 20 mtr as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge.	58.00	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only		Per Cum meter	8628.00
Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	25.56	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		Per Cum meter	5472.00
Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8:) 40 mm Agg.including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	54.90	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		Per Cum meter	240374.00
Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	36.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only		each	8717.00
			Quoted rate in figer+ /-(%-----)			263191.00
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.485075

Earnest Money:9700/

Time: One months

Work : C/O approach road to PHC Building at Ghorna (SH:- C/O PCC R/Wall at Rd 0/0 to 0/012)protection of building.

Description of Item	QTY	Rate		Unit	Amount
		Rate in fig.	Rate in words		
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	24.60	214.10	Rupees Hundred Fourteen and Paise Ten Only	Per cubic meter	5267
Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	103.90	4378.40	Rupees Thousand Three Hundred Seventy Eight and Paise Forty	Per cubic meter	454916
Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	36.00	242.15	Rupees Hundred Forty Two and Paise Fifteen Only	each	8717
Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	13.50	1050.00	Rupees Thousand Fifty Only	Per cubic meter	14175
					483075
	Quoted rate in figer +/- (%.....)				
	Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 466100

Earnest Money: 1000.00

Time: One Months

Name of work:- A/R & M/O Various Roads Under HPPWD Division Theog Distt. Shimla. 1. Road from Rail Nallah to Mundoo (Kms 0/0 to 7/300) 2. Ballah Kishore road (0/00 to 8/00) 3. Road from Thoht to Nolli (Kms 0/00 to 2/405) (SH:- Preparation of Digital Map Topo Sheet of Project and CA site with collection data from site under HPPWD Division Theog for A/R & M/O of Various Roads under HPPWD Theog with Preparation of FCA Case)					
Sr. No.	Description of Item	QTY	Rate		Unit
			Rate in fig.	Rate in words	
1	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G.P.S. Coordinates. CA Site with preparation of the proposal folder of project as per the Guidelines of MoEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval.	2.00	177000.00	one Hundred seventy Seven Thousand only	Per Case
2	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G.P.S. Coordinates. CA Site with preparation of the proposal folder of project as per the Guidelines of MoEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval.	1.00	112100.00	One Hundred Twelve Thousand one Hundred only	Per Case
Total					
			Quoted rate in figer+/-(%-----)		
			Quoted rate in words		
					466100.00


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 495600

Earnest Money: 1000.00

Time: One Months

Name of work:- A/R & M/O Various Roads Under HPPWD Division Theog Distt. Shimla. 1. Road from Link Kashna to Kailash in G.P Mündoo (0/00 to 9/500) 2. Road from Salana to Badlaog via Bagna road in G.O basadhar 0/00 to 10/300) (SH:- Preparation of Digital Map Topo Sheet of Project and CA site with collection data from site under HPPWD Division Theog for A/R & M/O of Various Roads under HPPWD Theog with Preparation of FCA Case)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G.P.S . Coordinates. CA Site with preparation of the proposal folder of project as per the Guidelines of MOEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval.	2.00	247800.00	Rupees Two hundred Forty Seven Thousand And Eight Hundreds only	Per Case	495600.00
Total						495600.00
			Quoted rate in figer+ /-(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

33

SCHEDULE OF QUANTITY

Estimated Cost 348100

Earnest Money: 1000 00

Time: One Months

Name of work:- C/O Various Roads Under HPPWD Division Theog Distt. Shimla. 1. Fagu Cheog Dhamandri Thenari Saini Road (Kma 0/00 to 28/000) (SH:- Preparation of Digital Map Topo Sheet of Project and CA site with collection data from site under HPPWD Division Theog for A/R & M/O of Various Roads under HPPWD Theog with Preparation of FCA Case)					
Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit
				Rate in words	
1	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G.P.S. Coordinates. CA Site with preparation of the proposal folder of project as per the Guidelines of MoEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval.	1.00	348100.00	Rupees Three Hundred Forty Eight Thousand one Hundred only	Per Case
	Total				
				Quoted rate in figer+ /-(%-----)	
				Quoted rate in words	
					348100.00


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost: 495600

Earnest Money: 1000.00

Time: One Months

Name of work:- C/O Various Roads Under HPPWD Division Theog Distt. Shimla. 1. Fagu Cheog Dhamandri Thenari Saini Road (Kma 0/00 to 28/000) (SH:- Preparation of Digital Map Topo Sheet of Project and CA site with collection data from site under HPPWD Division Theog for A/R & M/O of Various Roads under HPPWD Theog with Preparation of FCA Case)					
Sr. No.	Description of Item	QTY	Rate		Amount
			Rate in fig.	Rate in words	
1	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G P S Coordinates CA Site with preparation of the proposal folder of project as per the Guidelines of MoEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval	2.00	247800.00	Rupees Two Hundred Forty Seven Thousand Eighty Hundred only	495600.00
Total					495600.00
			Quoted rate in figer+ /-(%-----)		
			Quoted rate in words		


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

25

Earnest Money: 5100/

Name of Work	:R/R damages on	Damages on	Jais road km 0/0 to 7/00 (SH:-C/O PCC B/wall at RD 1/260 to 1/272 and 1/282 to 1/292.)	Time: One months	Earnest Money:5100/-


Executive Engineer,
Theog Division,
HP.PWD. Theog

Executive Engineer,
Theog Division,
HP.PWD. Theog