



Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-  
9722-30 DATED 17-09-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.

Executive Engineer,  
Baijnath Division,  
HP.PWD, Baijnath.



**Office of**  
**Executive Engineer Baijnath Division HP.PWD, Baijnath**  
**Himachal Pradesh Public works Department Baijnath-176125**  
**Phone No. 01894-263035 Fax 262704 e-mail:- [ce-baij-hp@nic.in](mailto:ce-baij-hp@nic.in)**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **28.09.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **27.09.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **26.09.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O OBC Bhawan at Ghirtholi (SH: Civil work) (Deposit work)	Rs.2,96,304/-	Rs.6,000/-	Rs.350/-	Two Months
2	Special repair of Govt. Ayurvedic Hospital Building at Paprola Distt. Kangra (H.P) (SH: Providing and Fixing Tile work)	Rs.4,99,880/-	Rs.10,000/-	Rs.350/-	Two Months
3	C/O Link road from Deora Basti to Ashok Kumar House (SH: P/L C.C. Pavement & Kharnja Stone Soling at Km 0/150 to 0/255) (Deposit work-SDP/2024/180)	Rs.3,93,008/-/-	Rs.7,900/-	Rs.350/-	Two Months
4	C/O Jeepable road from main road to Chaman Bhangalia House ward No.4 G.P. Bandiyan (SH: Providing and laying C.C. Pavement & Kharnja Soling at Km 0/00 to 0/079.50) (Deposit work-VKV/2023/1643)	Rs.2,97,529/-	Rs.6,000/-	Rs.350/-	Two Months
5	C/O Chobin to Balh Road (SH: P/L Kharnja stone Soling & C.C. Pavement at Km 0/110 to 0/215 (Deposit work and working program) (Deposit -VKV/6124/2024)	Rs.4,43,872/-	Rs.8,900/-/-	Rs.350/-	One Month
6	Special repair of Govt. Ayurvedic hospital Building at Paprola Distt. Kangra (H.P) (SH: Providing and Fixing water Supply and Sanitary Installation) (Deposit work)	Rs.4,90,915/-	Rs.9,900/-	Rs.350/-	Two Months
7	C/O Link road from Bari Mod to Bhugot via Dhai Mela Rest house Km 0/00 to 1/00 (C/O B/Wall at RD 0/555 to 0/565, 0/660 to 0/680)	Rs.2,87,570/-	Rs.5,800/-	Rs.350/-	Two Months
8	C/O Link road from Khalenu to Malehar (SH: P/L C.C. Pavement & Kharnja Stone Soling at Km 0/00 to 0/075)	Rs.3,01,929/-/-	Rs.6,100/-	Rs.350/-	Two Months
9	C/o Baijnath Chobin Balandar road Km 0/00 to 14/200 (SH: P/L 80mm thick Paver Block at km 0/620 to 0/640)	Rs.4,15,879/-/-	Rs.8,400/-	Rs.350/-	Two Months
10	R/D on Kunsal Nohra Bahi road km 0/00 to 3/00 (SH: C/O R/wall for protection of Vijay Kumar house at RD 2/310 to 2/315)	Rs.2,87,545/-	Rs.5,800/-	Rs.350/-	Two Months
11	S/R to Type-III Quarter Single story at HP.PWD, Baijnath (SH: Providing and Fixing water supply and Sanitary Installation & Distempering work, Painting work, Tile flooring i/c WS and SI/Fitting)	Rs.2,28,054/-	Rs.4,600/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.

**E/E.**



6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Bajinath Division.,  
H.P.PWD..Bajinath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/- 9722-30

Dated:- 17.09.2024

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
Bajinath Division.,  
H.P.PWD..Bajinath.

# DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O OBC Bhawan at Ghirtholi  
(SH:- Civil work) (DEPOSIT WORK)

Estimate Cost: 2,96,304.00  
Earnest Money: 6,000.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.55	Per Cum			
2	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing complete.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.57	Cum.			
3.a	Centering and shuttering including strutting, propping etc. and removal of form work for :Foundations, footings, bases for columns The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.36	sqm			
3.b	Centering and shuttering including strutting, propping etc. and removal of form work for :Surface such as suspended floor etc The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	33.47	sqm			
3.c	centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 ( four ) Mtrs.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	17.17	Sqm			



3.d	Centering and shuttering including strutting, propping etc. and removal of form work for : Beams Cantilever girder etc The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.67	sqm		
3.e	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm ( twenty centimetre ) wide The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	28.50	running mtr		
4	Providing and laying cement concrete 1:6:12 (One cement isto six sand isto twelve aggregate) graded crushed/broken stone aggregate 40mm (forty milimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.54	Per cubic metre		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one Cement : four coarse sand) : Eight graded stone aggregate 40 (forty )mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.05	Cum.		
6.a	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one Cement : Two coarse sand) : four graded stone aggregate 40 (forty ) mm nominal size in foundation Footings and Basis of columns The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.85	Per cubic metre		
6.b	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M 20 design mix to obtain the minimum compressive strength of M-20 N.mm2 with cement contents not less than of 320kg/m3 (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	7.90	Per cubic metre		
6.c	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and Coulmn Pillar Posts & sturrs and the like and mass concrete. reinforcement for reinforced concrete work in : The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.30	Per cubic metre		

7.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1523.00	kg			
8	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.24	Per cubic metre			
9	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.26	Per cubic metre			

Executive Engineer  
Bailjath Division  
H.P.F.W.D., Bailjath

## DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of work :- Special Repair Of Govt Ayurvedic Hospital Building at Paprola Distt Kangra (H.P)  
(SH:-Providing and Fixing Tile work)

Estimate Cost:4,99,880.00  
Earnest Money:10,000.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Dismantling Tile work in floors laid in cement mortar i/c stacking of unseviceable material with in 50 mtr lead for thickness or tiles above 25mm and upto 40 mm The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	282.47	cum			
2	Providing and laying antiskid Ceramic tiles of premium quality size 300x300 mm ( thickness)of Nitco/AGL/RAK/Simpolo/Kajaria /Somany/Johnson/BELL. to be specified by the manufacturer) of 1st Quality confirming to IS 15622 of approved make in colour such as white , Ivory. Grey fume red brown laid on 20 mm thick cement mortar 1:4 ( One cement:4 coarse sand) jointing with grey cement slurry @3.30 kg/sqm including pointing the joints with white cement and matching pigment etc. complete.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	74.24	Per Square metre			
3	Providing and laying 300x450 mm ceramic whit glazed tile Dado of Nitco/AGL/RAK/Simpolo/Kajaria /Somany/Johnson/BELL NTC or equivalent of approved make in all colours & shade , in skirting, riser of steps over 12mm thick bed of cement mortar 1:3 (1 cement :3 sand ) jointing with grey slurry @ 3.3kg/sqm including grouting the joint with white cement and matching pigments etc . complete.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	282.47	Per Square metre			

Executive Engineer  
Bajjnath Division  
H.R.P.W.D. Bajjnath



## DNIT/DRAFT SCHEDULE OF QUANTITY

3

Name of work :- C/O Link road from Deora Basti to Ashok Kumar House  
(SH:-P/L, C. C Pavement & Kharnja Stone Soling at km 0/150 to 0/255)

DEPOSIT WORK -SDP/2024/180

Estimate Cost: 3,93,008.00/-

Earnest Money: 7900.00/-

Time Limit :Two Months

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	44.66	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	44.66	Per Cubic metre			
Total						

Executive Engineer  
Bajjnath Division  
H.P.P.W.D., Bajjnath



4

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Jeepable Road from main road to Chaman Bhangalia House ward No. 4 G P Bandiyan.

(SH:-Providing and laying C. C Pavement &amp; Kharnja Soling at km 0/00 to 0/079.50 ) DEPOSIT WORK VKV/2023/1643

Estimate Cost: 2,97,529.00/-

Earnest Money: 6000.00/-

Time Limit : Two Month

## SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	33.81	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORU technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	33.81	Per Cubic metre			
Total						

Executive Engineer  
 Daljath Division  
 H.P.W.D., Daljath

## DNIT/DRAFT SCHEDULE OF QUANTITY

5

Name of work :- C/O Chobin to Balh Road

(SH:-P/L Kharnja stone Soling &amp; C. C Pavement at km 0/110 to 0/215 ) (Deposit work and working program )

Estimate Cost: 4,43,872.00/-

Earnest Money:8900.00/-

Time Limit :One Month

DEPOSIT - VKV/6124/2024

## SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	50.44	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	50.44	Per Cubic metre			
Total						

Executive Engineer  
Baljnath Division  
H.P.P.W.D., Baljnath

**DNIT/DRAFT SCHEDULE OF QUANTITY**

⑥ ①

Name of work: -Special Repair of Govt. Ayurvedic Hospital Building at Paprola Distt. Kangra H.P. (Sh:-Providing and Fixing water supply and Sainitary Installation) <b>DEPOSIT WORK</b>				Estimate Cost: 4,90,915.00 Earnest Money:9,900.00 Time Limit : Two Months		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing white vitreous china EWC water closet star S No 20087 ( S-10) of size 57x35x39 cm with Jet pressure and with 10 litre low level PVC cistern & C.P. flush bend with fittings & C.I. brackets. 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete. including painting of fittings and brackets, cutting and making good the walls and floors wherever required of Hindware or Equivalent The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	7.00	Each			
2	Providing and fixing water closet orissa pan No 20090 of size 53x41 CM (Indian type W.C. pan ) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pan of Hindware or Equivalent The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			
3	Providing and fixing wash basin with C.I. brackets, of DELTA NO 10010 of size 55x40 CM with pedestal of HINDWARE or equivalent with, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
4	Providing and fixing wash basin GARNET no 10080 of size 58x43 cm ( under Counter basins) of HINDWARE or Equivalent. 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
5	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia (Thirty Two ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each			



6	Providing and fixing 100mm (Hundred millimeter )dia CP iron grating of ESS-KSS for malhni trap. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each			
7	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.00	Each			
8	Providing and fixing 600x450 mm (six hundred into four hundred fifty only ) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (Six millimeter ) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
9	Providing and fixing 600x120x5 mm (Six hundred into one hundred twenty into five millimeter ) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (Forty Millimeter ) long screws, rawl plugs etc., complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
10	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, (Six hundred forty five ) width 78 mm (Seventy eight millimeter ) and effective height of 88 mm, (Eighty Eight Millimeter ) weighing not less than 190 gms. (One hundred ninety grams ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
11	Providing and fixing chromium plated brass soap dish of Jaguar or contra with C.P. brass brackets fixed to wooden cleats with C.P. brass screws The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
12	Providing and fixing C.P. brass long nose bib cock F-330011 Jaquar or equivalent single control of approved quality conforming to IS standards. 15 mm (Fifteen millimeter ) nominal bore The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.00	Each			

(6) (2)

13	Providing and fixing CP brass stop cock ( concealed) of standred design and app. I-330043 of HINDWARE 15mm (Fifteen millimeter ) nominal bore The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	28.00	Each			
14	Providing and Fixing Pillar cock F-330002 of HINDWARE 15 mm (Fifteen millimeter ) Jaquar or equivalent as per direction complete.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each			
15	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm (Forty Five ) length 15 mm (Fiften ) nominal bore The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.00	Each			
16	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3000.00	Liter			
17	Providing and fixing Polyethelene-Aluminium Polyethelene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge 1216, 16mm ( sixteen millimeter )OD Pipe) (Concealed work, including cutting chases and aking good the wall etc.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	72.00	Rm			
18	Providing and fixing G.I. pipes complete with G.I. Fittings including trenching and refilling etc. 20 mm (Twenty Millimeter ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	72.00	Rm			



⑥ (d)

19.a	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. 75 mm Dia (seventy five millimeter ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	48.00	Rmt		
19.b	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. 110 mm Dia (one hundred ten millimeter ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	48.00	Rmt		
20.a	Providing and fixing PVC Single Equal Branch with oval asses ISI Marked insertion rubber washer 3 mm thicj bolt and nuts complete i/c fixing with approved adhesive etc. Cpmplete 75 mm Dia (seventy five millimeter ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each		
20.b	Providing and fixing PVC Single Equal Branch with oval asses ISI Marked insertion rubber washer 3 mm thicj bolt and nuts complete i/c fixing with approved adhesive etc. Complete 110 mm Dia (one hundred ten millimeter ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each		
21	Providing and fixing vitreous China urinal large Flat back No 60002 of size 39x37.5x59 CM in White Shade of Perryware /Jaqar/ Hindware/ Cera or equivalent including cutting holes & making good the same and carriage of materials within all leads and lifts :- Of Superior quality The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each		
22	Providing and fixing Division Plate for urinals 600x300 mm (Six Hundred into three hundred ) Viterous Chiana The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.00	Each		
23	Providing and fixing ISI marked of self cleaning design including fixing with approved adhesive , cost of cutting and making good the wall and floor etc. Complete for size 110x75 mm (One hundred ten into seventy five ). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	24.00	Each		

Executive Engineer

Public Works Division  
M.P.W.D., Baljnath



# DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Link Road From Bari Mod to Bhugot via Dhari Mela Rest house km 0/00 to 1/00  
(SI:-C/O B/wall at RD 0/555 to 0/565, 0/660 to 0/680)

Estimate Cost: 2,87,570.00/-  
Earnest Money: 5,800.00/-  
Time Limit: Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	55.40	Per Cum			
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	28.00	Each			
Total						

Engineer  
Bajjnath Division  
Bajjnath

## DNIT/DRAFT SCHEDULE OF QUANTITY

8

Name of work :- C/O Link road from Khatenu to Malehar  
(SH:-P/L C. C Pavement & Kharanja Stone Soling at km 0/00 to 0/075)

Estimate Cost: 3,01,929.00/-  
Earnest Money: 6100.00/-  
Time Limit :Two Months

## SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P.
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	34.31	Per Cubic metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	34.31	Per Cubic metre				
Total							

Executive Engineer  
Balljath Division  
H.P.P.W.D., Balljath

# **D.N.I.T/ SCHEDULE OF QUANTITY**

Name of work :- C/O Baijnath Chobin Balander Road Km 0/00 to 14/200.

(Sht- P/L 80mm thick Paver Block at Km 0/620 to 0/640).

Estimated Cost: Rs. 415879.00

Earnest Money: Rs. 8,400.00

Time Limit : Two Months

## **SCHEDULE OF WORKS**

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm( forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	17.88	Cum				
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.38	Cum				
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge 80mm ( Eighty millimeter ) thick cement concrete paver block of M-35 grade with approved colour, design & pattern.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	173.95	Sqm				
<b>TOTAL</b>							

Executive Engineer  
Baijnath Division  
H.P.D.W.D. Baijnath



**DNIT/DRAFT SCHEDULE OF QUANTITY**

10

Name of work: R/D on Kunsal Nohra Bahi Road km 0/00 to 3/00.

(Sh:- C/O RAWall for protection of Vijay Kumar house at RD 2/310 to 2/315 ). D+R

Estimate Cost: 2,87,545.00/-

Earnest Money: 5,800.00/-

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.70	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidentals complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	56.10	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.30	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.00	Each			
<b>Total</b>						

Executive Engineer  
Bali Division  
H.P.R.D., Balinath

**DNIT/DRAFT SCHEDULE OF QUANTITY**

11 (a)

<b>Name of Work :-S/R to Type -III Qaurter Single storey at HPPWD Baijnath</b> <b>(Sh:-Providing and Fixing water supply and Saintary Installation &amp; Distempering work, Painting work, Tile flooring i/c WS and S/fitting)</b>				<b>Estimate Cost:2,28,054.00</b> <b>Earnest Money:4600.00</b> <b>Time Limit : Two Months</b>		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing white vitreous china EWC water closet star S No 20012 ( S-10) of size 57x35x39 (Fifty Seven into thirty five into thirty nine ) cm with Jet pressure and with 10 litre(Ten litre) low level PVC cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm(Forty) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required of Hindware or Equivalent to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each			
2	Providing and fixing wash basin with C.I. brackets, of DELTA NO 10010 of size 55x40 (Fifty Five into forty )CM with pedestal of HINDWARE or equivalent with, 32 mm (Thirty two) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China.to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each			
3	Providing and fixing PVC waste pipe for wash basin sink,i/c check nut to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each			
4	Providing and fixing 100mm (Hundred )dia CP iron grating of ESS-KSS for nalhni trap to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	4.00	Each			
5	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan.to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each			



6	Providing and fixing 600x450(Six hundred into Fifty) mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm(Six) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete to the entire satisfaction and direction of Engineer in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
7	Providing and fixing 600x120x5(Six hundred into One hundred twenty into five) mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm(Forty) long screws, rawl plugs etc., complete to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
8	600 mm (Six hundred)long towel rail with total length of 645 mm,(Six hundred forty five) width 78 mm( Seventy eight) and effective height of 88 mm( Eighty eight ), weighing not less than 190 gms(One hundred ninety),to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
9	Providing and fixing chromium plated brass soap dish of Jaguwar or contra with C.P. brass brackets fixed to wooden cleats with C.P. brass screws to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each		
10	Providing and fixing C.P. brass long nose bib cock F-330011 HINDWARE or equivalent single control of approved quality conforming to IS standards. 15 mm (Fifteen) nominal bore to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	3.00	Each		
11	Providing and fixing CP brass stop cock ( concealed) of standred design and app. F-330043 of HINDWARE 15mm (Fifteen) nominal bore to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	6.00	Each		
13	Providing and Fixing Sink Mixer F-330023 of HINDWARE 15 mm(Fifteen) Jaquar or equivalent as per direction complete. to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		



14	Providing and Fixing Pillar tap F-330014 of HINDWARE 15 mm(Fifteen) Jaquar or equivalent as per direction complete.to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
15	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm,( Forty) including painting of fittings and brackets, cutting and making good the walls wherever required :to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
16	Providing and fixing uplasticised PVC connection pipe with brass unions :15 mm (Fifteen) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	5.00	Each		
17. a	Providing and fixing Polyethylene-Aluminium Polyethylene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre(One metre) spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge.1216 and 1620 Concealed work, including cutting chases and aking good the wall etc.16 mm (Sixteen) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	30.00	Rmt		
17. b	Providing and fixing Polyethylene-Aluminium Polyethylene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre(One metre) spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge.1216 and 1620 Concealed work, including cutting chases and aking good the wall etc.25 mm (Twenty five) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	20.00	Rmt		

18	Providing and fixing G.I. pipes complete with G.I. Fittings including trenching and refilling etc. 20 mm (Twenty) complete as per direction of the engineer in charge. 1216 and 1620 Concealed work, including cutting chases and aking good the wall etc. 25 mm (Twenty five) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	18.00	Rmt		
19 a	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. 75 mm (Seventy five) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	12.00	Each		
19 b	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. 110mm (One hundred ten ) to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	12.00	Each		
20 a	Providing and fixing PVC Single Equal Branch with oval asses ISI Marked insertion rubber washer 3 mm(Three) thicj bolt and nuts complete i/c fixing with approved adhesive etc. Complete. 75 mm (Seventy five) as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each		
20 b	Providing and fixing PVC Single Equal Branch with oval asses ISI Marked insertion rubber washer 3 mm(Three) thicj bolt and nuts complete i/c fixing with approved adhesive etc. Complete. 100 mm (One hundred) as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each		
21	Providing and fixing ISI marked of self cleaning design including fixing with approved adhesive , cost of cutting and making good the wall and floor etc. Complete for size 110x75 mm (One hundred ten into seventy five).as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	4.00	Each		




22	Providing and placing water tank of makes (sintex) having capacity 1000 litres (One thousands litres) each with necessary fitting i/c over flow pipes scour pipe and bull valve and with cover locking arrangement i/c providing pads of sizes as required for inlet and outlet and inside painting of good quality all complete as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each			
23	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works including Carriage of Material with in all lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	96.00	Kg			
24	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty gms/litre) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coat as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	169.69	Sqm			
25	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	50.91	Sqm			
26	Applying Baijnathla white care wall putty over plaster surface after throughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	50.91	Sqm			
27	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point nine zero) ( over existing old paint of approved brand and manufacture as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	87.19	Sqm			



28	15 mm (Fifteen) cement plaster in single coat on rough side of brick/ stone masonry for interior plastering upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	19.49	Sqm			
29	Providing and laying cement concrete 1:3:6 crushed/broken stone aggregate 20mm (Twenty) nominal size and curing complete, excluding cost of form work in foundation and plinth.as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	0.35	Cum			
30	Providing and laying antiskid Ceramic glazed tiles of size 300x300 mm (Three hundred into three hundred for 300x450 mm(Three hundred into four hundred fifty) ( thickness to be specified by the manufacturer) of 1st Quality conforming to IS 15622 of approved make in colour such as white , Ivory, Grey fume red brown laid on 20 mm(Twenty) thick cement mortar 1:4 ( One cement:4 coarse sand) jointing with grey cement slurry @3.30 kg/sqm (Three point three zero) kg/sqm) including pointing the joints with white cement and matching pigment etc. complete.as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	17.49	Sqm			
31	Providing and laying ceramic glazed tiles skirting in different sizes 300x450/300x600 mm (Three hundred into four hundred fifty /three hundred into six hundred ) (thickness to be specified by the manufacturer) with water absorption less than 0.08%(zero point zero eight ) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm(twenty thick cement mortar 1:3 (1 cement : 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm(three point three) including grouting the joints with white cement and matching pigments etc., complete as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	14.40	Sqm			
32	Wall painting with acrylic exterior emulsion paint of approved brand and manufacture to give an even shade as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	134.29	Sqm			
33	Renewing glass panes and refixing existing wooden fillets: float glass 4 mm (Four)thick as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.52	Sqm			

34	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm(one point four) in both directions with wire of dia 0.63 mm,(zero point sixty three) for doors, windows and clerestory windows with hinges and necessary screws 35 mm (thirty five) thick as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.60	Sqm		
35	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (Eighteen) thick stone slab over 20 mm(Twenty) (average) thick base of cement mortar 1:4 (one cement : four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.98	Sqm		
36	Providing and fixing Electric tube complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	4.00	Each		
37	Providing and fixing Exhaust fan complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each		
38	Providing and fixing Gysr 15 Liter (Fifteen) complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		
39	Providing and fixing Solar Light of 150 W (One hundred fifty) in built battery complete in all respect as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each		

40	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm ( forty ) nominal size) as per entire satisfaction and direction of Engineer in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	6.71	Cum			

  
 Executive Engineer  
 Bailnath Division  
 H.P.W.D., Bailnath