



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

SHORT TERM NOTICE INVITING TENDERS

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **24/09/2024** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **23/09/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **21/09/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o link road from National Highwar Near Pnjab Kesri Office towards Neugal River from Hotel in G.P Pharer (SW:- P/L CC work) (Deposit work)	3,74,601/-	7400/-	Three Months	350/-
2	C/o link road from Chambi to Wah (SW:- Cutting in earth work in Km. 2/800 to 3/160)	4,07,166/-	8000/-	Three Months	350/-
3	1)Hydraulic Data of 40.00 mtr span bridge over Maul Khad at Rd 3/890 on Gallu Bhoda Shivr Nagar road 0/00 to 12/025 (PMGSY-III) (PKG No. HP-04-444) 2) Bridge estimate of 40.00 mtr span bridge over Maul Khad at Rd 3/890 on Gallu Bhoda Shivr Nagar road 0/00 to 12/025 (PMGSY-III)	1,18,000/-	2000/-	Three Months	350/-
4	C/o link road from Main road to Punjab Kesri office Pharer Colony (SW:- P/L CC work at Rd 0/00 to 0/065.50) (DC Deposit work)	1,62,348/-	3300/-	One Month	350/-
5	C/o link road near Village Bhattu (SW:- P/L CC work at Rd 0/00 to 0/047.50) (Deposit work)	99,780/-	2000/-	One Month	350/-
6	C/o Tikker to Balbhurian road Km. 0/0 to 4/0 (SW:- C/o 900mm dia Hume Pipe culvert at Rd 0/310)	2,59,981/-	5200/-	Three Months	350/-
7	C/o link road from Harbaral to Machalaina Km. 0/0 to 2/0 (SW:- C/o U-Shape drain in Km. 0/470 to 0/645) (RHS) and Km. 0/470 to 0/545) (LHS)	2,80,565/-	5600/-	Three Months	350/-
8	C/o Mansimbal to Satrehar road Km. 0/0 to 1/800 (SW:- C/o E/Wall at Rd 0/950 to 0/960 & V-Shape drain in Rd 0/920 to 0/960 & P/L CC pavement at Rd 0/920 to 0/950)	1,40,027/-	2900/-	Two Months	350/-
9	C/o Galu Ghanetta Baba Kripa Chahar Khola road Km. 0/00 to 4/00 (SW:- C/o U-Shape Drain at Rd 1/000 to 1/100)	1,12,875/-	2300/-	Two Months	350/-
10	C/o Kona Pihri Na Nahllian road Km. 0/0 to 5/00 (SW:- C/o PCC R/Wall at Rd 2/548 to 2/556)	4,88,660/-	9700/-	Two Months	350/-
12	C/o link road to village Khajurnu Km. 0/0 to 1/00 (SW:- P/L Interlocking Paver Blocks at Rd 0/0 to 0/050)	2,74,800/-	5400/-	Two Months	350/-
13	Restoration of rain damages on Malnu to Malnu road Km. 0/0 to 2/400 (SW:- C/o R/Wall at Rd 0/005 to 0/019)	2,42,318/-	4800/-	Two Months	350/-
14	Restoration of rain damages on Dehan ARTH Malag road km. 0/0 to 10/00 (SW:- P/L Crate work at Rd 5/990 to 6/000 (under SDRF)	1,76,650/-	3500/-	Two Months	350/-
15	C/o link road from Kiarwan to Gharana via Tibbi Badrer 9Jaladhari Temple) (SW:- C/o R/Wall at Rd 0/290 to 0/299.50 LHS)	2,42,978/-	4900/-	Two Months	350/-



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

16	C/o Duhak Kalan to Duhak Khurad road Km. 0/0 to 1/625 (SW:- C/o Breast wall at Rd 0/940 to 0/960)	2,18,950/-	4400/-	Two Months	350/-
17	C/o Bhagolu da Ghatta to Umri via Mohrian Km. 0/0 to 4/00 (SW:- P/L CC work at Rd 1/265 to 1/365 & R/Wall at Rd 0/390 to 0/399) (under SCDP)	4,88,292/-	9700/-	Two Months	350/-
18	Restoration of ran damages on Bhadal Kathiara road Km. 0/00 to 4/000 (SW:- C/o R/Wall at Rd 2/835 to 2/850, V-Shape drain at Rd 2/900 to 2/940 & U-shape drain at Rd 3/320 to 3/360)	2,56,920/-	5100/-	Two Months	350/-
19	C/o 19.75 metre span RCC T-Beam over Rian Khad on Sullah Majhakra Harbaral road at Rd 0/360 (SW:- C/o approaches Chowki side from Rd 0/363.50 to 0/375 Downstream side)	4,98,425/-	10000/-	Three Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK


Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2024-25/- 7642-7100

Dated:- 13/9/2024

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD. Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- C/o link road from National Highway Near Punjab Kesri Office toward Neugal River from Hotel in G.P Pharer.
(SH:-P/L CC work). (Deposit Work)

Estimated Cost :- Rs. 3,74,601/-
Earnest Money :- Rs. 7400/-
Time Limit :- Three Months

S. No	Description of item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	54.29			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- C/o Link road from Chambli to Wah. (SH:- Cutting in earth work in Km 2/800 to 3/160).

Estimate Cost :- Rs. 4,07,166/-

Earnest Money :- Rs. 8000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil soft Rock, Hard rock, chisseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302,1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unuseful material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 133.79cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2051.44			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

SOQ

WORK:- 1.)HYDRAULIC DATA OF 40.00 MTR SPAN BRIDGE OVER MAUL KHAD AT RD 3/890
ON GALU BHODA SHIVNAGAR ROAD 0/00 TO 12/025. (PMGSY-III)
(PKG NO:-HP-04-444)
2.) BRIDGE ESTIMATE OF 40.00 MTR SPAN BRIDGE OVER MAUL KHAD AT RD 3/890
ON GALU BHODA SHIVNAGAR ROAD 0/00 TO 12/025. (PKG NO:-HP-04-444)

ESTIMATED COST:- 118,000.00
EARNEST MONEY:- 2,000.00
TIME LIMIT :- THREE MONTHS

Sub Head : Preparation of Hydraulic data & Estimate of Bridge

Sr. No.	Description of Items	NO./QTY./IO B	Unit	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES
1	2	3	4	5	6	7
1	PREPARATION OF HYDRAULIC DATA COMPLETE IN ALL RESPECT IN MANUSCRIPT FORM AND SUBMISSION OF THE SAME IN HIGHER OFFICE FOR APPROVAL. IF ANY CORRECTION/AMENDMENT HAS DESIRED BY THE HEAD OFFICE THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY THE ENGINEER-IN-CHARGE AND HIGHER OFFICE COMPLETE IN ALL RESPECT, AFTER APPROVAL OF THE HYDRAULIC DATA FROM THE HIGHER OFFICE, THE SAME WILL BE SUBMITTED IN FAIR SHAPE TO THIS OFFICE IN TWO NUMBERS OF COPIES AND PAYMENT SHALL BE MADE AFTER THE APPROVAL OF THE SAME BY THE HIGHER OFFICE. THE RATE SHALL BE INCLUSIVE OF ALL TAXES IMPOSED BY THE GOVERNMENT.	1.000	JOB			
1	PREPARATION OF BRIDGE ESTIMATE IN SHAPE OF MANUSCRIPT ALONG WITH DRAWING WHICH INCLUDE THE FOLLOWING PROVISIONS AS GIVEN BELOW :- AND DRAWING COMPLETE IN ALL RESPECT IN MANUSCRIPT FROM AND SUBMISSION OF THE SAME IN HIGHER OFFICE FOR APPROVAL. IF ANY CORRECTION/AMENDMENT HAS DESIRED BY THE HEAD OFFICE THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY ENGINEER-IN-CHARGE COMPLETE IN ALL RESPECT. AFTER APPROVAL THE SAME SHOULD BE SUBMITTED IN TWO NO. SET OF THE FAIR DPR AND DRAWING AGAIN IF ANY CORRECTION/AMENDMENT AS DESIRED BY HEAD OFFICES. THE RATES ARE INCLUSIVE OF ALL TAXES I.E GST.	1.000	JOB			
TOTAL						

Amulya
EXECUTIVE ENGINEER
BHARNA DIVISION
HPPWD BHAWANNA

Schedule of Quantity

Name of Work :- C/o link road from Main road to Punjab Kesri Office Pharer Colony. (SH:-P/L CC work at RD 0/00 to 0/065.50).
(Deposit Work)

Estimated Cost :- Rs. 1,62,348/-
Earnest Money :- Rs. 3300/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.76			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.93			Per Cubic metre	
Total :-						


Executive Engineer
Bhawanra Division
HP PWD Bhawanra

Schedule of Quantity

Name of Work :- C/o link road near Village Bhattu. (SH:-P/L CC work at RD 0/00 to 0/047.50). (Deposit Work)

Estimated Cost :- Rs. 99,780/-
Earnest Money :- Rs. 2000/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.63			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of Tikker to Balbhurian Road Km 0/0 to 4/0. (SH:- C/o 900mm dia Hume Pipe culvert at RD 0/310).

Estimate Cost :- Rs. 2,59,981/-
Earnest Money :- Rs. 5200/-
Time Limit :- Three Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	38.49			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M O R D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	3.94			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (Twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetra and the like including the cost of form work as per drawings and M O R D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.07			Per Cubic metre	
4	Providing and laying (- to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement into two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M O R D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	7.50			Per Running metre	

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	29.40			Per Cubic metre
6	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5			Each

Total :-


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of work:- Construction of Link Road From Harbaral to Machalaina Km 0/0 to 2/0. (SH:- C/o U-shape drain in Km 0/470 to 0/645 (RHS) and Km 0/470 to 0/545 (LHS)).

Estimate Cost :- Rs. 2,80,565/-
Earnest Money :- Rs. 5600/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	96.26			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M O R D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	57.00			Per Cubic metre	
Total:-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work:- C/o Mansimbal to Satrehar road km 0/0 to 1/800. (SH:- C/o E/wall at Rd 0/950 to 0/960 & V-Shape drain in Rd 0/920 to 0/960 & P/L CC pavement at Rd 0/920 to 0/950).

Estimate Cost :- Rs. 1,40,027/-

Earnest Money :- Rs. 2900/-

Time Limit :- Two Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	11.61			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	4.96			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana toll tax sale tax or other taxes imposed by the Government	7.20			Per Cubic metre	
4	Providing and laying 100mm o a (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V) 20 (H) (one vertical twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax GST or other taxes imposed by the Government.	10.00			Each	

5	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 1 ½ 3 (One cement isto one and half sand three graded crushed stone aggregate) 20mm (Twenty millimetre) nominal mix) design to obtain the minimum compressive strength of grade M-25 (M- twenty five) in sub structure as per drawing and M.O.R.D technical specification clause 802, 804, 805, 806, 807, 1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work including curing complete including carriage of material within all leads, lifts and other incidental as per the directions of the Engineer-in-charge. The rate including of octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government. Government.	12 00			Each
Total:-					


 Executive Engineer,
 Bhawarna Divison.
 HP PWD Bhawarna.

Schedule of Quantity

Name of Work:- Construction of Galu Ghanetta Bab Kripa Chahar Khola Road Km. 0/00 to 4/000.(SH:-C/O U-Shape Drain at Rd 1/000 to 1/100).

Estimate Cost :- Rs.1,12,875/-
Earnest Money :- Rs. 2300/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	42.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	22.75			Per Cubic metre	
Total:-						


Executive Engineer,
Bhawana Division,
HP PWD Bhawana.

Schedule of Quantity

Name of Work:- C/o Kona Pihri Nahlian road Km 0/0 to 5/00 (SH:- Construction of PCC R/wall at RD 2/548 to 2/556).

Estimate Cost :- Rs. 4,88,660/-
Earnest Money :- Rs. 9700/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	81.44			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	115.20			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Each	
Total:-						

Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.


Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.

Schedule of Quantity

Name of Work : C/o link road to Village Khajurnu Km 0/0 t 1/00 (SW:- P/L Interlocking Paver Blocks at Rd 0/0 to 0/050).

Estimated Cost :- Rs. 2,74,800/-
Earnest Money :- Rs. 5400/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.50			Per Cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	135.00			Per Square metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.85			Per Cubic metre	
					Total :-	


Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.

Schedule of Quantity

Name of Work:- Restoration of rain damages on Malnu to Malnu road Km 0/0 to 2/400, (SH:-C/o R/Wall at Rd 0/005 to 0/019).

Estimate Cost :- Rs.2,42,318/-

Earnest Money :- Rs. 4800/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.27			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.50			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.00			Each	
Total:-						

Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.


Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.

Schedule of Quantity

Name of work:- Restoration of rain damages on Dehan Arth Malag Road Km 0/0 to 10/00. (SH:- P/L Crate work at RD 5/990 to 6/000). (Under SDRF)

Estimate Cost :- Rs. 1,76,650/-
Earnest Money :- Rs. 3500/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	56.60			Per Cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 150mm x150mm (One Hundred Fifty millimetre intoOneHundred Fifty millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	62.50			Per Cubic metre	
Total:-						



Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of work:- Construction of link road from kiarwan to Gharana Via Tibbi Badrer (Jaladhari Temple) (SH:- Construction of R/wall at RD 0/290 to 0/299.50 LHS).

Estimated Cost :- Rs. 2,42,978/-
Earnest Money :- Rs. 4900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.67			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.14			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24			Each	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of work:- Construction of Duhak Kalan to Duhak Khurad road Km 0/0 to 1/625. (SW):- Construction of Breast wall at RD 0/940 to 0/960).

Estimate Cost :- Rs. 2,18,950/-
Earnest Money :- Rs. 4400/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.40			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	52.40			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19			Each	
Total:-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- C/O Bhagolu da Ghatta to Umari Via Mohrian Km. 0/00 to 4/00(SH:- P/L CC Work at Rd 1/265 to 1/365 & R/Wall at Rd 0/390 to 0/399),(Under SCDP)

Estimate Cost :- Rs. 4,88,292/-
Earnest Money :- Rs. 9700/-
Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	24.30			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	53.28			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24			Each	
4	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38.13			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- Restoration of rain damages on Bhadal Kathiara Road Km. 0/00 to 4/000 (SH:- C/O R/Wall at Rd.2/835 to 2/850, V-Shape Drain at Rd 2/900 to 2/940 & U-Shape Drain at Rd. 3/320 to 3/360).

Estimate Cost :- Rs. 2,56,920/-
Earnest Money :- Rs. 5100/-
Time Limit :- Two Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	36.96			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	15.20			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	43.32			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	24			Each	
Total:-						21500

Murvi
Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work:- C/o 19.75 mtr Span RCC T-Beam Bridge over Rain Khad on Sullah Majhakra Harbaral road at Rd 0/360 (SW:- C/O Approches Chowki Side From Rd 0/363.50 to 0/375 Downstream side).

Estimate Cost :- Rs. 4,98,425/-
Earnest Money :- Rs. 10000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46.02			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M O R D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	116.82			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	29.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.70			Per Cubic metre	
				Total:-		

Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.


Executive Engineer,
Bhawarna Division,
HP PWD Bhawarna.