HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827
e-mail: ee-seraj-hp@gov.in

No. PW. SRJ/ CB /TA/ 2024-25 5025 Dated:- 19/9/2024

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar
Shimla-2

Subject:- **Regarding publication of the tender on departmental site**

Enclosed please find herewith the copies of notice inviting tender for the up-loading on department web –site before 25-09-2024 as per notification issued by the Pr. Sec. (PW) to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 16th July2021. As the works mentioned in the Tender Notice are urgent in nature.

DA:- As above

Executive Engineer,
HPPWD Division
Seraj at Janjehli

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827
e-mail: ee-seraj-hp@ gov. in

NOTICE INVITING TENDER

Sealed item rate short terms tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, Division, HP.PWD. Seraj at Janjehli Distt. Mandi (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class "C and D" so as to reach in this office on 26-09-2024 upto 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of contractors or their authorised representative who wish to be present at that time. The application for obtaining the tender form will be received on 25-09-2024 between 10.00 A.M. to 1:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 25-09-2024 between 11.00 AM to 5.00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, Division, HP.PWD. Seraj at Janjehli Distt. Mandi H.P. must accompany with the tender form. Ambiguous/ Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. **The Executive Engineer, Division, HP.PWD. Seraj at Janjehli reserve the right to reject/accept any offer of tender without assigning any reasons.**

Sr. No	Name of work	Estimated Cost	Earnest Money	Cost of Tender	Eligible class of Contractor
1	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/450) under SCDP	439787/-	10000/-	350/-	C&D
2	Construction of Brayogi Thanser Magrugalla road in Km. 0/00 to 8/510 (SH;- C/o 2.00 mtr slab culvert at RD. 0/275) under OTMNP CCN 2022-307-4281	499997/-	10000/-	350/-	C&D
3	Construction of road from Sudash to khunachi road in km. 0/00 to 1/500 (SH;- C/o 900mm dia hume pipe culvert at RD. 0/630)CCN-2019-307-1287 under SCDP	457007/-	9100/-	350/-	C&D
4	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/450) under SCDP	428736/-	10000/-	350/-	C&D
5	Construction of road from Mehach to Deori in Km. 0/00 to 7/500 (SH;- c/o 900 mm dia hume pipe culvert at RD. 1/120) CCN-2022-307-4609 under OTMNP	463561/-	9300/-	350/-	C&D
6	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/00) under SCDP	427938/-	10000/-	350/-	C&D
7	Construction of road from Gadagusain Thunadigard road in Km. 0/00 to 6/00 (SH;- C/o 900 mm dia hume pipe culvert at RD. 1/135) CCN-2008-307-55845 under OTMNP	286839/-	5700/-	350/-	C&D
8	Construction of road from Kohlugad to Rutatan road in Km. 0/00 to 6/500 (SH;- Providing and Laying Kharanja stone soling in Km. 0/700 to 0/900) CCN-2019-307-841 under OTMNP	224082/-	4500/-	350/-	C&D
9	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of slab and wing wall for 6.00 mtrs span RCC slab culvert at RD. 0/450) under SCDP	493527/-	10000/-	350/-	C&D

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827
e-mail: ee-seraj-hp@ gov. in

NOTICE INVITING TENDER

Sealed item rate short terms tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, Division, HP.PWD. Seraj at Janjehli Distt. Mandi (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class "C and D" so as to reach in this office on 26-09-2024 upto 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of contractors or their authorised representative who wish to be present at that time. The application for obtaining the tender form will be received on 25-09-2024 between 10.00 A.M. to 1:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 25-09-2024 between 11.00 AM to 5.00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, Division, HP.PWD. Seraj at Janjehli Distt. Mandi H.P. must accompany with the tender form. Ambiguous/ Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. **The Executive Engineer, Division, HP.PWD. Seraj at Janjehli reserve the right to reject/accept any offer of tender without assigning any reasons.**

Sr. No	Name of work	Estimated Cost	Earnest Money	Cost of Tender	Eligible class of Contractor
1	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/450) under SCDP	439787/-	10000/-	350/-	C&D
2	Construction of Brayogi Thanser Magrugalla road in Km. 0/00 to 8/510 (SH;- C/o 2.00 mtr slab culvert at RD. 0/275) under OTMNP CCN 2022-307-4281	499997/-	10000/-	350/-	C&D
3	Construction of road from Sudash to khunachi road in km. 0/00 to 1/500 (SH;- C/o 900mm dia hume pipe culvert at RD. 0/630)CCN-2019-307-1287 under SCDP	457007/-	9100/-	350/-	C&D
4	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/450) under SCDP	428736/-	10000/-	350/-	C&D
5	Construction of road from Mehach to Deori in Km. 0/00 to 7/500 (SH;- c/o 900 mm dia hume pipe culvert at RD. 1/120) CCN-2022-307-4609 under OTMNP	463561/-	9300/-	350/-	C&D
6	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of both side abutment up to 2.20 mtr hight for 6.00 meter span RCC slab culvert at RD. 0/00) under SCDP	427938/-	10000/-	350/-	C&D
7	Construction of road from Gadagusain Thunadigard road in Km. 0/00 to 6/00 (SH;- C/o 900 mm dia hume pipe culvert at RD. 1/135) CCN-2008-307-55845 under OTMNP	286839/-	5700/-	350/-	C&D
8	Construction of road from Kohlugad to Rutatan road in Km. 0/00 to 6/500 (SH;- Providing and Laying Kharanja stone soling in Km. 0/700 to 0/900) CCN-2019-307-841 under OTMNP	224082/-	4500/-	350/-	C&D
9	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of slab and wing wall for 6.00 mtrs span RCC slab culvert at RD. 0/450) under SCDP	493527/-	10000/-	350/-	C&D

10	Construction of road from Tapnali to Khauli road in Km. 0/00 to 15/00 (SH;- Providing and Laying Kharanja stone soling in Km. 2/560 to 2/610,2/640 to 2/800,2/850 to 2/895 and 3/490 to 3/550)	379538/-	7600/-	350/-	C&D
11	Construction of Link road Bagla via Damedi Khad (Param ka Gharat) village Thanar in GP Gudah Km. 0/00 to 2/400 (SH;- Construction of slab and wing wall for 6.00 mtrs span RCC slab culvert at RD. 0/00) under SCDP	484346/-	10000/-	350/-	C&D
12	RRD on various roads under Chhatri Sub- Division (SH;- Removal of slips and Land slide in various roads (1) Brayogi Thansern Magrugalla road Km. 4/800 to 4/920, 5/150 to 5/270. (2) Chhatri Magrugall via Bilgad road in Km. 5/150 to 5/270 (3) Brayogi Kakradhar road in Km. 1/160 to 1/280 (4) Chhatri magrugalla road via lassi road in Km. 3/020 to 3/140)	475445/-	10000/-	350/-	C&D

1 The contractors/firms are required to quote their rates clearly percentage rate, failing which the tender is liable to be rejected

2 The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.

3 The contractor will produce show their enlistment/renewal documents at the time of obtaining tender

4 Latest Income tax and s GST tax clearance certificates as well as Pan Number and GST number must be attached with the application failing which tender documents will not be issued.

5 The tender forms will be issued to only those contractors who have not more than two works in hand in any of HP.PWD. Circles.

6 The tender forms will not be issued to those contractors whose performance is not found satisfactory

Executive Engineer
Seraj Division
HPPWD Janjehli

No. PW-SRJ/NIT/2024-25- 503-24 Dated 19-4-2024

1 Copy to the director , Information and publication Department HP Shimla for favour of publication in one regional newspaper and one National newspaper.
2 Copy to the superintending Engineer 1st Circle HPPWD mandi for information please
3 Copy to Sub- Divisional office (Civil)Thunag Tehsil Thunag for information please.
4 Copy to Block Development office Janjehli Tehsil Thunag Distt. Mandi HP.
5 All the Assistant Engineer working under this Division .
6 Copy to Drawing Branch & Account Branch
7 Notice board of this office.

Executive Engineer
Seraj Division
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: 4,39,787.00 Only
Earnest Money: 10,000.00 Only
Time : Two months

Name of Work :- **Construction link road Bagla via Damedi khad (Perma ka Gharat) village Thanar in GP Gudah Km 0/00 to 2/400 (S.H:- Construction Both side abutment up to 2.20 m height for 6.000 meter span RCC slab culvert at RD 0/450) Under SCDP**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Course rubble Stone masonry second short) work in cement mortar 1:5(one cement : five sand)for sub structure complete as per drawing and technical specification clauses 702,704,1202 and 1206 and curing complete including carriage of materials with in all leads and lifts as per the direction of Engineer-in- Charge.	75.77	Per Cubic metre	5,699.10	4,31,821.00	Rupees Four Lakh(s) Thirty One Thousand Eight Hundred Twenty One Only
2.00	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads , lifts and carriage of materials and other incidentals .	20.00	Rach	398.30	7,966.00	Rupees Seven Thousand Nine Hundred Sixty Six Only
	Quated Rate in figure		**Total:-**		4,39,787.00	
	Quated Rate in words					

Executive Engineer
H.P.P.W.D. Division
Seraj at Banjahli

BILL OF QUANTITY (2)

Estimate Cost: Rs 4,99,997.00 Only
Earnest Money: 10,000.00 Only
Time :- Two Months

Name of Work:- Construction of Baryogi Thanser Magrugalla road in km. 0/000 to 8/510.(SH:- Construction of 2.00 metre slab culvert at Rd. 0/275). Under OTMNP CCN 2022-307-4281.

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filing the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	27.93	Per Cubic metre	552.35	15427.00	Rupees Fifteen Thousand Four Hundred Twenty Seven Only
2	Providing and laying plain concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) 40 mm (fourty millimetre) nominal size in open foundation complete as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	10.10	Per Cubic metre	5236.10	52885.00	Rupees Fifty Two Thousand Eight Hundred Eighty Five Only
3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 & 1203. P.C.C. M-10 grade (1:3:6) as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	48.09	Per Cubic metre	6085.00	292628.00	Rupees Two Lakh(s) Ninety Two Thousand Six Hundred Twenty Eight Only
4	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC M-20 For nominal mix 1:2:4 upto 5 m height Bed block & Dirt wall including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	3.90	Per Cubic metre	7331.20	28592.00	Rupees Twenty Eight Thousand Five Hundred Ninety Two Only
5	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M25 upto any height complete within all leads, lifts carriage of material and other incidentials and as per the entire satisfaction and direction of Engineer-in-Charge	5.85	Per Cubic metre	8504.55	49752.00	Rupees Forty Nine Thousand Seven Hundred Fifty Two Only
6	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	0.471	Per Tonne	101321.15	47722.00	Rupees Forty Seven Thousand Seven Hundred Twenty Two Only

7	Back filling behind abutment, wing wall and return walls complete as per drawing and technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	8.80	Per Cubic metre	1262.25	11108.00	Rupees Eleven Thousand One Hundred Eight Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads and lifts as per direction of the Engineer-in-Charge.	5.00	Each	376.50	1883.00	Rupees One Thousand Eight Hundred Eighty Three Only
			Total		**4,99,997.00**	
	Quated Rate in Figure					
	Quated Rate in Word					

Executive Engineer
Seraj Division (B&R)
HPPWD Janjehli

BILL OF QUANTITY (3)

Estimate Cost: Rs 4,57,007.00 Only
Earnest Money: 9,100.00 Only
Time :- Two Months

Name of Work :- Construction of road from Sudas to Khunachi road in km 0/000 to 1/500 (SH:- Construction of 900 mm dia hume pipe culvert at RD 0/630) CCN-2019 -307-1287 (Under SCDP)

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	63.85	Per Cubic metre	552.35	35,268.00	Rupees Thirty Five Thousand Two Hundred Sixty Eight Only
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	4.90	Per Cubic metre	4697.60	23,018.00	Rupees Twenty Three Thousand Eighteen Only
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materialwithin all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	5.46	Per Cubic metre	5236.10	28,589.00	Rupees Twenty Eight Thousand Five Hundred Eighty Nine Only
4	Cours rubble masonry Stone masonry in cement mortar In (1:5)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	8.27	per Cubic metre	5699.10	47,132.00	Rupees Forty Seven Thousand One Hundred Thirty Two Only
5	Random rubble masonry Stone masonry in cement mortar In (1:6)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	18.94	per Cubic metre	5558.90	1,05,286.00	Rupees One Lakh(s) Five Thousand Two Hundred Eighty Six Only
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	39.90	per Cubic metre	3980.50	1,58,822.00	Rupees One Lakh(s) Fifty Eight Thousand Eight Hundred Twenty Two Only

7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation , protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900mm (nine hundred millimeter) dia including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	7.50	Per Running metre	4499.00	33,743.00	Rupees Thirty Three Thousand Seven Hundred Forty Three Only
8	Providing and laying cement concrete 1 : 5 : 10 (one cement : five sand : ten graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in R/wall ,B/wall as per drawing and HPPWD technical specifications 802,803,1202, and 1203 within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. . .	2.40	Per Cubic metre	4723.00	11,335.00	Rupees Eleven Thousand Three Hundred Thirty Five Only
9	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	15.00	Each	398.30	5,975.00	Rupees Five Thousand Nine Hundred Seventy Five Only
10	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	6.00	per Cubic metre	1306.55	7,839.00	Rupees Seven Thousand Eight Hundred Thirty Nine Only
	Quated Rate in Figure		**Total**		**4,57,007.00**	
	Quated Rate in Word					

Executive Engineer
Seraj Division (B&R)
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: 4,28,736.00 Only
Earnest Money: 10,000.00 Only
Time : Two months

Name of Work :- **Construction link road Bagla via Damedi khad (Perma ka Gharat) village Thanar in GP Gudah Km 0/00 to 2/400 (S.H:- Construction Both side abutment 2.20 m height to top for 6.000 meter span RCC slab culvert at RD 0/450) Under SCDP**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Course rubble Stone masonry second short) work in cement mortar 1:5(one cement : five sand)for sub structure complete as per drawing and technical specification clauses 702,704,1202 and 1206 and curing complete including carriage of materials with in all leads and lifts as per the direction of Engineer-in- Charge.	60.28	Per Cubic metre	5,699.10	3,43,542.00	Rupees Three Lakh(s) Forty Three Thousand Five Hundred Forty Two Only
2.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	55.44	Per Cubic metre	1,321.15	73,245.00	Rupees Seventy Three Thousand Two Hundred Forty Five Only
3.00	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads , lifts and carriage of materials and other incidentals .	30.00	Rach	398.30	11,949.00	Rupees Eleven Thousand Nine Hundred Forty Nine Only
			Total:-		**4,28,736.00**	
	Quated Rate in figure					
	Quated Rate in words					

Executive Engineer
H.P.P.W.D. Division
Serai at Janjehli

BILL OF QUANTITY (5)

Estimate Cost: Rs 4,63,561.00 Only
Earnest Money: 9,300.00 Only
Time :- Two Months

Name of Work :- Construction of road from Mehach to Deori in km 0/000 to 7/500 (SH:- Construction of 900 mm dia hume pipe culvert at RD 1/120)) CCN-2022 - 307-4609 (Under OTMNP)

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	63.85	Per Cubic metre	552.35	35,268.00	Rupees Thirty Five Thousand Two Hundred Sixty Eight Only
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	4.90	Per Cubic metre	4697.60	23,018.00	Rupees Twenty Three Thousand Eighteen Only
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materialwithin all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	5.46	Per Cubic metre	5236.10	28,589.00	Rupees Twenty Eight Thousand Five Hundred Eighty Nine Only
4	Cours rubble masonry Stone masonry in cement mortar In (1:5)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	8.27	per Cubic metre	5699.10	47,132.00	Rupees Forty Seven Thousand One Hundred Thirty Two Only
5	Random rubble masonry Stone masonry in cement mortar In (1:6)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	18.94	per Cubic metre	5558.90	1,05,286.00	Rupees One Lakh(s) Five Thousand Two Hundred Eighty Six Only
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	39.90	per Cubic metre	3980.50	1,58,822.00	Rupees One Lakh(s) Fifty Eight Thousand Eight Hundred Twenty Two Only

7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation , protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900mm (nine hundred millimeter) dia including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	7.50	Per Running metre	4499.00	33,743.00	Rupees Thirty Three Thousand Seven Hundred Forty Three Only
8	Providing and laying cement concrete 1 : 5 : 10 (one cement : five sand : ten graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in R/wall ,B/wall as per drawing and HPPWD technical specifications 802,803,1202, and 1203 within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. . .	2.86	Per Cubic metre	4723.00	13,508.00	Rupees Thirteen Thousand Five Hundred Eight Only
9	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	26.00	Each	398.30	10,356.00	Rupees Ten Thousand Three Hundred Fifty Six Only
10	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	6.00	per Cubic metre	1306.55	7,839.00	Rupees Seven Thousand Eight Hundred Thirty Nine Only
			Total		**4,63,561.00**	
	Quated Rate in Figure					
	Quated Rate in Word					

Executive Engineer
Seraj Division (B&R)
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: 4,27,938.00 Only
Earnest Money: 10,000.00 Only
Time : Two months

Name of Work :- **Construction link road Bagla via Damedi khad (Perma ka Gharat) village Thanar in GP Gudah Km 0/00 to 2/400 (S.H:- Construction Both side abutment 2.20 m height to top for 6.000 meter span RCC slab culvert at RD 0/000) Under SCDP**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Course rubble Stone masonry second short) work in cement mortar 1:5(one cement : five sand)for sub structure complete as per drawing and technical specification clauses 702,704,1202 and 1206 and curing complete including carriage of materials with in all leads and lifts as per the direction of Engineer-in- Charge.	60.14	Per Cubic metre	5,699.10	3,42,744.00	Rupees Three Lakh(s) Forty Two Thousand Seven Hundred Forty Four Only
2.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	55.44	Per Cubic metre	1,321.15	73,245.00	Rupees Seventy Three Thousand Two Hundred Forty Five Only
3.00	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads , lifts and carriage of materials and other incidentals .	30.00	Rach	398.30	11,949.00	Rupees Eleven Thousand Nine Hundred Forty Nine Only
			Total:-		**4,27,938.00**	
	Quated Rate in figure					
	Quated Rate in words					

Executive Engineer
H.P.P.W.D. Division
Seraj

BILL OF QUANTITY

Estimate Cost: Rs 2,86,839.00 Only
Earnest Money: 5,700.00 Only
Time :- Two Months

Name of Work :- Construction of road from Gadagusain Thunadigard road in km 0/000 to 6/000 (SH:- Construction of 900 mm dia hume pipe culvert at RD 1/135) CCN-2008 -307-55845 (Under OTMNP)

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	47.90	Per Cubic metre	552.35	26,458.00	Rupees Twenty Six Thousand Four Hundred Fifty Eight Only
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	2.58	Per Cubic metre	4697.60	12,120.00	Rupees Twelve Thousand One Hundred Twenty Only
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materialwithin all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	3.42	Per Cubic metre	5236.10	17,907.00	Rupees Seventeen Thousand Nine Hundred Seven Only
4	Cours rubble masonry Stone masonry in cement mortar In (1:5)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	7.77	per Cubic metre	5699.10	44,282.00	Rupees Forty Four Thousand Two Hundred Eighty Two Only
5	Random rubble masonry Stone masonry in cement mortar In (1:6)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	12.04	per Cubic metre	5558.90	66,929.00	Rupees Sixty Six Thousand Nine Hundred Twenty Nine Only
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	16.98	per Cubic metre	3980.50	67,589.00	Rupees Sixty Seven Thousand Five Hundred Eighty Nine Only

7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation , protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900mm (nine hundred millimeter) dia including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	7.50	Per Running metre	4499.00	33,743.00	Rupees Thirty Three Thousand Seven Hundred Forty Three Only
8	Providing and laying cement concrete 1 : 5 : 10 (one cement : five sand : ten graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in R/wall ,B/wall as per drawing and HPPWD technical specifications 802,803,1202, and 1203 within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. . .	1.91	Per Cubic metre	4723.00	9,021.00	Rupees Nine Thousand Twenty One Only
9	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	14.00	Each	398.30	5,576.00	Rupees Five Thousand Five Hundred Seventy Six Only
10	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. ..	2.46	per Cubic metre	1306.55	3,214.00	Rupees Three Thousand Two Hundred Fourteen Only
			Total		**2,86,839.00**	
	Quated Rate in Figure					
	Quated Rate in Word					

Executive Engineer
Seraj Division (B&R)
HPPWD Janjehli

BILL OF QUANTITY

Name of Work:- Construction of road from Kohlugad to Rutatan road in km. 0/000 to 6/500.(SH:- Providing and Laying Kharanja Stone soling in km. 0/700 to 0/900). CCN 2019-307-841 Under OTMNP

Estimated cost Rs. 224082.00

Earnest Money cost Rs.- 2500.00

Time - One Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filing the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	66.75	Per Cubic metre	552.35	36869.00	Rupees Thirty Six Thousand Eight Hundred & Sixty Nine Only
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	100.13	Per Cubic metre	1869.70	187213.00	Rupees One Lakh Eighty Seven Thousand Two Hundred & Thirteen Only
					2,24,082.00	
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
HPPWD Division
Seraj at Janjehli

BILL OF QUANTITY

Estimate Cost: **4,93,527.00 Only**
Earnest Money: **10,000.00 Only**
Time : Two months

Name of Work :- **Construction link road Bagla via Damedi khad (Perma ka Gharat) village Thanar in GP Gudah Km 0/00 to 2/400 (S.H:- Construction slab and wing walls for 6.000 meter span RCC slab culvert at RD 0/450) Under SCDP**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M25 upto any height complete within all leads, lifts carriage of material and other incidentials and as per the entire satisfaction and direction of Engineer-in-Charge	23.29	Per Cubic metre	8,504.50	1,98,070.00	Rupees One Lakh(s) Ninety Eight Thousand Seventy Only
2.00	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	1.43	Per Tonne	1,01,321.15	1,44,889.00	Rupees One Lakh(s) Forty Four Thousand Eight Hundred Eighty Nine Only
3.00	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 & 1203. P.C.C. M-10 grade (1:3:6) as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	2.25	Per Cubic metre	6,085.00	13,691.00	Rupees Thirteen Thousand Six Hundred Ninety One Only
4.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	13.48	Per Cubic metre	552.35	7,446.00	Rupees Seven Thousand Four Hundred Forty Six Only
5.00	Providing and laying Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	2.06	Per Cubic metre	4,697.60	9,677.00	Rupees Nine Thousand Six Hundred Seventy Seven Only
6.00	Providing and laying plain concrete 1:4:8(1 cement : 4 sand :8 graded stone aggregate 25mm nominal size) in open foundation complete as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	0.84	Per Cubic metre	5,236.10	4,398.00	Rupees Four Thousand Three Hundred Ninety Eight Only

7.00	Random rubble masonry work in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing and technical specification Clauses 702,704, 1202 & 1203. complete as per the direction of Engineer-in-Charge within all leads and lifts.	13.46	Per Cubic metre	5,558.90	74,823.00	Rupees Seventy Four Thousand Eight Hundred Twenty Three Only
8.00	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5. within all leads and lifts and other incidentals.	6.51	Per Cubic metre	3,980.50	25,913.00	Rupees Twenty Five Thousand Nine Hundred Thirteen Only
9.00	Back filling behind abutment, wing wall and return walls complete as per drawing and technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals.	11.19	Per Cubic metre	1,306.55	14,620.00	Rupees Fourteen Thousand Six Hundred Twenty Only
			Total:-		**4,93,527.00**	
	Quated Rate in figure					
	Quated Rate in words					

Executive Engineer
H.P.P.W.D. Division
Seraj Banjehli

(10)

BILL OF QUANTITY

Name of Work:-Construction of Tapnali to Khauli road in km. 0/000 to 15/000. (SH:- Providing and Laying Kharanja stone soling in km. 2/560 to 2/610, 2/640 to 2/800, 2/850 to 2/895 and 3/490 to 3/550).

Estimated cost Rs. 379538.00

Earnest Money cost Rs.- 7600.00

Time - Two Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Loosening of the ground upto a level of 300 mm (three hundred millimetre) below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	317.52	Per Square metre	71.41	22674.00	Rupees Twenty Two Thousand Six Hundred & Seventy Four Only
2	Preparation of sub grade by dressing to cambor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications. including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	317.52	Per Square metre	2.10	667.00	Rupees Six Hundred & Sixty Seven Only
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	190.51	Per Cubic metre	1869.70	356197.00	Rupees Three Lakh Fifty Six Thousand One Hundred & Ninety Seven Only
					3,79,538.00	
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
HPPWD Division
Seraj at Janjehli

(11)

BILL OF QUANTITY

Estimate Cost: 4,84,346.00 Only
Earnest Money: 10,000.00 Only
Time : Two months

Name of Work :- **Construction link road Bagla via Damedi khad (Perma ka Gharat) village Thanar in GP Gudah Km 0/00 to 2/400 (S.H:- Construction slab and wing walls for 6.000 meter span RCC slab culvert at RD 0/000) Under SCDP**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M25 upto any height complete within all leads, lifts carriage of material and other incidentials and as per the entire satisfaction and direction of Engineer-in-Charge	22.93	Per Cubic metre	8,504.50	1,95,008.00	Rupees One Lakh(s) Ninety Five Thousand Eight Only
2.00	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	1.35	Per Tonne	1,01,321.15	1,36,784.00	Rupees One Lakh(s) Thirty Six Thousand Seven Hundred Eighty Four Only
3.00	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 & 1203. P.C.C. M-10 grade (1:3:6) as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	4.50	Per Cubic metre	6,085.00	27,383.00	Rupees Twenty Seven Thousand Three Hundred Eighty Three Only
4.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	13.48	Per Cubic metre	552.35	7,446.00	Rupees Seven Thousand Four Hundred Forty Six Only
5.00	Providing and laying Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	2.06	Per Cubic metre	4,697.60	9,677.00	Rupees Nine Thousand Six Hundred Seventy Seven Only
6.00	Providing and laying plain concrete 1:4:8(1 cement : 4 sand :8 graded stone aggregate 25mm nominal size) in open foundation complete as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	0.84	Per Cubic metre	5,236.10	4,398.00	Rupees Four Thousand Three Hundred Ninety Eight Only

7.00	Random rubble masonry work in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing and technical specification Clauses 702,704, 1202 & 1203. complete as per the direction of Engineer-in-Charge within all leads and lifts.	13.46	Per Cubic metre	5,558.90	74,823.00	Rupees Seventy Four Thousand Eight Hundred Twenty Three Only
8.00	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5. within all leads and lifts and other incidentals.	6.51	Per Cubic metre	3,980.50	25,913.00	Rupees Twenty Five Thousand Nine Hundred Thirteen Only
9.00	Back filling behind abutment, wing wall and return walls complete as per drawing and technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals.	2.23	Per Cubic metre	1,306.55	2,914.00	Rupees Two Thousand Nine Hundred Fourteen Only
			Total:-		**4,84,346.00**	
	Quated Rate in figure					
	Quated Rate in words					

Executive Engineer
H.P.P.W.D. Division
Seraj at Banjehli

(12)

BILL OF QUANTITY

Estimate Cost: 4,75,445.00 Only
Earnest Money: 10,000.00 Only
Time : Two months.

Name of Work:- RR Damaged on various roads under Chhatri Sub Division (SH:- Removal of slips and land slide in various roads 1. Baryogi Thanser Magrugla road in KM 4/800 to 4/920 , 5/150 to 5/270. 2. Chhatri Magrugala via Bilagad road in KM 5/150 to 5/270. 3. baryogi Kakradhar road in KM 1/160 to 1/280 . 4. Chatri magrugala road via Lassi road in KM 3/020 to 3/140 .

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	4025.78	Cum	118.10	4,75,445.00	Rupees Four Lakh(s) Seventy Five Thousand Four Hundred Forty Five Only
		Total:-			**4,75,445.00**	
	Quated Rate in figure					
	Quated Rate in words					

Executive Engineer
HPPWD Division
Seraj at Janjehli