

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2024- 3413-15

Dated:- 10/09/2024

To

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:- Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

HP.P.W.D. TENDER NOTICE.(offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP, PWD, Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before 19-09-2024 up to 10.30 A.M. and shall be opened on the same day at 11:00 AM in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto 4:00 P.M. on 18-09-2024 No application for issue of tender forms will be received on 18-09-2024 after 4:00 PM. If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R.s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	S/R to HPPWD Rest House at Kalpa in District Kinnaur HP (SH:-Providing and fixing paneling, tile flooring, plastering etc.)	4,98,111/-	10,000/-	Three Months	350/-	D Class
2	R/R damages on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- Removal of slips from Km. 0/550 to 1/00 and 3/100 to 3/700)	4,99,554/-	10,000/-	One Month	350/-	D Class
3	Restoration of rain damages on link road from PHC Kanam to Kanam Dogri Km. 0/00 7/500 (SH:- Removal of slips/landslides from Km. 0/00 to 4/00)	4,99,769/-	10,000/-	One Month	350/-	D Class
4	Restoration of rain damages on link road from PHC Kanam to Kanam Dogri Km. 0/00 7/500 (SH:- Removal of slips/landslides from Km. 4/00 to 7/500)	4,99,769/-	10,000/-	One Month	350/-	D Class
5	R/R damages on link road from Thangi to Kunnu Charang Km. 0/00 to 20/00 (SH:- Hiring of JCB for removal of slips)	4,95,000/-	10,000/-	Three Months	350/-	D Class
6	R/R damages on various roads in Ribba Section under Moorang Sub Division (SH:- Hiring of JCB for removal of slips)	4,95,000/-	10,000/-	Three Months	350/-	D Class
7	R/R damages on link road from Ropa to Thropa Km. 0/00 to 2/500 (SH:- Removal of slips)	4,99,830/-	10,000/-	Three Months	350/-	D Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:-

No.PW/KNR-E-Tender/NIT/2024-

3416-30

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block development officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.

Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this

office Letter No. PW/KNR/E-Tender/2024-3416-30 dated 10-9-2024 from Sr.

No. 1 to 7 are of urgent nature and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.


①

SCHEDULE OF QUANTITY

Name of work:- Special repair to HPPWD Rest House at Kalpa in District Kinnaur (H.P.)
(SH:- Providing and fixing paneling , tile flooring, plastering etc
Estimated Cost :- 4,98,111/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. 2nd class teak Wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	0.32			Per Cubic meter	
2	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	66.35			Per Square meter	
3	Providing and fixing Pine wood panelling with plank size 75 x 25mm (Seventy five millimeter into twenty five millimeter) & 75mm x 12.5mm (Seventy five millimeter into twelve point five millimeter) in combination over frame of wood work (to be paid separately) with top moulding complete in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.18			Per Square meter	
4	Providing and fixing HDF decorative laminate core board German kerono panelling AC 4 class 32.7mm thick placed over cushion of 2mm thick expended polythene foam plus 100 micron thick polythene sheet, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.18			Per Square meter	
5	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :2nd class teak wood, 50x20mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.20			Per Running meter	

6	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.30			Per Square meter
7	15 mm cement plaster on the rough side of single or half brick wall of mix : 1 : 6 (1 cement : 6 fine sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.30			Per Square meter
8	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement : 3 sand) and jointed with cement slurry, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19.08			Per Square meter
9	Providing and fixing 10mm thick anti skid water proof stain and impervious heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.40			Per Square meter
10	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed 75 mm diameter, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00			Per Running meter
11	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.00			Each

12	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	
13	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	
14	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	
15	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	
16	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	
17	Providing and fixing C.P. Brass Towel rail complete 750mm x 20mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00				Each	

18	Providing and fixing 600mm x 120 mm glass shelf with C.P. Brass bracket and guard rail complete, fixed to wooden plugs with C.P.Brass screws, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Each	
19	Providing and fixing Toilet Paper Holder C.P Brass, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00			Each	
20	Providing and fixing chromium plated brass soap dish, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00			Each	
21	Providing and fixing CP brass bib tap with capastan head 15mm*dia. of Jal or its Equivalent, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00			Each	
22	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.80 mm thick with zinc coating not less than 275 gm/m ² , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.72			Per Square meter	
23	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per Cubic meter	

24	P/L heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curring rubbing and polishing complet Subbase concrete floor to be paid for :- 60 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.00			Per Square meter
Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

2

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on on link road from Leo Bridge to Hango Km. 0/00 to 16/00
(SH:- Removal of slips from Km 0/550 to 1/00 and 3/100 to 3/700).

Estimated Cost :- 4,99,554/-
Earnest Money :- 10,000/-
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e, breaker etc, including cutting and trimming of slopes and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	3132.00			Per Cubic meter	
	Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,769/-
 Earnest Money :- 10,000/-
 Time :- One Month

Name of work:- Restoration of rain damages on Link road from PHC Kanam to Kanam Dogri Km. 0/00 to 7/500
 (SH:-Removal of slips/landslides from Km. 0/00 to 4/00).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e. breaker etc. including cutting and trimming of slops and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	3133.35			Per Cubic meter	
	Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

4

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Link road from PHC Kanam to Kanam Dogri Km. 0/00 to 7/500
(SH:-Removal of slips/landslides from Km. 4/00 to 7/500).

Estimated Cost :- 4,99,769/-
Earnest Money :- 10,000/-
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e. breaker etc. including cutting and trimming of slops and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	3133.35			Per Cubic meter	
	Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Thangi to Kunnu Charang 0/00 to 20/00
(SH:- Herring of ICB for removal of slips).

Estimated Cost :- 4,95,000/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. ICB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00			Per Hours	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP. PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,000/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Restoration of rain damages on various roads in Ribba section under Moorang Sub-Division
 (SH:- Hurring of JCB for removal of slips).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00			Per Hours	
	Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

7

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,830/-
Earnest Money :- 10,000/-
Time :- Three Months

Name of work:- Restoration of rain damages on link road from Ropa to Thropa km 0/00 to 2/500
(SH:- Removal of slips)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e. breaker etc. including cutting and trimming of slops and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	3133.73			Per Cubic meter	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.