



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.THD/CB/TENDER/Tender Notice/2024 **3428-30**

Dated:-

19/9/2024

To

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:-

Publication of tender Notice.

Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Sealed Percent rates tender form No 7 & 8 are hereby invited by the
Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of
Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per
time schedule Given below:-

- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 25.09.2024 upto 12:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 26.09.2024 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 27.09.2024 upto 10:30 AM |
| 4 | Date of opening of Tender | 27.09.2024 upto 11:00 AM |

Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	R/R Damages on Theog Kotkhai Hatkoti road NH 705 k.m. 0/0 to 69/00 (SH:- Hiring of Exccavator for the demolition of un-authorized encroachment at Anti Bazzar R.D. R.D. 157/00 to 157/180.)	492300/-	9500/-	350/-	1 Month
2	2	A/R & M/O Theog Kotkhai Hatkoti road NH 705 k.m. 0/0 to 69/00 (SH:- Hiring of Tipper for dumping of demolished encroachments at anti Bazzar RD 157/00 to 157/186.)	486550/-	10000/-	350/-	1 Month
3	3	R/R Damages on Theog Kotkhai Hatkoti road NH 705 k.m. 0/0 to 69/00 (SH:- Hiring of Tipper for dumping of demolished encroachments at Saraswati Nagar RD 160/0 to 160/470)	486550/-	10000/-	350/-	1 Month
4	4	R/R Damages on Theog Kotkhai Hatkoti road NH 705 k.m. 0/0 to 69/00 (SH:- Hiring of Excavator for the demolition of un-authorized encroachment at Saraswati Nagar R.D. R.D.160/00 to 160/470.)	492300/-	9500/-	350/-	1 Month
5	5	Consultancy service for Report and Design of Retaining Wall at R.D. 151/070 to 151/225. in stud of non physibality of 15.00 mtr Span Bridge on Poanta Sahib Rajban Meenus Hatkoti Road NH 707 k.m. 149/00 to 161/715. (S.H:- Report and Designing of Retaining Wall at R.D. 151/070 to 151/150.)	4,99,000	9900	350/-	1 Month

6	6	Consultancy service for Report and Design of Retaining Wall at R.D. 151/070 to 151/225. in stud of non physibility of 15.00 mtr Span Bridge on Poanta Sahib Rajban Meenus Hatkoti Road NH 707 k.m. 149/00 to 161/715. (S.H:- Report and Designing of Retaining Wall at R.D. 151/150 to 151/225.)	4,99,000	9900	350/-	1 Month
7	7	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o B/wall in PCC M15 at R.D. 39/750 to 39/765).	487657.00	10000	350/-	2 Month
8	8	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000(SH:- C/O supplying and stacking of GSB at various damaged portion)	495509.00	10000	350/-	2 Month
9	9	O/R of Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:- Removal of Slips between 17/740 to 17/795)	300713.00	6100	350/-	1 Months
10	10	R/R Damages on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:- C/O R/Wall in PCC M-15 at R.D.39/755 to 39/762	478306	9600	350/-	2 Months
11	11	R/R Damages on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:- C/O B/Wall in PCC M-15 at R.D.41/ 380 to 41/395	490660	10000	350/-	2 Months
12	12	O/R on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/00 (SH:- Hiring of Tipper at K.M. 20/000 to 30/000	465000	9300	350/-	2 Months
13	13	O/R on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/00 (SH:- Hiring of Tipper at K.M. 00/000 to 20/000	465000	9300	350/-	2 Months
14	14	R/R on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/000 (SH:- Hiring of JCB for removal of slips, dressing of berm, clearance of side drain and catch pit between K.M. 10/000 to 20/000	495000	10000	350/-	2 Months
15	15	R/R Damages on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/000 (SH:- Hiring of JCB for removal of slips, dressing of berm, clearance of side drain and catch pit between K.M. 00/000 to 10/000	495000	10000	350/-	2 Months

16	16	R/R Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/0 to 69/00 (S.H:- Clearance of hillside chocked drain between 52/000 /5600)	494000	10000	350/-	1 Month
17	17	O.R. on Kalka Shimla Wangtoo road k.m. 13/00 to 24/250 (S.H:- C/O U-Shape Drain in K.M. 154/120 to 154/270.	491302	10000	350/-	2 Months
18	18	O.R. on Shimla bye pass road Km 13/0 to 24/250(S.H:- P/F M.S Grating over drain RD 154/120 to 154/270.	487427	10000	350	2 Months
19	19	R/R Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 13/175.55 to 13/179.55	492548	10000	350/-	2 Months
20	20	R/R Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 13/179.55 to 13/183.35)	486118	10000	350/-	2 Months
21	21	R/R Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 19/730 to 19/733.80)	486118	10000	350/-	2 Month
22	22	A/R & M/O Shimla Bye Pass road portion k.m. 13/00 to 24/250 (SH:- Supplying and fixing of retro Reflective type between k.m. 16/000 To 17/000	497250	10000	350/-	2 Months
23	23	O.R. on of NH Office Building at Theog (S.H:-P/F Cup Bord)	126791	2600	350/-	2 Months
24	24	R/R Dasmages on Kalka Shimla Wangtoo road Nh 05 k.m. 167/00 to 236/00 (S.H. -C/O R/Wall between RD 170/245 to 170/248	481541	9700	350/-	2 Months
25	25	R/R. Damages on Kalka Shimla Wangtoo road Nh 05 k.m. 167/00 to 236/00 (SH:- Hiring of Excavator Cum loader for removal of Snow/slips at various RD Narkanda Sub Division.)	242000	5000	350/-	2 Months
26	26	R/R. Damages on Kalka Shimla Wangtoo road Nh 05 k.m. 167/00 to 236/00 (SH:- Hiring of Excavator Cum loader for removal of Snow/slips at various RD Narkanda Sub Division.)	495000	10000	350/-	2 Months

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)

- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.
- 12 Works should be completed by the contractor within the stipulated period.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog
Dated 19/09/2024

No/PW/NH/CB/Tender/2024 3418-27

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Superintending Engineer NH Circle HP PWD Shimla . It is therefore requested to kindly issue the certificate the tender of above emergent nature in public interest.
- 4 All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog



NATIONAL HIGHWAY (NH-05)
HIMACHAL PRADESH PUBLIC WORKS DE
PARTMENT DIVISION THEOG

Certificate

Certified that the tenders of works as called
vide this office NIT No/PW/NH/CB/Tender/2023-3418-21 Dated 19/9/2024
are urgent nature and public interest.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Schedule of Quantity

Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 KM 0/00 to 69/00 (Sh: Hiring of Excavator for the demolition of un-authorized encroachments at Anti Bazaar RD 157/00 to 157/180)					
Estimated Cost				492300	
Earnest Money				10000	
Time				One month	
Sr. No.	Description of item	Quantity	Unit	Rate	Amount
1	Hiring of Excavator of 0.90 cum bucket capacity for the demolition of un-authorized construction as per the direction Engineer-in-Charge	150	Rmt	3282.00	492300
Total					492300
(Quoted Rates in Figure) (+/-)		(_____ %)			
(Quoted Rates in words)					

Conditions

1. Rates shall be quoted for all heights including all leads and lifts.
2. The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost
3. Cement shall be procured from HP State Civil Supply Corporation.


Executive Engineer
NH Division, HP PWD
Theog

Schedule of Quantity

Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 KM 0/00 to 69/00 (Sh: Hiring of Tipper for dumping of demolished encroachments at Anti Bazaar RD 157/00 to 157/186)			Estimated Cost		486550
			Earnest Money		10000
			Time		One month
Sr. No.	Description of item	Quantity	Unit	Rate	Amount
1	Hiring of Tipper of 10cum capacity for the dumping of demolished encroachments as per the direction Engineer-in-Charge	185	Rmt	2630.00	486550
	Total				486550
(Quoted Rates in Figure) (+/-)		(_____ %)			
(Quoted Rates in words)					

Conditions

1. Rates shall be quoted for all heights including all leads and lifts.
2. The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost
3. Cement shall be procured from HP State Civil Supply Corporation.



 Executive Engineer
 NH Division, HP PWD
 Theog

Schedule of Quantity

Schedule of Quantity					
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 KM 0/00 to 69/00 (Sh: Hiring of Tipper for dumping of demolished encroachments at Saraswati Nagar RD 160/00 to 160/470)			Estimated Cost		486550
			Earnest Money		10000
			Time		One month
Sr. No.	Description of item	Quantity	Unit	Rate	Amount
1	Hiring of Tipper of 10cum capacity for the dumping of demolished encroachments as per the direction Engineer-in-Charge	185	Rmt	2630.00	486550
Total					486550
(Quoted Rates in Figure) (+/-)		(_____ %)			
(Quoted Rates in words)					

Conditions

1. Rates shall be quoted for all heights including all leads and lifts.
2. The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost
3. Cement shall be procured from HP State Civil Supply Corporation.



 Executive Engineer
 NH Division, HP PWD
 Theog

Schedule of Quantity

Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 KM 0/00 to 69/00 (Sh: Hiring of Excavator for the demolition of un-authorized encroachments at Saraswati Nagar RD 160/00 to 160/470)					
Estimated Cost				492300	
Earnest Money				10000	
Time				One month	
Sr. No.	Description of item	Quantity	Unit	Rate	Amount
1	Hiring of Excavator of 0.90 cum bucket capacity for the demolition of un-authorized construction as per the direction Engineer-in-Charge	150	Rmt	3282.00	492300
Total					492300
(Quoted Rates in Figure) (+/-)					
(Quoted Rates in words)					(_____ %)

Conditions

1. Rates shall be quoted for all heights including all leads and lifts.
2. The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost
3. Cement shall be procured from HP State Civil Supply Corporation.


 Executive Engineer
 NH Division, HP PWD
 Theog

SCHEDULE OF QUANTITY

Estt. Cost:- Rs:- 4,49,400= only

Earnest Money:- 9000.00 only

Time:- One Month.

Name of work :- Consultancy service for Report and Design of Retaining Wall at R.D. 151/070 to 151/225 in ~~area~~ ^{area} of non physibility of 15.00 mtr Span Bridge on Poanta Sahib Rajban Meenus Hatkoti Road NH 707 k.m. 149/00 to 161/715. (S.H:- Report and Designing of Retaining Wall at R.D.151/070 to 151/150)

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Consultancy service for Report and Design of Retaining Wall complete including all lead and lift or as per the direction of Engineer-In- Charge.	1No.	per Job.	499000	Rupees Four Lakhs Ninety Nine Thousand Only	499000
	Total					499000
	(Quoted Rates in Figures)(+/ -)	(..... %)				
	(Quoted Rates in words)(+/ -)					

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estt. Cost:- Rs:- 4,47,488= only

Earnest Money:- 9000.00 only

Time:- One Month.

Name of work :- Consultancy service for Report and Design of Retaining Wall at R.D. 151/070 to 151/225 in ~~study of~~ ^{and.} non physibility of 15.00 mtr Span Bridge on Poanta Sahib Rajban Meenus Hatkoti Road NH 707 k.m. 149/00 to 161/715. (S.H:- Report and Designing of Retaining Wall at R.D.151/1504/151/225)

Sr.No.	Description of Item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Consultancy service for Report and Design of Retaining Wall complete including all lead and lift or as per the direction of Engineer-In- Charge.	1No.	per Job.	499000	Rupees Four Lakhs Ninety Nine Thousand Only	499000
	Total					499000
	(Quoted Rates in Figures)(+/ -)				(.....%)	
	(Quoted Rates in words)(+/ -)					

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:-	487657.00
Earnest Money	Rs:-	10000.00
Time.	2 Month.	

Name of work :- R/R. Damages on Theog Kotkhai Hatkotli road NH-705 k.m. 0/000 to 69/000.(SH:C/o B/wall in PCC M15 at R.D. 39/750 to 39/765).

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utlising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	45.00	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	13723.00
3	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	61.88	Per Cum.	7500	Rupees Seven Thousand Five Hundred Only	464100.00
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	37.50	Per Rmt.	262.25	Rupees Two Hundred Sixty Two and Paise Twenty Five Only	9834.00
Total						487657
		(Quoted Rates in Figures)(+/ -)		(.....%)		
		(Quoted Rates in words)(+/ -)				

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost
- 3 Cement Shall be procured HP state CIVIL Supply corporation.

Executive Engineer,
NH Division HPPWD,
Theog.

2

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Rs:-	495509	
				Cost:		
				Earnest Rs:-	10,000	
				Money		
				Time.	2 Month.	
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000(SH:- C/O supplying and stacking of GSB at various damaged portion)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Supplying and stacking Of Granular Sub Base by providing close graded material, mixing in a mechanical mix plant at OMC carriage of mixed material to work site spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired denisty, complete as per clause 401. in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	143	Cum.	3465.10	Rupees Three Thousand Four Hundred Sixty Five and Paise Ten Only	495509
	Total					495509

(Quoted Rates in Figures)(+/-%)

(.....%)

(Quoted Rates in words)(+/-%)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Rs:- Cost:		300713
				Earnest Rs:- Money		6100.00
Name of work :- O/R of Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:-Removal of Slips between 17/740 to 17/795)				Time.	3 Month.	
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Removal of landslide /unserviceable soil in all type of rock, including hard rock and opening of catchpits for choked culverts including cutting by a hydraulic excavator , loading and disposal upto10 km lead as per MORTH specification 2019 clause 3000 . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	1190.00	Per Cum.	252.70	Rupees Two Hundred Fifty Two and Paise Seventy Only	300713
	Total					300713
		(Quoted Rates in Figures)(+/ -)		(.....%)		
		(Quoted Rates in words)(+/ -)				
Conditions						

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:-	478306
Earnest Money:-	9600
Time:- 2 Month.	

Name of work :- O/R of Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:- C/O R/Wall in PCC M-15 at R.D.39/755 to 39/762

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	26.32	Per Cum.	650.6	Rupees Six Hundred Fifty and Paise Sixty Only	17124
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	56.7	Per Cum.	7505.45	Rupees Seven Thousand Five Hundred Five and Paise Forty Five Only	425559.015
3	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	9.24	Per Cum.	3358.6	Rupees Three Thousand Three Hundred Fifty Eight and Paise Sixty Only	31033
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	17.50	Per Rmt.	262.25	Rupees Two Hundred Sixty Two and Paise Twenty Five Only	4589
Total						478306


(Quoted Rates in Figures)(+/ -)

(.....%)

(Quoted Rates in words)(+/ -)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Rs:-	490660.00
Cost:	
Earnest Money Rs:-	10000.00
Time.	2 Month.

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o B/wall in PCC M15 at R.D.41/380 to 41/395).

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	33.75	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	10292.00
3	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	63.00	Per Cum.	7500	Rupees Seven Thousand Five Hundred Only	472500.00
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	30.00	Per Rmt.	262.25	Rupees Two Hundred Sixty Two and Paise Twenty Five Only	7868.00
Total						490660
(Quoted Rates in Figures)(+/ -)				(..... %)		
(Quoted Rates in words)(+/ -)						

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost
- 3 Cement Shall be procured HP state CIVIL Supply corporation.

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Rs:- 4,65,000.00

Earnest 9300.00

Money

Time. 1 Month.

O/R on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/00 (SH:- Hiring of Tipper at K.M. 20/000 to 30/000

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to caride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	75	Days	6200	Rupees Six Thousand Two Hundred Only	465000
	Total					465000
	(Quoted Rates in Figures)(+/ -)		(.....%)			
	(Quoted Rates in words)(+/ -)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Divisional Engineer

Executive Engineer,
NH Division, PWD,
Theog.

DRAFT SCHEDULE OF QUANTITY


		Estt. Cost:- Rs:-	465000
		Earnest Money:-	9300
		Time:-	Two Month.

Name of work :- O.R On Theog Kotkhai Hatkoti Road NH-705 K.M . 0/0 to 69/00 (SH:- Hiring of Tipper At K.M. 0/00 To 20/00)

Sr.No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	75	Days	6200	Rupee Six Thousand Two Hundred only	465000
	Total					465000

DNIT No. 91 Approved for amounting to Rs:- 46,500.00 only for the year 2024-25


Assistant Engineer,
N.H. Sub-Division,HPPWD,
Kharapather


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:- 4,95,000.00 only

Earnest Money:- 10000.00 only

Time:- 2 Month.

Name of work :- R/R on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/000 (SH:- Hiring of JCB for removal of slips, dressing of berm, clearance of side drain and catch pit between K.M. 10/000 to 20/000)

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of jcb or L & T Make having loading bucket of capacity of 0.90 to 1.00 cubic meter capacity and back bucket of capacity of 0.20 to 0.30 cubic meter for removal of slips, dressing of berm, clearance of side drain and catch pit in all leads and lift and disposal of unserviceable materials up to dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction by the Engineer-in-charge.	450	hour	1100.00	Rupees one thousand one hundred only	495000.00
	Total					495000.00
	(Quoted Rates in Figures)(+/-)				(.....%)	
	(Quoted Rates in words)(+/-)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:- 4,95,000.00 only

Earnest Money:- 10000.00 only

Time:- 2 Month.

Name of work :- R/R Damages on Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/000 to 69/000 (SH:- Hiring of JCB for removal of slips, dressing of berm, clearance of side drain and catch pit between K.M. 00/000 to 10/000

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of jcb or L & T Make having loading bucket of cepacity of 0.90 to 1.00 cubic meter capacity and back bucket of capacity of 0.20 to 0.30 cubic meter for removal of slips, dressing of berm, clearance of side drain and catch pit in all leads and lift and disposal of un serviceable materials up to duming site and stacking of serveceable material along road side and neatly dressing the road as per direction by the Engineer-in-charge.	450	hour	1100.00	Rupees one thousand one hundred only	495000.00
	Total					495000.00
	(Quoted Rates in Figures)(+/-)		(.....%)			
	(Quoted Rates in words)(+/-)					

Conditions


- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY						
				Estimated Cost:	Rs:-	494000
				Earnest Money	Rs:-	Rs:-10000 only.
				Time.	1 Month.	
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 KM 0/00 to 69/00 (Sh: Clearance of hillside choked drain between 52/000 to 56/000)						
Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Removal of earth from the choked hill side drain and disposing it on the valley side manually	3800	Rmt	130	Rupees One Hundred Thirty Only	494000
	Total					494000
	(Quoted Rates in Figures)(+/ -)			(.....%)		
	(Quoted Rates in words)(+/ -)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

				Estt. Cost:- Rs:-	491302	
				Earnest Money:-	10000	
				Time:-	Two Month.	
Name of work :- O/R On Kalka Shimla Bye Pass Road k.m. 153/180 to 167/000 . (S.H:- C/O U-Shape drain At R.D. 154/120 to 154/270)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	63.00	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	19212
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	33	Per Cum.	8000.50	Rupees Eight Thousand and Paise Fifty Only	264017
3	Supplying Fitting and placing un-coating HYSD bar Reinforcement in foundation complete as per drawing and technical specification.n all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	1000	Per Kg	95.00	Rupees Ninety Five Only	95000
4	Steel work welded in built up sections./ framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts:In gratings, framed, guards, bars ladders and railing, brackets and similar works: including all leads and lifts, as per specification or as directed by the Engineer-In-Charge.	775.27	Per K.G.	123.60	Rupees One Hundred Twenty Three and Paise Sixty Only	95823
5	Finishing with epoxy paint two coat at all location prepaired and applied as per manufacturing specification including appropriate prunning and preperetion of surface etc and as per directed by the Engineer-In-Charge.	150	Per sqm	115.00	Rupees One Hundred Fifteen Only	17250
Total						491302
(Quoted Rates in Figures)(+/)-				(.....%)		
(Quoted Rates in words)(+/)-						

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

Quantity

Unit.

Rate


In words

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Cost: RS 4,87,427.00		
				Earnest Money R.S 10,000.00		
				Time. 2 Month.		
Name of workO.R. on Shimla Bye Pass road portion k.m. 13/00 to 24/250 (S.H:- P/F M.S Grating over drain at R.D 154/120 To 154/270)						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Steel work welded in build up section trusses and framed work including hoisting fixing position and applying a priming coat of red lead paint including carriage of material width in all leads and lifts in grating framed guard bars ladders and railing brakers and similar works and as per the direction of Engineer-in-Charge.	3617.94	Per KG	123.60	Rupees One Hundred Twenty Three and Paise Sixty Only	447177.38
	Finishing with apoxy paint two coat at all locationprepared and applied as per manufacturing specification including appropriate pruning and preperiton on surface etc and as per direction of Engineer-in-Charge.	350.00	Per sqm	115.00	Rupees One Hundred Fifteen Only	40250.00
	Total					487427

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:-	492548
Earnest Money:-	10000
Time:- 2 Month.	

of work:-R/R Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 13/175.55 to 13/179.55

Description of item

	Quantity	Unit.	Rate		Amount
			In figure	In words	
1 Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	28.88	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	8807.00
2 Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	58.33	Per Cum.	8000.50	Rupees Eight Thousand and Paise Fifty Only	466669.00
4 Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.16	Per Cum.	2170.50	Rupees Two Thousand One Hundred Seventy and Paise Fifty Only	9029.00
3 Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	29.45	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	8043.00
Total					492548.00

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY				Estimated Cost:-		486118	
				Earnest Money:-		10000	
Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 13/179.55 to 13/183.35)				Time:- 2 Month.			
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining eath locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	28.50	Per Cum.	In 304.95	In words Rupees Three Hundred Four and Paise Ninety Five Only	8691.00	
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	57.57	Per Cum.	8000.50	Rupees Eight Thousand and Paise Fifty Only	460589.00	
3	Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.10	Per Cum.	2170.50	Rupees Two Thousand One Hundred Seventy and Paise Fifty Only	8899.00	
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	29.07	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	7939.00	
Total						486118.00	

Conditions

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

Name of work:-R/R Dasmages on Shimla Bye Pass Road K.M. 13/000 to 24/250 (S.H. -C/O R/Wall between RD 13/175.55 to 13/179.55		Estimated Cost:-		486118		
		Earnest Money:-		10000		
		Time:- 2 Month.				
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In	In words	
1	Excavation for Structures. Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	28.50	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	8691.00
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	57.57	Per Cum.	8000.50	Rupees Eight Thousand and Paise Fifty Only	460589.00
	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment, wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.10	Per Cum.	2170.50	Rupees Two Thousand One Hundred Seventy and Paise Fifty Only	8899.00
	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	29.07	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	7939.00
Total						486118.00
		(Quoted Rates in Figures)(+/-)				
		(Quoted Rates in words)(+/-)				
				(.....%)		

Conditions

ates shall be Quoted for all heights including all leads and lifts

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Cost:	Rs:-	497250
				Earnest Money	Rs:-	Rs:-10000 only.
				Time.	1 Month.	
Name of work :- A/R & M/O Shimla Bye Pass Road portion K.M 13/000 To 24/250 . (SH:- Supplying and fixing of retro reflective tape between K.M. 16/00 To 17/000)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Supplying and fixing of retro reflective sheeting type -I size 1ft x 1.5Ft. Fixing over cresh beam proper including carriage of materials and equipment in all leads and lefts by all modes of transportation as per the direction by the Engineer -In -Charge.	585	No	850	Rupees Eight Hundred Fifty Only	497250
Total						497250
				(Quoted Rates in Figures)(+/ -)		(.....%)
				(Quoted Rates in words)(+/ -)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

DRAFT SCHEDULE OF QUANTITY

Name of work :O.R. on of NH Office Building at theog (S.H.:P/F Cup Bord Etc.)		Estimated Cost:-		126791		
		Earnest Money:-		2600		
		Time:- 2 Month.				
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Providing and fixing 19 mm thick commercial board water proof in shelves, lining,box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lefts.	48.50	Per Sqm.	1344.00	Rupees One Thousand Three Hundred Forty Four Only	65184.00
2	Providing and fixing 6 mm thick ply wood lining with butt jointing and nails (frame and cover fillets to be measured and paid for separately including complete including carriage of material in all leads and lefts.	16.56	Per Sqm.	606.00	Rupees Six Hundred Six Only	10035.36
3	P/F 1.00 mm thick coloured or plain lamination sheet (sunmica) on boards/ ply wood sheets with approved adhesive and nails etc complete including carriage of material in all leads and lefts.	28.74	Per Sqm.	900.0	Rupees Nine Hundred Only	25866.00
4	Providing and fixing ess make furniture handles with screws etc comlete 125 mm including carriage of material in all leads and lefts.	8.00	No.	262.00	Rupees Two Hundred Sixty Two Only	2096.00
4	Providing and fixing ess make furniture handles with screws etc comlete 200 mm including carriage of material in all leads and lefts.	20.00	No.	368.00	Rupees Three Hundred Sixty Eight Only	7360.00
5	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. Triple strip vertical type.	52.00	No.	64.00	Rupees Sixty Four Only	3328.00
6	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc.complete.	2.00	No.	521.00	Rupees Five Hundred Twenty One Only	1042.00
	Providing and fixing hydrolic hinges fixing with necessary screws etc complete.	54.00	No.	220.00	Rupees Two Hundred Twenty Only	11880.00
						126791

- 1,26,791.00 only for the year 2024-25

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Name of work :- O/R of Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (SH:- C/O R/Wall in PCC M-15 at R.D.170/245 to 170/248)

Estimated Cost:- 481541
Earnest Money:- 9700
Time:- 2 Month.

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	38.70	Per Cum.	340.10	Rupees Three Hundred Forty and Paise Ten Only	13162.00
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	57.96	Per Cum.	7657.40	Rupees Seven Thousand Six Hundred Fifty Seven and Paise	443823.00
3	Providing weep holes in Brick masonry/plain/reinforced concrete abutment, wing wall/return wall with 100 mm dia. AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	13.50	Per Rmt.	279.25	Rupees Two Hundred Seventy Nine and Paise Twenty Five Only	3770.00
4	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment, wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	8.10	Per Cum.	2566.15	Rupees Two Thousand Five Hundred Sixty Six and Paise Fifteen Only	20786.00
Total						481541.00
		(Quoted Rates in Figures)(+/-)	%		
		(Quoted Rates in words)(+/-)				

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

				Estimated Cost: RS 2,42,000.00		
				Earnest Money R.S 5000.00		
				Time. 2 Month.		
Name of work :- R/R. Damages on Kalka Shimla Wangtoo road Nh 05 k.m. 167/00 to 236/00 (SH:- Hiring of Excavator Cum loader for removal of Snow/slips at various RD Narkanda Sub Division.)						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of Snow / slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	220	hour	1100.00	Rupees one thousand one hundred only	242000.00
Total						242000.00
		(Quoted Rates in Figures)(+/ -)		(.....%)		
		(Quoted Rates in words)(+/ -)				

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost: RS 495000.00

Earnest Money R.S 10000.00

Time. 2 Month.

Name of work :- R/R. Damages on Kalka Shimla Wangtoo road Nh 05 k.m. 167/00 to 236/00 (SH:- Hiring of Excavator Cum loader for removal of Snow/slips at various RD Narkanda Sub Division.)

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of Snow / slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the	450	hour	1100.00	Rupees one thousand one hundred only	495000.00
	Total					495000.00
	(Quoted Rates in Figures)(+/-)				(.....%)	
	(Quoted Rates in words)(+/-)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.