

**Himachal Pradesh
Public Works Department
Notice inviting Tender**

Sealed percentage rate tender on form PWD 6 & 7 are invited by the Executive Engineer Nahan, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD, so as to reach in this office as per time schedule given below.

- | | |
|--|-------------------------|
| 1. Date of receipt of application of tenders forms:- | 20.9.2024 upto 11:00 AM |
| 2. Date of issue/ sale of tender Forms.: | 21.9.2024 upto 10.30 AM |
| 3. Date of receipt of tender | 21.9.2024 at 11:00 AM |
| 4. Date of opening of tender:- | 21.9.2024 at 12:00 Noon |

Sr. No.	Name of Work	Estimated Cost (in ₹)	Earnest Money (in ₹)	Time Limit	Cost of Tender Form (in ₹)
1	C/O balance work of L/R to Mata Mantra Devi Mandir.(SH:-P/L Middle Rail, Steel Grating & Paint on steel along the Pedestrian path)	315967/-	6500/-	02 Month	350/-
2	R/R damages to L/R Village Jhajjar Km.0/0 to 1/745. (SH:-P/L Kharanja stone soling & CC pavement from 0/791 to 1/070)	492676/-	10000/-	02 Month	350/-
3	R/R damages to Palion Andheri Trilokpur road km 0/0 to 4/0 (SH:- C/O wire crate at RD.3/720 to 3/733.30 R/S & 3/720 to 3/736.20 L/S).	410246/-	9000/-	02 Month	350/-
4	C/o Govt. Sr. Sec. School Surla at Nahan. (SH:- R/O doors, windows. Flooring work, plaster work & remaining work of B/wall)	497533/-	10000/-	02 Month	350/-
5	R/O Govt. Shamsher (Boys) Sr. Sec. School at Nahan.(SH:- Brick work, plaster, steel work & other Misc. work (Vocational Lab)	499913/-	9700/-	02 Month	350/-
6	C/O drain near home of Sh.Nain Singh Mohal:MC Nahan, C/O pucca path near Gugga Mari Nahan Mohal:MC Nahan, C/O drain behind the house of Jhooma Chauhan Paramjeet Singh & others opposite MC Rest House Nahan Mohal:MC Nahan.	499894/-	10000/-	02 Month	350/-
7	R/R damages to Bohlion to Shambhalka road km 0/0 to 6/650 (SH:- C/o PCC R/Wall at RD 4/710 to 4/722)	425017/-	9000/-	02 Month	350/-
8	R/R damages to Bohlion to Shambhalka road km 0/0 to 6/650 (SH:- C/o Wire Crate at RD 5/215 to 5/225 & PCC R/wall at RD 5/890 to 5/902)	463732/-	10000/-	02 Month	350/-
9	R/R damages to Khajurna Bikram bagh Suketi Kala Amb road Km.0/0 to 15/0 & Bohlion to Jogiban road Km.0/0 to 1/660.(SH:-C/O 900mm dia hume pipe culvert at RD.1/210 on Khajurna suketi road & C/o R/wall at RD.0/400 to 0/420 on Bohlion to jogiban road)).	470099/-	10000/-	02 Month	350/-

CERTIFICATE:- It is certified that the tenders of above works are of exigency/ emergent nature in public interest.

Terms & Conditions:-


- The Contractors/ Bidders must submit copy of their Permanent Income Tax Account Number/ GST Number/ EPF No. along with the application for tender.
- The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
- The Contractors/Firms should attach copy of the Registration/ Renewal with the application.
- The contractor/ bidder should quote his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
- Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
- The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 Crore each or above.
- The offer shall remain valid up to 75 days.
- The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
- The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reasons.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

For & on behalf of Governor of Himachal Pradesh.

Dated:-12.9.24

4. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading of Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please..
9. All the Assistant Engineers under this division to display on their respective
10. The Notice Board.


Executive Engineer,
Nahan Division,
HPPWD Nahan.

SCHEDULE OF QUANTITY

Item of work:- Construction of Balance Work of L/R to Mata Mantra Devi Mandir. (SH:- P/L Middle Rail, Steel Grating & Steel along the Pedestrian Path)

Sub Head and item of work				Estimated Cost Rs.3,15,967/- Earnest money: Rs. 6500/- Time:- Two Months		
Sub Head and item of work	Qty	Unit	Rate	Amount		
Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings, framed, guard bar, ladder, railings, brackets and similar works as directed by Engineer-in-Charge.	2.87	Per Quintal	11,550.00	Rs Ten Thousand Five Hundred Fifty & Paise Nil Only	33149.00	
Steel work in built up tubular (round, square or rectangular hollow tubes etc) trusses etc. Including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes as directed by Engineer-in-Charge.	23.27	Per Quintal	12,100.00	Rs Twelve Thousand One Hundred & Paise Nil Only	281567.00	
Painting two coats (excluding priming cost on new steel and other metal surfaces with enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foreign matters :- Enamel paint other than white including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	15.84	Per square metre	79.00	Rs. Seventy Nine & paise Nil Only	1251.00	
Total					315967.00	

Quoted Rate in Figure (+/-) {% }

Quoted Rate in Words (+/-) {% }

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....

Cutting.....

Over Writing.....

Erasing.....

Condition.....

E.E.

Executive Engineer
Nahan Division,
HP, PWD, Nahan

SCHEDULE OF QUANTITY

Sub Head and item of work				Estimated Cost Rs.4,92,676/- Earnest Money: Rs. 10,000/- Time:- Two Months	
Qty	Unit	Rate	Amount		
150.66	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only	45198.00	
94.16	Per cubic metre	1044.05	Rs. Four thousand Two Hundred Eleven & Paise Thirty Only	98308.00	
56.50	Per cubic metre	6180.00	Rs. Six thousand One Hundred Eighty and Paise nil only	349170.00	
Total				492676.00	

Work:- R/R Damages to Link road Village jajjar km 0/00 to 1/745 (SH:- Providing & Laying Kharanja Stone Soling
CC Pavement from 0/791 to 1/070)

Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.

Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.

Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802.803, 1202 & 1203 nominal mix P.C.C. Grade M 20 Nominal mix (1:2:4) (i) upto 5 m height including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.

Quoted Rate in Figure(+-) {.....%}
Quoted Rate in Words (+/-) {.....%}

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....

Cutting.....

Over Writing.....

Erasing.....

Condition.....

E.E.

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

of work:- R/R Damages to Palion Andheri Trilokpur road km 0/0 to 4/0 (SH:- C/o Wire Gate at RD 3/720 to 3/733.30 3/720 to 3/736.20 L/S)				Estimated Cost Rs.4,10,246/- Earnest money: Rs. 9,000/- Time:- Two Months		
Sub Head and item of work				Rate		Amount
				Figure	Words	
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.				300.00	Rs. Three hundred & Paise nil only	10374.00
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 25 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.				2981.90	Rs Two thousand nine hundred eighty one & Paise ninety only	387856.00
Construction of Embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5				98.90	Rs. Ninety eight & paise ninety only	12016.00
Total:						410246.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Opened By Me.....

Cutting.....

Over Writing.....

Erasing.....

Condition.....

E.E.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

Time of work:-C/O Govt. Sen. Sec. School Surla at Nahan. (SH:-Repair of doors, windows, flooring work, plaster work & remaining work of boundary wall)

Sub Head and item of work				Estimated Cost Rs.4,97,533/- Earnest money: Rs. 10000/- Time:- Two Months		
No	Qty	Unit	Rate	Amount		
Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with:- Cement Mortar 1:5 (1 Cement : 5 Sand) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	58.80	Per square metre	265.00	Rs. Two Hundred Sixty Five & Paise Nil Only	15582.00	
Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	361.04	Per Square metre	11.80	Rs. Eleven & Paise Eighty Only	4260.00	
Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	120.33	Per square metre	55.00	Rs. Fifty Five & Paise Nil Only.	6618.00	
Applying priming with cement primer coat on new concrete/Masonry/ asbestos cement/plastered surface and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with : Ready Mixed primer including carriage of materials with in all leads and other incidental complete as per entire satisfaction of the Engineer-in-charge.	120.33	Per square metre	35.00	Rs. Thirty Five & Paise Only.	4212.00	
Distempering (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth priming coat with distemper primer. Upto Floor all level including carriage of materials with in all leads, lifts and other incidentals charges complete as per entire satisfaction of the Engineer-in-charge.	361.04	Per square metre	85.00	Rs. Eighty Five & Paise Only.	30688.00	
Providing and laying vitrified tiles (400x400mmx10mm) in grey/coloured or of approved shade in flooring. & walls treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1 cement : 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	40.29	Per Square metre	1365.30	Rs. One Thousand Three Hundred Sixty Five & Paise Thirty Only.	55008.00	
Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete. 8 mm thick including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	5.14	Per square metre	1068.95	Rs. One Thousand Sixty Eight & Paise Ninety Five Only.	5494.00	
15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone wall for interior plastering upto floor all level including arises, internal rounded angles, chamfers and or rounded angle in all girth & finished even & smooth on rough side with cement mortar 1:6 (one cement : six sand) upto all floor level including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	281.84	Per Square metre	205.00	Rs. Two Hundred Five & Paise Nil Only.	57777.00	
Supplying and fixing glass pans with putty and nails (4mm thick) Four millimetre) thick including carriage of materials with in all leads lifts and other incidentals complete as per entire satisfaction of the Engineer-in-	1.62	Per square	715.00	Rs. Seven Hundred Fifteen & Paise Nil	1158.00	

0	Dismantling doors, windows and clerestories etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 50 metres laid : of area 3 sq metres and below all complete as per the direction of the Engineer-in-charge.	4	Each	156.25	Rs. One Hundred Fifty Six & Paise Twenty Five Only.	625.00
1	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	10	Each	171.45	Rs. One Hundred Seventy One & Paise Forty Five Only.	1715.00
2	Painting two coats (excluding priming coat) on new wood & wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust & other foreign matter sand papering & stopping with enamel paint other than white including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	31.32	Per Square metre	106.00	Rs. One Hundred Six & Paise Nil Only.	3320.00
3	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter With white readymixed paint all complete as per the direction of the Engineer-in-charge.	28.80	Per Square metre	92.00	Rs. Ninety Two & Paise Nil Only.	2650.00
4	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete 150x10 mm all complete as per the direction of the Engineer-in-charge.	4	Each	48.45	Rs. Forty Eight & Paise Forty Five Only.	194.00
5	Providing and fixing ISI marked oxidised M.S. door sliding conforming to IS:5930 with screws etc. complete 250x20x6 mm all complete as per the direction of the Engineer-in-charge.	3	Each	254.00	Rs. Two Hundred Fifty Four & Paise Nil Only.	762.00
6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	0.50	Per Cubic metre	120619.05	Rs. One Lac Twenty Thousand Six Hundred Nineteen & Paise Five Only.	60310.00
7	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood all complete as per the direction of the Engineer-in-charge.	4.32	Per square metre	3425.65	Rs. Three Thousand Four Hundred Twenty Five & Paise Sixty Five Only.	14799.00
8	Providing and fixing wire gauge shutters using stainless steel grade 304 wire gauge with wire of dia 0.5 mm and average width of aperture 1.4 mm in both directions for doors, windows and clerestory windows with necessary screws : 35 mm thick shutters Second class teak wood all complete as per the direction of the Engineer-in-charge.	4.32	Per square metre	4028.00	Rs. Four Thousand Twenty Eight & Paise Nil Only.	17401.00
9	Providing and fixing Mild steel Channels in door, windows frames, manufactured from Mild steel channels section of size 75x40mm (seventy five into forty millimetre), M.S flat 78x4mm (Seventy five into four millimetre) combination as per design drawing including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	233.52	Per Kilogram	105.00	Rs. One Hundred Five & Paise Nil Only.	24520.00
20	Providing & fixing steel glazed doors, windows & ventilators of standard rolled steel Z section with horizontal & vertical Sashbar of angle iron (25x25x3mm) (Twenty five into twenty five into three millimetre) T-section (25x25x3mm) in fixed and openable shutters as per standard Architectural drawing, jointed mitred & welded with mild steel Channel framed or with fixing clips or with bolts & nuts as required & iron fitting, including providing & fixing of glass pans with glazing clips & special metal sash putty of approved make complete including applying a priming coat of red lead paint as per HP. PWD, specification volume-I (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.					

i) Fixed steel windows.	5.28	Per square metre	1599.00	Rs. One Thousand Five Hundred Ninety Nine & Paise Nil Only.	8443.00
iii) Side hung windows.	2.64	Per square metre	1799.00	Rs. One Thousand Seven Hundred Ninety Nine & Paise Nil Only.	4749.00
Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestory windows of standard rolled steel section joints mitred & welded with 16*3.15mm (Sixteen into three point one five millimetre) including carriage of materials with in all leads, lifts and other incidentals charges complete as per entire satisfaction of the Engineer-in-charge.	2.64	Per Square metre	1600.00	Rs. One Thousand Six Hundred & Paise Nil Only.	4224.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	15.75	Per Cubic metre	295.00	Rs. Two Hundred Ninety Five & Paise Nil Only.	4646.00
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8. (one cement four sand : eight crushed stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts , including all incidental charges.	17.00	Per Cubic metre	4,200.00	Rs. Four Thousand Two Hundred & Paise Nil Only.	71400.00
Brick work using second class common burnt clay building bricks in super structure in cement mortar 1:6(one cement:six sand) Upto Floor to all level including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	8.79	Per cubic metre	6500.00	Rs. Six Thousand Five Hundred & Paise Nil Only.	57135.00
Finishing wall with weather proof exterior grade emulsion of approved design (apexultima) or its equarled on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dir, dust and other foreign matter etc including sand paper smooth complete all complete as per the direction of the Engineer-in-charge.	90.93	Per Square metre	92.00	Rs. Ninety Two & Paise Nil Only.	8366.00
Steel work welded in built up sections, trusses and framed work including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works.	2.73	Per Quintal	11530.00	Rs. Eleven Thousand Five Hundred Thirty & Paise Nil Only.	31477.00
Total					497533.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.


Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

of work:- Repair of Govt. Shamsher (Boys) Sr. Sec. School at Nahan. (SH:-Brick work, plaster, steel work & other work. (Vocational Lab)

Estimated Cost Rs.4,99,913/-
Earnest Money: Rs. 10,000/-
Time:- Two Months

Sub Head and item of work	Qty	Unit	Rate			Amount
			Figure	Words		
Brick work using common burnt clay building bricks in foundation and plinth in Cement Mortar 1:6 (1 Cement : 6 Sand) Second Class Bricks including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	6.26	Per Cubic metre	6500.00	Rs Six Thousand Five Hundred & Paise Nil Only.		40690.00
Half brick masonry in 2nd class common burnt clay building bricks in Super structure in cement mortar 1:4 (1 cement : 4 sand) up to floor all level including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	15.42	Per square metre	700.00	Rs. Seven Hundred & Paise Nil Only		10794.00
Providing mild steel/Tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level : Tor Steel including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	8.65	Per K.g.	78.00	Rs. Seventy Eight & paise Nil only		675.00
Providing form work with steel plates 3.15mm (Three point fifteen millimeter) welded with angle iron in frame 30x30x5mm(Thirty into Thirty into Five millimeter) so as to give a fair finish including centring, shuttering, strutting and propping etc. height of propping and centring below supporting floor to ceiling in all heights. and removal of the same for in situ reinforced concrete and plain concrete work upto floor to all level including carriage of materials with in all leads, lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.						0.00
Beams, cantilevers, girders, and lintels, sides and soffits of Beams, beam haunchings, cantilevers, girders, brassumers and lintels not exceeding 1 meter (One meter) in depth in all heights upto all floor level including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	0.58	Per square metre	387.15	Rs. Three Hundred Eighty Seven Paise Fifteen Only		225.00
Providing concrete for plan/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 804, 805, 806, 807, 1202 and 1204 R.C.C. grade M-25 nominal size mix (1:1.5:3) (one cement: one point five sand: three crushed stone aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	0.06	Per Cubic metre	6,768.30	Rs Six Thousand Seven Hundred Sixty Eight & Paise Thirty Only.		426.00
Steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing brackets and similar works including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	8.90	Per Quintal	10000.00	Rs. Ten Thousand & Paise Nil Only		89000.00
Providing and fixing 0.60mm (Zero point sixty millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge.	14.44	Per Square metre	1360.80	Rs. One Thousand Three Hundred Sixty Paise Eighty Only		19650.00
Providing and fixing M.S. BP sheet 1.66mm one point sixty six millimetres) to 2mm (two millimetres) thick in eaves boards/faciars/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (base members of steel work shall be measured paid separately) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	5.94	Per Square metre	1590.00	Rs. One Thousand Five Hundred Ninety Only		9445.00
Providing and fixing interlinked wire mesh of size 25mm X 25mm (chicken mesh) including cutting, fixing and welding to steel and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	30.78	Per Square metre	1080.00	Rs. One Thousand Eighty & paise nil Only		33242.00

15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1:6 (1 Cement:6 Sand) including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	81.66	Per Square Metre	200.00	Rs. Two Hundred & paise nil Only	16332.00
Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	138.70	Per square metre	50.00	Rs. Fifty & paise nil Only	6935.00
Applying priming with cement primer coat on new concrete/Masonry/ asbestos cement/plastered surface and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with Ready Mixed primer including carriage of materials with in all leads and other incidental complete as per entire satisfaction of the Engineer-in-Charge.	138.70	Per square metre	32.00	Rs. Thirty Two & paise nil Only	4438.00
Distempering (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth priming coat with distemper primer. Upto Floor all level including carriage of materials with in all leads, lifts and other incidentals charges complete as per entire satisfaction of the Engineer-in-Charge.	138.70	Per square metre	82.00	Rs. Eighty Two & paise Nil only	11373.00
Providing and fixing angle steel glazed door, windows and ventilators of standard rolled steel sections joints mitred and welded with 16x3.15mm (Sixteen into three point five millimetre) lugs 10 cm (Ten centimetre) long embedded in cement concrete blocks 15 cm x 10cm x 10cm (Fifteen centimetre into ten centimetre into ten centimetre) size of 1:3 :6 (One cement: Three sand: six graded stone aggregate 20mm nominal size) with wooden plugs and screws of rawl plug and screws or with fixing clips bolts and nuts as required and iron fittings, including providing and fixing of glass panes with glazing clips and special metal sash putty of approved make complete including applying a primer coat of red paint. with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.					0.00
Fixed steel windows.	10.59	Per square metre	1383.00	Rs. One Thousand Three Hundred Eighty Three Paise Nil Only	14646.00
Side hung windows.	10.59	Per square metre	1526.70	Rs. One Thousand Five Hundred Twenty Six Paise Seventy Only	16168.00
Providing & fixing M.S wire gauge shutter doors, windows & ventilators of standard rolled steel Z section with horizontal & vertical Sashbar of angle iron (25x25x3mm) (Twenty five into twenty five into three millimetre) T-section (25x25x3mm) in fixed and openable shutters as per standard Architectural drawing, jointed mitred & welded with mild steel Channel framed or with fixing clips or with bolts & nuts as required & iron fitting, including providing & fixing of glass panes with glazing clips & special metal sash putty of approved make complete including applying a priming coat of red lead paint as per HP PWD, specification volume-I (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.					0.00
Steel windows Side hung windows as per HP.PWD, specification volume-I (one) including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	10.60	Per Square Metre	1850.00	Rs. One Thousand Eight Hundred fifty Paise Nil Only	19610.00
Providing and fixing oxidised M.S. handles with necessary screws (barrel type) with necessary screws etc. complete.	60.00	Each	48.45	Rs. Forty Eight & Paise Forty Five	2907.00
Providing and fixing oxidised M.S. tower bolts (barrel type) with necessary screws etc. complete. 250x10 mm	30.00	Each	61.00	Rs. Sixty One & Paise nil Only	1830.00
Providing and fixing hooks and eyes 300mm dia including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	30.00	Each	55.50	Rs. Fifty Five & Paise Fifty Only	1665.00

Demolition of above G.L. upto floor two level including disposal of unservicable materials within 20 metres lead including cutting the necessary reinforcement and separating out from R.C.C. works all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	3.69	Per Cubic metre	1,600.00	Rs. One Thousand Six Hundred & Paise nil Only	5904.00
Cement concrete flooring 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 40mm nominal size) laid in one layer finished with a floating coat of neat Cement. 40 mm thick including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	73.78	Per Square metre	378.95	Rs. Three Hundred Seventy Eight Paise Ninety Five Only	27959.00
Providing and fixing glass strips in joints of terrazzo floors. 40 mm wide and 4 mm thick including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	64.70	Per Running metre	56.76	Rs. Fifty Six & Paise Seventy Six Only	3672.00
Providing and fixing False ceiling at all height Providing and fixing made with Frame of perimeter channels suitably fixed all complete as per drawing cost of painting with ACP Sheets of approved shade 60*60 cm including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	78.32	Per Square Metre	2000.00	Rs. Two thousand & paise nil Only	156640.00
Painting two coats (excluding priming cost on new steel and other metal surfaces with enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foreign matters :- Enamel paint other than white including carriage of all labour equipments & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of Engineer-in-Charge.	75.83	Per Square Metre	75.00	Rs. Seventy Five & Paise Nil Only	5687.00
Total:					499913.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Drain Near Home of Sh. Nain Singh Mohal: MC Nahan, Construction of Pucca Path near Gugga Mari Nahan Mohal : MC Nahan, Construction of Drain behind the house of Jhooma Chauhan Paramjeet Singh and others opposite MC Rest House Nahan Mohal: MC Nahan.				Estimated Cost Rs.4,99,894/- Earnest money: Rs. 10,000/- Time:- Two Months			
Sr.No.	Sub Head and item of work	Qty	Unit	Rate	Figure	Words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	281.15	Per cubic metre		295.00	Rs. Two Hundred Ninety Five & Paise Nil Only.	82939.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802.803,1202 & 1203 nominal mix P.C.C. Grade M 10 Nominal mix 1:3:6 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	18.20	Per cubic metre		5200.00	Rs. Five thousand two hundred & Paise Nil only	94640.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803,1202 & 1203 in PCC grade Nominal size 1:6:12(one cement: six sand: twelve grade stone aggregate 40mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.00	Per cubic metre		3500.00	Rs. Three Thousand Five Hundred & Paise Nil Only.	35000.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802.804,805, 806,807,1202 and 1204 R.C.C. grade M-25 nominal size mix (1:1.5:3) (one cement: one point five sand: three crushed stone aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.72	Per cubic metre		6800.00	Rs. Six Thousand Eight Hundred & Paise Nil Only.	66096.00
5	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications.	1.92	Per Tonne		75300.00	Rs. Seventy Five Thousand Three Hundred & Paise Nil Only.	144576.00
6	Demolition of brick work above G.L. upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres. lead. In cement mortar including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	28.25	Per Cubic Metre		866.10	Rupees Eight Hundred Sixty Six Paise Ten Only.	22735.00
7	Construction of brick masonry chamber for under ground cat iron chamber and bends with common burnt clay buildinf bricks in Cement Mortar 1:5 (One Cement : Five Sand) Cast iron cover with frame (light duty) 355 x 610 (Three Hundred Fifty Five into Six Hundred Ten) millimetres internal diamensions total weight of cover and frame to be not less than 38 kg (Thirty Eight) (weight of frame 23kg (Twenty Three) and frame Fifteen kilograms) Reinforced Cement Concrete top slab with 1:2:4 (One Cement : Two Sand : Four graded stone aggregate 20 (Twenty millimetre) nominal size) inside plaster 15 (Fifteen Milimetre) thick with cement mortar 1:3 (One cement : Three Sand) finished smooth with a floating coat of neat cement on walls and bed concrete etc complete inside dimension 455 x 610 x 450 (Four Hundred Fifty Five into Six Hundred Ten into Four Hundred Fifty) millimetres single pipe line complete including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	5	Each		9131.50	Rs. Nine Thousand One Hundred Thirty One & Paise Fifty only	45658.00
8	Providing and fixing on wall face PVC (D-plast) accessories for rain water pipes including filing the joints with approved adhesive complete PVC plain bend 100mm (one hundred millimetre) dia including all leads lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	25.00	Per Running metre		330.00	Rs. Three Hundred Thirty & Paise Nil only	8250.00
Total							499894.00

Opened By Me.....
 Cutting.....
 Cover Writing.....
 Erasing.....
 Condition.....

Condition :-
 Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
 Nahan Division,
 HP PWD, Nahan

E.E.

SCHEDULE OF QUANTITY

Item of work:- R/R Damages to Bohlion to Sambhalka road km 0/0 to 6/650 (SH:- C/o PCC R/Wall retaining at RD 4/710

Estimated Cost Rs.4,25,017/-

Earnest money: Rs. 9,000/-

Time:- Two Months

Sub Head and item of work	Qty	Unit	Rate		Amount
			Figure	Words	
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	41.58	Per cubic metre	300.00	Rs. Three hundred & Paise nil only	12474.00
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	88.92	Per Cubic Metre	4,261.30	Rs. Four Thousand Two Hundred Sixty One & Paise Thirty Only	378915.00
Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 m in horizontal towards drawing face complete as per specification clause 614, 709, 1204.3.7 including hauling of material in all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	30.00	Per Each	280.00	Rs. Two Hundred Eighty & Paise Nil Only	8400.00
Back filling behind wing walls and return walls complete as per drawing and technical specification clause 1204.3.8 as per HP PWD specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	21.38	Per Cubic Metre	1,180.00	Rs. One Thousand One Hundred Eighty & Paise Nil Only	25228.00
Total:					425017.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

me of work:- R/R Damages to Bohlion to Sambhalka road km 0/0 to 6/650 (SH:- C/o Wire Crate at RD 5/215 to 5/225 & C RWall ~~repointing~~ at RD 5/890 to 5/902)

Sub Head and item of work				Estimated Cost Rs.4,63,732/- Earnest money: Rs. 10,000/- Time:- Two Months		
No	Qty	Unit	Figure	Words	Amount	
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	61.51	Per cubic metre	300.00	Rs. Three hundred & Paise nil only	18453.00	
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 25 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.	54.00	Per cubic metre	2981.90	Rs. Two thousand nine hundred eighty one & Paise ninety only	161023.00	
Construction of Embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5	26.00	Per cubic metre	98.90	Rs. Ninety eight & paise ninety only	2571.00	
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	61.20	Per Cubic Metre	4,281.30	Rs Four Thousand Two Hundred Sixty One & Paise Thirty Only.	260792.00	
Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 m in horizontal towards drawing face complete as per specification clause 614, 709 1204.3.7 including hauling of material in all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	20.00	Per Each	280.00	Rs. Two Hundred Eighty & Paise Nil Only.	5600.00	
Back filling behind wing walls and return walls complete as per drawing and technical specification clause 1204.3.8 as per HP PWD ., specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	12.96	Per Cubic Metre	1,180.00	Rs One Thousand One Hundred Eighty & Paise Nil Only	15293.00	
Total:					463732.00	


Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

Particulars of work:- R/R Damages to Khajurna Bikram Bag Suketi Kala Amb road KM 0/00 to 15/00 & Bohlion to Jogiban road 0/00 to 1/660 (SH: C/o 900mm dia Hume Pipe culvert at RD 1/210 on Khajurna Suekti road & C/o R/wall at RD 0/400 to 0 on Bohlion to Jogiban road)					Estimated Cost Rs.4,70,099 /- Earnest money: Rs.10,000 /- Time:- Two Months		
Sub Head and item of work					Figure	Rate Words	Amount
		Qty	Unit				
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 20 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge		70.33	Per Cubic Metre		300.00	Rs. Three Hundred & Paise Nil Only	21099.00
Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in PCC Grade Nominal Size 1:6:12 (One Cement: Six Sand: Twelve graded stone aggregates 40 mm Nominal Size) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.		1.32	Per Cubic Metre		3,602.20	Rs. Three Thousand Six Hundred Two & Paise Twenty Only.	4755.00
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.		81.24	Per Cubic Metre		4,261.30	Rs. Four Thousand Two Hundred Sixty One & Paise Thirty Only.	346188.00
Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 III. P.C.C. grade M 20 Nominal mix (1:2.4:3) upto 5m height including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.		5.96	Per Cubic Metre		6,032.60	Rs. Six Thousand Thirty Two & Paise Sixty Only.	36135.00
Providing and laying 900 mm dia reinforced cement concrete pipe NP2 for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapet clause 1108 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.		7.50	Per Running Metre		4,050.30	Rs. Four Thousand Fifty & Paise Thirty Only.	30377.00
Back filling behind wing walls and return walls complete as per drawing and technical specification clause 1204 3.8 as per HP PWD specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.		21.75	Per Cubic Metre		1,180.00	Rs. One Thousand One Hundred Eighty & Paise Nil Only	25665.00
Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 m in horizontal towards drawing face complete as per specification clause 614, 709, 1204 3.7 including hauling of material in all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge		21.00	Per Each		280.00	Rs. Two Hundred Eighty & Paise Nil Only	5880.00
Total							470099.00

Quoted Rate in Figure (+/-) {% }
 Quoted Rate in Words (+/-) {% }

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
 Nahar Division,
 HP PWD, Nahar