



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Telephone No: 01782-233017

e-mail: ee-rum-hp@nic.in

No. PW/ RMP/TA-I/Publication/2024-

6922

Dated:- 12-09-2024

To

The Executive Engineer (IT Cell),  
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of tender Notice.

Enclosed please find herewith the tender Notice of various works as given in the tender inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated 16<sup>th</sup> July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA: - As above.

*Shakti Negi*  
Executive Engineer,  
B&R Division HPPWD,  
Rampur.  
*CP*



Telephone No: 01782-233017  
e-mail: pc-ran-hp@nic.in

## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

### NOTICE INVITING TENDER

Sealed item rate tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD, Rampur Distt. Shimla (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class so as to reach in this office on **21.09.2024** upto 10:30 A.M. and will be opened on the same day at 11:00 A.M. in the presence of contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **20.09.2024** between 10:00 A.M. to 2:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **20.09.2024** between 02:00 PM to 5:00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, B&R Division, HP. PWD, Rampur Bushahr Distt. Shimla H.P. must accompany with the tender form. Ambiguous/Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer, B&R Division, HP.PWD, Rampur Bushahr reserve the right to reject/accept any offer of tender without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of tender form	Time limit
1	A/R & M/O 88.00 mtr. Span Suspension bridge at Chatti on Satluj River (SH:- P/F Rocker bearing and lifting of existing bridge).	4,98,000/-	10,000/-	350/-	One month
2	R/R damages on various roads in Ganvi section under HPPWD Sub Division Sarahan (SH:- Deployment/Hiring of Poclain 210 excavator-cum loader for removal of slips, boulders etc.)	4,97,260/-	10,000/-	350/-	One month
3	A/R & M/O Treasury Office at Rampur Distt. Shimla (SH:- P/L anti skid tiles, paneling and distempering)	1,24,827/-	2,500/-	350/-	One month

### **Terms and conditions:-**

1. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.
2. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender form.
3. Latest Income tax and sale tax clearance certificates as well as Pan Number and GST number must be attached with the application failing which tender documents will not be issued.
4. The tender forms will be issued to only those contractors who have not more than two works in hand in any of H.P.PWD. Circles.

5. The contractor will have to submit the proof of registration under Employees Providing Funds & Miscellaneous provision Act. 1952 at the time of tender. Failure to observe this condition shall render the tender of the contractor liable to summary rejection.

No: - RMP/Tender/2024

6923-24

Dated:-

12-09-2024

Copy forwarded for information:-


1. The Superintending Engineer 11<sup>th</sup> Circle HPPWD, Shimla.
2. Copy to Notice Board.

<sup>su</sup>  
Executive Engineer,  
Rampur Division (B&R),  
HPPWD, Rampur Bsr.

<sup>su</sup>  
Executive Engineer,  
Rampur Division (B&R),  
HPPWD, Rampur Bsr.

### SCHEDULE OF QUANTITY

Name of Work:- A/R and M/O 88.00 mtr Span Suspension bridge at chatti on satluj River (Sub Head :- P/F Rocker bearing and lifting of existing bridge)				Estimated Cost :-		4,98,000.00
				Earnest Money :-		10,000.00
				Time Allowed :-		15 Days
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Lifting of span, Resetting of Rocker/ Roller Bearings for both the ends including cleaning of the surface thoroughly from grease, dust and foreign matter, the cost includes all materials, labour, machinery, T&P and making all arrangements like scaffolding cribs etc. as per MORT&H specification 2808 & conforming to IRC:183(part-II) Section-IX	1.00	348000			
2	Providing and Fixing in position of Rocker/ Roller Bearings includes complet as per drawing and approved technical specifications, to execute the job, The bearing shall be installed in the presence of authorised representative of the bearing manufacturer for which nothing extra shall be paid including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	2.00	75000			
				Total:-		

  
 Executive Engineer,  
 B & R Division, HP.PWD,  
 Rampur Bsr.

## SCHEDULE OF QUANTITY

Estimated cost:- 4,97,260.00  
 Earnest money 10,000.00  
 Time One Month

**NAME OF WORK:- R/R Damages on various roads in Ganvi Section under HPPWD Sub-Division Sarahan**

(SH:- Deployment/Hiring of Poclain 210 excavator-cum loader for removal of slips, boulders etc.).

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Hiring of earth cutting/excavating machinery Poclain 210 of 1.5 cubic metre bucket capacity @ 90 cubic metre per hour loading capacity to be deployment for earth cutting/excavation/filling/removal of slips / boulders and clearance of blocked side drain etc. Any repair/breakage during operation will be carried out by the contractor /owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in Tippers/ Trucks, removal / disposal of the same in all leads and lifts to the entire satisfaction of Engineer-in-charge.	115.00	Per Hour			
					<b>Total:-</b>	

*Chaiti Negi*  
 Executive Engineer,  
 Rampur Division B&R,  
 H.P.P.W.D., Rampur.

## SCHEDULE OF QUANTITY

Estimated cost:- **1,24,827.00**  
 Earnest money **2,500.00**  
 Time **One Month**

Name of Work:- A/R & M/O Treasury Office at Rampur Bsr. Distt. Shimla (HP).

SH-P/L anti Skid tiles, panelling and distempering).

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Providing and fixing specified wood frame work consisting of battens of 2.5cmx3.5cm size fixed with rawl plug and drilling necessary holes for rawl plug etc, including priming coat complete :Kiln seasoned and chemically treated hollock wood, ncluding hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.17	Per Cubic Metre			
2	Providing and fixing in wall lining/pannelling with pine wood including back side strip of 12mm thick ply and poly sheet with necessary fixing arrangement and screws etc. complete: ncluding hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.08	Per Square Metre			
3	French spirit polishing : Two or more coats on new works including a coat of wood filler including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.08	Per Square Metre			
4	Providing second class deodar wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	0.02	Per Cubic Metre			
5	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metreslead (wooden/concrete joists to be measured and paid for separately For thickness of tiles above 25mm and upto 40mm including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.71	Per Cubic Metre			
6	Providing and fixing 10mm thick antiskid water proof stain and impact resistant heavy duty vetrified tiles Nitco or equivalent 300x300mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement: 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete.including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.76	Per Square Metre			
7	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40 mm flush bend, 20 mm over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: White vitreous china dual purpose WC pan with white solid plastic seat and lid with white vitreous china flushing cistern and C.P. flush bend including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I and as per direction of Engineer-in-Charge.	2.00	Each			
8	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I and as per direction of Engineer-in-Charge.	13.20	Per Square Metre			
9	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil, grease, dirt and other foreign matter) sand papering and knotting readymixed paint brushing wood primer pink including applying a priming coat of red lead paint as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transpotion within all leads and lifts and as per direction of Engineer-in- Charge.	6.93	Per Square Metre			



10	Distempering (two coats) with synthetic/acrylic washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	13.20	Per Square Metre			
11	Painting two coats (excluding priming coat) on new wood and wood based surfaces, with enamel paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	6.93	Per Square Metre			
12	Providing and fixing 110 mm X 90 mm PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	2.00	Each			
13	Providing and fixing CP grating for 100mm dia of superior quality for floor, gully or nahani trap including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
14	Providing and fixing 600mm x 450 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. Brass screws and washers as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	2.00	Each			
15	Providing and fixing 600mm x 20mm C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
16	Providing and fixing 600mm x 120mm glass shelf with C.P. Brass bracket and guard rail complete including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
17	Providing and fixing C.P. Brass toilet paper holder complete including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
18	Providing and fixing chromium plated brass soap dish with C.P. brass brackets fixed to wooden cleats with C.P. brass screws complete, including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Chargé.	2.00	Each			
19	Providing and fixing 15mm nominal dia C.P brass bib tap with capstan head as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
20	Providing and fixing 15mm dia.C.P brass pillar tap with capstan head including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			
21	Providing and fixing 15mm nominal bore P.V.C connection with brass unions (a) 300/450mm length including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	8.00	Each			
22	Providing and fixing vitreous China wash basin 55x40 centimetre cat No.10001 of Hindware or its Equivalent with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	2.00	Each			

23	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	2.00	Each			
					Total:	

  
 Executive Engineer,  
 Rampur Division B&R,  
 H.P.W.D., Rampur.