



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 17-09-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 13-09-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 16-09-2024 from 2.00 P.M. to 5.00 P.m. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Dhaghen Salehra Fagle rod km. 0/00 to 1/500 (SH:- C/O Wire Crated Breast wall at km. 1/480 to 1/500)	Rs.2,53,890/-	Rs.4,100/-	Rs.350/-	Class "D"	Three Months
2	Restoration of Rain damages on Garoru Majharnu Bassi road km. 0/00 to 4/000 (SH:- C/O U Shape drain at km. 2/980 to 3/020 and steel grating over drain at km. 2/990 to 3/020)	Rs.1,43,028/-	Rs.2,900/-	Rs.350/-	Class "D"	Three Months
3	Restoration of Rain damages on Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Basal Drubbal Charanj Banwar Kun Ka Tar Mandokhar Bhargoon Kotli road (MDR-57) km. 0/00 to 80/00 (SH:- Construction of Retaining wall at km. 45/30 to 46/50)	Rs.2,62,729/-	Rs.5,700/-	Rs.350/-	Class "D"	Three Months
4	A/R & M/O k to various Non Residential Buildings under HP PWD, Division Joginder Nagar (SH:- Providing and fixing wooden wall Tile Paneling at Division Office Building)	Rs.3,35,131/-	Rs.6,700/-	Rs.350/-	Class "D"	Three Months
5	A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Supplying of various Office Articles under Harabag Section)	Rs.99,567/-	Rs.2,000/-	Rs.350/-	Class "D"	Two Months
6	Construction of Bridge over river Beas in GP Tullah near Tulne Bharen Temple in Joginder Nagar Constituency to connect the Dharampur Constituency (SH:- Construction of RCC Hume pipe culvert along with both side wing walls on approach road to bridge at km. 0/210)	Rs.2,35,884/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
7	Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarain road km. 0/00 to 34/000 (SH:- Construction of Unlined drain and Maintenance of Hume pipe culvert in km. 26/00 to 34/00)	Rs.98,025/-	Rs.2,000/-	Rs.350/-	Class "D"	Two Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-UNIT/Press/2023-24-

9123-72

Dated:-

12-08-2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITY

Name of Work : Construction of Dhaghon Salehra Fagla road km 0/00 to 1/500
(SH: Construction of wire crated Breast wall at km 1/480 to 1/500)

Name of Work : Construction of Dhagbon Salehra Fagla road km 0/00 to 1/500 (SH: Construction of wire crated Breast wall at km 1/480 to 1/500)				Estimate Cost: Earnest Money: Time Limit :			2,03,890.00 4,100.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time excluding GST.	22.20	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	12.60	Per cubic metre				

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	62.50	Per Cubic metre			
	Total					


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Garoru Majharnu Bassi road Km 0/00 to 4/000 (SH: Construction of U Shape Drain at km 2/980 to 3/020 and steel grating over drain at km 2/990 to 3/020)				Estimate Cost: Earnest Money: Time Limit :		1,43,026.00 2,900,000 Three Months	
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.60	Per cubic metre				
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	612.00	Per Kilogramme			
	Total					

Executive Engineer
B & R Division HP (PWD),
Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Sandapattan Bhari Bagora Bagla Hard Ropari Kolang Triambli Basha Drubhal Charanj Banwar Kun Ka Tar Mandokhar Bhargoon Kotli Road (MDR-57) km 0.00 to 80.00 (SH: Construction of Retaining wall at km 46.630 to 46.650)				Estimate Cost: Earnest Money: Time Limit :		2,82,729.00 5,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.60	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is not with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.10	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 612, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	38.00	Each			
	Total					


 Executive Engineer
 B & R Division HP PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to Various Non-Residential Buildings Under HP.PWD., Division Joginder Nagar (SH / Providing and Fixing Wooden wall Tile Panneling at Division Office Building)				Estimate Cost: Earnest Money: Time Limit :			3,35,131.00 6,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Providing and Fixing wooden tile in skirting/walls cement concrete base with polythine sheet and thermo sheet cushion below complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	108.89	Per cubic metre					
2	Polishing on New wood work with ready mixed wax polish of approved brand and manufacture. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	108.89	Per Square Meter					
		Total						


 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar (SH: Supplying of Various Office Articles under Harabag Section)				Estimate Cost: Earnest Money: Time Limit :			99,567.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	Rs.	P
				Figures	Words			
1	Supplying Godrej Revolving metal chair with 360° swivel along with Knee Tilt Synchro mechanism with three different tilt positions, supports healthy body movements and gives great back support high back ubberized Seat Of Size 761x114-128x761mm (Seven hundred sixty one by one hundred fourteen to one hundred twenty eight by Seven hundred sixty one millimeter) and having castor unit with hydraulic system with 5 (Five) numbers PVC wheels. The back is made up of injection moulded glass-filled nylon & upholstered using mesh fabric with high tenacity yarn. Covered with best quality furnishing cloth with push back spring having double action i.e. fixed and pushed back Seat should be fitted with shoulder action complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each					
2	Supplying Revolving metal chair with high back, ubberized Seat Of Size 360x360mm (three hundred sixty by three hundred sixty millimeter) and back 725x475 mm (seven hundred twenty five by four hundred seventy five millimeter) having castor unit with hydraulic system with 5 (Five) numbers PVC wheels. Seat/back cushion should be made of flexible polyurethane foam having density of 28 kg/m (twenty eight kg/m) and indentation hardness shall be 18 to 25 kg per cum (eighteen to twenty five kilogramme per cubic meter) covered with best quality leather foam furnishing cloth with push back spring having double action i.e. fixed and pushed back Seat should be fitted with shoulder action complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Supplying Office Writing Tables 900mmx1200mmx 760mm (Nine hundred by twelve hundred ten by seven hundred sixty millimeter) made Of mild steel sq. pipe of section 25x25x1.25mm (twenty five by twenty five by one point two five millimeter) painted with synthebe enamel paint with 3 (three) drawers on the right side with beking device in mild steel sq. pipe of section 25x25x1.25 mm (twenty five by twenty five by one point two five millimeter). The drawers of cup board made of 0.8mm (zero point eight millimeter) thick sheet. Table top should be Of 18 mm (eighteen millimeter) thick pre-laminated Board/MDF. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
4	Supplying Computer Table having dimensions 600X900X750mm (six hundred by nine hundred by seven hundred fifty millimeter). The table shall be supplied with steel members duly welded and rigidly fixed table top and provided with a slideable keyboard tray, modesty panel and footrest. The frame shall comprise of hollow rectangular M.S. section of size 50x25x1.6 mm (fifty by twenty five by one point six millimeter). Two side member of the frame identical in shape shall be joined with welding at bottom with a footrest (hollow rectangular M.S. section of size 50x25x1.6mm (fifty by twenty five by one point six millimeter) angularly welded, and at the top in front side welded with a angle size 17x17x3mm (seventeen by seventeen by three millimeter) and at the back on the top side of the frame, a modesty panel of size 200x17x0.8mm (two hundred by seventeen by zero point eight millimeter) thick CRC sheet shall be welded. Thus making the frame rigid in construction. The keyboard tray shall be of size 710x300mm (seven hundred ten by three hundred millimeter) approximately is to be provided with end fittings mad from minimum 2mm (two millimeter) thick MS steel mounted on either side and the keyboard tray shall be easily slideable, provided with two telescopic channels with balls. All exposed steel sections shall be painted with black in colour with powder coating 40-50 micron thickness. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Supplying office metal chair with fabric cushion back and Seat of Size 450x450mm (four hundred fifty by four hundred fifty millimeter) and back 450x250 mm (four hundred fifty by two hundred fifty millimeter). Seat/back cushion should be made of foam covered with best quality fabric with wooden arms complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.00	Each			
6	Supplying Steel Almirah door and shelves made of 1 mm (one millimeter) thick and body made of 0.8mm (zero point eight millimeter thick) thick M.S sheets of size 1980x1010x530mm (one thousand nine hundred eighty by one thousand ten by five hundred thirty millimeter) with 4 (four) shelves 5 (five) compartment shall be painted With synthetic enamel paint on inside and spray hammer tone paint from outside in silver ash/ olive green or as requested by the indenter complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each			
	Total					


 Executive Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Bridge over river Beas in GP Tullah near Tuine Bharari Temple in Joginder Nagar Constituency to connect the Dharampur Constituency (Sub Head:- Construction of RCC Hume Pipe culvert along with both side wing walls on approach road to bridge at km 0/210)					Estimate Cost: Earnest Money: Time Limit :		2,35,884.00 4,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate		AMOUNT	
					Words	Rs. P		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.52	Per cubic metre					
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre					
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.81	Per cubic metre					
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre					
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre					

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.60	Per cubic metre			
8	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of rain Damages on Joginder Ngar Sarkaghat Chumarwin Road km 0/00 to 34/300 (SH: Construction of Unlined Drain and Maintenance of Hume pipe Culvert in km 26/00 to 34/00)					Estimate Cost: Earnest Money: Time Limit :		
					98,025.00 2,000.00 Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT		
					Figures	Words	
1	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each				
2	Construction of unlined drain of average cross section area 40sqm (fourty square meter) in soil to specified lines grade levels and dimensions. Excavated materials to be used in embankment with a lift upto 3m (three millimeter) and lead of 50m (fifty meter) (average lead 25m (twenty five meter)) as per technical specifications clause 307(Mechanical means) within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3800.00	Per running metre				
Total							


 Executive Engineer
 B & R Division HP.PWD,
 Jodhpur Nagar