

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2024- 3309-10
To

Dated:- 31/8/2024

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD, Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

HP.P.W.D. TENDER NOTICE.(offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP, PWD. Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **07-09-2024 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M. on 06-09-2024** No application for issue of tender forms will be received on **06-09-2024** after **4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Balance work for Construction of Sub Jail Building at Reckong Peo in District Kinnaur HP (SH:- Providing steel work in Check post (Gumti) etc.	4,95,054/-	10,000/-	Three Months	350/-	D Class
2	Balance work for Construction of Sub Jail Building at Reckong Peo in District Kinnaur HP (SH:- Providing RCC work in Check Post (Gumti). Etc.	4,99,580/-	10,000/-	Three Months	350/-	D Class
3	Balance work for Construction of Sub Jail Building at Reckong Peo in District Kinnaur HP (SH:- Providing Brick work, Painting and distempering etc. in Administrative Block)	4,99,734/--	10,000/-	Three Months	350/-	D Class
4	Balance work for Construction of Sub Jail Building at Reckong Peo in District Kinnaur HP (SH:- Ply board work in Pantry and Kitchen, wood work in DSP Jail room, Cupboard etc.)	4,99,705/-	10,000/-	Three Months	350/-	D Class
5	Balance work for Construction of Sub Jail Building at Reckong Peo in District Kinnaur HP (SH:- Providing and fixing Interlocking paver block in Courtyard of Administrative Block etc.)	4,99,976/-	10,000/-	Three Months	350/-	D Class
6	Special repair to Old PHC building at Kapa in District Kinnaur HP (SH:- Providing and fixing Paneling Job No.-1)	4,93,200/-	10,000/-	Three Months	350/-	D Class
7	Special repair to Old PHC building at Kapa in District Kinnaur HP (SH:- Providing and fixing Paneling Job No.-2)	4,99,626/-	10,000/-	Three Months	350/-	D Class

8	Special repair to Regional Hospital at R/Peo in District Kinnaur (HP) (SH:- C/O B/wall behind Geriatric ward Job No. 1.	4,86,359/-	10,000/-	Three Months	350/-	D Class
9	Special repair to Regional Hospital at R/Peo in District Kinnaur (HP) (SH:- C/O B/wall behind Geriatric ward Job No. 2	4,98,999/-	10,000/-	Three Months	350/-	D Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:- 

No.PW/KNR-E-Tender/NIT/2024-
Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block development officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office
Letter No. PW/KNR/E-Tender/2024- 3311-24 dated 31-08-2024
from Sr. No. 1 to 9 are of urgent nature and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.


SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,054/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing Steel Work in check post (Gumti) etc.)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (within all lead and lift including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all lead, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	41.93			Per Cubic meter	
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	778.05			Per Kilogram	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1045.81			Per Kilogram	
4	Providing and fixing 1st quality white /coloured glazed wall tiles 30x45 cm conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.10			Per Square meter	

5	Providing and fixing MS BP sheet 1.66mm to 20mm thick in eaves board /facia and soffit etc, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	13.84			Per Square meter
6	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	10.08			Per Square meter
7	Providing ridges or hips 60 cm over all in plain with galvanised iron G.I.sheet J or L hooks, bolts and nuts 8mm dia G.I. Limpet and bitumen washers complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.40			Per Running meter
8	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) :3 graded stone aggregate 20 mm nominal size),foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 90x80 cm and 45 cm deep including Precast RCC Cementate or equivalent cover with frame (heavy duty) of size 455x610 mm internal dimensions, With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 Precast RCC Cementate or equivalent (Heavy Grade) cover with frame forgully trape (Standard Pattern), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	10.00			Each

9	P/L heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curring rubbing and polishing complet Subbase concrete floor to be paid for :- 40 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.52				Per Square meter	
Total:-							


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

(2)

SCHEDULE OF QUANTITY

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing RCC Work in check post(Gumti)etc.)

Estimated Cost :- 4,99,580/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (within all lead and lift including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all lead, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	125.35			Per Cubic meter	
2	Boulder filling under floor, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	45.99			Per Cubic meter	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), including carriage of materials	30.66			Per Cubic meter	
4	Making plinth protection 50mm (Fifty millimeter) thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm (Seventy five millimeter) thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	42.12			Per Square meter	
5	Providing and laying mirror polished Kota stone slab of size 55x55 CM (Fifty tivr into fifty five centimeter) in flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm (Twenty five millimeter) thick, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	67.00			Per Square meter	

6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.84			Per Cubic meter
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone) aggregate 20 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.06			Per Cubic meter
8	Centering and shuttering including strutting, propping etc. and removal of form for all heights : form for all heights, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.				
8.01	Suspended floors, roofs, landings, balconies and access platform	4.41			Per Square meter
8.02	Lintels, beams, plinth beams, girders, bressumers and cantilevers	5.04			Per Square meter
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars Thermo-Mechanically Treated bars of grade Fe-500D or more, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	669.36			Per Kilogram
	Total:-				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing Brick work, Painting & Distempering etc. in Administrative Block).

Estimated Cost :- 4,99,734/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit
			In Fig.	In Words	
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shape s and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	8.02			Per Cubic meter
2	15mm (Fifteen millimeter) cement plaster on the rough side of single or half brick wall of mix : 1 : 6 (1 cement : 6 fine sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	154.04			Per Square meter
3	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equal on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete in Super-structure for all floors, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	637.74			Per Square meter
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: New work (two or more coats) over and include water thinnable priming coat with cement primer, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.20			Per Square meter

5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Painting Steel work with Deluxe Multi Surface Paint to give an even shade.Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD	257.98			Per Square meter
6	Providing and applying white cement based putty of average thickness 1 mm,of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	662.94			Per Square meter
7	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.50			Per Cubic meter
8	Providing and fixing 9mm (Nine millimeter) thick ply wood lining with butt jointing and nails. (framework and cover fillet to be measured and paid for separately.), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	49.86			Per Square meter
	Total:-				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,705/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
 (SH:- Ply board work in pantry and Kitchen, wood work in DSP Jail room. Cupboard etc.)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), jointstreated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.46			Per Square meter	
2	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	62.20			Per Square meter	
3	Providing & fixing Toughened glass panes 6 mm thick with putty and glazing clips in steel doors, windows, clerestory windows, all complete with, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	11.40			Per Square meter	
4	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. 2nd class Kail Wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	0.65			Per Cubic meter	
5	Providing and fixing 6mm thick ply wood lining with butt jointing and nails. (framework and cover fillet to be measured and paid for separately.), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.53			Per Square meter	

6	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1.0 mm thick, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	17.03			Per Square meter	
7	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
8	Providing and fixing Pine wood panelling with plank size 75 x 25mm (Seventy five millimeter into twenty five millimeter) & 75mm x 12.5mm (Seventy five millimeter into twelve point five millimeter) in combination over frame of wood work (to be paid separately) with top moulding complete in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	92.11			Per Square meter	
9	Providing and fixing decorative veneering 4mm thick, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.47			Per Square meter	
10	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.00			Each	
11	Providing and fixing MS BP sheet 1.66mm to 20mm thick in eaves board /facia and soffit etc, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	26.10			Per Square meter	
Total:-						

Executive Engineer
Kalpa Division
HP. PWD, Kalpa

SCHEDULE OF QUANTITY

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing and fixing interlocking paver block in courtyard of Administrative Block etc)

Estimated Cost :- 4,99,976/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	P/L heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curring rubbing and polishing complet Subbase concrete floor to be paid for :- 40 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	261.74			Per Square meter	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Estimated Cost :- 4,93,200/-
Earnest Money :- 10,000/-
Time :- Three Months

Name of work:- Special repair to Old PHC Building at Kalpa in Distt. Kinnaur (H.P.)
(SH:- Providing and fixing Panelling Job No.I)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. 2nd class Kail Wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.46			Per Cubic meter	
2	Providing and fixing Pine wood panelling with plank size 75 x 25mm (Seventy five millimeter into twenty five millimeter) & 75mm x 12.5mm (Seventy five millimeter into twelve point five millimeter) in combination over frame of wood work (to be paid separately) with top moulding complete in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	105.82			Per Square meter	
3	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :2nd class teak wood, 50x20mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	106.70			Per Running meter	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Name of work:- Special repair to Old PHC Building at Kalpa in Distt. Kinnaur (H.P.)
(SH:- Providing and fixing Panelling Job No.2)

Estimated Cost :- 4,99,626/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	113.47			Per Square meter	
2	Providing and fixing Pine wood panelling with plank size 75 x 25mm (Seventy five millimeter into twenty five millimeter) & 75mm x 12.5mm (Seventy five millimeter into twelve point five millimeter) in combination over frame of wood work (to be paid separately) with top moulding complete in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	115.88			Per Square meter	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,86,359/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Special repair to Regional Hospital at R/Peo in Distt. Kinnaur (H.P.)
 (SH:- C/O B/Wall behind Geretric wars Job No.-I).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.50			Per Cubic meter	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802.803 1202 and 1203. 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimeter) nominal size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.06			Per Cubic meter	
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	85.14			Per Cubic meter	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.00			Per Cubic meter	

5	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.00				Each	
Total:-							


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,999/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Special repair to Regional Hospital at R/Peo in Distt. Kinnaur (H.P.)
(SH:- C/O B/Wall behind Geretric wars Job No.-2).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	19.55			Per Cubic meter	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803 1202 and 1203. 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimeter) nominal size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.29			Per Cubic meter	
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	89.01			Per Cubic meter	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	21.85			Per Cubic meter	

5	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.00			Each
Total:-					



Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.