



**OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229 , e-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)

No.PW-KSG-E-Tenders/2023-

3508

Dated:- 7.9.2024

To

✓ The Executive Engineer (IT) Cell,  
HPPWD, Nirman Bhawan, Nigam Vihar,  
Shimla-2.

**Subject :-**

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 09.09.2024 per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16 July, 2021. Certified that the works mentioned in the Tender Notice are urgent in nature.

**Encl:- As above.**

Executive Engineer,  
B&R Division,  
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**  
PH: 01907-222229 Fax: 222229, E-mail: [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)  
**Notice inviting tender**

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **21.09.2024 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 19.09.2024** for which the application should reach in this office **upto 1.00 PM 19.09.2024**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	Construction of Primary Health Centre at Mahog Tehsil Karsog Distt. H.P. (SH:- Site development at PHC Mahog) Deposit & Medical Fund	4,58,735/-	9,200/-	One month	350/-
2	Construction of Jingal Mod to Ghanufri via Kotla link road Km. 0/00 to (SH:- F/C 5/7 mtr wide road in Km. 0/720 to 1/060)	4,08,597	8,200/-	One month	350/-
3	A/R & M/O various road under Churag Sub-Division (SH:- Supplying and stacking dual directional delineator for road side)	94,960/-	1,900/-	One month	350/-
4	A/R & M/O various road under Churag Sub-Division (SH:- Supplying and stacking of directional retro reflective cat eyes ABS plastic sutds)	94,900/-	1,900/-	One month	350/-
5	Construction of link road from Navidhar to Mahog via Thach (SH:- F/C 5/7 mtr wide road in Km. 0/135 to 0/240)	78,608/-	1,600/-	One month	350/-
6	C/o Paralakshot to Sahal village (Harizan Basti) G.P. Pangna Km. 0/00 to 1/600(SH:- C/o 900mm dia NP2 Hume pipe culvert at Rd 0/460)	3,24,350/-	6,500/-	One month	350/-
7	C/o Sainj Nang via Sainjeli Shout road Km. 0/00 to 8/500 (SH:- C/o 900mm dia Hume pipe culvert at RD 4/840)	3,09,223/-	6,200/-	One month	350/-
8	C/o Paralakshot to Sahal village (Harizan Basti) GP Pangna Km. 0/00 to 1/600(SH:- C/o 900mm dia NP2 Hume pipe culvert at RD 1/135)	3,25,843/-	6,600/-	One month	350/-
9	Restoration of rain damages on Nehal to Shaloo Km. 0/00 to 6/00 (SH:- C/o Retaining wall at RD 0/090 to 0/094)	1,98,649/-	4,000/-	Two months	350/-
10	R/R damages on Lower Karsog to Takrol road km. 0/00 to 10/00 (SH:- C/o R/wall at RD 0/615 to 0/635)	3,92,374/-	7,900/-	Two months	350/-
11	C/o Karsog to Shopa via Nali road km. 0/00 to 2/500 (SH:- P/L cement concrete and P/L paver block in Km. 0/315 to 0/420)	4,92,248/-	9850/-	One month	350/-
12	R/R damages due to laying of cable on Chindi Pangna road Km. 0/00 to 12/480 (SH:- C/o PCC R/wall at RD 3/260 to 3/275)	4,71,367/-	9,500/-	One month	350/-
13	R/R damages due to laying of cable on Chindi Pangna road Km. 0/00 to 12/480 (SH:- C/o PCC R/wall at RD 3/460 to 3/472)	4,61,253/-	9,300/-	One month	350/-

14	Repair of tractor of road Chewari to Thani Nallah Km. 0/00 to 3/500 (SH:- Removal of slips at various RDs) DC Deposit NDF/2023/757.	1,98,408/-	4,000/-	One month	350/-
15	Repair of Ambulance road Kotlu to Kevidhr Km. 0/00 to 5/00 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/752	2,98,962/-	6,000/-	One month	350/-
16	Repair of Tractor road Kanail to Sarail Km. 0/00 to 1/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/754	87,694/-	1,800/-	One month	350/-
17	Repair of Tractor road Gatat Nallah to Khanmarla Km. 0/00 to 2/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/759	1,47,151/-	3,000/-	One month	350/-
18	Repair of Tractor road Rashog to Khenda Km. 0/00 to 3/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/755	1,97,606/-	4,000/-	One month	350/-
19	Repair of road Narahan to Chowki Km. 0/00 to 3/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/758	1,97,710/-	4,000/-	One month	350/-
20	Restoration of rain damages on Bhourgali to Beludhank road Km. 0/00 to 3/00 (SH:- Removal of slips at various RDs)	4,98,715)	10,000/-	One month	350/-
21	Repair of road Kenahal to Dhardalou Km. 0/00 to 1/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/756	87,214/-	1,800/-	One month	350/-
22	Repair of road Chewari to Pekwadhar Km. 0/00 to 1/500 (SH:- removal of slips on various RDs) DC Deposit NDF/2023/753	88,646/-	1,800/-	One month	350/-
23	C/o road Pangna Majhangan road Km. 0/00 to 8/00 (SH:- C/o 900mm dia pipe culvert & wing wall at RD 6/105)	4,29,478/-	8,600/-	Two month	350/-
24	C/o road Kelodhr to Dharahal in GP Kelodhar (SH:- Repair of pot holes)	1,47,918/-	3,000/-	One month	350/-

#### TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer  
B&R Division  
HPPWD Karsog,

No. PW-E-Tender-NIT/23

3500-07

Dated:- 7.9.2024

1. Copy to the Superintending Engineer, 1<sup>st</sup> Circle, HP,PWD, Mandi for information please.
2. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
3. The Block Development Officer Karsog, Tehsil Karsog Distt. Mandi HP.
4. All the Assistant Engineers, working under this Division.
5. Copy to Drawing & Account Branch.
6. Notice board of this office.

Executive Engineer,  
B&R Division,  
HP PWD Karsog

## Percentage Schedule of Quantity

Estimated Cost      458735  
Earnest Money      9200  
Time      One month

**Name of Work:-** Construction of Primary Health Centre at Mahog Tehsil Karsog Distt. Mandi H.P. (SH:- Site development at PHC Mahog) Deposit & Medical Fund

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.-)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 130.03 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 39009/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, as per direction of Engineer-in-Charge including carriage of material within all heads and lifts and other incidentals.	2203.34	Per Cubic Metre	208.20	458735.00	Rupees Four Lakhs Fifty Eight Thousand Seven Hundred Thirty Five and Paise Zero Only
<b>Total in Figures</b>					458735.00	
<b>Quoted Rate in Figures</b>			Select		0.00	
<b>Quoted Rate in Words</b>						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.



## Percentage Schedule Of Quantity

Estimated Cost      408597  
Earnest Money      8200  
Time      One month

Name of Work:-Construction of Jingal Mod to Ghanufri via Kotla Katachi link road km 0/00 to 1/300 (SH:- F/C 5/7 mtr wide road In Km 0/720 to 1/060).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Total Amount with all taxes	Total Amount with all taxes including GST
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 70.84 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 21252/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2059.98	Per Cubic Metre	198.35	408597.00	Rupees Four Lakhs Eight Thousand Five Hundred Ninety Seven and Paise Zero Only
Total in Figures					408597.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
GPPWD, Karsog.

# Percentage Schedule of Quantity

Estimated Cost 94960  
Earnest Money 1900  
Time One Month

Name of Work:- A/R & M/O various road under Churag Sub Division (SH:- Supplying and stacking dual directional Delineator for road side)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Supplying and stacking Dual-directional delineator made of 18 gauge M S rectangular pipe of size 25*68 mm and of length 600mm. Pipe powder coated. Head made of impact resistant plastic rectangular moulded with flat face provided with High intensity Prismatic Reflectors on colour (white/yellow/red) of size 100*125 mm with additional 2 reflective strips of 25 mm wide. CAT PART No. GPL-UBPH-1-56 including as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and proper stacking in all respect.	119.00	Each	797.98	94960.00	Rupees Ninety Four Thousand Nine Hundred Sixty and Paise Zero Only
Total in Figures					94960.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
DAPPWD, Karsog.

# Percentage Schedule of Quantity

Estimated Cost 94900  
Earnest Money 1900  
Time One Month

Name of Work:- A/R & M/O various road under Churag Sub Division (SH:-Supplying and stacking of directional retro reflective cat-eyes ABS plastic studs).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Supplying and stacking of dual directional retro reflective cat eyes studs made from high quantity ABS plastic studs of 102*90*16 mm (one hundred two into ninety into sixteen millimeter) size in yellow and red colour two way Acrylic prismatic reflectores providing with fixing to roads by hammering made of gree lite as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and proper stacking in all respect.	224.00	Each	423.66	94900.00	Rupees Ninety Four Thousand Nine Hundred and Paise Zero Only
Total in Figures					94900.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Name of Work:-Construction of link road from Navdhar to Mahog via Thach (SH:- F/C 5/7 mtr wide road in Km. 0/135 to 0/240)

Estimated Cost 78608  
Earnest Money 1600  
Time One month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 22.25 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 6675/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	351.15	Per Cubic Metre	223.86	78608.00	Rupees Seventy Eight Thousand Six Hundred Eight and Paise Zero Only
Total in Figures					78608.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words			Select			

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.



## Schedule of Quantity

Estimated Cost  
Earnest Money

324350  
6500  
One Month

Time

One Month

Name of work :- C/O Paralakshot to Sahal village (Harizan Basti ) G.P. Pangna Km 0/00 to 1/600 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 0/460)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.11	Per Cubic Metre	559.05	24101.00	Rupees Twenty Four Thousand One Hundred One and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.04	Per Cubic Metre	6306.30	63315.00	Rupees Sixty Three Thousand Three Hundred Fifteen and Paise Zero Only
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
4	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.94	Per Cubic Metre	5546.80	177165.00	Rupees One Lakh Seventy Seven Thousand One Hundred Sixty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.36	Per Cubic Metre	1322.40	13700.00	Rupees Thirteen Thousand Seven Hundred and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	14.00	Each	373.15	5224.00	Rupees Five Thousand Two Hundred Twenty Four and Paise Zero Only
<b>Total in Figures</b>						
<b>Quoted Rate in Figures</b>					324350.00	
<b>Quoted Rate in Words</b>			Select		0.00	

Executive Engineer,  
Katsog Division,  
HPPWD, Karsog.

# Percentage Schedule of Quantity

Estimated Cost      309223  
Earnest Money      6200  
Time      One Month

Name of Work:- C/O Saini Nanji via Sainjly Shout road Km. 0/00 to 8/500(SH):- C/O 900 mm dia Hume Pipe culvert at RD 4/840)

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.15	Per Cubic Metre	390.20	16447.00	Rupees Sixteen Thousand Four Hundred Forty Seven and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Noimnal mix 1:4:8. ( one cement : four sand: eight graded stone aggregate as per direction of Engineer in charge including carriage of materials with in all lead and lifts and other incidentals As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	29.43	Per Cubic Metre	5500.00	161865.00	Rupees One Lakh Sixty One Thousand Eight Hundred Sixty Five and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.04	Per Cubic Metre	5700.00	80028.00	Rupees Eighty Thousand Twenty Eight and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5100.00	38250.00	Rupees Thirty Eight Thousand Two Hundred Fifty and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.04	Per Cubic Metre	1200.00	9648.00	Rupees Nine Thousand Six Hundred Forty Eight and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	Rupees Two Thousand Nine Hundred Eighty Five and Paise Zero Only
Total in Figures					309223.00	
Quoted Rate in Figures						
Quoted Rate in Words			Select	#VALUE!	0.00	

Executing Engineer,  
Karsog Division,  
AHPWD, Karsog.

## Schedule of Quantity

Name of work :- C/O Paralakshmi Sahai village (Harizan Basti) G.P. Pangna Km 0/00 to 1/600 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 1/135)

Estimated Cost 325843  
Earnest Money 6600  
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Total Amount with all taxes	Total Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.11	Per Cubic Metre	559.05	24101.00	Rupees Twenty Four Thousand One Hundred One and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.04	Per Cubic Metre	6306.30	63315.00	Rupees Sixty Three Thousand Three Hundred Fifteen and Paise Zero Only
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
4	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.94	Per Cubic Metre	5546.80	177165.00	Rupees One Lakh Seventy Seven Thousand One Hundred Sixty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.36	Per Cubic Metre	1322.40	13700.00	Rupees Thirteen Thousand Seven Hundred and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	373.15	6717.00	Rupees Six Thousand Seven Hundred Seventeen and Paise Zero Only
Total in Figures					325843.00	
Quoted Rate in Figures			Select			0.00
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Name of Work:- Restoration of rain damages on Nehal to Shalwa Km 0/00 to 6/00 (SH:- C/O Retaining Wall at RD 00/090 to 00/94) NDF 2023/1702

Sr.No.

Sub-Head and items of works.

Estimated Cost 198649

Earnest Money 4000

Time Two Months

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in	Total Amount with all taxes	Total Amount with all taxes including GST
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.92	Per Cubic Metre	390.20	3090.00	Rupees Three Thousand Ninety and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:4:8 ( one cement: four sand: eight graded stone aggregate 40mm ( forty millimetre) nominal size as per direction of Engineer in charge including carriage of materials within all lead and lifts and other incidentals As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	32.02	Per Cubic Metre	5546.80	177608.00	Rupees One Lakh Seventy Seven Thousand Six Hundred Eight and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.52	Per Cubic Metre	1322.40	8622.00	Rupees Eight Thousand Six Hundred Twenty Two and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	25.00	Each	373.15	9329.00	Rupees Nine Thousand Three Hundred Twenty Nine and Paise Zero Only
Total in Figures					198649.00	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	

Executive Engineer,  
Karsog Division,  
41PPWD, Karsog.

## Percentage Schedule of Quantity

Name of Work:- R/R Damages on Lower Karsog to Takrol road Km. 0/00 to 10/00 (SH:- C/O R/Wall at RD 0/615 to 0/635)

Estimated Cost      392374  
Earnest Money      7900  
Time      Two Months

Sub-Head and items of works.						
Sr.No.		No. Or Qty.	Unit	Estimated Rate (In	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	34.40	Per Cubic Metre	379.90	13069.00	Rupees Thirteen Thousand Sixty Nine and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:4:8 ( one cement: four sand: eight graded stone aggregate 40mm ( forty millimetre) nominal size as per direction of Engineer in charge including carriage of materials within all lead and lifts and other incidentals As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	66.50	Per Cubic Metre	5457.80	362944.00	Rupees Three Lakhs Sixty Two Thousand Nine Hundred Forty Four and Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692.00	Rupees Six Thousand Six Hundred Ninety Two and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	7.00	Per Cubic Metre	1381.34	9669.00	Rupees Nine Thousand Six Hundred Sixty Nine and Paise Zero Only
Total In Figures					392374.00	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.



Percentage Schedule Of Quantity

Estimated Cost      492248  
Earnest Money      9850

Time      One Month

Name of Work:- C/O Karsog to Shopa via Nali road km 0/00 to 2/500 (SH:-P/L Cement Concrete and P/L Paver Block in km 0/315 to 0/420 )

Sr.No.	Sub-Head and items of works.	Qty	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Providing concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.84	Per Cubic Meter	7476.60	13757	Rupees Thirteen Thousand Seven Hundred Fifty Six and Paise Ninety Four Only
2	Providing and laying inter locking concrete block pavement having thickness 80 mm (milli meter) as per drawings and technical specification clause 1504. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	373.50	Per Cubic Meter	1281.10	478491	Rupees Four Lakhs Seventy Eight Thousand Four Hundred Ninety and Paise Eighty Five Only
Total in Figures					492248	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

  
**Executive Engineer,**  
 Karsog Division,  
 HPPWD, Karsog.

## Percentage Schedule Of Quantity

Estimated Cost      471367  
Earnest money      9500  
Time      One Month

**Name of Work:- R/R Damages due to laying of cable on Chindi Pangna road Km 0/00 to 12/480/SH:- C/O P.C.C R/Wall at R.D 3/260 to 3/275).OFC Deposit**

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount	
					with all taxes	Taxal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of matenal within all leads and lifts and other incidentals.	44.25	Per Cubic Meter	390.20	17266.00	Rupees Seventeen Thousand Two Hundred Sixty Six and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Noimnal mix 1:4:8 ( one cement: four sand: eight graded stone aggregate 40mm ( forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	76.78	Per Cubic Meter	5500.00	422290.00	Rupees Four Lakhs Twenty Two Thousand Two Hundred Ninety and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	373.15	11195.00	Rupees Eleven Thousand One Hundred Ninety Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.18	Per Cubic Meter	1200.00	20616.00	Rupees Twenty Thousand Six Hundred Sixteen and Paise Zero Only
<b>Total in Figures</b>					471367.00	
<b>Quoted Rate in Figures</b>			Select		0.00	
<b>Quoted Rate in Words</b>				#VALUE!		

Executive Engineer,  
Karspg Division,  
DPPWD, Karsog.

### Percentage Schedule Of Quantity

Estimated Cost                      461253  
Earnest money                      9300  
Time                      One Month

**Name of Work:- R/R Damages due to laying of cable on Chindi Pangna road Km 0/00 to 12/480/SH:- C/O P.C.C R/Wall at R.D 3/460 to 3/472), OFC Deposit**

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.50	Per Cubic Meter	390.20	16974.00	Rupees Sixteen Thousand Nine Hundred Seventy Four and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimnal mix 1:4:8. ( one cement: four sand: eight graded stone aggregate 40mm ( forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	75.02	Per Cubic Meter	5500.00	412610.00	Rupees Four Lakhs Twelve Thousand Six Hundred Ten and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	32.00	Each	373.15	11941.00	Rupees Eleven Thousand Nine Hundred Forty One and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.44	Per Cubic Meter	1200.00	19728.00	Rupees Nineteen Thousand Seven Hundred Twenty Eight and Paise Zero Only

<b>Total in Figures</b>					461253.00	
<b>Quoted Rate in Figures</b>		Select			0.00	
<b>Quoted Rate in Words</b>				#VALUE!		

Executive Engineer,  
Karsbg Division,  
HPPWD, Karsog.

**Percentage Schedule Of Quantity**

Estimated Cost      198408  
Earnest Money      4000  
Time      One Month

Name of Work:- Repair of tractor road Chewari to Thani Nallah Km 0/00 to 3/500 (SH:- Removal of slips on various RD's) D.C Deposit NDF/2023/757.						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees One Lakh Ninety Eight Thousand Four Hundred Eight and Paise Zero Only
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1653.40	Per Cubic Meter	120.00	198408.00	
Total in Figures					198408.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

  
Executive Engineer,  
Karsod Division,  
APPWD, Karsod.

# Percentage Schedule Of Quantity

Estimated Cost 238962  
Earnest Money 6000  
Time One Month

Name of Work:- Repair of ambulance road Kotlu to Kevidhar Km 0/00 to 5/00 (SH:- Removal of slips on various RD/S) D.C Deposit NDF/2023/752.					
Sr.No.	Sub-Head and Items of works.				
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes
		2491.35	Per Cubic Meter	120.00	298962.00
Total in Figures					298962.00
Quoted Rate in Figures					0.00
Quoted Rate in Words					Zero and Paise Zero Only

Executive Engineer,  
Karsog Division,  
DHPPWD, Karsog.



**Percentage Schedule Of Quantity**

Estimated Cost      87694  
Earnest Money      1800  
Time      One Month

Name of Work:- Repair of tractor roadKanail to Sarail Km 0/00 to 1/500 (SH:- Removal of slips on various RD'S) D.C Deposit NDF/2023/754.						
Sub-Head and Items of works.						
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material, with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other Incidentals	730.78	Per Cubic Meter	120.00	87694.00	Rupees Eighty Seven Thousand Six Hundred Ninety Four and Paise Zero Only
Total in Figures					87694.00	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	
Zero and Paise Zero Only						

Executive Engineer,  
Karsog Division,  
DPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost 147151  
Earnest Money 3000  
Time One Month

Name of Work:- Repair of tractor road Gatat Nallah to Khanmarla Km 0/00 to 2/500 (SH:- Removal of slips on various RD's) D.C Deposit NDF/2023/759.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes Including GST in Rupees One Lakh Forty Seven Thousand One Hundred Fifty One and Paise Zero Only
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1226.26	Per Cubic Meter	120.00	147151.00	
Total in Figures					147151.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost 197606  
Earnest Money 4000  
Time One Month

Name of Work:- Repair of tractor road Rashog to Khenda Km 0/00 to 3/500 (SH:- Removal of slips on various RD/S) D.C Deposit NDF/2023/755						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees One Lakh Ninety Seven Thousand Six Hundred Six and Paise Zero Only
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1646.72	Per Cubic Meter	120.00	197606.00	
Total in Figures					197606.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      197710  
Earnest Money      4000  
Time      One Month

Name of Work:- Repair of road Narahan to Chowki Km 0/00 to 3/500 (SH:- Removal of slips on various RD's) D.C Deposit NDF/2023/758.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1647.58	Per Cubic Meter	120.00	197710.00	Rupees One Lakh Ninety Seven Thousand Seven Hundred Ten and Paise Zero Only
Total in Figures					197710.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

  
Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

### Percentage Schedule of Quantity

Name of Work:- Restoration of Rain Damages on Bourgailli to Beludhank road Km. 0/00 to 3/000 (SH:- Removal of slips on various RD)

Estimated Cost      498715  
Earnest Money      10000  
Time      One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3945.53	Per Cubic Metre	126.40	498715.00	Rupees Four Lakhs Ninety Eight Thousand Seven Hundred Fifteen and Paise Zero Only
Total in Figures					498715.00	
Quoted Rate in Figures						
Quoted Rate in Words		Select		#VALUE!	0.00	

Executive Engineer,  
Karsog Division,  
dHPPWD, Karsog.



### Percentage Schedule Of Quantity

Estimated Cost      87214  
Earnest Money      1800  
Time      One Month

Name of Work:- Repair of Tractor road Kanehal to Dhardalou Km 0/00 to 1/500(SH):- Removal of slips at various RD) Deposit NDF 2023/756

Sr.N o.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	726.78	Per Cubic Metre	120.00	87214.00	Rupees Eighty Seven Thousand Two Hundred Fourteen and Paise Zero Only
<b>Total in Figures</b>					87214.00	
<b>Quoted Rate in Figures</b>			Select		0.00	
<b>Quoted Rate in Words</b>			Zero and Paise Zero Only			

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

### Percentage Schedule Of Quantity

Estimated Cost      88646  
Earnest Money      1800  
Time      One Month

Name of Work:- Repair of Tractor road Chewari to Pekwadhar Km 0/00 to 1/500(SH):- Removal of slips at various RD) Deposit NDF 2023/753

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	738.72	Per Cubic Metre	120.00	88646.00	Rupees Eighty Eight Thousand Six Hundred Forty Six and Paise Zero Only
Total in Figures					88646.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		

  
Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

## Percentage Schedule of Quantity

Estimated Cost      429478  
Earnest Money      8600  
Time      Two Months

Name of Work:- C/O road Pangna Majhangan road Km. 0/00 to 8/00 (SH:- C/O 900 mm dia Hume Pipe culvert & Wing Wall at RD 6/105)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (1/n)	Total Amount with all taxes	Total Amount with all taxes including GST
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	51.16	Per Cubic Metre	390.20	19963.00	Rupees Nineteen Thousand Nine Hundred Sixty Three and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	53.10	Per Cubic Metre	5500.00	292050.00	Rupees Two Lakhs Ninety Two Thousand Fifty and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	11.25	Per Cubic Metre	5700.00	64125.00	Rupees Sixty Four Thousand One Hundred Twenty Five and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5100.00	38250.00	Rupees Thirty Eight Thousand Two Hundred Fifty and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.60	Per Cubic Metre	1200.00	9120.00	Rupees Nine Thousand One Hundred Twenty and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,7/09,1204,3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	16.00	Each	373.15	5970.00	Rupees Five Thousand Nine Hundred Seventy and Paise Zero Only
<b>Total in Figures</b>					429478.00	
<b>Quoted Rate in Figures</b>			Select		0.00	
<b>Quoted Rate in Words</b>						


Executive Engineer,  
Karsog Division,  
4 HPPWD, Karsog.

# Percentage Schedule of Quantity

Estimated Cost      147918  
Earnest Money      3000  
Time      One Month

Name of Work:- C/O road Kelodhar to Dharhal in G.P. Kelodhar (SH:- Repair of Pot Holes)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in	Total Amount with all taxes	Total Amount with all taxes including GST
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.29	Per Cubic Metre	3516.45	88931.00	Rupees Eighty Eight Thousand Nine Hundred Thirty One and Paise Zero Only
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	172.68	Per Square Metre	341.60	58987.00	Rupees Fifty Eight Thousand Nine Hundred Eighty Seven and Paise Zero Only
Total in Figures					147918.00	
Quoted Rate in Figures						0.00
Quoted Rate in Words			Select			

  
Executive Engineer,  
Karsog Division,  
DHPPWD, Karsog.