

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 & 8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 09-10-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 A.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/ Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.


| S N    | Tender Schedule                                                                                                                             |                            |               |             |              |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|---------------|-------------|--------------|
| 1      | Last date for tender receipt of application for tender form                                                                                 | 07-10-2024 up to 4:00 PM   |               |             |              |
| 2      | Last date of sale of tender forms                                                                                                           | 08-10-2024 up to 4:00 PM   |               |             |              |
| 3      | Date of receipt of tender forms                                                                                                             | 09-10-2024 up to 11:00 A.M |               |             |              |
| 4      | Date of opening of tenders                                                                                                                  | 09-10-2024 at 11:30 A.M    |               |             |              |
| Sr. No | Name of Work                                                                                                                                | Estimat ed cost            | Earnest Money | Time Limit  | Cost of Form |
| 1      | C/O Narag wasni Dinger road Km 0/0 to 17/600 (SH:- ROFD in Km 10/00 to 10/050)                                                              | 133984                     | 2500          | three month | 350/-        |
| 2      | R/R damages on Lawass Chowki Preet Nagar road Km 0/0 to 42/00 (SH:- C/O R/wall at RD 35/290 & C/O B/Wall at RD 35/270 to 35/285)            | 499874                     | 10000         | three month | 350/-        |
| 3      | R/R damages on Banalag Dhamesha Panchpir road Km 0/0 to 12/0 (SH:- C/O B/wall Between RS 2/330 to 2/345 & R/wall between RD 5/900 to 5/915) | 498560                     | 10000         | three month | 350/-        |
| 4      | R/R Damages on Prem Nagar Chandog road Km 0/0 to 15/00 (SH:- C/O PCC R/wall at RD 1/165 to 1/180)                                           | 480562                     | 10000         | Two month   | 350/-        |
| 5      | R/R damages on Dilman Deol Tikkeri road Km 0/0 to 7/0 (SH:- C/O PCC R/wall at RD 4/445 to 4/465)                                            | 491021                     | 10000         | Three month | 350/-        |
| 6      | R/R damages on link road to village Ganyar Km 0/0 to 5/0 (SH:- P/L G-III (WBM) from RD 2/100 to 4/750 for correction in different RD;s)     | 499305                     | 10000         | Three month | 350/-        |
| 7      | R/R Oachghat Narag road Km 0/0 to 14/00 (SH:- P/L interlocking paver block in Km 8/380 to 8/445)                                            | 433477                     | 9000          | Three month | 350/-        |
| 8      | R/R damages on Machher Jabiyana Wasni road Km 0/0 to 9/0 (SH:- C/O PCC R/Wall at RD 5/100 to 5/113)                                         | 487123                     | 10000         | Three month | 350/-        |
| 9      | R/R damages on Kalaghat Banona road Km 0/0 to 5/0 (SH:- C/O unlined drain and dressing of earthen shoulders in Km 0/0 to 5/00)              | 499724                     | 10000         | Three month | 350/-        |
| 10     | R/R damages on Dilman Deol Tikkeri road Km 0/0 to 7/0 (SH:- C/O PCC R/wall at RD 5/150 to 5/160)                                            | 488883                     | 10000         | Three month | 350/-        |
| 11     | R/R damages on Machher Jabiyana Wasni road Km 0/0 to 9/0 (SH:- C/O PCC R/Wall at RD 5/500 to 5/524)                                         | 484794                     | 10000         | Three month | 350/-        |
| 12     | C/O Two No's Class rooms at GSSS Apron Tehsil Pachhad Distt. Sirmour H.P (SH:- P/F M.S Gril in windows).                                    | 46967                      | 1000          | Three Month | 350/-        |
| 13     | R/R damages on link road to village Ganyar Km 0/0 to 5/0 (SH:- P/L G-III (WBM) from RD 0/00 to 2/00 for correction in different RD;s)       | 495203                     | 10000         | Three month | 350/-        |
| 14     | R/R damages on Sirmouri Mandir Bagthan road Km 0/0 to 10/375 (SH:- C/O R/wall at RD 1/795 to 1/810)                                         | 334463                     | 7000          | Three month | 350/-        |

|    |                                                                                                                          |        |       |             |       |
|----|--------------------------------------------------------------------------------------------------------------------------|--------|-------|-------------|-------|
| 14 | Link road to village Gandhal Km 0/10 to 7/0(SH:- C/O 900 mm dia Hume Pipe Culvert alongwith wing wall at RD 1/300)       | 300619 | 6000  | Three month | 350/- |
| 15 | R/R damages on Lawassa Chowki Preet Nagar road Km 0/0 to 42/00 (SH:- C/O R/wall between RD 2/730 to 2/742)               | 315100 | 6000  | Three month | 350/- |
| 16 | R/R damages on Lawassa Chowki Preet Nagar road Km 0/0 to 42/0 (SH:- P/L G-II , interlocking tiles in Km 7/060 to 7/140). | 493971 | 10000 | Three month | 350/- |

**Certificate:-** It is certified that the tender of above work are exigency/emergent nature and in public interest to

**Terms & conditions:-**

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

  
Executive Engineer  
Sarhan B&R Division.  
HP.PWD, Sarhan.

No.PW/SRN/Estt-Tender/2022-23-

3356-3406

Copy forwarded for information and necessary action to:-

Dated:- 24-9-24

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12<sup>th</sup> Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.

  
Executive Engineer  
Sarhan B&R Division.  
HP.PWD, Sarhan.

# SCHEDULE OF QUANTITY

Name of work:-A/R & M/O Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- ROFD in km 10/00 to 10/050)

Estimated cost:-Rs. 1,33,984/-✓

Earnest money:- Rs. 2,500 ✓

Time Limit:- Three Month.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Qty.     | Unit            | Rate        |                                                       | Amount    |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-------------|-------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |                 | in figures. | in words                                              |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 3        | 4               | 5           | 6                                                     | 7         |
| 1      | Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 84.65 cum (eighty four point sixty five) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases. | 507.90 ✓ | Per cubic Metre | 263.80 ✓    | Rupees two hudred sixty three and paise eighty only ✓ | 133984.00 |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |                 |             | Total                                                 | 133984.00 |

Executive Engineer  
KS Sarahan Division  
HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:-R/R Damages on Lawassa Chowki Preet Nagar road km 0/0 to 42/0 (SH:- C/O R/wall at RD 35/275 to 35/290 & C/O B/Wall at RD 35/270 to 35/285)


Estimated cost:-Rs. 4,99,874/-

Earnest money:- Rs 10,000

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Qty.     | Unit             | Rate        |                                                                        | Amount    |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-------------|------------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |                  | in figures. | in words                                                               |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 3        | 4                | 5           | 6                                                                      | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.                                                                                                                                                                                                   | 20.69 ✓  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only ✓                      | 5400.00   |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                            | 92.17 ✓  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only ✓ | 476192.00 |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge | 29.000 ✓ | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only ✓                            | 8120.00   |

|   |                                                                                                                                                                                                                                                                                                                                                                                                |       |                  |        |                                                       |           |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|--------|-------------------------------------------------------|-----------|
| 4 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 12.87 | Per Cubic Metre. | 789.60 | Rupees seven hundred eighty nine and paise sixty only | 10162.00  |
|   |                                                                                                                                                                                                                                                                                                                                                                                                |       |                  |        |                                                       | 499874.00 |

  
 Executive Engineer  
 Sarahan Division  
 HP, PWD, Sarahan

### SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Banalag Dhamesha Panchpir road km 0/0 to 12/00 (SH:- C/O B/wall Between RD 2/330 to 2/345 & R/Wall Between RD 5/900 to 5/915)

Estimated cost:- Rs. 4,98,560/-

Earnest money:- Rs 10,000

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.     | Unit             | Rate        |                                                                        | Amount      |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-------------|------------------------------------------------------------------------|-------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | in figures. | in words                                                               |             |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3        | 4                | 5           | 6                                                                      | 7           |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 28.76 ✓  | Per Cubic Metre. | 261.00 ✓    | Rupees two hundred sixty one and paise nil only ✓                      | 7506.00 ✓   |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                          | 91.68 ✓  | Per Cubic Metre. | 5166.45 ✓   | Rupees five thousand one hundred sixty six and paise forty five only ✓ | 473660.00 ✓ |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 30.000 ✓ | Each             | 280.00 ✓    | Rs. Two Hundred eighty and paise nil only ✓                            | 8400.00 ✓   |

|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |        |                                                       |             |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------|--------|-------------------------------------------------------|-------------|
| 4 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 11.39 ✓ | Per Cubic Metre. | 789.60 | Rupees seven hundred eighty nine and paise sixty only | 8994.00 ✓   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |        |                                                       | 498560.00 ✓ |

Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2024-25

Draft Schedule of Quantity approved for Rs. 498560.00 ✓ only.

*[Signature]*  
Executive Engineer

*[Signature]*  
Sarahan Division  
HP, PWD, Sarahan

# **SCHEDULE OF QUANTITY**

Name of work:- R/R Damages on Prem Nagar Chandog Road km 0/0 to 15/0 (SH:- C/O PCC R/Wall at RD 1/165 to 1/180)

Estimated cost:- Rs. 4,80,562/-

Earnest money:- Rs 10,000/-  
Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.   | Unit             | Rate        |                                                                      | Amount    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                  | in figures. | in words                                                             |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3      | 4                | 5           | 6                                                                    | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 51.76  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 13509.00  |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                          | 87.94  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 454338.00 |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven ), including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 18.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 5040.00   |

|   |                                                                                                                                                                                                                                                                                                                                                                                                               |        |                  |        |                                                                     |             |
|---|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|--------|---------------------------------------------------------------------|-------------|
| 4 | <del>Backfilling behind abutment, wing wall and return wall complete as per drawings &amp; technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.</del> | 9.72 ✓ | Per Cubic Metre. | 789.60 | Rupees. <del>hundred</del> seven eighty nine and paise sixty only ✓ | 7675.00 ✓   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                               |        |                  |        | Total                                                               | 480562.00 ✓ |

  
 Executive Engineer  
 Sarahan Division  
 HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dilman Deol Tikkeri Road km 0/0 to 7/0 (SH:- C/O PCC R/Wall at RD 4/945 to 4/965)

Estimated cost:- Rs. 4,91,021/-

Earnest money:- Rs 10,000/-  
Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.   | Unit             | Rate        |                                                                      | Amount    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                  | in figures. | in words                                                             |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3      | 4                | 5           | 6                                                                    | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 42.18  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 11009.00  |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                          | 88.31  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 456249.00 |
| 3      | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.                                                                                                                                                                                                                                                                           | 20.52  | Per Cubic Metre. | 789.60      | Rupees seven hundred eighty nine and paise sixty only                | 16203.00  |
| 4      | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 27.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 7560.00   |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                  |             |                                                                      | 491021.00 |

Executive Engineer  
Sarahan Division  
HPPWD, Sarahan

6

SCHEDULE OF QUANTITIES

Name of work:- R/R Damages on Link road to village Ganyar km 0/0 to 5/0 (SH:- P/L-G-III (WBM) from RD 2/100 to 4/750 for correction in different RD's)

Estimated cost:-Rs. 4,99,305/-

Earnest money:-Rs. 10,000/-

Time Limit:- three Months.

| Sr. | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty. | Unit            | Rate        |                                                                        | Amount    |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----------------|-------------|------------------------------------------------------------------------|-----------|
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |                 | in figures. | in words                                                               |           |
| 1   | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand-packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm size Grading -III as per Technical Specification Clause 405 by Manual means | 3    | Per cubic Metre | 149.73      | Rupees three thousand three hundred thirty four and paise seventy only | 499305.00 |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |                 |             |                                                                        | 499305.00 |

  
Executive Engineer  
KS Sarahan Division  
HP, PWD, Sarahan

7

# SCHEDULE OF QUANTITY

Estimated cost:-Rs 4,33,477/-

Name of work:- ~~A/R & M/O~~ Oachgaht Narag road km 0/0 to 14/00 (P/L interlocking paver blocks in km

8/380 to 8/445)

Earnest money:- Rs. 9,000/-

Time Limit:- Three Month.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.     | Unit             | Rate        |                                                                       | Amount    |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-------------|-----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                  | in figures. | in words                                                              |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 3        | 4                | 5           | 6                                                                     | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.                                 | 5.20 ✓   | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only ✓                     | 1357.00   |
| 2      | Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. | 5.20 ✓   | Per Cubic Metre. | 6925.10     | Rupees six thousand nine hundred twenty five and paise ten only ✓     | 36011.00  |
| 3      | Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge                                                                                                                                                 | 261.00 ✓ | Per Square metre | 1517.66     | Rupees one thousand five hundred seventeen and paise sixty six only ✓ | 396109.00 |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                  |             |                                                                       | 433477.00 |

Executive Engineer  
KS Sarahan Division  
HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Macher Jabiayana Wasni Road in km 0/0 to 9/0 (SH:- C/O PCC R/Wall at RD 5/100 to 5/113)

Estimated cost:- Rs. 4,87,123/-

Earnest money:- Rs 10,000/-

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.   | Unit             | Rate        |                                                                      | Amount    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                  | in figures. | in words                                                             |           |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 51.96  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 13562.00  |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                          | 87.72  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 453201.00 |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 25.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 7000.00   |



# SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,99,724/- ✓

Kalaghat Banona road km 0/0 to 5/0 (SH:- C/O unlined surface drain and dressing of earthen shoulder in km 0/0 to 5/00)

Earnest money:- Rs. 10,000/- ✓

Time Limit:- One Month.

| Sr. No | Description Items of work                                                                                                                                                                                                              | Qty.      | Unit              | Rate        |                                             | Amount      |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------------------|-------------|---------------------------------------------|-------------|
|        |                                                                                                                                                                                                                                        |           |                   | in figures. | in words                                    |             |
| 1      | Construction of <del>unlined</del> surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. ✓           | 3         | 4                 | 5           | 6                                           | 7           |
|        |                                                                                                                                                                                                                                        | 4400.00 ✓ | Per Running Metre | 66.52       | Rupees sixty six and paise fifty two only ✓ | 292688.00   |
| 2      | Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 | 3697.07 ✓ | Per square metre  | 56.00       | Rupees fifty six and paise nil only ✓       | 207036.00   |
|        |                                                                                                                                                                                                                                        |           |                   |             |                                             | 499724.00 ✓ |

Executive Engineer

KS Sarahan Division

HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dilman Deol Tikkeri Road km 0/0 to 7/0 (SH:- C/O PCC R/Wall at RD 5/150 to 5/160)


Estimated cost:- Rs. 4,88,883-

Earnest money:- Rs 10,000/-

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.   | Unit             | in figures. | Rate                                                                 |           | Amount |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |                  |             | in words                                                             |           |        |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 3      | 4                | 5           | 6                                                                    | 7         |        |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                 | 65.46  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 17085.00  |        |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                         | 88.35  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 456456.00 |        |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 13.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 3640.00   |        |

|       |                                                                                                                                                                                                                                                                                                                                                                                                            |         |                  |          |                                                                                 |            |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------|----------|---------------------------------------------------------------------------------|------------|
| 4     | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification <del>Clauses 1204.3.8</del> in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 14.82 ✓ | Per Cubic Metre. | 789.60 ✓ | Rupees <del>seven hundred and eighty nine</del> <b>hundred and sixty</b> only ✓ | 11702.00 ✓ |
| Total |                                                                                                                                                                                                                                                                                                                                                                                                            |         |                  |          |                                                                                 | 488883.00  |

  
 KS Sarahan  
 Executive Engineer  
 HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Macher Jabiyana Wasni Road in km 0/0 to 9/0 (SH:- C/O PCC R/Wall at RD 5/500 to 5/524)

Estimated cost:- Rs. 4,84,794/-

Earnest money:- Rs 10,000/-

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.   | Unit             | Rate        |                                                                      | Amount    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                  | in figures. | in words                                                             |           |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 3      | 4                | 5           | 6                                                                    | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                  | 47.76  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 12465.00  |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                          | 85.92  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 443901.00 |
| 3      | Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 44.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 12320.00  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |          |                                      |                                     |             |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------|----------|--------------------------------------|-------------------------------------|-------------|
| 4 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 4204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 20.40 ✓ | Per Cubic Metre. | 789.60 ✓ | Rupees hundred and ninety six only ✓ | seven hundred and eighty nine paise | 16108.00 ✓  |
|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |          | Total                                |                                     | 484794.00 ✓ |

Executive Engineer

K. Sarahan Division

HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work: C/O Two No's Class rooms at GSSS Apron Tehsil Pachhad Distt. Sirmour H.P (Sh: P/F M.S Grill in windows )

Job No.

Estimated cost:- Rs 46,967/-

Earnest money:- Rs. 1000/-

Time Limit:- Three months

| Sr. No | Description Items of work                                                                                                                                                                                                                                                       | Qty.   | Unit             | Rate   | in figures. | in words                                        | Amount   |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|--------|-------------|-------------------------------------------------|----------|
| 21     | 2 Providing and fixing M.S. grill of required pattern in wooden frames of windows frames etc. with M.S. lats square on round bars with round headed bolts and nuts or by screws plain grill including carriage of materials in all leads, lifts and 1 other incidental charges. | 311.04 | Per Killo gramme | 151.00 | 5           | Rupees one hundred fifty one and paise nil only | 46967.00 |
|        |                                                                                                                                                                                                                                                                                 |        |                  |        |             |                                                 | 46967.00 |

Executive Engineer  
Sarhan Division  
HP, PWD, Sarhan

Estimated cost:- Rs. 4,95,203/-

SCHEDULE OF QUANTITY.  
Name of work:- R/R Damages on Link road to village Ganyar km 0/0 to 5/0 (SH:- P/L-G-III (WBM) from RD 0/00 to 2/00 for correction in diffrent RD's)

Earnest money:- Rs. 10,000/-

Time Limit:- Three Months.

| Sr. | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.   | Unit            | Rate        |                                                                         | Amount    |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----------------|-------------|-------------------------------------------------------------------------|-----------|
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                 | in figures. | in words                                                                |           |
| 1   | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm size Grading -III as per Technical Specification Clause 405 by Manual means | 148.50 | Per cubic Metre | 3334.70     | Rupees three thousand three hundred thirty four and paise seventy only. | 495203.00 |
|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |                 |             |                                                                         | 495203.00 |

Executive Engineer  
KS Sarahan Division  
HP, PWD, Sarahan

(14)

# SCHEDULE OF QUANTITY

Estimated cost:-Rs. 3,34,463/-

Name of work:-R/R Damages on Sirmouri Mandir Bagthan road km 0/0 to 10/375 (SH:- C/O R/Wall at RD 1/795 to 1/810)

Earnest money:- Rs 7,000/-

Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Qty.     | Unit             | Rate        |                                                                        | Amount    |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-------------|------------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  | in figures. | in words                                                               |           |
| 1      | 2<br>Earth work in excavations, for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                               | 32.00 ✓  | Per Cubic Metre. | 261.00 ✓    | Rupees two hundred sixty one and paise nil only ✓                      | 8352.00   |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                             | 57.75 ✓  | Per Cubic Metre. | 5166.45 ✓   | Rupees five thousand one hundred sixty six and paise forty five only ✓ | 298362.00 |
| 3      | Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ), including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 42.000 ✓ | Each             | 280.00 ✓    | Rs. Two Hundred eighty and paise nil only ✓                            | 11760.00  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |          |                                            |             |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------|----------|--------------------------------------------|-------------|
| 4 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 20.25 ✓ | Per Cubic Metre. | 789.60 ✓ | Rupees seven hundred and ninety six only ✓ | 15989.00 ✓  |
|   |                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |          | Total                                      | 334463.00 ✓ |

  
 Executive Engineer  
 KS Sarahan Division  
 HPPWD, Sarahan

SCHEDULE OF QUANTITY

Name of work: Link road to village Gandal km 0/0 to 7/0 (SH:- C/O 900 mm dia Hume pipe culvert along with wing walls RD 1/300)

Estimated cost: Rs. 3,00,619/-

Earnest money: - Rs. 6,000/-

Time Limit: - three Month.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty.  | Unit             | in figures. | Rate                                                    |   | Amount    |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|-------------|---------------------------------------------------------|---|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |                  |             | in words                                                |   |           |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                       | 55.65 | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only         | 7 | 14525.00  |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. | 35.06 | Per Cubic Meter. | 5166.45     | Rupees five hundred sixty six and paise forty five only |   | 181136.00 |
| 3      | Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty) millimeter nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                  | 10.18 | Per cubic meter. | 6029.00     | Rupees six thousand twenty nine and paise nil only      |   | 61375.00  |

|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |           |                                                                          |             |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|-----------|--------------------------------------------------------------------------|-------------|
| 1.49   | Providing and laying concrete 1:6:12 (One cement six sand two graded crushed stone aggregate 40(Earty) millimeter nominal size) in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802.803.1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer in Charge                                                                                                                                                                                         | Per cubic meter.   | 4601.50   | Rupees four thousand six hundred one and paise fifty only ✓              | 6856.00 ✓   |
| 7.50 ✓ | Laying reinforced cement concrete 900 mm nine Hundred millimeter diameter pipe class NP-2 (Non-Pressure Pipe) including jointing for culverts or first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement two sand) including backfilling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.                                                                                                     | Per Running Metre. | 4167.64 ✓ | Rupees four thousand one hundred sixty seven and paise sixty four only ✓ | 31257.00 ✓  |
| 6.00 ✓ | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven ) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | Each               | 280.00 ✓  | Rupees two hundred eighty and paise nil only ✓                           | 1680.00 ✓   |
| 4.80 ✓ | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.                                                                                                                                                                                                                                                                            | Per Cubic Meter.   | 789.60 ✓  | Rupees seven hundred eighty nine and paise sixty only ✓                  | 3790.00 ✓   |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |           |                                                                          | 300619.00 ✓ |

  
 Executive Engineer  
 Sarahan Division  
 HP, PWD, Sarahan

# SCHEDULE OF QUANTITY

Name of work:- R/R damages on Lawassa Chowki Preet Nagar Road km 0/0 to 42/00 (SH:- C/O R/Wall between RD 2/715 to 2/725, B/Wall 2/730 to 2/742)

Estimated cost:- Rs. 3,15,100/-

Earnest money:- Rs 6,000/-  
Time Limit:- Three Months.

| Sr. No | Description Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Qty.   | Unit             | Rate        |                                                                      | Amount    |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|----------------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        |                  | in figures. | in words                                                             |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 3      | 4                | 5           | 6                                                                    | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                                                                                                                                                                                    | 14.16  | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only                      | 3696.00   |
| 2      | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                            | 57.72  | Per Cubic Metre. | 5166.45     | Rupees five thousand one hundred sixty six and paise forty five only | 298207.00 |
| 3      | Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred ) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ), including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge | 16.000 | Each             | 280.00      | Rs. Two Hundred eighty and paise nil only                            | 4480.00   |

|       |                                                                                                                                                                                                                                                                                                                                                                                                |       |                  |        |                                     |                    |           |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|--------|-------------------------------------|--------------------|-----------|
| 4     | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. | 11.04 | Per Cubic Metre. | 789.60 | Rupees hundred nine and sixty only, | seven eighty paise | 8717.00   |
| Total |                                                                                                                                                                                                                                                                                                                                                                                                |       |                  |        | Total                               |                    | 315100.00 |

  
 KS Sarahan  
 Executive Engineer  
 HP, PWD, Sarahan

R.R. Damago

## SCHEDULE OF QUANTITY

Name of work: P/L G-II, Interlocking tiles  
in km 7/060 & 7/140)

Estimated cost:-Rs 4,93,971/-

Earnest money:- Rs. 10,000/-

Time Limit:- Three Month.

| Sr. No | Description Items of work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Qty.   | Unit             | Rate        |                                                             | Amount    |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|-------------|-------------------------------------------------------------|-----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |                  | in figures. | in words                                                    |           |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 3      | 4                | 5           | 6                                                           | 7         |
| 1      | Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.                                     | 3.20   | Per Cubic Metre. | 261.00      | Rupees two hundred sixty one and paise nil only             | 835.00    |
| 2      | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading -II (63 mm to 45 mm ) as per HPPWD Technical Specification Clause 405.by Manual means | 20.40  | Per Cubic Metre. | 2851.55     | Rupees thousand hundred fifty one and paise fifty five only | 58172.00  |
| 3      | Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802; 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.    | 3.20   | Per Cubic Metre. | 6925.10     | Rupees thousand hundred fifty five and paise ten only       | 22160.00  |
| 4      | Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge                                                                                                                                                      | 272.00 | Per Square metre | 1517.66     | Rupees thousand hundred seventeen and paise sixty six only  | 412804.00 |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |                  |             |                                                             | 493971.00 |

Executive Engineer  
Saraha Division  
HPPWD, Saraha