




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
10800-808 DATED 05-10-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.**


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **22.10.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **21.10.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **19.10.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/D on Bhirdi Balh to Sunka Ram House km 0/00 to 1/500 (SH: C/O R/Wall at RD 0/210 to 0/223)	Rs.2,46,233/-	Rs.5,000/-	Rs.350/-	Two Months
2	R/R Damages on Sangrehar to Dharman Road Km 0/00 to 2/100 (SH: Construction of R/Wall in wire crates along with C.C. Pusta at Km 0/141 to 0/155)	Rs.3,89,676/-	Rs.7,800/-	Rs.350/-	Two Months
3	Balance work C/O Community Bhawan (Parsu Ram Bhawan) Nagar Panchayat Paprola Baijnath (SH: Balance work estimate of G.floor)	Rs.1,13,526/-	Rs.2,300/-	Rs.350/-	Two Months
4	Restoration of Rain Damages on various roads under Baijnath Division Sub-Division Baijnath (Chobin Section) (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debries and C/O road side katcha drains)	Rs.99,000/-	Rs.2,000/-	Rs.350/-	Two Months
5	C/O Baijnath Chobin Balandar road (SH: C/O R/Wall at RD 13/850 to 13/860) (MNP)	Rs.1,93,243/-	Rs.3,900/-	Rs.350/-	Two Months
6	A/R & M/O various roads under Bir Sub-Division (SH: Painting and Writing of Sign boards, Km Stones, Rain Shelter, Village boards etc.)	Rs.69,228/-	Rs.1,400/-	Rs.350/-	Two Months
7	C/O road from main road to Shri Ajit Kumar Shop (SH: C/O R/Wall at RD 0/00 to 0/010) (Deposit Work) (VKV/2024/44)	Rs.1,95,019/-	Rs.3,900/-	Rs.350/-	Two Months
8	PM Shri Jawahar Navodaya Vidayalya Paprola (SH: P/L 80mm thick Paver Block at Km 0/430 to 0/474) SDP/2024/185	Rs.4,94,516/-	Rs.9,900/-	Rs.350/-	Two Months
9	R/D on Ahju Bir Gunehar road Km 0/00 to 16/00 (SH: C/O R/Wall at RD 5/010 to 5/015)	Rs.89,095/-	Rs.1,800/-	Rs.350/-	Two Months
10	C/O Canteen Block in Pandit Sant Ram Govt. Degree Collage at Baijnath (SH: Balance work of Canteen Blok)	Rs.4,98,289/-	Rs.10,000/-	Rs.350/-	Three Months
11	R/R Damage on Ahju Bir Gunehar road Km 0/00 to 6/00 (SH: C/O B/Wall at RD 4/510 to 4/528)	Rs.2,19,288/-	Rs.4,400/-	Rs.350/-	Two Months
12	R/D on Bahi Rangehar via Chobu Road (Portion Bahi to Lower Bahi) (SH: P/L C.C. Pavement & WBM G-II at Km 1/00 to 1/120)	Rs.4,69,177/-	Rs.9,400/-	Rs.350/-	Two Months
13	Restoration of rain damages on Sansai Dhandhol road Km 0/00 to 8/00 (SH: Hiring of Hydraulic Excavator/JCB for removal of slips and cleaning of slush from eatcpit of culvert.	Rs.1,54,000/-	Rs.3,100/-	Rs.350/-	One Month
14	Restoration of rain damages on Holta Chadhiar road Km 56/00 to 75/00 (MDR-78) (SH: Hiring of Hydraulic Excavator/JCB for removal of slips and cleaning of slush form eatcpit of culvert)	Rs.99,000/-	Rs.2,000/-	Rs.350/-	One Month

E.E.

15	Restoration of rain damages on Uttrala to Surahi Pass (Km 0/00 to 13/00 (SH: Removal of slips at various reaches)	Rs.4,81,876/-	Rs.9,700/-	Rs.350/-	Two Months
----	---	---------------	------------	----------	------------

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/- 10800-808

Dated:- 05.10.2024

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

1

Name of work: R/D on Bhirdi Bath to sunka Ram House km 0/00 to 1/500
(Sh:- C/O R/wall at RD 0/210 to 0/223)

Estimate Cost: 2,46,233.00/-
Earnest Money: 5,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qy.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.50	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	46.00	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.20	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
Total						

Executive Engineer
Bajnath Division
HPPWD, Bajnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: R/R Damages on Sangrehar to Dharman Road km 0/00 to 2/100
(SH : Construction of R/wall in wire crates along with C C pista at km 0/141 to 0/155)

Estimate Cost: 3,89,676.00/-
Earnest Money: 7,800.00/-
Time Limit: Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	5.46	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm (forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	20.16	Per cubic metre			
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	80.64	Per Cubic metre			
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	18.34	Per Cubic metre			

Executive Engineer
Bajinath Division
H.P.W.D., Bajinath

2

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Balance work C/O Community Bhawan (Parsu Ram Bhawan) Nagar Panchayat Paprola Baijnath
(sh:- Balance work estimate of G.floor)

Estimate Cost: 1,13,526.00
Earnest Money:2,300.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm,(Thirty five into five) joints mired and welded by angle iron 35x35x5 mm (Thirty five into five) or 35x 5 mm (Thirty five into five) flat pieces to the existing T iron frame or to the wall with dash fastener. including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	34.06	Per Kilogram			
2	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists, channels, angles, etc. flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like work including cutting hoisting fixing in position & applying a priming coat of red lead paint The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	372.00	Per Kilogram			
3	24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59x24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides. The styles and rails mired and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 20x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x24 mm and 2 mm (± 0.2 mm) wall thickness, fixed to the shutter styles by means of plastic/galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge. (For W.C. and bathroom door shutter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	2.60	Sqm			

4	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	209.30	kg				
5	Providing and fixing 40 mm (Forty millimetre) thick second class Decodar wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clearstory windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.40	Per square metre				
6	cement concrete flooring of specified grade excluding the cost of centering and shuttering laid in one layer 1:2:4 (one Cement: two coarse sand) : four graded stone aggregate 40 mm (Forty millimetre) nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	4.95	sqm				
7	Providing and fixing on wall three P.V.C. (10-plus) rain water pipes of working pressure not less than 4.5 kg (four decimal five kilogram) per square meter including filling the joints with approved adhesive complete 100 mm (one hundred millimeter) dia. along with plain bend including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.00	Per running metre				
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one Cement : two coarse sand) : four graded stone aggregate 40 mm (Forty millimetre) nominal size) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	0.55	Per cubic metre				
9	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centering, shuttering strutting and propping etc. with wooden battens and ballies for all heights/depths of propping and centering below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in vertical surface such as walls up to any thickness but not. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	15.00	Per square metre				
TOTAL							

Executive Engineer
Bajna Division
HPPWD, Baitath

DNIT/DRAFT SCHEDULE OF QUANTITY

(4)

Name of Work: Restoration of Rain Damages on Various roads under Baijnath Division Sub Division (Chobin Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains)

Estimate Cost: 99,000.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of Hydraulic Excavator cum loader having 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive all taxes including GST levy by the government time to time.	90.00	Per working hour			
	Total					


Executive Engineer
 Baijnath Division
 HPPW/ Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Baijnath Chobin Balandar Road
(Sh:- C/O R/wall at RD 13/850 to 13/860) MNP)

Estimate Cost: 1,93,243.00/-
Earnest Money: 3,900.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	35.80	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.70	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
Total						

Executive Engineer
Baijnath Division
H.P.M.D., Baijnath

DNIT/Schedule of Qnty

Estimated Cost :- Rs 69228
Earnest money :- Rs 1400.00
Time limit :- Two months

Name of Work :- A/R & M/O Various roads under Bir sub Division

(Sub Head :- Painting and Writing of Sign boards, km stones, Rain shelter, Village boards etc.)

S. No.	Description of items	Quantity	Rate (in Rupees)		Unit	Amount (in Rupees)
			In figure	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. Clause 13.91				sqm	
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade on concrete/plastered surface @ 0.73 ltr/10 sqm : (zero point seven three) One or more coats on old work. Clause 13.98.1				sqm	
4	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade @ 0.46 ltr/10 sqm. (Zero point four six per ten square meter) Clause 13.92.1 Old work (one or more coats)				sqm	
5	Writing letter of figures on any surface with Black Japan Paint (stop, commas, hyphens and like not to be measured and paid separately within all leads and lifts @ 0.56 ltr (Zero Point five six liter) for 100 (hundred) letters of 15 (fifteen) cm height. Clause 13.71. Block Letters/ Figures, Indian Letters/ Figures				per cm/ per height	
6	Painting Index hands normal size of arrows (upto 40 (forty) cm long) on any surface with Black Japan Paint within all leads and lifts.				sqm	
	Total					

Executive Engineer
Bajnath Division
HPP MD, P.
N/A

6

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O road from main road to Shri Ajit Kumar shop.
(Sh:- C/O R/wall at RD 0/00 to 0/010) Deposit Work VKV/2024/44)

Estimate Cost: 1,95,019.00/-
Earnest Money: 3,900,000/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	13.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone aggs. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	35.80	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.10	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
Total						

Executive Engineer
Bajnath Division
H.P.P.L.D., Bajjnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- PM Shri Jawahar Navodaya Vidyalaya Paprola .
(Sh:- P/L 80mm thick Paver Block at Km 0/430 to 0/474).SDP/2024/185 .

Estimated Cost: Rs. 494516.00
Earnest Money: Rs. 9,900.00
Time Limit : Two Month

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	22.00	Cum			
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.88	Cum			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Chage 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	220.00	Sqm			
TOTAL						

Executive Engineer
Bajinath Division
H.P.P.W.D. Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: R/D on Ahju Bir Gunchar road km 0/00 to 16/00
(Sh:- C/O R/wall at RD 5/010 to 5/015)

Estimate Cost: 89,095.00/-
Earnest Money: 1,800.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	16.00	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.50	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.00	Each			
Total						

Executive Engineer
Bajnath Division
H.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Canteen Block in Pandit Sant Ram Govt. Degree collage at Baijnath
(SH: Balance work of Canteen Block.)

Estimate Cost: 4,98,289.00
Earnest Money 10,000.00
Time Limit : Three Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing 600mm x 450mm (Six hundred into four hundred fifty) bevelled edge mirror of superior glass mounted on 60 mm (Sixty millimeter) thick A.C. Sheet or plywood sheet abd fixed to wooden plugs with C.P. Brass screws and washers as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			
2	Particle board (bwp phenol bonded exterior/interior grade) Cement bonded particle board 8 mm (Eight millimeter) thick as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	117.98	Per square metre			
3	Steel work welded in built up sections, trussess and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In drahtings framed guard bars, ladders, railing brackets and similar works, as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	943.00	Per Kilo gram			
4	Suppling and sixing glass panes with putty and nails nclnding removal of broken glass panes wherever necessary plain glass. 4 mm (four millimeter) thick. In fixed and side hung window, as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	33.21	Per square metre			
5	Providing and fixing aluminium tower bolt 101 marked anodized 150x10mm (one hundred fifty into ten millimeter) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	44.00	Each			
6	Providing and fixing aluminium tower bolt 101 marked anodized 125mm (one hundred twenty five millimeter) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			
7	Providing and fixing aluminium tower bolt 101 marked anodized transparent 100mm (hundred millimeter) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	44.00	Each			

8	Providing and fixing anodized aluminium hooks and eyes, 150 mm (one hundred fifty millimeter) for window ventilator shutters complete in all respect as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.00	Each				
9	Kota stone slab flooring 20mm (Twenty millimeter) (average) thick base of cement mortar 1:4 (cement:4 sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab. Including rubbing and polishing complete 40 mm (Forty millimeter) thick as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	117.84	Per square metre				
10	Disiempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	100.40	Per square metre				
11	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight) and conforming to IS: 15622, of approved make, in all colours and shade, laid on 20 mm (Twenty Millimeter) thick cement mortar 1:4 (one cement : four coarse sand), joining with grey cement slurry @ 3.3 kg/sqm (three point three kilogram per square meter) including grouting the joints with white cement and matching pigments etc., completing size of tile 600 x 600 mm (Six hundred into six hundred), as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.63	Per square metre				
12	Providing and laying Ceramic glazed floor tiles of size 300 x 300 mm (three hundred into three hundred) (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm (Twenty millimeter) thick bed of cement slurry @ 3.3 kg/sqm (three point three kilogram per square meter) including pointing the joints with white cement and matching pigments etc., complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	30.16	Per square metre				
TOTAL							


 Executive Engineer
 Bajjnath Division
 H.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: R/R Damage on Ahju Bir Gunchar road Km 0/00 to 6/00
(SH:-C/O B/wall at RD 4/510 to 4/528)

Estimate Cost: 2,19,288.00/-
Earnest Money: 4,400.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps, and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness, including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	42.12	Per Cum			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and North technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	17.00	Each			
	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government					
	Total					

Executive Engineer
Bajna
H.P.W.D.
2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/D on Bahi Rangehar Via Chobu Road (Portion Bahi to Lower Bahi) .
(SH:-P/L C. C Pavement & W B M G-II at km 1/00 to 1/120)

Estimate Cost: 4,69,177.00/-
Earnest Money: 9400.00/-
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.31	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	66.15	Per Cubic metre			
Total						

Executive Engineer
Bajna Division
HPPWD, Bafra

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : Restoration of rain damages on Sansai Dhandhol road Km 0/00 to 8/00
 Sub Head: Hiring of Hydraulic Excavator/JCB for removal of slips and cleaning of slush from catchpit of culvert.

Estimate Cost: 154,000.00/-
 Earnest Money: 3100,000/-
 Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per hour basis excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL, charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. the rate including hauling / carriage of materials to various location of transportation in all leads lifts and other incidental complete in all respect and entire satisfactions of Engineer -in -Charge. The rates are inclusive all taxes levy by the govt time to time including GST	140.00	Per Hour			
Total						


Executive Engineer
 Bajjnath Division
 H.P.P.W.D., Bajjnath

SCHEDULE OF QUANTITY

(14)

Name of work : Restoration of rain damages on Holta Chadhiar road Km 56/00 to 75/00 (MIDR-78).
 Sub Head: Hiring of Hydraulic Excavator-JCB for removal of slips and cleaning of slash from catchpit of culvert.


Estimate Cost: 99,000/-
 Earnest Money: 25000/-
 Time Limit: One Month

Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT
				Words	Rs.	
1	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per hour basis excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. the rate including hauling / carriage of materials to various location of transportation in all leads lifts and other incidental complete in all respect and entire satisfactions of Engineer -in -Charge. The rates are inclusive all taxes levy by the govt time to time including GST	90.00	Per Hour			
Total						

Executive Engineer
 Bajina Division
 H.P.P.W.D., Bajinath

ABSTRACT OF COST

Name of Work:- Restoration of rain damages on Utrala to Surahi Pass (km 0/00 to 13/00)						Estimated Cost:- 481876.00	
(SH:- Removal of slips at various reaches .)						Earnest Money:- 9,700.00	
SR. No.	Description of work	No.or Qty.	Unit	Time:-		Two Month	
				In Figure	Rate Figures	AMOUNT Rs. P	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.50 mtr. And less than 100 mtr. As per technical specification 302.3.5 and 1611. Including carriage of materials within leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3982.45	Per cum				
Total:-							


Executive Engineer
 Bailinath Division
 H.P.R.W.D. Bajinath