




Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-  
11005-14 DATED 11-10-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.

  
Executive Engineer,  
Baijnath Division,  
HP.PWD, Baijnath.





**Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **26.10.2024 up to 11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **25.10.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **24.10.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Bhadar Ghar at Village Lower Rajot (SH: C/O Shed) Deposit work (SDP120241191)	Rs.1,79,249/-	Rs.3,600/-	Rs.350/-	Two Months
2	C/O Link road from village Pehloon to Karota Nai Basti Km 0/00 to 1/500 (SH: P/L C.C. Pavement at km 0/800 to 0/905)	Rs.3,50,558/-	Rs.7,100/-	Rs.350/-	Two Months
3	R/D on upper Thehad to Chadhiar via Bakshi Partap Singh House Km 0/00 to 2/060 (SH: P/L C.C. Pavement & WBM G-II at Km 0/250 to 0/275)	Rs.82,757/-	Rs.1,700/-	Rs.350/-	Two Months
4	Restoration on rain damage Gawal Tikker road km 0/00 to 4/200 (SH: C/O B/Wall at RD 3/570 to 3/585)	Rs.2,01,901/-	Rs.4,100/-	Rs.350/-	Two Months
5	C/O Link Road from Doli Khurad Chordu Dangore Km 0/00 to 4/900 (SH: P/L 2cm Thick Premix carpet with Seal Coat at 3/315 to 3/615)	Rs.3,45,021/-	Rs.6,900/-	Rs.350/-	Two Months
6	C/O Road Chougan to Village Chougan Km 0/00 to 1/00 (SH: P/L C.C. Pavement & WBM G-II at Km 0/180 to 0/245)	Rs.2,73,388/-	Rs.5,500/-	Rs.350/-	Two Months
7	R/D on Baijnath Gandhigram road Km 0/00 to 5/700 (SH: C/O R/Wall at RD 4/625 to 4/634.40)	Rs.2,37,064/-	Rs.4,800/-	Rs.350/-	Two Months
8	C/O Keori Suja Road Km 0/00 to 1/100 (SH: P/L G-III and Tarring work on RD 0/00 to 0/050)	Rs.1,11,972/-	Rs.2,300/-	Rs.350/-	Two Months
9	P/M Shri Jawahar Navodaya Vidyalaya Paprola (SH: P/L 80mm thick Paver Block at Km 0/474 to 0/500) SDP/2024/185	Rs.2,92,214/-	Rs.5,900/-	Rs.350/-	Two Months
10	C/O Canteen Block in Pandit Sant Ram Govt. Degree Collage at Baijnath (SH: Balance work of Canteen Block)	Rs.4,98,215/-	Rs.10,000/-	Rs.350/-	Three Months
11	C/O Sansal to Mandher road Km 0/00 to 2/00 (SH: C/O Railing, C.C. Pavement, V-Shape Drain and Edge wall)	Rs.1,98,964/-	Rs.4,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.

**E.E.**



7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Bajjnath Division.,  
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/-

11005-14

Dated:- 11.10.2024

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
Bajjnath Division.,  
H.P.PWD..Bajjnath.



# **DNT/DRAFT SCHEDULE OF QUANTITY**

Name of work :- C/O Bhadar Ghar at Village Lower Rajot **Deposited work (SDP180824/191)**  
(SH:- C/O Shed )

Estimate Cost: 1,79,249.00  
Earnest Money: 3,600.00  
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.98	Per Cum			
2	Providing and laying reinforced cement concrete 1:2:4 (one cement:two sand:four graded stone aggregate 40mm ( forty millimeter ) nominal size and curing complete excluding cost of form work in Foundation and plinth ) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.73	Cum.			
3	Stone filling under floor complete as per PWD specification The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.35	Per Cubic metre			
4	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.77	Cum.			
5	52 mm ( fifty two millimeter ) thick cement concrete flooring of specified grade excluding the cost of centering and shuttering laid in one layer 1:2:4 (one Cement : two coarse sand) : four graded stone aggregate 40 mm (Forty millimeter ) nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	13.50	Per cubic metre			
6	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like work including cutting hoisting fixing in position & applying a priming coat of red lead paint The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	436.00	Per Kilogram			

**(D)**



① (b)

7	Providing and fixing 0.60mm (zero point sixty millimeter) thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with preprinted iron J or L hooks, bolts and nuts 6mm (six millimeter) dia metre with preprinted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	26.40	Sqm				
8	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimeter) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm (zero point sixty centimeter) cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimeter) C/C crest distance. There will be two ribs at the centre for stiffening having crest depth of 2.50mm (two point five millimeter) the main crest with at top zinc waiting top coat with regular modified polyester coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimeter) dia and 55mm (fifty five millimeter) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	5.50	Per running metre				
9	Providing and fixing plang M.S. B.P. sheet 1.66mm (one decimal sixty six millimeter) thick to 2.00mm in levels board/ Facia / Soft / Ceiling including cutting fixing jointing with gass/electric welding to steel roofs members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	11.80	Per square metre				
10	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.26	Per cubic metre				
<b>TOTAL</b>							

Executive Engineer  
Gajinath Division  
H.P.P.W.D., Bajjnath

# DNIT/DRAFT SCHEDULE OF QUANTITY

(2)

Name of Work : C/O Link road from village Pahloun to Karota Nai Basti km 0/00 to 1/500 .  
(SH:-P/L C. C Pavement at km 0/800 to 0/905 )

Estimate Cost: 3,50,558.00/-  
Earnest Money: 7100.00/-  
Time Limit : Two Months

## SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including cartiage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	50.44	Per Cubic metre			
Total						

*(Signature)*  
Executive Engineer  
Bajnath Division  
H.P.P.W.D., Bajinath



**DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of Work : R/D on Upper Thehad to chadhari via Bakshi Partap singh House km 0/00 o 2/060  
(SH:-P/L C. C Pavement & W B M G-II at km 0/250 to 0/275 )

Estimate Cost: 82,757.00/-  
Earnest Money: 1700.00/-  
Time Limit : Two Months

**SCHEDULE OF WORKS**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.14	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.44	Per Cubic metre			
<b>Total</b>						

**Executive Engineer**  
Bajinath Division  
H.P.W.D., Bajinath



Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost: 2,01,901.00/- Earnest Money: 4,100.00/- Time Limit : Two Months		AMOUNT Rs. P
				Figures	Rate Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.40	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	39.30	Per Cum			
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.00	Each			
Total						

Executive Engineer  
Bajinath Division  
H.P.F.W.D., Bajinath



**DNT/DRAFT SCHEDULE OF QUANTITY**  
 Name of work :- C/O Link Road From Doji Khurad Chordu Dangore km 0/00 to 4/900  
 Thick Premix carpet with Seal Coat at 3/315 to 3/615

(SH:- P/L 2 cm

Estimate Cost: 3,45,021.00  
 Earnest Money: 6,900.00  
 Time Limit : Two Months

Sr. No.		Description of work	SCHEDULE OF WORKS					Time Limit : Two Months	
No.			No. or Qty.	Unit	Rate		AMOUNT		
1		Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.70 to 1.00 Kg. per Square metres using mechanical means as per MORD technical specification clause 502, and as per directions of Engineer - in- Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	945.00	Per Square metre	Figures	Words	Rs. P		
2		Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the Rate of 0.275 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	945.00	Per Square metre					
3		Providing, laying and rolling of open-graded premix carpet of 20 mm compacted thickness withness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. Taking Qty. from item No 1. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	945.00	Per Square metre					
4		Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. Taking Qty. from item No 1. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	945.00	Per Square metre					
Total									

**Executive Engineer**  
**Balimath Division**  
 H.P. Road, Balimath



**DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of Work : C/O Road Chaughan to Village Chaughan km 0/00 to 1/00  
(SH:-P/L C. C Pavement & W B M G-II at km 0/180 to 0/245 )

Estimate Cost: 2,73,388.00/-  
Earnest Money: 5500.00/-  
Time Limit : Two Months

**SCHEDULE OF WORKS**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interspaces of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	7.88	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	35.84	Per Cubic metre			
<b>Total</b>						

**Executive Engineer**  
**Bajnal Division**  
**H.P.P.W.D., Bajinath**



# **DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of work: R/D on Bajinath Gandhigram road km 0/00 to 5/700 .  
( Sh:- C/O R/wall at RD 4/625 to 4/634.40 )

Estimate Cost: 2,37,064.00/-  
Earnest Money: 4,800.00/-  
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.04	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone aggr. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	44.96	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.98	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
<b>Total</b>						

**Executive Engineer**  
**Bajinath Division**  
**H.P.P.W.D., Bajinath**



# **DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of work :- C/O Keori Sujia Road Km 0/00 to 1/100 .  
(Sh:- P/L G -III and Tarring work on RD 0/00 to 0/050 )

Estimate Cost: 1,11,972.00  
Earnest Money: 2,300.00  
Time Limit : Two Months

## **SCHEDULE OF WORKS**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing laying spreading and compacting stone aggregate Grading-III to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	13.88	Per Cubic metre			
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero point eight five Kilogram) per Square metres using mechanical means as per MORD technical specification clause 502, and as per directions of Engineer - in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	180.00	Per Square metre			
3	Providing and applying tack coat with Bitumen emulsion using (RS-1) emulsion pressure distributor at the rate of 0.275 kg ( at rate of zero point two seven five kilogram ) per Square metre on the prepared bituminous surface and cleaned with hydraulic broom as per M.O.R.D. technical specifications section No. 503 . The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	180.00	Per Square metre			
4	Providing and laying 25 mm (twenty five millimeter ) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 ( Seventy five ) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six ) per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects as per the direction and entire satisfaction of Engineer-In Charge. The rate is inclusive all taxes levy by the government time to time excluding G.S.T .	5.40	Per Cubic Meter			

**Executive Engineer**  
Bajnath Division  
H.P.P.W.D., Bajjnath



# D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- PNI Shri Jawahar Navodaya Vidyalaya Paprola .  
( Su:- P/L 80mm thick Paver Block at Km 0/474 To 0/500 ).SDP/2024/185 .

Estimated Cost: Rs. 292214.00  
Earnest Money: Rs. 5,900.00

Time Limit : Two Month

## SCHEDULE OF WORKS

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and piers as per drawing and Month technical specification section 802, 803 & 1203 for nominal mix 1:2:4 (one cement : two sand; four aggregate) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	13.00	Cum			
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.52	Cum			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	130.00	Sqm			
<b>TOTAL</b>						

Executive Engineer  
Bajnal Division  
H.P.P.V. Bajnal



# DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Canteen Block in Pandit Sant Ram Govt. Degree college at Bainnath  
(SH: Balance work of Canteen Block.)

Estimate Cost: 4,98,215.00  
Earnest Money: 10,000.00  
Time Limit : Three Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing aluminium work for doors, windows ventilators and partitions with extended built up tubular section / appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium section shall be smooth, rust free, straight, milled and jointed mechanically wherever required including clear angle. Aluminium nap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (Glazing, paneling and dash fasteners to be paid for separately).: Power coated aluminium (minimum thickness of powder coating 50 micron) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	353.11	Per Kilo gram			
2	For shutters of doors, window & ventilators including providing and fixing hinges/pivots and making provision for fixing of fitting wherever required including the cost of EPDM rubber / neoprene gasket required (fitting shall be paid for separately) Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 (Fifty micron) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	311.50	Per Kilo gram			
3	Providing and fixing 19 mm (Nineteen millimeter ) thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete, as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.78	Per square metre			
4	Providing and fixing 19 mm (Nineteen millimeter ) thick water proof commercial board water proof shutters for cup boards i/c fixing with nickel plated piano hinges with screws etc complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.28	Per square metre			
5	Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete 250x10mm (Two hundred fifty into sixteen millimeter ) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			
6	Providing and fixing aluminium tower bolt 101 marked anodized 250x10mm (Two hundred fifty into ten millimeter ) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			

4609



7	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approval make conforming to IS 1868, Minimum anodic coating of grade AC 15) fixed with rawplugs or dyed to required shade according to IS 1868, Minimum anodic coating of grade AC 15) fixed with rawplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junction, at top-bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight mitered and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge. For doors windows and ventilations and glazed partitions frames as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.68	Per square metre				
8	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting Ready mixed paint brushing with white lead for priming as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	23.00	Per square metre				
9	Painting two coats (excluding coat) on new wood and based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and the other foreign matter sand papering & stopping with enamel paint other than white as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	117.84	Per square metre				
TOTAL							

Executive Engineer  
Bajinath Division  
H.P.P.W.D., Bajinath



**DNT/DRAFT SCHEDULE OF QUANTITY**

Name of work: C/O Sansal to Mandher Road km 0/00 to 2/00  
( Sh:- C/O Railing, C C Pavement, V-Shape Drain and Edge wall )

Estimate Cost: 1,98,964.00/-  
Earnest Money: 4,000.00/-  
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge Hard rock (blasting prohibited) and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. <b>Recovery for useful stone of 300/- per cum</b> shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	19.8	Per Cubic metre			
2	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.03	Per Cum			
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.30	Per Cubic metre			



4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone age: 40mm (forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.96	Per cubic metre			
5	Providing and Laying, spreading and compacting stone aggregates size 90mm to 45 mm (Ninety millimeter to forty five millimeter) grading-II(100 mm Consolidated thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, Crushable type such as Moorum or Gravel for grading-I @ 0.30 cum per ten square meter and binding material at the rate of 0.08 cum ( Zero point zero eight cubic meters) per ten Sqm ( ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORC technical specification clause no 405 complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.20	Per Cubic metre			
6	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 (one cement : four sand :Eight graded stone age: 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.50	Per Cum			
7	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals; the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.00	Each			
8	Construction of precast RCC railing of M-25 grade , true to line and grade ,tolerance of vertical RCC post not to exceeding 1 in 500 e/c spacing between vertical post not to exceed 2000 m leaving adequate space between vertical post for expansion complete as per drawings. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.00	Rmt			
9	Doweling with 25 mm (Twenty Five millimeter ) diameter steel bars in stone as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.00	Cum			

  
 Baijnath Division  
 H.P.P.W.D., Baijnath