

Himachal Pradesh  
Public works Department

**Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD, Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before 16-10-2024 up to 11.00 A.M. and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on 15-10-2024. The applications for issue of tender forms will be received up to 2.00 P.M. on 14-10-2024.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1.	Construction of neori to Katwandi road Km. 0/00 to 5/00 (SH:- Construction of RCC Hume Pipe culvert at Rd 0/815) Under OTMNP	208599	4200	Two Months
2.	Construction of Bassa Kuthar nehra chail road Km 0/00 to 4/00 (SH:- construction of RCC Hume pipe Culvert at Rd 2/740)Under OTMNP	227571	4600	Two Months
3.	Construction of Neori to katwandi road Km 0/00 to 5/00 (SH:- Construction of RCC Hume Pipe Culvert at RD 0/615) Under OTMNP	208712	4200	Two Months
4.	Construction of Sianj Nandi road Km 0/00 to 3/00 (SH:- construction of RCC Hume pipe Culvert at RD 1/630) under SCDP	232572	4700	Two Months
5.	Construction of Sianj Pangliur road Km 0/00 to 2/00 (SH:- construction of 900 mm Hume pipe Culvert at RD 0/330 with both side wing wall )Under SCDP	259174	5200	Two Months
6.	Construction of Saroa to Kamrunag road Km 0/00 to 4/760 (SH:- ROFD/ Formation cutting at RD 1/755 to 1/965) under OTMNP	99016	2000	Two Months
7.	C/o link road from Naulakha to Lower Chowk Km 0/00 to 1/00 (SH:- C/o Pavers Block at RD 0/150 to 0/240)under OTMNP	494778	10000	Two Months

**Certified that tender of above works are being called for emergent nature in exigency of public interest.**

**GENERAL CONDITIONS:-**

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R. along with the application form for getting issued the tender forms. Applications with cut EMD shall be summarily rejected.
6. As per Govt. Notification No.PEW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto

approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.

7. The contractor can apply only for one work at a time
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

—8d—  
Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.  
Dated 5-10-2024

No. PW-GHR-Tender/NIT/2024 6082-99  
Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1<sup>st</sup> Circle, HP.PWD Mandi.
4. ✓ The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

Q1  
Executive Engineer,  
Gohar Division (B&R),  
HPPWD., Gohar



HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

CORRIGENDUM

The offline Tenders as called vide this office NIT No.-PW-GHR-Tender/NIT/ 2024-6082-99 dated 05-10-2024 which is schedule to be opened on 16-10-2024 at 11:00 A.M. but the tender case has not uploaded in the departmental site due to some administrative reason hence, now the tender will be opened on 23-10-2024 and the corrigendum of critical dates are as under:-

Sr. No.	Description	Critical dates
1	Application	14-10-2024 may be read as 23-10-2024
2	Sale of form	15-10-2024 may be read as 24-10-2024
3	Tender to be opened	16-10-2024 may be read as 25-10-2024

All other terms & conditions will remain un-changed.

— *SL* —  
Executive Engineer,  
Gohar Division,(B&R),  
HP.PWD.Gohar.

No.-PW-GHR-TA/Tender/NIT/

6519-40

Dated:- 14-10-2024

Copy forwarded for information please:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
- ✓ 4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

*OM*  
Executive Engineer,  
Gohar Division,(B&R),  
HP.PWD.Gohar

# BILL OF QUANTITY

Name of work :- Construction of Neori to Katwandi road Km 0/00 to 5/000 (SH:- Construction of RCC Hume pipe Culvert at Rd 0/815) Under OTMNP

Estimated cost Rs. - 2,08,599/-

Earnest Money cost Rs. 4200/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.33	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	3.11	Per Cubic meter			
3	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	0.45	Per Cubic meter			
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	8.26	Per Cubic meter			
5	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	19.22	Per Cubic meter			
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	7.50	Per Running meter			

Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge completer in all respect.	3.48	Per Cubic meter			
Total:-					
Quoted rate in figure					
Quoted rate in words					

04  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD  
 1



### BILL OF QUANTITY

Name of work :- Construction of Bassa Kuther Nehra Chail road Km 0/00 to 4/000 (SH:- Construction of RCC Hume pipe Culvert at Rd 2/740) Under OTMNP


Estimated cost Rs. - 2,27,571/-

Earnest Money cost Rs. 4600/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.33	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	3.11	Per Cubic meter			
3	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 within all leads , lifts and carriage of materials and other incidentals .as directed by Engineer-incharge.	0.45	Per Cubic meter			
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704, 1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	8.26	Per Cubic meter			
5	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	22.68	Per Cubic meter			
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	7.50	Per Running meter			
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.48	Per Cubic meter			

Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of	6.00	Each			
Total:-					
Quoted rate in figure					
Quoted rate in words					

  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD Gohar.



# BILL OF QUANTITY

Name of work :- Construction of Neori to Katwandi road Km 0/00 to 5/000 (SH:- Construction of RCC Hume pipe Culvert at Rd 0/615) Under OTMNP

Estimated cost Rs. - 2,08,712/-


Earnest Money cost Rs. 4200/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.68	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	3.11	Per Cubic meter			
3	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	0.45	Per Cubic meter			
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704, 1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	8.26	Per Cubic meter			
5	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	19.22	Per Cubic meter			
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	7.50	Per Running meter			



Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.48	Per Cubic meter			
<b>Total:-</b>					
<b>Quoted rate in figure</b>					
<b>Quoted rate in words</b>					

  
 Executive Engineer  
 Gohar Division (B&R)  
 H.P.W.D Gohar.



195

# BILL OF QUANTITY

Name of work :- Construction of Slanj Nandi road Km 0/00 to 7/000 (SH:- Construction of RCC Hume pipe Culvert at Rd 1/630) Under <del>ATMNP</del> <i>Scop</i>						Estimated cost Rs. - 2,32,5722/-	
						Earnest Money cost Rs. 4700/-	
						Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	49.52	Per Cubic meter				
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	3.11	Per Cubic meter				
3	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	0.45	Per Cubic meter				
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704, 1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	8.26	Per Cubic meter				
5	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	23.76	Per Cubic meter				
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	7.50	Per Running meter				



Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge completer in all respect.		4.14	Per Cubic meter			
<b>Total:-</b>						
Quoted rate in figure						
Quoted rate in words						

  
 Executive Engineer  
 Gohar Division (B&R)  
 H.P. DWD 

# **BILL OF QUANTITY**

Name of work:- Construction of Slant Panglur road Km 0/00 to 2/000 (SI):- Construction of 900 mm Hume pipe Culvert at Rd 0/330 with both side wing wall) Under SCDP

Estimated cost Rs. - 2,59,174/-

Earnest Money cost Rs. 5200/-

Time - Two Month

SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	50.43	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	27.68	Per Cubic meter			
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704, 1202 and 1204 ( random rubble masonry in cement mortar . 1:6( one cement : six sand ) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	10.96	Per Cubic meter			
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	7.50	Per Running meter			
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	4.32	Per Cubic meter			



6	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614.709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	10.00	Each			
	<b>Total:-</b>					
	<b>Quoted rate in figure</b>					
	<b>Quoted rate in words</b>					

  
 Executive Engineer  
 Gohar Division (B&R)  
 H.P.PWD Ghar.

# BILL OF QUANTITY

Name of work :- Construction of Saroa to Kamrunag road km 0/00 to 4/760 ( SH:- ROFD/Formation cutting at RD 1/755 to 1/965) Under OTMNP

Estimated cost Rs. - 99,016/-

Earnest Money cost Rs. 2000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock ( where blasting is prohibited ) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and sefety measures and incidentals necessary to complete the work by all means ( if any required ) recovery for <b>29.55 cubic metre @ Rs. 300.00</b> per cubic metre amount <b>Rs.8865/-</b> shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	505.88	Per Cubic meter			
	<b>Total:-</b>					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer  
Gohar Division (B&R)  
HP.PWD Gohar.



# BILL OF QUANTITY

Name of work :- C/o link road from Naulakha to Lower Chowk km 0/0 to 1/000 (SH:- C/o Pavers Block at Rd 0/150 to 0/240) Under OTMNP

Estimated cost Rs. - 4,94,778.00

Earnest Money cost Rs. 10,000.00

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	71.25	Per Cubic meter			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	28.50	Per Cubic meter			
3	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	2.02	Per Cubic meter			
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. as per direction of Engineer - in - charge . <b>80 mm thick C.C. paver block of M-50 grade</b> with approved color design and pattern. with in all lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer - in - charge .	285.00	Per Cubic meter			
Total:-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar