



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 05-11-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 04-11-2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 02-11-2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Link rod from Balotu to Gwaila via Nugal Mahadev (SH:- Formation cutting in km. 3/825 to 4/009)	Rs. 4,95,789/-	Rs. 9,900/-	Rs.350/-	Class "D"	Three Months
2	Construction of Guini Kotla (Bani) Link road km. 0/0 to 3/00 under SCSP (SH:- Formation cutting at km. 1/605 to 1/715)	Rs. 99,209/-	Rs.2,000/-	Rs.350/-	Class "D"	Two Months
3	Construction & M/T on Jeepable link rod Joginder Nagar Kathla Dul km. 0/00 to 3/00 (SH:- Providing and laying Tarring at km. 2/000 to 2/500).	RS.4,75,788/-	Rs.9,500/-	Rs.350/-	Class "D"	Three Months
4	Construction of Link road from Balotu to Gwaila via Nugal Mahadev (SH:- Formation cutting in km. 3/680 to 3/825)	Rs.4,95,440/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
5	Construction of link road Galu to Baned km. 0/00 to 0/075 under Depoist (SH:- Formation cutting in km. 0/00 to 0/075).	Rs. 1,04,006/-	Rs. 2,100/-	Rs.350/-	Class "D"	Three Months
6	Construction of LPG Gas Office Cum Show room at Joginder nagar Distrcit Mandi (H.P.) (Deposit) (SH:- Providing and fixing Aluminum work, Painting work and Flooring of Room and Barendah).	Rs. 1,17,506/-	Rs. 2,400/-	Rs.350/-	Class "D"	Three Months
7	Construction of Fegru-Suhi Dhundha Bagra Mehra road from Zim-Zima road and construction of bridge (SH:- Providing and laying Kharanja Soling & Cement Concrete Pavement at km. 1/100 to 1/200)	Rs 3,68,220/-	Rs.7,400/-	Rs.350/-	Class "D"	Three Months
8	Construction & M/T on Jeepable link road Joginder Nagar Kathla Dul km. 0/00 to 3/00(SH:- Providing and laying wearing Grade-II at km. 2/000 to 2/500).	Rs. 3,22,424/-	Rs.6,400/-	Rs.350/-	Class "D"	Three Months
9	Construction of link road Harbag to Degli via Nagehala in Joginder Nagar Tehsil km. 0/00 to 5/00 (SH:- Providing and laying Kharanja Soling & Cement Concrete Pavement at km. 0/200 to 0/250)	Rs. 1,84,120/-	Rs.3,700/-	Rs.350/-	Class "D"	Three Months
10	Construction & M/T Jhamehar Shanan Kunkar Nagan road in G.P. Dhar (SH:- Formation cutting in km. 2/490 to 2/865)	Rs. 4,88,657/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
11	Construction & M/T on link road Chimnu to Village Kheri Naldu km. 0/0 to 2/500 (SH:- Providing and laying Soling at km. 0/00 to 0/100).	Rs. 1,10,994/-	Rs.2,200/-	Rs.350/-	Class "D"	Three Months
12	Construction & M/T on Joginder Nagar Arthi road Garoru Bridge to Majharnoo km. 0/00 to 1/500 (SH:- Providing and laying Kharanja Soling & Cement Concrete pavement at km. 0/00 to 0/100)	Rs. 3,68,220/-	Rs.7,400/-	Rs.350/-	Class "D"	Three Months
13	Construction of road from NH Chanang to Village Madvana (SGH:- Providing and laying Kharanja Soling & Cement Concrete Pavement at km. 0/480 to 0/580).	Rs. 3,68,220/-	Rs.7,400/-	Rs.350/-	Class "D"	Three Months
14	Construction of Galu Bhatwar to Bhatwar km. 0/00 to 1/00(SH:- Formation cutting in km. 0/510 to 0/720).	Rs. 1,45,563/-	Rs.2,900/-	Rs.350/-	Class "D"	Three Months
15	Construction of road from Panjalag to Harizan Basti Katoun via Nichala Panjalag km. 0/0 to 2/0 under SCSP (SH:- Providing and laying Kharanja Soling and Cement Concrete Pavement at km. 0/165 to 0/220 & 1/440 to 1/540).	Rs.4,16,155/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
16	Constructing of Jeepable road from Khud Shamshaanghat to Harizan Basti Nagan Khola in G.P. Daled km. 0/0 to 4/500 (SH:- Construction of 900mm dia RCC Hume Pipe Culvert at km. 1/060)	Rs.2,86,467/-	Rs.5,700/-	Rs.350/-	Class "D"	Three Months

17	Construction on link road from Bhala Rihra to Harizan Basti Bharola Sainthal km. 0/00 to 2/500(SH:- Providing and laying Wearing G-II & Cement Concrete Pavement at km. 0/400 to 0/550).	Rs.4,95,321/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
18	Construction of link rod from Drubbal to Harizan Basti Basoti Ropru km. 0/0 to 1/500 (SH:- C/O RCC Hume Pipe culvert along with both side wing walls at km. 1/160)	Rs. 2,33,573/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
19	Construction of road to Sainthal Malehar upto Nichla Chauntra km. 0/00 to 1/500 OTMNP (SH:- Providing and laying Wearing Grade-II & Cement Concrete pavement from km. 1/050 to 1/150).	Rs.2,37,289/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
20	Construction of link road from Drubbal to Harizan Basti Bagoti Ropru km. 0/00 to 1/500(SH:- Providing and laying Wearing Grade-II from km. 0/090 to 0/340).	Rs.1,43,983/-	Rs.2,900/-	Rs.350/-	Class "D"	Three Months
21	Construction of link road Upper Bella to Lower Bella km. 0/00 to 1/600 under Head OTMNP (SGH:- ROFD by Providing Breast Wall at km. 0/203 to 0/215)	Rs.1,58,018/-	Rs.3,200/-	Rs.350/-	Class "D"	Three Months
22	Restoration of rain damages on various rod under Joginder Nagar Sub Division HP PWD, Joginder Nagar (Local Section)(SH:- Hiring of tractor with trolley for carriage/shifting of various type of materials etc).	Rs.98,800/-	Rs.2,000/-	Rs.350/-	Class "D"	Three Months
23	Construction of Guini Kotla (Bani) Link road km. 0/0 to 3/00 under SCSP (SH:- Formation cutting at km. 1/465 to 1/595)	Rs. 99,574/-	Rs.2,000/-	Rs.350/-	Class "D"	Two Months
22	Construction of basket ball Court at Govt. Degree College at Joginder Nagar Distt. Mandi (H.P.) (SH:- Balance work of Basket Ball Court along with all side fencing) (Deposit).	Rs.4,16,393/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
25	Construction of link road from Panjalatar Nallah to Magharoo link road km. 0/0 to 0/370 (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips dressing of berms cleaning of road side drains, debris and Construction of road side katach	Rs. 99,060/-	Rs.2,000/-	Rs.350/-	Class-"D"	Two Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222035

No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 13284-333

Dated:- 19/10/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The SuperIntending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

Job No -1

SCHEDULE OF QUANTITY

of Work: Construction of Link road from Balotu to Gwaila via Nugal Mahadev
Formation cutting in km 3/825 to 4/009)

Description of work	No. or Qty.	Unit	Estimate Cost:		
			Earnest Money:		
			Time Limit :	Rate	AMOUNT
			Figures	Words	Rs. P
Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all roads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 120.72 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2414.36	Per cubic metre			4,95,789.00
Total					9,900.00

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

Job No 2

SCHEDULE OF QUANTITY

Name of Work: Construction of Guini Kotla (Bani) Link Road km 0/00 to 3/00 Under SCSP
(SH: Formation Cutting at km 1/605 to 1/715)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost: 99,205		
				Earnest Money: 2,000		Two Mon
				Figures	Rate	AMOUNT
					Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 24.16 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	483.12	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Job No - 3

Name of Work : Construction & M/T on jeepable link road Joginder Nagar Kathla Dul km 0/00 to 3/00
(SH: Providing and laying Tarring at km 2/000 to 2/500)

Estimate Cost: 4,75,7
Earnest Money: 9,5
Time Limit :

Three M
AMOUN
Rs. 1

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs.
				Figures	Words	
1	Providing and applying primer/tack with bituminous primer (VG-10) at the rate of 1.00 (one point zero zero) kilogram per square metre on existing WBM (Water bound macadam) surface cleaned with mechanical brooms as per HP.PWD./MORD specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	1443.75	Per square metre			
2	Providing, laying and rolling by mechanical means bitumen (VG-10) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen at the rate of 1.46 (one point four six) kilogramme per square metre to required line, grade and level to surge as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per technical specification Clause 508 including all corrective measures such as patching pot holes, sealing of cracks including all profile correction for all depths and hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	1443.75	Per square metre			
3	Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (VG-10) at the rate of 0.68 (zero point six eight) kilogramme per square metre as per technical specification Clause 510 including hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	1443.75	Per square metre			
Total						


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction of Link road from Balota to Gwaila via Nugal Mahadev
(Slh: Formation cutting in km 3/680 to 3/825)

Estimate Cost: 4,95,440
Earnest Money: 9,900
Time Limit : Three Mon

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
206	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 120.55 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2410.90	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.P.W.D.
Jagjinder Nagar

Job No - 5

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Galu to Banded km 0/00 to 0/075 under Deposit BASP (SH: Formation cutting in km 0/00 to 0/075)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost:		AMOUNT
				Figures	Rate	
					Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 24.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	486.76	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Is No 6 SCHEDULE OF QUANTITY


Name of work : Construction of LPG Gas Office cum Show room at Joginder Nagar District Mandi (H.P.)
(SH: Providing and Fixing Aluminum work, Painting work and Flooring of Room and Varendah)

Estimate Cost: 1,17,42,400
Earnest Money: 2,40,000
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.
				Figures	Words	
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion, Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	78.25	Per Kilogramme			
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket require (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.82	Per Kilogramme			
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. With float glass panes of 4.0 mm (four millimeter) thickness (weight not less than 10 kg/ sqm (ten kilogramme per square meter)) with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.59	Per square metre			

4	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm (two hundred millimeter) centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-Charge. (Only weight of grill to be measured for payment). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.50	Per Kilogramme			
5	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm (one point four millimeter) in both directions with wire of dia 0.63 mm (zero point six three) all complete. With 12 mm (twelve millimeter) mild steel U heading. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.89	Per square metre			
6	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 125mm (one hundred twenty five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
7	Providing and fixing anodized aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetera complete 150x10mm (One hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
8	12 mm (twelve millimeter) cement plaster of mix in 1 : 4 (one cement isto four coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	131.67	Per Square Metre			
9	Providing and applying white cement based putty of average thickness 1 mm. (one millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	131.67	Per Square Metre			

10	Distemping in Two coats with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 (fifty) grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	131.67	Per Square Metre				
11	Cement concrete flooring 1:2:4 (one cement isto two coarse sand isto four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (fourty millimeter) thick with 20 mm (twenty millimeter) nominal size stone aggregate) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.60	Per Square Meter				
	Total						


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

Job No - 7

SCHEDULE OF QUANTITY

Name of Work : Construction of Fegru-Sahi Dhundha Bagra Mehra road from Zim-Zima road and construction of bridge (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 1/100 to 1/200)				Estimate Cost: 3,68,227.44 Earnest Money: 7.44 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.25	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.38	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD.
Jalandhar Nagar

Job No 8


SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on Jeepable link road Joginder Nagar Kathla Dul km 0/00 to 3/00
(Sub Head:- Providing and laying Wearing Grade-II at km 2/000 to 2/500)

Estimate Cost:
Earnest Money:
Time Limit :

3,22,4
6,4
Three Mo

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	118.13	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

Job No 9

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Harabag to Degli via Nagchala in Joginder Nagar Tehsil. Km 0/00 to 5/00
(Sl: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/200 to 0/250)

Estimate Cost: 1.84.11
Earnest Money: 3.7
Time Limit : Three M

Sr. No.	Description of work	No. of Qty.	Unit	Rate		AMOUNT Rs.
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.63	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.69	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar
22

Shb No - 10

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T Jhamchar Shanan Kunkar Nagan road in GP Dhar
(Nk Formation cutting in km 2/490 to 2/865)

Estimate Cost:
Earnest Money:
Time Limit:

4,88,657
9,800
Three Mon

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 123.79 cum @ 300- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2370.28	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Jammu Nagar

Job No - 11

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on link road Chimmu to village Kheri Naidu Km. 0/0 to 2/500.
(Sub Head:- Providing and laying Soling at km 0/00 to 0/100)

Estimate Cost: 1,10,99
Earnest Money: 2,22
Time Limit : Three Mo

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs. P
				Figures	Words	
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre			
2	Stone soling properly handpacked filling intersices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	51.98	Per Cubic metre			
Total						


B & R Division HP.PWD.
Jalandhar

Job No - 12

SCHEDULE OF QUANTITY

Name of Work : Construction of & M/T on Joginder Nagar Ardi road Garora Bridge to Majharnoo Km. 0/0 to 1/500.
(SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/00 to 6/100)

Estimate Cost: 3,68,2
Earnest Money: 7,4
Time Limit : Three M

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs.
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.25	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.38	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

Job No 13

SCHEDULE OF QUANTITY

Name of Work : Construction of road from NH Chanang to village Madvana
(SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/480 to 0/580)

Estimate Cost: 3,68,27,4
Earnest Money: 7,4
Time Limit : Three M

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs.
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.25	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383. maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.38	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Jalandhar Nagar

SCHEDULE OF QUANTITY

Job No - 14

Name of Work: Construction of Galu Bhatwar to Bhatwar km 0/00 to 1/00
(SH: Formation Cutting in km 0/510 to 0/720)

Estimate Cost: 1,45,563
Earnest Money: 2,900
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all heads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 29.59 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	739.65	Per cubic metre			
Total						

Executive Engineer
 B & R Division HP.PWD.
 Jodhpur


Job No 15

SCHEDULE OF QUANTITY

Name of Work : Construction of road from Panjalag to Harizan Basti Karam via Nichala Panjalag Km. 0/0 to 2/0 under SCSP (SH: Providing and laying Kharanja Soling and Cement Concrete Pavement at km 0/165 to 0/220 & 1/440 to 1/540)

Estimate Cost: 4,16,15
Earnest Money: 8,30
Time Limit : Three Mo

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	351.75	Per square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	351.75	Per square metre			
3	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.76	Per Cubic metre			
4	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.50	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY


7065 No - 16

Name of Work : Construction of jeepable road from Khud Shamshanghat to Harizan Basti Nagan Kholra in G.P.
Dated K.n. 3/0 to 4/500. (Sub Head:- Construction of 900mm dia RCC Hume Pipe Culvert at km 1/060)

Estimate Cost: 2,86,467
Earnest Money: 5,700
Time Limit : Three Mon

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, canber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	66.92	Per cubic metre			
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.71	Per cubic metre			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	10.54	Per cubic metre			

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Per running metre			
6	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.15	Per cubic metre			
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.96	Per cubic metre			
	Total					



 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

566 NO - 17 **SCHEDULE OF QUANTITY**

Name of Work : Construction on link road from Bhala Rihra to Harizan Basti Bharola Sainthal km 0/00 to 2/500
(SH: Providing and Laying Wearing G-II & Cement Concrete Pavement at km 0/400 to 0/550)

Estimate Cost: 4,95,33
Earnest Money: 9,90
Time Limit : Three Mo

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.62	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	58.13	Per Cubic metre			
Total						


Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

Job No - 18


SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Drubbal to Harizan Basti Basoti Ropru km. 0/0 to 1/500 (Sub Head:- Construction of RCC Hume Pipe culvert along with both side wing walls at km 1/160) Scs 50

Estimate Cost: 2,33,573.00
Earnest Money: 4,700.00
Time Limit : Three Months

Sr.	Description of work	No. or	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	44.18	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre			
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.87	Per cubic metre			
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			

Sr.	Description of work	No. or	Unit	Rate		AMOUNT
				Figures	Words	
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.72	Per cubic metre			
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jyotinder Nagar

506NO-19

SCHEDULE OF QUANTITY

Name of Work : Construction of road to Sainthal Malehar upto Nichia Chaurtra km 0/00 to 1/500. *0.7 m² P.*
 (Sub Head:- Providing and laying Wearing Grade-II & cement concrete pavement from km. 1/050 to 1/150)

Estimate Cost: 2,37,289.00
 Earnest Money: 4,700.00
 Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the intersics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.66	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.88	Per Cubic metre			
Total						-

Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job No 20


SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Drubbhal to Harizan Basti Basoti Ropru km 0/00 to 1/500.
(Sub Head:- Providing and laying Wearing Grade-II from km. 0/090 to 0/340) (Scs1)

Estimate Cost:
Earnest Money:
Time Limit :

One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	54.14	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job No - 21

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Upper Bella to Lower Bella km 0/00 to 1/600 under head OTMNP.
(SH: ROFD by Providing Breast wall at km 0/203 to 0/215)

Estimate Cost:
Earnest Money:

Time Limit :

1,58,600
3,22,000
Three Months
Rs. 1

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.68	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.84	Per cubic metre			

3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	28.20	Per cubic metre				
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST	11.00	Each				
Total							


 B & R Division HP, P.W.D.
 Jodhpur Nagar


Job No - 22

Schedule of Quantity

Estimated Cost:- 98800.00
Earnest Money:- 2000.00
Time:- Two months

Name of work:- A/R&M/O various roads under Joginder Nagar Sub Division No. II, HPPWD Joginder Nagar (Local Section) (SH: Hiring of tractor with trolley for carriage/shifting of various type of materials etc.).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tractor with trolley in working condition per day basis (eight working hour per day) with including Sunday/ Holiday for carriage of patch work materials etc. The operational , maintenance and P.O.L charges and other miscellaneous supply / replacement required for smooth running of vehicle will be borne by the owner of the tractor within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	38.00			Per day	
				Total:-		



Executive Engineer,
 B&R Division HP.PWD,
 Joginder Nagar

Job No 23

SCHEDULE OF QUANTITY

Name of Work: Construction of Guini Kotla (Bani) Link Road km 0/00 to 3/00 Under SCSP
(SH: Formation Cutting at km 1/465 to 1/595)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost: 99,57,2,000	
				Earnest Money: 2,000	Two Months
				Time Limit :	AMOUNT
				Figures	Words
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 24.25 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	484.90	Per cubic metre		
Total					


Executive Engineer
B & R Division HP, PWD,
Jyotinder Nagar

505 No 24

SCHEDULE OF QUANTITY

Name of work : Construction of basket ball court at Govt. Degree college at Joginder Nagar District Mandi (H.P.)

(SH: Balance work of Basket ball court along with all side fencing) (Deposited)

Estimate Cost:
Earnest Money:
Time Limit :

4,16,399
8,3000
Three Mon

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying cement concrete 1:5:10 (one Cement isto five Sand isto ten graded stone aggregate 40mm (forty millimeter) nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.36	Per cubic metre			
2	Providing and laying cement concrete work 1:2:4 (one Cement isto two Sand isto four graded stone aggregate twenty millimeter nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in Foundations, footings bases of columns and the like and mass concrete as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.67	Per cubic metre			
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	44.39	Per cubic metre			
Total						

~~Executive Engineer~~
B & R Division HP, PWD,
Joginder Nagar

Executive Engineer,
B&R Division, HP.PWD
Jodhpur Nagar.