

**Himachal Pradesh
Public Works Department**

NO/PW/SNG/CB/E-16/Tender/24-25- 4555-80

Dated: - 16/10/2024

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.
cc-pwd-hp@nic.in

Subject: -Publication of Tender Notice.

Sir,

Enclosed please find herewith notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla -2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

Encl: -NIT and Schedule of Quantity

Yours faithfully,


Executive Engineer
Sangrah Division
HPPWD Sangrah

Copy forwarded to the following for information and necessary action :-

1. The Engineer -in- Chief, , HPPWD Shimla-2 please.
2. The Chief Engineer (SZ), HPPWD Shimla-2 please.
3. The Deputy Commissioner, Sirmour Distt. Sirmour at Nahan Please.
4. The SDM Sangrah please.
5. The Superintending Engineer, 12th Circle HPPWD Nahan please.
6. The BDO Sangrah please.
7. All the Assistant Engineers under this division to display on their respective Notice Boards.
8. The Notice Board.

Executive Engineer
Sangrah Division
HPPWD Sangrah

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS**

Sealed **percentage rate tenders** on from 6 & 8 are hereby invited by the Executive Engineer, Sangrah Division, HP.PWD. Sangrah on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form-25.10.2024 up to 04:00 PM

Date and time of issue/Sale of tender form-28.10.2024 up to 12:00 Noon

Date and time of receipt of tender form-28.10.2024 up to 02:30 PM

Date and time of opening tender form-28.10.2024 at 03:00 PM

The tender form can be had from the office of the Executive Engineer against Cash (**Non-refundable**). The earnest money should be in the shape of **Fixed Deposit** duly **pledged in favour of the Executive Engineer Sangrah Division HPPWD Sangrah** must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for **75 days. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.**

Sr. No.	Name of work	Estimated cost in Rs.	EMD in Rs.	Cost of Tender	Time Allowed	Class of Contractor
1.	R/R damages on various road under Haripurdhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)	485163	9,700/-	Rs. 350/-	03 Months	Class C & D
2.	A/R & M/O Haripurdhar Kupvi Road km. 0/00 to 6/500 (SH: Providing and laying G-III at essential reaches between km. 2/00 to 5/00).	485048/-	9,700/-	Rs. 350/-	03 Months	Class C & D
3.	A/R & M/O Dalyanoo Pullilani Nainidhar Road km. 0/00 to 22/800 (SH: Providing and laying G-III at essential reaches between km. 4/00 to 8/00).	485280/-	9,700/-	Rs. 350/-	03 Months	Class C & D
4.	Construction of R/wall, CD & M/T on link road from Shillahan to Hundyari Bharmash dolna Korag km 0/00 to 4/500 (SH:- C/O PCC R/Wall from km. 0/117 to 0/129).Under MNP	489709/-	9,800/-	Rs. 350/-	03 Months	Class C & D

5.	R/R damages on Ratwa to Kuna via Jadna Balina km. 0/00 to 6/500 (SH:- C/O PCC B/Wall from km. 1/740 to 1/782).	487444/-	9,800/-	Rs. 350/-	03 Months	Class C & D
6.	Construction of Link road from Ratwa to Kunna via Tholla, Kalyari, Jedana and Balaina km. 0/0 to 6/500 (SH:- C/O 900 MM Dia RCC Hume pipe culvert at RD. 1/370 with wing wall both side) Under MNP.	4,03,710/-	8,100/-	Rs. 350/-	03 Months	Class C & D
7.	Construction of Link road from Ratwa to Kunna via Tholla, Kalyari, Jedana and Balaina km. 0/0 to 7/0 (SH:- 5/7 mtr. Wide formation cutting from km. 6/180 to 6/240)	4,95,841/-	10,000/-	Rs. 350/-	03 Months	Class C & D
8.	R/R damages on Nahan Dadahu Haripurdhar Road km. 79/00 to 87/00 (SH:- C/O PCC R/Wall from km. 79/110 to 79/125).	368624/-	7,400/-	Rs. 350/-	03 Months	Class C & D
9.	A/R & M/O PWD Rest House at Ghandoori Distt. Sirmour H.P. (Providing furniture and Livery/ crokery articles)	4,70,469/-	9,400/-	Rs. 350/-	03 Months	Class C & D
10.	A/R & M/O Office of Executive Engineer HP.PWD., Sangrah (SH:- Providing and fixing pie wooden panel Seiling/wall lining painting etc).	4,79,119/-	9,600/-	Rs. 350/-	03 Months	Class C & D

Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ GST Registration / EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected.
3. The offer shall remain valid up to 75 days.
4. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
5. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
6. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.
7. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.
8. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996-38095 dated 13.03.2023.


Executive Engineer,
Sangrah Division,
HP.PWD; Sangrah.

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Chief Engineer (SZ) HPPWD Shimla-2 please.
3. The Deputy Commissioner Distt. at Nahan please.
4. The Superintending Engineers 12th Circle HPPWD Nahan please.
5. The SDM/BDO, Sangrah please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangrah.

Schedule of Quantity				Job No. 1	Estimated Cost: 485163
Name of work:- R/R damages on various road under Haripurdhar Sub-Division (SH:- Hiring of JCB for removal of slips, cleaning of drain, Improvement of shoulders & and dressing of berms)					Earnest Money: 9,700/-
					Time Limit: Three Month
S.No	Description of Item	Quantity	Unit	Rate	
				In Figure	In Word
1	Hiring of excavator-cum-loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clering of drains with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the HP.PWD specifications and the direction of Engineer-in-charge.	453.00	Hrs	1071.00	Rupees One Thousand Seventy One & paise Zero
Total:-					485163

Quoted rate in figure (+/-)%

Quoted rate in words (+/-) %)

Signature of contractor with full address.


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173025

Schedule of Quantity				Job No. 2		Estimated Cost:-	
Name of work :- A/R & M/O Haripurdhar Kupvi Road km. 0/00 to 6/500 (SH: Providing and laying G-III at essential reaches between km. 2/00 to 5/00).				Earnest Money		9,700/-	
				Time Period		Two Months	
S.No.	Description of Item	Quantity	Unit	Rate		Fig	Amount
				Words			
1	2	3	4	5	6	7	
1	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with 3-wheeled static roller 8-10 (Eight to Ten) tonnes in stages to proper grade and camber applying and brooming crushable screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per technical specification clause 405 by Mechanical means including haulage of material within all leads, lifts and carriage of materials and as per direction of Engineer-in-Charge. WBM Grading- 111	220.88	Cubic metre	Per Cubic metre	2195.98	Rupees. Two thousand one hundred ninety five & paise Ninty eight only	485048
Total:-							485048

Quated rate in figure (+/-) %)

Quated rate in words (+/-) %)

Signature of contractor with full address.


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173022

Schedule of Quantity				Job No 3		Estimated Cost:-	
Name of work :- A/R & M/O Dalyanoo Pullilani Nainidhar Road km. 0/00 to 22/800 (SH: Providing and laying G-III at essential reaches between km. 4/00 to 8/00).				Earnest Money		9,700/-	
				Time Period		Two Months	
S.No.	Description of Item	Quantity	Unit	Rate		Amount	
				Fig	Words		
1	2	3	4	5	6	7	
1	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with 3-wheeled static roller 8-10 (Eight to Ten) tonnes in stages to proper grade and camber applying and brooming crushable screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per technical specification clause 405 by Mechanical means including haulage of material within all leads, lifts and carriage of materials and as per direction of Engineer-in-Charge. WBM Grading- 111	220.88	Cubic metre	Per Cubic metre	2197.03	Rupees. Two thousand one hundred ninety seven & paise three only	485280
Total:-							485280

Quoted rate in figure (+/-)%)

Quoted rate in words (+/-) %)

Signature of contractor with full address.


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023


Schedule of Quantity				Job No. 4	Estimated Cost:	
Name of Work:- Construction of R/wall, CD & M/T on link road from Shillahan to Hundyari Bharmash dolna Korag km 0/00 to 4/500 (SH:- C/O PCC R/Wall from km. 0/117 to 0/129). Under MNP					Earnest Money:	489709
					Time Limit:	9,800/-
					Rate	Two Months
					In Figure	Amount
					In Words	
Sr No	Description of Item	Net Quantity	Unit	In Figure	In Words	
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge	30.00	cubic metre	328.00	Rupees (Three Hundred Twenty Eight & Paise Zero) Only	9840
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the useful materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechaneries materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge	20.40	cubic metre	498.00	Rupees (Four Hundred Ninty Eight & Paise Zero) Only	10159

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203.1.4.8 (One Cement : Four Sand : Eight Graded Stone Aggregate : 40mm (Forty Milimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	100.80	cubic metre	Per cubic metre	4481.83	Rupees (Four Thousand four hundred eighty one & Paise eighty three) Only	451769
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of i(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7.	25	No's	Each	227.00	Rupees (two Hundred twenty seven & Paise zero) Only	5675
5	Backfilling behind abutment ,wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with granular material as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	14.76	cubic metre	Per cubic metre	831.00	Rupees (Eight Hundred thirty one & Paise Zero) Only	12266
Total							489709

Signature of contractor with full address.

Quoted rate in figure (+/-)%

Quoted rate in words (+/-)%


Executive Engineer,
Sangrah Division,
HP.PWD, Sangraha

Schedule of Quantity					Job No. 5		Estimated Cost:		487444
Name of Work:- R/R damages on Ratwa to Kuna via Jadna Balina km. 0/00 to 6/500 (SH:- C/O PCC B/Wall from km. 1/740 to 1/782).							Earnest Money:		9,800/-
							Time Limit:		Two Months
							Rate		Amount
Sr. No	Description of Item				Net Quantity	Unit	In Figure	In Words	
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.				50.40	cubic metre	328.00	Rupees (Three Hundred Twenty Eight & Paise Zero) Only	16531
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the useful materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechaneries materials, tools equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.				19.32	cubic metre	498.00	Rupees (Four Hundred Ninty Eight & Paise Zero) Only	9621

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203.1.4.8 (One Cement : Four Sand: Eight Graded Stone Aggregate) 40mm (Forty Milimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	100.33	cubic metre	Per cubic metre	4484.13	Rupees (Four Thousand four hundred eighty four & Paise thirteen) Only	449892
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7.	50	No's	Each	228.00	Rupees (two Hundred twenty eight & Paise zero) Only	11400
Total							487444

Signature of contractor with full address.

Quoted rate in figure (+/-)%

Quoted rate in words (+/-)%


Executive Engineer,
Sangrah Division,
HP.PWD. Sangraha

Schedule of Quantity				Job No. 6		Estimated Cost:		403710
Name of work :- Construction of Link road from Ratwa to Kunna via Tholla, Kalyari, Jedana and Balaina km. 0/0 to 6/500 (SH:- C/O 900 MM Dia RCC Hume pipe culvert at RD. 1/370 with wing wall both side) Under MNP.				0/0 to 6/500 (SH:- C/O 900 MM Dia		Earnest Money:		8,500/-
						Time		Two Months
Sr. No	Description of Item	Net Quantity	Unit	In Figure	Rate In Words	Amount		
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	8.44	cubic metre	328.00	Rupees (Three Hundred Twenty Eight & Paise Zero) Only	2768		
2	Excavation in foundation trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the usefull materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechaneries materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge	48.01	cubic metre	498.00	Rupees (Four Hundred Ninety Eight & Paise zero) Only	23909		

3	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One Cement, four Sand, Eight graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and technical specification clause 802.803, 1202 & 1203, as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	56.16	cubic metre	Per cubic metre	4547.00	Rupees (Four thousand five hundred forty seven & paise zero)only	255360
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and specification clause 802.803, 1202 & 1203(PCC Grade M10 Nominal mix 1:3:6) upto all Height, as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	12.74	cubic metre	Per cubic metre	5586.30	Rupees (Five thousand five hundred eighty six & paise thirty)only	71169
5	Providing and laying reinforced cement concrete pipe NP2 as per design in single row, culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:3 but excluding excavation protection works back filling concrete and masonry works in head walls and parapets clause 1106 RCC pipe NP2 900mm dia as per design.	10.00	Rmt	Per Running metre	4234.70	Rupees (Four thousand two hundred thirty four & paise seventy)only	42347
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structure with slopes of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7, as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	18	Nos	Each	227.00	Rupees (Two Hundred Twenty Seven & paise Zero)only.	4086
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with granular material as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	7.68	cubic metre	Per cubic metre	890.44	Rupees (Eight hundred Ninety & paise Forty Four)only	6839
	Total						403710

Quoted rate in figure (+/-)%)

Signature of contractor with full address.

Quoted rate in words (+/-)%)


 Executive Engineer,
 Sangraha Division,
 HP.PWD, Sangraha

Schedule of Quantity		Job No. <u>7</u>	Estimated Cost:		495841
Name of work :- Construction of Link road from Ratwa to Kunna via Tholla, Kalyari, Jedana and Balaina km. 0/0 to 7/0 (SH:- 5/7 mtr. Wide formation cutting from km. 6/180 to 6/240)			Earnest Money:		10,000/-
			Time Limit:		Two Month
S.No	Description of Item	Quantity	Unit	Rate	
				In Figure	In Word
1	Excavation in earth work in in hilly area all height and depths and in all kinds of soils including saturated soil comprising of mixed soil ordinary rock and hard rock. All works road rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc, and to protect stability of hill side. Rock shall be excavated with chieseling and wedging out rock(where blasting is prohibited). All earth work in cutting/ excavation, including rock excavation shall be carried out true to lines grades sides slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge in conformity with the requirement of technical specification of Rural road August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable cut material and specified manner, including arrangement of dumping site trimming, filling of unvenness blindage and finishing of the road to specified diamensions including disposal of surplus materials with all leads, and lifts at the locatuion specified in the tender document or as directed by the Engineer-in-Charge for smooth riding. The recovery for stones where useful or not i.e. 330.99 (THREE HUNDRED THIRTY POINT NINTY NINE)cubic metre @ 300/- (Rs. THREE HUNDRED) only per cubic metre shall be effected on pro-rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	2829.82	cubic metre	175.22	Rupees (One Hundred seventy five & Paise twenty two) Only
Total:-					495841

Signature of contractor with full address.

Quated rate in figure (+/-)

Quated rate in words (+/-)

.....%

Executive Engineer
H.P. P.W.D. Division
Sangrah 173023

Schedule of Quantity			Job No.	Estimated Cost:		
Name of Work:- R/R damages on Nahan Dadahu Haripurdhar Road km. 79/00 to 87/00 (SH:- C/O PCC R/Wall from km. 79/110 to 79/125)				Earnest Money:		
				Time Limit:		
				Amount		
Sr. No	Description of Item	Net Quantity	Unit	In Figure	In Words	Rate
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	15.90	cubic metre	328.00	Rupees (Three Hundred Twenty Eight & Paise Zero) Only	5215
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the useful materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechaneries materials tools equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	21.00	cubic metre	498.00	Rupees (Four Hundred Ninty Eight & Paise Zero) Only	10458

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1 4.8 (One Cement : Four Sand Eight Graded Stone Aggregate) 40mm (Forty Milimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge	75.00	cubic metre	Per cubic metre	4430.56	Rupees (Four Thousand four hundred thirty & Paise fifty six) Only	332292
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7	35	No's	Each	227.00	Rupees (two Hundred twenty seven & Paise zero) Only	7945
5	Backfilling behind abutment ,wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with granular material as per HP.PWD specification including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	15.30	cubic metre	Per cubic metre	831.00	Rupees (Eight Hundred thirty one & Paise Zero) Only	12714
Total							368624

Quoted rate in figure (+/-)%)

Quoted rate in words (+/-)%)

Signature of contractor with full address.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangra.

Schedule of Quantity							Estimated Cost:-		470469
Name of work :- A/R & M/O PWD Rest House at Ghandoori Distt. Sirmour H.P. (SH:-							Earnest Money		9,400/-
Providing furniture articles etc.)							Time Period		Two Months
S.No.	Description of Item	Quantity		Unit	Rate		Fig	Words	Amount
1	2	3	4		5	6			7
1	Providing Double Bed with side table made of superior quality teak board with box with laminated sides finished in wall nut finished size 6ft x6ft. (as per Sample approved by the purchase committee) (in V.I.P. suite).	1	Each	Each	45500.00	Rupees. Forty Five thousand five hundred & paise zero only			45500
	Providing Sofa set frame made of best quality sofa wood cushioned with high density foam covered with best quality upholstery cloth and arms made of teak wood finished with melamine polish (as persample approved by the purchase committee) (a) 5 seater= (in V.I.P. suite).	1	Each	Each	38500.00	Rupees. Thirty eight thousand five hundred & paise zero only			38500
	Providing Centre Table 4'x2' size with glass top for VIP Set. (as per Sample approved by the purchase committee)	2	Each	Each	9500.00	Rupees. Nine thousand five hundred & paise zero only			19000
	Providing Ordinary Double Bed made of 1st class quality teak board with laminated sides finished in wall nut finished size 6ft x6ft. (as per Sample approved by the purchase committee) for suite No. 2,3,&4.	3	Each	Each	35000.00	Rupees. Thirty five thousand & paise zero only			105000
	Providing Ordinary chair for teak wood easy type for suite No. 3 & 4(as per Sample approved by the purchase committee)	4	Each	Each	4250.00	Rupees. Four thousand two hundred fifty & paise zero only			17000
	Providing 30 Nos chair (as per Sample approved by the purchase committee) Cello comfortable/CHR 2197 brown/Neelkamal mid/ Italica or equivalent	50	Each	Each	500.00	Rupees. Five hundred & paise zero only			25000

	Providing Dinning table with six chairs (table size 6ft x 3ft.) Made of teak wood with mila top chair cushion seat cover with best quality upholstery cloth finished in mela mine polish (as per Sample approved by the purchase committee.)	1	Each	Each	45500.00	Rupees. Forty five thousand five hundred & paise zero only	45500
	Livery articles						
2	Providing sleepwell mattress (ultra) 72" x35" (as per Sample approved by the purchase committee.)	6	Each	Each	3500.00	Rupees. Three thousand five hundred & paise zero only	21000
	Providing sleepwell mattress (active) 72" x35" for VIP suite (as per Sample approved by the purchase committee.)	2	Each	Each	4372.00	Rupees. Four thousand three hundred seventy two & paise zero only	8744
	Providing bed sheet Deouble bed(100x108)cm white (as per Sample approved by the purchase committee.)	8	Each	Each	810.00	Rupees. Eight hundred ten & paise zero only	6480
	Providing bed cover SATIN (90x100) for VIP suite (as per Sample approved by the purchase committee.)	2	Each	Each	1800.00	Rupees. One Thousand Eight hundred & paise zero only	3600
	Providing bed sheet JAMES BOND ORDINARY.(as per Sample approved by the purchase committee.)	8	Each	Each	900.00	Rupees. Nine hundred & paise zero only	7200
	Providing towel (60" x30") esport (as per Sample approved by the purchase committee.)	4	Each	Each	430.00	Rupees. Four hundred thirty & paise zero only	1720
	Providing Blankets for double side (VIP)(as per Sample approved by the purchase committee.)	1	Each	Each	3000.00	Rupees. Three thousand & paise zero only	3000
	Providing Blankets ordinary (as per Sample approved by the purchase committee.)	6	Each	Each	2500.00	Rupees. Two thousand five hundred & paise zero only	15000
	Priving Quilts 5kg (as per Sample approved by the purchase committee.)	6	Each	Each	1500.00	Rupees. One thousand five hundred & paise zero only	9000
	Providing Pillow 1kg (as per Sample approved by the purchase committee.)	6	Each	Each	800.00	Rupees. eight hundred & paise zero only	4800

	Providing Pillow cover (as per Sample approved by the purchase committee.)	6	Each	Each	350.00	Rupees. Three hundred fifty & paise zero only	2100
	Providing cushion for chair in Drg Room (as per Sample approved by the purchase committee.)	6	Each	Each	250.00	Rupees. Two hundred fifty & paise zero only	1500
	Crocery articles						
3	Providing Aqua Guard (as per Sample approved by the purchase committee.)	1	Each	Each	7600.00	Rupees. Seven thousand Six hundred & paise zero only	7600
	Providing Refrigerator 165 ltr (as per Sample approved by the purchase committee.)	1	Each	Each	15000.00	Rupees. Fifteen thousand & paise zero only	15000
	Providing Dinner Set Bon chaina (as per Sample approved by the purchase committee.)	1	Each	Each	5000.00	Rupees. Five thousand & paise zero only	5000
	Providing Tea set bone china (as per Sample approved by the purchase committee.)	1	Each	Each	2500.00	Rupees. Two thousand five hundred & paise zero only	2500
	Providing Pressure Cooker 5.00 ltrs SS (as per Sample approved by the purchase committee.)	2	Each	Each	1800.00	Rupees. One thousand Eighteen hundred & paise zero only	3600
	Providing carpet/bed side runner for VIP (24' x 72')(as per Sample approved by the purchase committee)	2	Each	Each	600.00	Rupees. Six hundred & paise zero only	1200
	Providing Dinner set (Steel) (as per Sample approved by the purchase committee.)	1	Each	Each	3500.00	Rupees. Three thousand five hundred & paise zero only	3500
	Providing stainless steel Jug (as per Sample approved by the purchase committee.)	2	Each	Each	400.00	Rupees. Four hundred & paise zero only	800
	Providing Curtain for V.I.P. Suite (as per Sample approved by the purchase committee.)	12	Each	Each	900.00	Rupees. Nine hundred & paise zero only	10800
	Providing footmate VIP (as per Sample approved by the purchase committee.)	1	Each	Each	600.00	Rupees. Six hundred & paise zero only	600
	Providing footmate Ordinary (as per Sample approved by the purchase committee.)	4	Each	Each	500.00	Rupees. Five hundred & paise zero only	2000
	Providing coordless bell (as per Sample approved by the purchase committee.)	1	Each	Each	1000.00	Rupees. One thousand & paise zero only	1000

Providing emergency light (as per Sample approved by the purchase committee.)	4	Each	Each	2000.00	Rupees. Two thousand & paise zero only	8000
Providing charging bulbs (as per Sample approved by the purchase committee.)	4	Each	Each	500.00	Rupees. five hundred & paise zero only	2000
Providing TV 46' size with DTH (as per Sample approved by the purchase committee.)	1	Each	Each	18000.00	Rupees. Eighteen thousand & paise zero only	18000
Providing buckets cello 15 ltr (as per Sample approved by the purchase committee.)	5	Each	Each	600.00	Rupees. Six hundred fifty & paise zero only	3000
Providing PVC Jug (as per Sample approved by the purchase committee.)	5	Each	Each	45.00	Rupees. Forty five & paise zero only	225
Providing vertical Heat Pillar (Balco)(as per Sample approved by the purchase committee.)	2	Each	Each	3000.00	Rupees. Three Thousand seven hundred & paise zero only	6000
Total:-						470469

Note:- All rates are including GST

Quoted rate in figure (+/-)%)

Signature of contractor with full address.

Quoted rate in words (+/-) %)


Executive Engineer
Sangrah Division
HP.PWD. Sangrah

Schedule of Quantity			Job No. 10		Estimated Cost:		479119
Name of Work:- A/R & M/O Office of Executive Engineer HP.PWD., Sangraha (SH:- Providing and fixing pie wooden panel eiling/wall lining painting etc).					Earnest Money:		9,600/-
					Time Limit:		Two Months
Sr. No	Description of Item	Net Quantity	Unit	In Figure	Rate In Words	Amount	
1	Providing and fixing pine wooden panel ceiling/ wall lining with tongued and grooved jointeing and wood screw/nail (frame work and cover fillets to be measured and paid for saperately)	203.1	Sqm	1583.70	Rupees One thousand five hundred eighty three & paise seventy only	321649	
2	Providing wood work in frames of false ceiling/wall lining ,partition etc. sawn and fixed in poistion.	0.508	Sqm	147370.60	Rupees One lace forty seven thousand three hundred seventy only	74864	
3	Polishing two coat with french spirit polish on new wood and wood based surfaces to give an even shade surface including cleaning the surface of all dirt,dust and sand papered smooth and including a coat of wood filler.	203.1	Sqm	148.10	Rupees One hundred forty eight & paise ten only	30079	
4	Removing old paint or polish from wood and wood based surface with paint remover of approved brands and manufacture and making the surface even with paint remover of approved brand	17.61	Sqm	66.80	Rupees Sixty six & paise eighty only	1176	
5	Painting two coat(execuding priming coat) on previously painted wood and wood based surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt,dust and otther foreign matter sand papering and stopping.	17.61	Sqm	76.70	Rupees Seventy six & paise seventy only	1351	
6	Lump-sum amount of Electricity wiring internal & open, curtain Rod etc.					50000	
	Total					479119	

Quated rate in figure (+/-)%

Signature of contractor with full address.

Quated rate in words (+/-)%


Executive Engineer,
Sangraha Division,
HP.PWD. Sangraha.