

INVITATION FOR BIDS (IFB)

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer, Sundernagar Division, HPPWD Sundernagar on behalf of Governor of HP for the following works from the approved and eligible Contractors so as to reach in this office on or before 04.11.2024 up to 11:00 AM and will be opened on the same day at 11:30 AM in the presence of the intending contractors or their authorized representatives if any. The application shall be received on 02.11.2024 upto 12:00 Noon and tender forms will be issued on same day up to 5:00 PM against cash payment (Non refundable).

The earnest money in the shape of Nation Saving Certificate / Time Deposit Account / Saving Account in any of the Post Office and Bank in H.P. duly pledged in favour of Executive Engineer, Sundernagar Division, HPPWD Sundernagar must be accompany with each tender. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reasons.

Sr. No	Name of Work	Estimated Cost (in Rs.)	Earnest Money	Time
1	A/R & M/O old NH Chandigarh Mandi Manali road between KM 156/750 to 165/300 (SH:- Providing and fixing of high intensity Engineering Grade reflecting Sheeting at various RD's).	4,98,750/-	10,000/-	Three Months
2	Improvement of black spots on Shimla Mandi Tattapani road KM 135/00 to 146/00 (SH: - Supplying cat part 11-11 Delineator ST).	4,96,800/-	10,000/-	Three Months
3	A/R & M/O Chandigarh Mandi Manali road(OLD NH-21) KM 173/900 to 179/600(SH:- Manufacturing and erecting of overhead signage at KM 173/900).	4,95,000/-	10,000/-	Three Months

Conditions:-

1. Application must be accompanied with EMD and cost of tender. Applications without EMD/ cost of tender shall be summarily rejected.
2. The application of only those contractors shall be accepted who remain present at the time of application and similarly tender forms shall be issued to the intended contractors in person.
3. The application forms shall not be issued to those contractors who have two works or more in hand or should have atleast completed 75% of the works already awarded to them. The undertaking for the same is required from the participating contractors.
4. The contractors are required to submit the valid enlistment/G.S.T. registration and latest ITR alongwith application form.
5. Conditional and incomplete tenders shall be rejected.
6. The contractors can apply for one work at a time.
7. The Executive Engineer reserves the right to accept or reject the tender without assigning any reason.


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.


No: - PW/SNR-E-Tender/Giriraj/2024-

7822-32

Dated: **24.10.2024**

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief, Nirman Bhawan HPPWD Shimla.
2. The Executive Engineer (IT Cell) o/o Engineer-in-Chief, Nirman Bhawan, Nigam Viahar HPPWD Shimla-2 for uploading the NIT on Departmental website please.
3. The Superintending Engineer, 1st Circle H.P.P.W.D. Mandi.
4. All the Assistant Engineers working under this Division.
5. Notice Board/ Accounts/ Drawing Branch in this office.


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY


Estimate Cost: Rs. 4,98,750/- only

Earnest Money: Rs 10,000/- only

Time : Two months

Name of Work :- A/R & M/O Old NH-21 Chandigarh Mandi Manali road between km 156/750 to 165/300
(SH:- Providing and Fixing of high intensity Engineering Grade reflective Sheeting at various RD's)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and Fixing of high intensity Engineering Grade reflective Sheeting on the front side of existing "W" metal beam crash barrier size 300 X 450 mm (Three Hundred into four hundred fifty millimetres) in yellow and black colour at site as per direction of Engineer - in - charge including carriage of materials, with in all leads, lifts and other incidentals .	525.00 Rmt			Per Running metre	
					Total	


 Execd. Engineer,
 Sunder Nagar District,
 H.P.W.D. Sunder Nagar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 4,96,800/- only

Earnest Money: Rs 10,000/- only

Time :Two months

Name of Work :- Improvement of black spots on Shimla Mandi Tattpani road km 135/0 to 146/00 (SH:- Supplying cat part 11-11 Delineator ST)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Supplying cat part 11-11 Delineator ST all directional retro- reflective round delineator short made out of 16 gauge and pipe of outer dia 47 mm (forty seven millimetre) and of length 600 mm Delineator stove enamelled and booked to 120 c. Delineator to have 200 mm (two hundred millimetre) wide reflective band of colour white and red refletive welded wire mesh cage as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals .	540.00 No.			Each	
					Total	


 Executive Engineer,
 Sunder Nagar Division,
 H.P.W.D. Sunder Nagar.

SCHEDULE OF QUANTITY


Estimate Cost: Rs. 4,95,000/- only

Earnest Money: Rs 10,000/- only

Time : Three months

Name of Work :- A/R & M/O Chandigarh Mandi Manali road (Old NH-21) km 173/900 to 179/600
(SH: Manufacturing and Erection of overhead signage at km 173/900)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Manufacturing and Erection of overhead Signage system of Cantilever shape made of 305NB Dia MS circular Hallow section with clear height of 6m from the bottom of top section made of 48NB(M) and 25 NB(M)circular hallow section jointed with 2 Nos of 80cm X80cm of 08mm thickness MS plate fasten with 8 Nos fastener of 25 mm dia and base plate of 90cmX90 cm of 10 mm supported by stiffener of 4 Nos , 8mm thickness and retro reflective Signage on both side with size of 6m X 1.20 m in type IX retro reflective sheeting over the Aluminium Composite panel sheet with thickness of 3mm supported on angle frame 35x34x4 mm on top section in desire shade of Engineer incharge erected at side on pedestal of CC 1:2:4 (one cement : Two Sand : four crashed stone aggregate) with 12 Nos of foundation bolt of 25 mm dia of as per IRC specification with all lead and lifts complete in all respect.	1.00 No.			Each	
					Total	


Executive Engineer,
Sunder Nagar Division,
HPPWD Sunder Nagar.