




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS,
AS CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-
24/- 13442-50 DATED 23/11/24 ARE URGENT
NATURE AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **09.12.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **07.12.2024** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **06.12.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Link road Khalenu to Maleher km 0/00 to 1/00 (SH: C/O R/Wall at RD 0/010 to 0/015 and 0/025 to 0/028 & P/L Khamja Stone Soling and C.C. Pavement at RD 0/075 to 0/110)	Rs.2,64,589/-	Rs.5,300/-	Rs.350/-	Two Months
2	S/R to Type III qtr. at PWD Colony Baijnath (SH: Painting, Distemping, 40mm thick Paver Block Steel work, Vetrified tile W S and Sanitary fitting)	Rs.3,62,052/-	Rs.7,300/-	Rs.350/-	Two Months
3	Restoration of Rain Damage on Bir Barot road Km 0/00 to 40/00 (SH: C/O Pusta wall at RD 15/090 to 15/106)	Rs.4,31,981/-	Rs.8,700/-	Rs.350/-	Two Months
4	A/R & M/O link road from village Chaugan to village Chaugan & Keori Suja road (SH: Providing laying Patch work in damaged Reaches)	Rs.4,98,373/-	Rs.10,000/-	Rs.350/-	Two Months
5	Renovation of Rooms in Govt. High School Gunehar (VKV/2023/1305) (SH: C/O Civil work)	Rs.1,23,033/-	Rs.2,500/-	Rs.350/-	Two Months
6	Construction of Padhiar Khar Jandpur Trehal road Km 0/00 to 4/00 (SH: Construction of 1.00 mtr. Span RCC Slab Culvert at RD 3/105)	Rs.1,94,622/-	Rs.3,900/-	Rs.350/-	Two Months
7	C/O Civil Hospital Chadhiar (SH: P/F 2 No. Gate P/F door & Collapsible Shutter etc.	Rs.1,45,650/-	Rs.3,000/-	Rs.350/-	Two Months
8	C/O Barot Nalhot Road Km 0/00 to 15/500 (SH: Laying G-II, Prime Coat, Tack Coat and Bituminous Concrete (25mm thick) on Portion from Nalhot to Baragran at RD 15/370 to 15/435)	Rs.92,127/-	Rs.1,900/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.
For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/-

13442-50

Dated:- 23.11.2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.80	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	23.12	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.60	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.00	Each			
5	Providing and laying hard stone Soling properly hand packed intersects with Kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	16.01	Per Cubic metre			
6	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	16.01	Per Cubic metre			
Total						

DNIT/DRAFT SCHEDULE OF QUANTITY

2/2

Name of work S/R to Type III qtr at PWD Colony Baijnath .
(Sh:- Painting , Distemping, 40 mm thick Paver Block Steel work , Vetrified tile W S and Sanitary Fitting .)

Estimate Cost: 3,62,052.00/-
Earnest Money: 7,300.00/-
Time Limit : Two Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs P
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.15	Cum.			
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundations and plinth in : cement mortar 1:4 (one cement : four coarse sand) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	6.54	sqm			
3	15mm (Fifteen millimeter) Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeter) in girth and finished even and smooth Cement Mortar 1:6 (one Cement:six Sand) . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Per square metre			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.47	Per cubic metre			
5	Providing and fixing 40 mm (Forty millimetre) thick second class Deodar wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clerestory windows including bright finished black enameled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.05	Per square metre			
6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in Charge. 40mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	67.31	Per Square metre			

7	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces(two coats and a subsequent coat) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	211.16	Per square metre			
8	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer	158.52	sqm			
9	Painting two coats (excluding priming coat) on old wood and wood based surfaces, with readymixed paint other then white, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	61.36	Per square metre			
10	Applying priming coat over new steel and steel based surface after and including preparing the surface by thoroughly clacening oil, grease, dirt and other foreign matter sand papering and knotting. Ready mixed paint brushing with white lead for priming as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.40	Per square metre			
11	Painting two coat (excluding priming coat) on previously painted steel & other metal surfaces with readymixed paint other than white, brushing oil, grease to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	2.40	Per square metre			
12	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight) and conforming, to IS: 15622, of approved make, in all colours and shade, laid on 20 mm (Twenty Millimeter) thick cement mortar 1:4 (one cement : four coarse sand) , jointing with grey cement slurry @ 3.3 kg/sqm (three point three kilogram per square meter) including grouting the joints with white cement and matching pigments etc., completing size of tile 600 x 600 mm (Six hundred into six hundred) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.46	Per square metre			
13	Providing and laying granite stone in flooring 20mm (twenty millimeter) (average) thickness base of cement mortar 1:3 (one cement iso three sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone i/c rubbing and polishing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.25	Per square metre			

14	Providing and laying Ceramic glazed floor tiles of size 300 x 300 mm (three hundred into three hundred) (thickness to be specified by the manufacturer), of 1st quality conforming to IS:15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm(Twenty millimeter) thick bed of cement slurry @ 3.3 kg/sqm (three point three kilogram per square meter) including pointing the joints with white cement and matching pigments etc. complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	15.54	Per square metre				
15	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	131.62	P/KG				
16	Providing and fixing aluminium work for doors, windows ventilators and partitions with extended built up tubular section / Factory Made frame and windows and other sections of approved make conforming to IS:733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium section shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (Glazing, paneling and dash fasteners to be paid for separately). Power coated aluminium (minimum thickness of powder coating 50 micron) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	1.00	Each				
17	Providing and fixing aluminium work for doors, windows ventilators and partitions with PVC gasket glazing with glass pan 4 mmthick. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	0.75	sqm				
18	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :125 mm (One twenty five millimetre)The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	8.00	Each				

19	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	0.95	Per cubic metre			
20	Providing and placing water tank of makes (sintex) having capacity 1000 (One Thousand) litres each with necessary fitting including over flow pipes scour pipe and ball valve and with cover locking arrangement including providing pads of sizes as required for inlet and outlet and inside painting of good quality all complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	1000.00	per ltr			
21	Providing and fixing Orrisa pattern vitreous China water closet squatting pan (Anglo Indian type W.C. pan) size 580mm (five hundred eighty millimetre) (earth work, bed concrete, foot rest and trap to be measured and paid for separately) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	1.00	Each			
22	Providing and fixing 32mm (Thirty two millimetres) diameters C.P. brass waste pipe ESS-ESS / Cera / Hindware/ (Heavy duty make ISI marked NO-8931 & 8934) for Sink. Within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	2.00	Each			
23	Providing and fixing 100 mm (One hundred millimeter) dia chromium plated grating of superior quality for floor, gully or nahani trap including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	4.00	Each			
24	Providing and fixing PVC inlet connection for pipe with brass union 15 mm dia including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	6.00	Each			
25	Providing and fixing cast in iron floor trap of self cleaning design with sand cast iron screwed down or hinged grating without vent arm complete including cost of cutting and making goods the walls and floor for 100 mm (Hundred millimeter) nominal size diameter. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each			
26	Providing and Laying PVC Pipe for sink or wash basin PVC fitting complete 100 mm dia. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.50	Mtr			

26 B	Providing and Laying PVC Pipe for sink or wash basin PVC fitting complete 90 mm dia The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Mtr				
27	Providing and fixing PVC Pipe Bend door inserting rubber washer 3 mm thick complete 100 mm dia The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
27 B	Providing and fixing PVC Pipe Bend door inserting rubber washer 3 mm thick complete 90 mm dia The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
28	Providing and fixing vitreous china wash basin No 1002 of 55x40cm (fifty five into forty centimetre) of CERA with double hole for pillar tap with C.I. or M.S. brackets painted white i/c cutting holes and making good the same including fitting (Flat back) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.00	Each				
29	Providing and Fixing Pillar cock F-330002 of HINDWARE 15 mm (Fifteen millimeter) Jaquar or equivalent as per direction complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each				
30	Providing and fixing chromium plated brass soap dish of ESS-ESS / Cera / Hindware with C.P. brass brackets fixed to wooden cleats with C.P. brass screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	2.00	Each				
31	Providing and fixing 600mmx450mm (six hundred millimeter into four hundred fifty millimeter) bevelled edge mirror of superior glass mounted on 6mm (six millimeter) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.00	Each				
32	Providing and fixing brass towel rail of Ess- Ess complete with C.P. brass brackets fixed to wooden plugs with C.P. brass brackets fixed to wooden plugs with C.P. brass 600x20mm (Six hundred into twenty millimetre) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.00	Each				
33	Providing and fixing wall mixture complete for kitchen including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	4.00	Each				
34	Providing and fixing of jet pressure of ESS-ESS / Cera / Hindware for European seat with one meter tube of approved brand and manufacture, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	2.00	Each				
35	Providing and fixing PVC pressure pipe conforming to IS 15450 UV stabilized for inlet and out let water with stand temperature upto 80 degree complete, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	34.00	Rmt				

36	Providing and Fixing Plythine - Aluminium Polythelene (PE-AE-PE) Composite Internal Seal Compression as per IS-15450 Female Thread Connector 1216 x 15 mm the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each				
37	Providing and Fixing Composite End Seal Compression Fitting of approved brand ISI Mark as per IS-15450-2004 for Cold Water Supply Reducer * 1216 as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each				
38	Providing and fixing C.P. brass angle valve 15mm (fifteen millimetre) without Nuts and pipe. including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	3.00	Each				
39	Providing and fixing canealed C.P. stop cock of ESS-ESS / Cera / Hindware 15mm (fifteen millimetre) dia (Heavy duty makes ISI marked No. 8931 & 8934) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	2.00	Each				
40	Providing and fixing 15mm (fifteen millimetres) diameters C.P. brass bib tap of ESS-ESS / Cera / Hindware with capstan head, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.00	Each				
41	Providing and fixing C.P. brass long nose bib cock.F-330011 Jaquar or equivalent single control of approved quality conforming to IS standards. 15 mm (Fifteen millimeter) nominal bore The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each				
42	Providing and fixing G.I hook for water supply pipe The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.00	Each				
43	Providing and fixing S.I cup The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.00	Each				
44	Providing and fixing Exhaust fan complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
45	Providing and fixing Gyser 15 Liter (Fifteen) complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
46	Providing and fixing Door bell complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				

47	Providing and fixing Ceiling Fan complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
48	Providing and fixing electric tube complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each				
49	Providing and fixing G.I Pipe 100 mm for solar light as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	6.00	Rmt				
50	Providing and fixing solar light as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
51	Providing and fixing Socket 16 amp as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each				
52	Providing and fixing Bulb Holder for bulb as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
53	Providing and fixing round sheet PVC board as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	7.00	Each				
54	Providing and fixing switch box seat 4"x 4" as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00	Each				
55	Providing and fixing 6 amp socket as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	4.00	Each				
56	Providing and fixing switch board as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
57	Providing and fixing switch box sheet 10"x12" as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				

58	Providing and fixing switch box sheet 10"x 6" as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00					
59	Providing and fixing Battan for Electric wire as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	6.00					
60	Providing and fixing switch and socket 16 amp as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	2.00					
61	Providing and fixing Electric wire 2.5 mm as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	25.00					
62	Providing and fixing instant Gysar 5 Liter complete in all respect Make Havel or equivalent along with socket ie male or female GI tee , union ,nipple ,hook ,solution tube ,elbow angle coke P V C connection, taplon etc complete in all manner as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00					
63	Providing and fixing brass curtain rail with rollers stop ends and brackets in pelmet instead of wooden curtain rod 25 mm dia and brackets of ply wood (actual length) of rails of be measured. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	6.00					
64	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers HOLLOW TYPE Black or white plastic seat and cover The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00					
65	Providing and fixing Bend Mixer for over head shower The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00					
66	Providing and fixing over head shower with rod The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00					
67	Providing and fixing 10 (ten) litres net capacity PITMT Coloured / white automatic flushing cistern with a pair of PVC / C.I. or M.S. bracket complete with fittings including PVC syphonic apparatus, mosquito proof lid, PVC union and coupling for connections with inlet, outlet and over flow pipes including cutting holes and making good the same (over flow pipe to be measured and paid for separately) including all fittings entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00					

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Restoration of Rain Damage on Bir Barot Road km 0/00 to 40/00
(Sh:- C/O Pusta wall at RD 15/090 to 15/106).

Estimate Cost: 4,31,981.00/-
Earnest Money: 8,700.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.24	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone age. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.	69.12	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	21.12	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	24.00	Each			
Total						

Executive Engineer
Bailnath Division
H.P.P.W.D., Bailnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O link road from Village Chaugan to Village Chaugan & Keori Suja Road .

Estimate Cost: 4,98,373.00
Earnest Money: 10,000.00
Time Limit : Two Months

(Sh:-Providing laying Patch work in damaged Reaches)

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing laying spreading and compacting stone aggregate Grading-III to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	13.20	Per Cubic metre			
2	Providing and applying tack coat with Bitument emulsion (RS-I) using emulsion pressure distributor at the rate of 0.225 kg. (zero point two two five kilograms) per/ Square metre on the prepared bituminous cleaned with hydraulic broom as per M.O.R.D. technical specifications section No. 503 as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the government.	1647.33	Per Square metre			
3	Providing laying and rolling by mechanical means of open grades premix carpet of 20mm (twenty millimeter) compacted thickness withness composed of 13.2mm (thirteen decimal two millimeter) and 11.20 (eleven decimal twenty millimetre) aggregate mixed in the ratio 2:1 (two is to one) and @0.27 cum (zero decimal twenty seven cubic metres) mixed with bitumen VG-30 (Thirty) (ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square metre of road surface required line grade and level to serve as wearing course on a previously prepared base, including heating binder and aggregate in plant 30/40 ton capacity per hour transporting mixed material with tippers and laying with pavers finisher to the required grade to be followed by seal coat of type-B and camber and rolling with a three Wheel 80-100 KN static road roller to required level and grade as per MORD technical specifications clause No. 506 and as per directions of Engineer-In-Charge including hauling / carriage of materials to various location through all modes of transportation in all leads, lift and other incidental complete in all respect.	1647.33	Per Square metre			

4	Providing and laying seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 508 premixd with 6.8 kg (six point eight) kilogram VG-30 (Thirty) (ten) bitumen 0.06 (zero point zero six) cubic metre of fine aggregate per 10 sqm (ten square metre) heated in mini hot mix plant and laying of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per direction of Engineer-In-Charge including hauling / carriage of materials to various location through all modes of transportation in all leads, lift and other incidental complete in all respect	1647.33	Per Square metre			
Total						

Executive Engineer
Bajinath Division
H.P.W.D., Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

56

Name of work :- Renovation of Rooms in Govt High School Gunehar (VKV/2023/1305)
(SH:- C/O Civil Work)

Estimate Cost: 1,23,033.00
Earnest Money: 2,500.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.82	Per cubic metre			
2	Half brick masonry in common burnt clay building bricks in Cement Mortar 1:4 (one cement : four sand) Second Class Bricks The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.25	Sqm			
3	Providing and fixing angle iron door, window, clerestory window frame manufactured from M.S.Angle iron section of 40X40X5 mm ,thickness including hinges jamb,lock jamb,beed and if required angle threshold of mild steel angle 40X25 mm welded or rigidly fixed by mechanical means,lugs with split end tails to each jamb including steel butt hinges 2.5 mm thick with provision for locking arrangement and shock observer as specified and applying a coat of approved steel primer after pretreatment of the surface including The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	49.00	Per running metre			
4	20mm (Twenty millimeter) thick cement plaster in single coat on the fair side of brick/concrete/stone walls for interior plastering upto any floor level including artises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeters) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.82	Per square metre			

5	15mm (fifteen millimeter) Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arisies, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeter) in girth and finished even and smooth Cement Mortar 1:6 (one Cement:six Sand) . . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.82	Per square metre			
6	Providing and fixing 40 mm (Forty millimetre) flush doors, shutters including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	2.15	Per square metre			
7	Providing and fixing 40 mm (Forty millimetre) thick panelled glazed or panelled and glazed shutter second class teak wood for doors, windows and clear story windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.47	Per Square Metre			
8	Providing and fixing 40 mm (Forty millimetre) thick second class teak wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clearstory windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.70	Per square metre			
9	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	108.30	kg			
10	Providing and fixing 300x16mm (three hundred by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			

11	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150 mm The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each				
12	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm (One Hundred millimetre) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	10.00	Each				
13	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x10mm (Two hundred fifty into ten millimeter) size. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each				
14	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Each				
15	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface Water thinnable cement primer The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	29.64	Sqm				
16	Wall painting with acrylic exterior emulsion paint of approved brand and manufacture to give an even shade as per entire satisfaction and direction of Engineer - in - Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	75.45	Sqm				

Executive Engineer
Bajnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Construction of Padhiar Khar Jandpur Trehal Road km 0/00 to 4/000
(SH:- Construction of 1.00 mtr span RCC slab culvert at RD 3/105)

Estimate Cost: 1,94,622.00
Earnest Money: 3,900.00
Time Limit : Two Month

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.(Ordinary rock and hard rock) as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	21.20	Cum			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (P.C.C M-10-1:3:6 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.25	Cum			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.49	Cum			
4	Providing concrete for plain/reinforced concrete bedding complete as per drawings and technical specifications Clause 1303 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.93	Cum			

66

(66)

5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.84	Cum				
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.69	Cum				
7	Supplying, fitting, and placing HYSD bar reinforcement in sub structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	84.00	Kg				
8	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	230.00	Kg				
9	Demolishing stone rubble masonry by mechanical means including stacking of serviceable material recovery of 70% useful stone 9.17 @ 500 cum = 4585 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.10	Cum				

Executive Engineer
Bajinath Division
H.P.W.D., Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

(7) (a)

Name of work :- C/O Civil Hospital Chadhar
(SH:- P/F 2 No. Gate P/F door & Collapsible shutter etc

Estimate Cost: 1,45,650.00
Earnest Money: 3,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.92	Per Cum			
2 .a	Centering and shuttering including strutting, propping etc.code no. 5.9.1 Foundations footing bases of column etc for mass concrete The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	7.20	sqm			
2 .b	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	11.52	sqm			
3 .a	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) in foundation Footings and Basis of columns The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.72	Per cubic metre			
3 .b	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth foundations, footings, bases for columns level :1:2:4 (One Cement : Two coarse sand) : Four graded stone aggregate 20 mm (twenty millimeter) nominal size The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.62	Per cubic metre			

4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	334.00	P/kg				
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	313.20	Per Kilogram				
6	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, (Thirty five into Thirty Five into five) joints mitred and welded by angle iron 35x35x5 mm (Thirty five into Thirty Five into five) or 35x 5 mm (Thirty five into five) flat pieces to the existing T iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	27.60	Per Kilogram				
7	24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59x24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 20x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x24 mm and 2 mm (± 0.2 mm) wall thickness, fixed to the shutter styles by means of plastic/galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge. (For W.C. and bathroom door shutter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	4.20	Sqm				
8	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	4.95	sqm				

DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of work :- C/O Barot Nalhota Road km 0/00 to 15/500.
(Sh:-Laying G-II, Prime coat, Tack Coat and Bituminous Concrete (25 mm thick) on Portion from Nalhota to Baragran at RD 15/370 to 15/435)

Estimate Cost: 92,127.00
Earnest Money: 1,900.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Laying, spreading and compacting stone aggregates size 63mm to 45 mm (Sixty three millimeter to forty five millimeter) grading-II(75 mm Consolidated compacted thickness withness) to water bound macadam specification including spreading in uniform compacted thickness withness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming. Crushable type such as Moorum or Gravel for grading II & III @ 0.22 cum (zero point two two cubic meter) per ten square meter and binding material at the rate of 0.06 cum (Zero point zero Six Cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD technical specification clause no 405 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the government.	15.61	Per Cubic metre			
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero point eight five Kilogram) per Square metres using mechanical means as per MORD technical specification clause 502, and as per directions of Engineer - in- Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	208.16	Per Square metre			
3	Providing and applying tack coat with Bitumen emulsion using (RS-I) emulsion pressure distributor at the rate of 0.275 kg (at rate of zero point two seven five kilogram) per Square metre on the prepared bituminous surface and cleaned with hydraulic broom as per M.O.R.D. technical specifications section No. 503. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	208.16	Per Square metre			
4	Providing and laying 25 mm (twenty five millimeter) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 (Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects as per the direction and entire satisfaction of Engineer-In Charge. The rate is inclusive all taxes levy by the government time to time excluding G.S.T.	5.20	Per Cubic Meter			

Executive Engineer
Railhead Division
H.P.P.W.D., Baijnath