

HPPWD NOTICE INVITING TENDER BHARWAIN DIVISION HPPWD BHARWAIN TEHSIL AMB DISTRICT UNA (H.P).
Phone No. 01976-255822, Web :- www. hppwd.gov.in & email address ee-bharw-hp@nic.in.

Sealed tenders on item rates basis are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer Bharwain Division, HPPWD, Bharwain Tehsil Amb District Una (HP) from the experienced contractors/ firms enlisted in appropriate class with Himachal Pradesh PWD for the following works. The tender shall be received in his office on or before 06-11.2024 up to 10.30 A.M and shall be opened on the same day at 11.00 A. M in the presence of contractors / firms or their authorized representatives, who wish to be present at the time of opening of tenders. The tender applications shall be entertained and tender form shall be sold up to two days before the date of opening of tender i.e 04.11.2024 up to 12.00 Noon. Draft Notice Inviting Tenders/ Drawing/ Specifications can be seen in the office of the Executive Engineer on any working day between 11.00 A. M to 4.00P. M. Ambiguous / Telegraphic / Conditional tenders or tender by Fax shall not be entertained/ considered in any case. The earnest money in the shape of National Saving Certificate / Time Deposit Account / FDR in any of the Post Office in H.P./ Nationalized Bank duly pledged in favour of Executive Engineer must be accompanied with the application. Conditional tenders and the tenders received without earnest money will out rightly be rejected. The contractor shall accompany his enlistment/ renewal orders with his application for obtaining the tender documents. The Executive Engineer reserves the right to reject the tender without assigning any reasons. The work will be completed by the contractor within the stipulated period. The contractor will have to submit his registration under the H. P General Sale Tax Act 1968 and also labour license under contract Act 1970 from the competent authority. The contractors/ firms are requested to insert the rate of each item in words as well as figures, failing which XEN reserves the right to accept/ reject any or overall tenders. The tender shall only be issued to those contractors/ firms, who are found eligible/ suitable and competent as per the above conditions. The offer shall remain valid up to 45 days after the opening of tender. If any of the date mentioned above happens to be Local / Gazetted Holidays the same shall be process on next date. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No	Name of work.	Estimated cost.	Earnest Money	Time Limit	Form No.	Cost of Form
1	Restoration of damages due to laying of pipe on Jijjar to Sarda (Aranwal) km. 0/0 to 5/800 (SH:-Repair of pot holes between 0/0 to 3/800) against IPH deposit	485990/-	10000/-	Three month	PWD-8	350/-
2.	Restoration of damages due to laying of pipe on Repoh Majhar Suri Paloh road Km. 0/0 to 15/500 (SH:- Repair of pot holes between Km. 0/0 to 8/0) against IPH deposit	495183/-	10000/-	Three Months	PWD-8	350/-
3.	Restoration of rain damages link road NMT to Dhandari km. 0/0 to 4/800 & link road Ambotu to Dhar Gujran km. 0/ to 6/0 (SH:- Dressing of berms, cleaning of drains & maintenance of earthen shoulder)	499460/-	10000/-	Three Months	PWD-8	350/-
4.	Restoration of rain damages link road Jole to Khurwain km. 0/0 to 8/00 (SH:- Dressing of berms, cleaning of drains & maintenance of earthen shoulder)	499530/-	10000/-	Three months	PWD-8	350/-
5.	C/O Link road to village Santoo Tila Km. 0/0 to 2/220 (SH:- C/O Retaining wall at RD 1/505 to 1/515 RHS & C/O U/V Shape drain at RD 1/340 to 1/400) against MNP	472552/-	9500/-	Three months	PWD-8	350/-

1. The Xen reserve the right to accept or reject the tender with assigning any reason.
2. The tender forms will not be issued to those contractors whose performance is not founds satisfactory.
3. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should accompany with application.
4. Certificate: - Certificate that the tender have been invited in exigencies/emergency of work.

Executive Engineer.
Bharwain Division.
HPPWD, Bharwain.


No. PWB/CBTA/Tender/2024- **7242-62** Dated **28-10-2024**
Copy forwarded to the following for information and necessary action, please.

- 1 The Engineer in Chief, HPPWD, Shimla for information.
- 2 The Chief Engineer, (HZ) HPPWD, Hamirpur.
- 3 The Superintending Engineer, 15th Circle, HPPWD, Una.
- 4 All the contractor working under this Division.
- 5 Drawing Branch in this office.
- 6 All the Assistant Engineer, working under this Division.
- 7 Notice Board.


Executive Engineer.
Bharwain Division.
HPPWD, Bharwain.

Certificate

Certified that the works are of urgent in nature and for large public Interest, so there are exigencies /emergency in calling these without press vide this office letter No PWB/CB/TA-1/ Tender/2024:- 7242-62 dated 28/10/2024


Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Schedule of Quantity

Estimated Cost:- 485990/-
Earnest Money:- 10000/-
Time:- Three months

Name of Work:-Restoration of damages due to laying of pipe on Jijjar to Sarda (Aranwal) km. 0/0 to 5/800 (SH:-Repair of pot holes between 0/0 to 3/800) against IPH deposit

Sr.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	48.49	Cum	1650.00	Rs. one thousand six hundred fifty paise zero only	Per Square metre	80009
2	Providing and applying primer coat with RS-1 setting bitumen emulsion W.B.M / WMM @ 0.4 Kg Per Sqm (at the rate of zero point four kilogram per Square metre) using bitumen emulsion conforming to IS: 8887 , using emulsion pressure distributor i/c the preparing the surface and cleaning with mechanical broom and direction of Engineer- in -Charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	548.25	Square metre	30.00	Rs. thirty and paise zero only	Per Square metre	16448
3	Repair of pot holes and removal of loose material , trimming of sides , cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre, 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	1320.45	Square metre	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	389533
Total							485990
Percentage rate (Above or Below)							

Executive Engineer
Bharwain Division
JPPWD Bharwain

Schedule of Quantity

Estimated Cost:- 495183/-
Earnest Money:- 10000/-
Time:- Three months

Name of Work:- Restoration of damages due to laying of pipe on Repoh Majhar road Km. 0/0 to 15/500 (SH:- Repair of pot holes between Km. 0/0 to 8/0) against IPH deposit

Sr.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words			
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	50.52	Cum	1650.00	Rs.one thousand six hundred fifty paise zero only	Per Cubic metre	83358
2	Providing and applying primer coat with RS-1 setting bitumen emulsion W.B.M / WMM @ 0.4 Kg Per Sqm (at the rate of zero point four kilogram per Square metre) using bitumen emulsion conforming to IS: 8887 , using emulsion pressure distributor i/c the preparing the surface and cleaning with machanical broom and direction of Engineer- in -Charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	548.25	Square metre	30.00	Rs.thirty and paise zero only	Per Square metre	16448
3	Repair of pot holes and removal of loose material , trimming of sides , cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre, 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	1340.26	Square metre	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	395377
	Total						495183
	Percentage rate (Above or Below)						

Executive Engineer
Bharwan Division
JIPPWD Bharwan

Schedule of Quantity


Estimated Cost:- 499460/-

Earnest Money:- 10000/-

Time:- Three months

Name of Work:- Restoration of rain damages link road NMT to Dhandari km. 0/0 to 4/800 & link road Ambotu to Dhar Gujran km. 0/ to 6/0 (SH:- Dressing of berms, cleaning of drains & maintenance of earthen shoulder)

Sr.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words			
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 .as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	8768.00	Square metre	Rs. Fifteen and paise zero only	Per Square metre	131520	
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift .as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3250.00	Running metre	Rs.thirty eight and paise zero only	Per running metre	123500	
3	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000m as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6111.00	Square metre	Rs. Forty and paise zero only	Per Square metre	244440	
	Percentage Rate (Above or Below)						
	Total						499460


 Executive Engineer
 Bharwain Division
 HPPWD Bharwain

Schedule of Quantity

Estimated Cost:- 499530/-
Earnest Money:- 10000/-
Time:- Three months

Name of Work:- Restoration of rain damages link road Jole to Khurwain km. 0/0 to 8/00 (SH:- Dressing of berms, cleaning of drains & maintenance of earthen shoulder)

Sr.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words			
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification clause 1903 .as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	8770.00	Square metre	Rs. Fifteen and paise zero only	Per Square metre	131550	
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift .as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3250.00	Running metre	Rs.thirty eight and paise zero only	Per running metre	123500	
3	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000m as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6112.00	Square metre	Rs. Forty and paise zero only	Per Square metre	244480	
	Total						499530
Percentage Rate (Above or Below)							

Executive Engineer
Bharwain Division
HPPWD Bharwain

Schedule of Quantity

Estimated Cost:- 472552/-
Earnest Money:-9500/-
Time:- Three months

Name of Work:-C/O Link road to village Santoo Tila Km. 0/0 to 2/220 (SH:- C/O Retaining wall at RD 1/505 to 1/515 RHS & C/O U/V Shape drain at RD 1/340 to 1/400)

Sr.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals.The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	31.40	Cum	180.00	Rs. One hundred eighty and paise zero only	Per cubic metre	5652
2	Providing and laying in position cement concrete 1:3:6 (one cement three sand: six graded/crushed stone aggregate 20mm (twenty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centring and shuttering in foundation and plinth level as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals.The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	45.50	Cum	4000.00	Rs. Four thousand and paise zero only	Per cubic metre	182000
3	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	73.70	Cum	3600.00	Rs. Three thousand six hundred and paise zero only	Per cubic metre	265320
4	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals.The rate includes octroi , royalty , Malkhana , toll tax,	34.40	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	8600

Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.300	Cum	600.00	Rs. Six hundred and paise zero only	Per cubic metre	10980
Total						472552
Percentage rate (Above or Below)						


 Executive Engineer
 Bharwain Division
 HPPWD Bharwain