

**Himachal Pradesh  
Public Works Department**

**Registered**

NO:- PW-DKD-N.I.T/2024-25 / 10/6

Dated:- 07/11/2024

To

**The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.**

Subject:-


**Publication of Tender notice.**

**Jai Haind**

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. Of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup>. July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & Sechedule of Quantity.

  
**Executive Engineer,  
B&R Division HP.PWD,  
Dodra Kwar**

# HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

## NOTICE INVITING TENDER

Sealed Percentage rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer B&R Division HP.PWD, Rohru Distt Shimla(HP) on behalf of the Governor of H.P for the following works from registered contractors in HPPWD (B&R) in appropriate class so as to reach in this office on **18 /11/2024** up to **10:30 AM** and will be opened on the same day at **11:00 AM** in the presence of contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **16/11/2024 between 10:00 AM to 2 :00 PM** The tender form can be had from this office against cash payment (Non-refundable) on **16/11/2024 between 02:00 PM to 5:00PM**.

**The Earnest money in the shape of NSC/FDR/Saving account of the Post office bank in H.P duly pledged in favour of the XEN must accompany with each tender condition/incomplete tenders & tender without earnest money will be similarly rejected .The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reason.**

Sr. No.	Name of Work	Estimated Cost	EMD (Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1.	C/o Shiladesh to Thalather road km 0/00 to 2/500(SH:- C/o R/wall in PCC 1:3:6 at Rd 0/136.10 to 0/146.10)	491268/-	9825/-	350/-	Two Months	Calss "C&D"
2.	R/R Damage to RCD road under Larot Sub Division (SH:- Hiring of Tipper for carriage of muck on RCD road km 21/195 to 49/500 and other various link roads)	490000/-	9800/-	350/-	Two Months	Calss "C&D"
3.	R/R Damage to RCD road under Larot Sub Division (SH:- Hiring of Tipper for carriage of muck on RCD road km 21/195 to 49/500 and other various link roads)	490000/-	9800/-	350/-	Two Months	Calss "C&D"
4.	R/R Damage to RCD road km 0/00 to 92/695(SH:- Hiring of JCB Excavator cum Loader for removal of slips C/o katcha drain and repair of shoulders etc under Larot Section of Larot Sub Division km 21/195 to 49/500)	475000/-	9500/-	350/-	Two Months	Calss "C&D"
5.	R/R Damage to RCD road km 0/00 to 92/695(SH:- Hiring of JCB removal of slips and maintenance of road km 21/195 to 51/00)	475000/-	9500/-	350/-	Two Months	Calss "C&D"
6.	R/R Damage to RCD road km 0/00 to 92/695(SH:-Hiring of JCB Excavator cum Loader for removal of slips,C/ katcha drain and repair of shoulders etc under larot Section Sub Division km)	472500/-	9828/-	350/-	Two Months	Calss "C&D"
7.	R/R Damage to RCD road km 0/00 to 92/695(SH:-Hiring of JCB Excavator cum Loader for removal of slips,C/ katcha drain and repair of shoulders etc under larot Section Sub	480000/-	9600/-	350/-	Two Months	Calss "C&D"



	Division km 30/00 to 49/500 and other link roads)					
8.	R/R Damage to RCD road under Larot Sub Division(SH:- Hiring of Tipper for carriage of muck on RCD road km 30/00 to 49/500 and other various link roads)	497000/-	9940/-	350/-	Two Months	Calss "C&D"
9.	R/R Damage to RCD road km 0/00 to 92/695(SH:-Hiring of JCB Excavator cum Loader for removal of slips,C/ katcha drain and repair of shoulders etc under larot Section Sub Division km 21/195 to 49/500 and other link roads)	468750/-	9375/-	350/-	Two Months	Calss "C&D"
10.	R/R Damage to RCD road km0/00 to 92/695(SH:- C/o R/wall in R/R masonry at RD 24/379 to 24/388.30)	494691/-	9894/-	350/-	Two Months	Calss "C&D"
11.	R/R Damage to RCD road km0/00 to 92/695(SH:- C/o R/wall in R/R masonry at RD 24/388.3 to 24/397.20)	489457/-	9789/-	350/-	Two Months	Calss "C&D"
12.	R/R Damage RCD road km 0/00 to 92/695 (SH:- Hiring of JCb removal of slips and maintenance of road km 51/00 to 71/750 and various road)	490000/-	9800/-	350/-	Two Months	Calss "C&D"
13.	R/R Damage RCD road km 0/00 to 92/695 (SH:- Hiring of JCb removal of slips and maintenance of road km 71/750 to 92/695and various road)	481250/-	9625/-	350/-	Two Months	Calss "C&D"
14.	A/R & M/O RCD road km 0/00 to 92/965 (SH:- Hiring of JCB removal of slips and maintenance of road km 71/750 to 92/695 and other link roads)	490000/-	9800/-	350/-	Two Months	Calss "C&D"
15.	R/R Damage to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)	480000/-	9600/-	350/-	Two Months	Calss "C&D"
16.	A/R & M/O link road to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)	480000/-	9600/-	350/-	Two Months	Calss "C&D"
17.	R/R Damage to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of Pock lane for breaking of boulders & removal of slips RD 0/00 to 8/00)	494000/-	9880/-	350/-	Two Months	Calss "C&D"
18.	A/R & M/O link road to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of Pock Tipper for carriage of muck/stone km 0/00 to 8/00 and other various roads under Kawar sub division)	420000/-	8400/-	350/-	Two Months	Calss "C&D"
19.	A/R & M/O link road to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of Pock Tipper for carriage of muck/stone km 0/00 to 8/00 and other various roads under Kawar sub division)	420000/-	8400/-	350/-	Two Months	Calss "C&D"
20.	R/R Damage to RCD road km 0/00 to 92/695(SH:- (SH:- Hiring of Pock Tipper for carriage of muck/stone km 71/750 to 92/695 and other various road under Kawar Sub Division)	420000/-	8400/-	350/-	Two Months	Calss "C&D"
21.	R/R Damage to link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of Tractor for carriage of muck/stone in km 0/00 to 8/00 and other link road)	493000/-	9860/-	350/-	Two Months	Calss "C&D"
22.	A/R & M/o RCD road km 0/00 to 92/695 (SH:- Hiring of JCB removal of slips and maintenance of road km 51/00 to 71/750 and other link roads)	481250/-	9625/-	350/-	Two Months	Calss "C&D"
23.	R/R Damage to Link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of JCB removal of slips and maintenance of roads)	487500/-	9750/-	350/-	Two Months	Calss "C&D"
24.	R/R Damage to RCD road km 0/00 to 92/965 (SH:-Hiring Tipper for carriage of muck/stone km 71/750 to 92/695 and other various roads)	490000/-	9800/-	350/-	Three Months	Calss "C&D"
25.	Construction of 57.92 mtr. Span Steel truss Bridge over Shelwaan Khad to connect the Pandar Village.	495000/-	9900/-	350/-	One Months	Calss "C&D"



	Preparation of Detailed Project Report of various roads under Dodrakawar Division :- 1. C/o Link Road From Sharidhar to dhaniya dhol. Km 0/00 to 1/850. 2. C/o Link Road From Khaneti Kenchi to Kiterwari. Km 0/00 to 2/100. 3. C/o Link Road From Gumma to Kharshali. Km 0/00 to 2/730. 4. C/o Link Road From Kharshali to Bangsar. km 0/00 to 2/100. 5. C/o Link Road from Sr. Sec . Kawar To Paatiun ke Devta Bagicha. Km 0/00 to 2/000.	499800/-	9996/-	350/-	Two Months	Calss "C&D"
27.	Balance work C/o Rest House Building at Kawar tehsil Dodra kawar Distt Shimla(SH:- C/o Form Work)	497701/-	9954/-	350/-	Two Months	Calss "C&D"
28.	Balance work C/o Rest House Building at Kawar tehsil Dodra Kawar Distt Shimla(SH:- P/L RCC 1:1.5:3 for slab)	499733/-	9995/-	350/-	Two Months	Calss "C&D"
29.	Balance work C/o Rest House Building at Kawar tehsil Dodra Kawar Distt Shimla(SH:- P/L RCC 1:1.5:3 for slab)	499733/-	9995/-	350/-	Two Months	Calss "C&D"
30.	Balance work C/o Rest House Building at Kawar tehsil Dodra Kawar Distt Shimla(SH:- P/L Steel work)	499950/-	9999/-	350/-	Two Months	Calss "C&D"
31.	C/o Govt Sr.Sec School Kawar (C/o Steel work for porch in GSS School at Kawar)	483435/-	9669/-	350/-	Two Months	Calss "C&D"
32.	A/R & M/O link road village Jiskoon km 0/00 to 8/00(SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)	480000/-	9600/-	350/-	Two Months	Calss "C&D"
33.	C/o link road from jarkot to Jilari Dangrighad road 0/00 to 3/500(SH:-Providing and laying Kharanja stone soling in essential reaches at RD 0/480 to 0/720)	481047/-	9621/-	350/-	Two Months	Calss "C&D"

**Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest**

**TERMS AND CONDITIONS:-**1. The Earnest money for the above works should be submitted with the application for the application for the purchase of the tender-documents.

2. The intending contractor/firm have to produce the DAC & copy of latest enlistment and renewal enlisted in HP.PWD.
3. The Contractors should quoted the rates of the items in the tenders both in figures and words.
4. The Contractors should apply for two works only at a time for tenders.
5. Work should be completed by the contractor within stipulated period.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

*[Signature]*  
Executive Engineer  
B&R Division HP.PWD,  
Dodra Kawar

Dated 07/11/2024

NO:- PW-RD-CB-Tender/2024-25 :- / 1017-25  
Copy forwarded for information and wide publicity to:-  
7. The Chief Engineer (S) HPPWD Shimla-2

8. The S.E 14<sup>th</sup> Circle HPPWD Rohru
9. All the EE's under 14<sup>th</sup> Circle HPPWD Rohru
10. All the A.E's working under this Division (B&R)
11. The Sub Divisional Magistrate ROHRU
12. The BDO Rohru.
18. The Naib tehsildhar Dodra Kaware
19. A/B and D/B in this office
20. Notice Board

  
Executive Engineer  
B&R Division HP.PWD,  
Dodra kaware

SCHEDULE OF QUANTITY						Job no. 1
						ESTIMATED COST :- 491268
						EARNEST MONEY:- 9825
						TIME:- Two months.
Name of work:- C/O Shiladesh to Thalathar Road km 0/00 to 2/500.						
SH:- C/O R/Wall in PCC 1:3:6 at RD 0/136.10 to 0/146.10 )						
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Change	18.23	410.00	Rupees Four Hundred & Ten Only	Cum	7474
2	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Change	65.56	7010.00	Rupees Seven Thousand & Ten Only	Cum	459576
3	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Change	10.80	1335.00	Rupees One Thousand Three Hundred & Thirty Five Only	Cum	14418
4	Providing weephole in brick masonry /stone masonry ,plain/ rainforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3.7.as directed by the Engineer-in-Change	28.00	350.00	Rupees Three Hundred & Fifty Only	Each	9800
	<b>Total</b>					<b>491268</b>
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

Conditions:-

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

  
 Executive Engineer  
 B&R Division  
 HP.PWD Dodra Kavar.



JOB NO:-

2

Name of Work :- R/R Damage to RCD road under Larot Sub Division(SH:- Hiring of Tipper for carriage of muck on RCD road km 21/195 to 51/00 and other various link road)

## Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		
				Rate		
				In Fig.	In Words	Amount.
				5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	70	Per Day	7000	Seven thousand only	490000
	Total					490000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

JOB NO:-

3

Name of Work :- R/R Damage to RCD road under Larot Sub Division(SH:- Hiring of Tipper for carriage of muck on RCD road km 21/195 to 51/00 and other various link road)

## Schedule of Qty

				ESTIMATED COST		490000
				EARNEST MONEY		9800
				TIME LIMIT:		Three month
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	70	Per Day	7000	Seven thousand only	490000
Total						490000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar



JOB NO:-

4

Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of JCB Excavator-Cum-Loader for removal of slips, C/o Katcha drain and repair of shoulders etc. under larot Section of larot Sub Division km 21/195 to 49/500)

Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST	475000	
				EARNEST MONEY	9500	
1	2	3	4	TIME LIMIT:	Two Month	
				Rate	In Words	Amount.
				In Fig.		
				5	6	7
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	380	Per Hours	1250	One thousand One hundred only	475000
Total						475000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/ - )

Quoted rate Words ( +/ - )

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra kwar

JOB NO:-

5

Name of Work :- R/R Damage RCD road km 0/00 to 92/695(SH:- Hiring of JCB removal of slips and maintenance of road km 21/195 to 51/00)

Schedule of Qty

ESTIMATED COST		475000
EARNEST MONEY		9500
TIME LIMIT:		Two Month
Rate		
In Fig.	In Words	Amount.
5	6	7
1250	Rupees One Thousand Two Hundred & Fifty Only	475000
		475000

Sr. No	Description of items.	Qty	Unit
1	2	3	4
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	380	Per Hour
	Total		

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)
Quoted rate Words ( +/-)
Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

Name of Work:-R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of JCB Excavator-Cum-Loader for removal of slips, C/o Katcha drain and repair of shoulders etc. under larot Section of larot Sub Division km )					Schedule of Qty		JOB NO:- 6	
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST	EARNEST MONEY	TIME LIMIT:		
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	378	Per Hours	1250	One thousand One hundred only	472500	9450	Two Month
	Total							

1 The rates Should be quoted for all heights including all lead and lifts.


The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra kwar



JOB NO:- 7

Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of JCB Excavator-Cum-Loader for removal of slips, C/o Katcha drain and repair of shoulders etc. under larot Section of larot Sub Division km 30/00 to 49/500 and other link roads)

## Schedule of Qty


Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		
				Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	384	Per Hours	1250	One thousand One hundred only	480000
Total						480000

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra kwar

JOB NO:- 3

Name of Work :- R/R Damage to RCD road under Larot Sub Division (SH:- Hiring of Tipper for carriage of muck on RCD road km 30/00 to 49/500 and other various link road)				Schedule of Qty		
				ESTIMATED COST		497000
				EARNEST MONEY		9940
				TIME LIMIT:		Three month
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	71	Per Day	7000	Seven thousand only	497000
Total						497000

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

Name of Work:- R/R Damage to RCD road km 0/00 to 92/695 (SH:- Hiring of JCB Excavator-Cum-Loader for removal of slips, C/o Katcha drain and repair of shoulders etc. under larot Section of larot Sub Division km 21/195 to 49/500 and other link roads)

JOB NO:-

9

Schedule of Qty


Schedule of Qty						ESTIMATED COST		468750		
						EARNEST MONEY		9375		
						TIME LIMIT:		Two Month		
Description of items.						Qty	Unit	Rate	In Words	Amount.
1						3	4	5	6	7
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.					375	Per Hours	1250	One thousand One hundred only	468750
Total										468750

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra kwar



SCHEDULE OF QUANTITY						Job no. 10
Name of work:- R/R Damages to RCD road km 0/00 to 92/695 (SH:- C/O R/Wall in RR Masonary at RD 24/379 to 24/388.30)						ESTIMATED COST :- 494691
						EARNEST MONEY:- 9894
						TIME:- Two months.
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	24.18	320.00	Rupees Three Hundred & Twenty Only	Per cum	7738
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as	19.34	410.00	Rupees Four Hundred & Ten Only	Per cum	7929
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.58	5800.00	Rupees Five Thousand Eight Hundred Only	Per cum	32364
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	1.30	6700.00	Rupees Six Thousand Seven Hundred Only	Per cum	8710
5	Stone masonry in cement mortar 1:6 (1Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	74.03	5700.00	Rupees Five Thousand Seven Hundred Only	Per cum	421971

6	Providing weephole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3.7 as directed by the Engineer-in-Charge	18.00	350.00	Rupees Three Hundred & Fifty Only	Each	6300
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	7.25	1335.00	Rupees One Thousand Three Hundred & Thirty Five Only	Per cum	9679
	<b>Total</b>					<b>494691</b>
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

**Conditions:-**

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

  
 Executive Engineer  
 B&R Division  
 HP.PWD Dodra Kwar.

SCHEDULE OF QUANTITY						Job no. 11
Name of work:- R/R Damages to RCD road km 0/00 to 92/695 (SH:- C/O R/Wall in RR Masonary at RD 24/388.30 to 24/397.20)						ESTIMATED COST :- 489457
						EARNEST MONEY:- 9789
						TIME:- Two months.
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	23.92	320.00	Rupees Three Hundred & Twenty Only	Per cum	7654
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as	19.14	410.00	Rupees Four Hundred & Ten Only	Per cum	7847
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.52	5800.00	Rupees Five Thousand Eight Hundred Only	Per cum	32016
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	1.29	6700.00	Rupees Six Thousand Seven Hundred Only	Per cum	8643
5	Stone masonry in cement mortar 1:6 (1Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	73.23	5700.00	Rupees Five Thousand Seven Hundred Only	Per cum	417411



6	Providing weephole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3.7. as directed by the Engineer-in-Charge	18.00	350.00	Rupees Three Hundred & Fifty Only	Each	6300
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	7.18	1335.00	Rupees One Thousand Three Hundred & Thirty Five Only	Per cum	9585
	<b>Total</b>					<b>489457</b>
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

**Conditions:-**

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

  
 Executive Engineer  
 B&R Division  
 HP.PWD Dodra Kwar.

JOB NO:-

12

## Schedule of Qty

Name of Work :- R/r Damage RCD road km 0/00 to 92/695(SH:- Hiring of JCB removal of slips and maintenance of road km 51/00 to 71/750 and other various link roads)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		
1				Rate		
				In Fig.	In Words	Amount.
		3	4	5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	392	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only	490000
	Total					490000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

JOB NO:-

13

Name of Work :- R/R Damage RCD road km 0/00 to 92/695 (SH:- Hiring of JCB removal of slips and maintenance of road km 71/750 to 92/695)

## Schedule of Qty

				ESTIMATED COST		481250
				EARNEST MONEY		9625
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate		
				In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	385	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only	481250
Total						481250

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar



JOB NO:-

14

Name of Work:-A/r & M/O RCD road km 0/00 to 92/695 (SH:- Hiring of JCB Excavator-Cum-Loader for removal of slips, and maintenance of road surface km 71/750 to 92/695 and other various road)

## Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNST MONEY		
				TIME LIMIT:		
1	2	3	4	Rate In Fig.	In Words	Amount.
				5	6	7
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	392	Per Hours	1250	One thousand One hundred only	490000
Total						490000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra kwar

Name of Work :- R/r Damage to Link road village Jiskoon km 0/00 to 8/00 (SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)				JOB NO:- 15	
Schedule of Qty				ESTIMATED COST	
				EARNEST MONEY	
				TIME LIMIT:	
				Two Month	
Sr. No	Description of items.	Qty	Unit	Rate	
				In Fig.	In Words
1	2	3	4	5	6
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	384	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only
Total					480000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

JOB NO:-

16

Name of Work :- A/r & M/O Link road village Jiskoon km 0/00 to 8/00 (SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)

## Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		
1	2	3	4	Rate In Fig.	In Words	Amount.
				5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	384	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only	480000
Total						480000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar



Name of Work :- R/R Damage to link road village Jiskoon km 0/00 to 8/00 (SH:- Hiring of Pock lane for breaking of boulders & removal of slips RD 0/00 to 8/00)		Schedule of Qty		ESTIMATED COST		494000
				EARNEST MONEY		9880
				TIME LIMIT:		Two Months
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	In Fig.	6	7
1	Hiring of Excavator-Cum-Loader (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kmgs with rock breaker including P.O.L charge, shifting charges and other ancillary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rock etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the accquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standred width formation width 5 meters in straight and 7 meter in curve as per their radius. Minimum 40cm of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer-In Charge including all leads and lifts. with rock breaker.	130	Per Hours	3800	Rupees Three Thousand Eight Hundred Only	494000
Total						494000

JOB NO:- 17

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HEPWD  
Dodra Kwar

JOB NO:-

18

## Schedule of Qty

Name of Work :- A/r & M/o Link road to village Jiskoon km 0/00 to 8/00 (SH:- Hiring of Tipper for carriage of muck/stone km 0/00 to 8/00 and other various road under Kawar sub Division)

ESTIMATED COST	420000
EARNEST MONEY	8400
TIME LIMIT:	Two month
Rate	
In Fig.	In Words
5	6
7000	Seven thousand only
	Amount.
	7
	420000
	420000

Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	60	Per Day	7000	Seven thousand only	420000
	Total					420000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/- )

Quoted rate Words ( +/- )

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

JOB NO:-

19

Schedule of Qty						
Name of Work :- A/r & M/o Link road to village Jiskoon km 0/00 to 8/00(SH:- Hiring of Tipper for carriage of muck/stone km 0/00 to 8/00 and other various road under Kavar sub Division)				ESTIMATED COST		420000
				EARNEST MONEY		8400
				TIME LIMIT:		Two month
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	60	Per Day	7000	Seven thousand only	420000
Total						420000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kavar



JOB NO:- 20

Schedule of Qty						
Name of Work :- R/R Damage to RCD road km 0/00 to 92/695(SH:- Hiring of Tipper for carriage of muck/stone km 71/750 to 92/695 and other various road under Kavar sub Division)				ESTIMATED COST		420000
				EARNEST MONEY		8400
				TIME LIMIT:		Two month
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	60	Per Day	7000	Seven thousand only	420000
Total						420000

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)
Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kavar

JOB NO:-

21

Schedule of Qty						
Name of Work :-R/R Damage to link road village Jiskoon km 0/00 to 8/00( Sh:- Hiring of Tractor for carriage of muck/stone in km 0/00 to 8/00 and other link roads)				ESTIMATED COST		493000
				EARNEST MONEY		9860
				TIME LIMIT:		Five Month
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of Tractor for carriage of material having capacity 90 cft. including P.O.L charge and other ancillary equipments as required at the site as per instructions of the Engineer-in- Charge including all leads and lifts.	145	Per Day	3400	Rupees Three Thousand Four Hundred Only	493000
Total						493000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar

SCHEDULE OF QUANTITY						Job no.22
						ESTIMATED COST :- 481250
						EARNEST MONEY:- 9625
						TIME:- Two months.
Name of work:- A/R & M/O RCD road km 0/00 to 92/695.						
(SH:- Hiring of JCB Excavator cum loader for removal of slips and maintenance of road surface km 51/00 to 71/750 and other various road)						
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Hiring of JCB (Excavator cum loader) front end loader 0.45 cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such as spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this undervicable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quarried stone shall belong to the department and manikurnum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 30.00 cubic metre of earth work shall be done by the machine in one hour and 200 cum of snow shall be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts.	385.00	1250.00	Rupees One Thousand Two Hundred & Fifty Only	Per hours	481250
	<b>Total</b>					<b>481250</b>
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

Conditions:-

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

  
Executive Engineer  
B&R Division  
HP.PWD Dodra Kwar.



JOB NO:- 23

Name of Work :- R/R Damage to Link road road village Jiskoon km 0/00 to 8/00(SH:- Hiring of JCB removal of slips and maintenance of roads)						
Schedule of Qty				ESTIMATED COST		487500
				EARNEST MONEY		9750
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate		
1	2	3	4	In Fig.	In Words	Amount.
				5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other anciliary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	390	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only	487500
	Total					487500

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

24

Schedule of Qty						
Name of Work :- R/R Damage to RCD road km 0/00 to 92/695(SH:- Hiring of Tipper for carriage of muck/stone km 71/750 to 92/695 and other various roads)				ESTIMATED COST		490000
				EARNEST MONEY		9800
				TIME LIMIT:		Three month
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	70	Per Day	7000	Seven thousand only	490000
Total						490000

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/-)
Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

25

## SCHEDULE OF QUANTITY

**NAME OF WORK:-** Construction of 57.92 mtr. Span Steel truss Bridge over Shelwaan Khad to connect the Pandar Village.


**(SH-Geotechnical Investigation)**

**Estimated Cost : Rs** 495000.00

**Earnest Money : Rs** 9900.00

**Time Limit :** One Month

S.No	Description of Item	Quantity		Rate		Unit	Amount
				In fig.	In word		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia(2 no bores of 25.0 m depth each)for investigation of soil rock conditions at site of work . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer-in Charge.	50.00	Running meter	9900.00	Rupees Nine Thousand Nine Hundred only	Per running meter	495000.00
Total Amount in figures:-							495000.00

  
Executive Engineer,  
Dodrakawar Division  
H.P.PWD Dodrakawar



26

SCHEDULE OF QUANTITY						
<b>Name of Work :- Preparation of Detailed Project Report of various roads under Dodrakawar Division :-</b> 1. C/o Link Road From Sharidhar to dhaniya dhol. Km 0/00 to 1/850. 2. C/o Link Road From Khaneti Kenchi to Kiterwari. Km 0/00 to 2/100. 3. C/o Link Road From Gumma to Kharshali. Km 0/00 to 2/730. 4. C/o Link Road From Kharshali to Bangsar. km 0/00 to 2/100. 5. C/o Link Road from Sr. Sec . Kawar To Paatiun ke Devta Bagicha. Km 0/00 to 2/000.				Estimated Cost : Rs 499800.00		
				Earnest Money : Rs 9996.00		
				Time Limit : 30 Days		
S.No	Description of Item	Quantity	Unit	Rate		Amount
				In Fig.	In words	
1	<b>Preparation of Detailed Project Report of which includes following provision as mentioned below :-</b> i) Topography survey by digital total station with two second accuracy showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, school, Habitants villages etc. ii) Draw cross-sections at 15m intervals, L-sections and calculate the quantity of earthwork in standard format of autocad showing all layers of pavement components as applicable. iii) Preparation of survey plan showing all details as per MORD guidelines and specifications. If any correction/amendment will be desired by the office the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respect. After approval of the same from the head office the same should be submitted in three fair copies and soft copy as per the requirement of this office and upto entire satisfaction of Engineer-In-Charge including all type of incidental charges.	10.780	Per Km	37500.00	Rupees Thirty Seven Thousand Five Hundred Only	404250.00
2	CBR test including gain size analysis, atterberbs limit, proctor compaction and CBR value upto the entire satisfaction of Engineer-In-Charge including all type of incidental charges.	21	Per Sample	4550.00	Rupees Four Thousand Five Hundred and Fifty Only	95550.00
Total:-						499800.00

Draft Schedule Quantity Recommended for Approval for Rs \_\_\_\_\_ only.

  
 Executive Engineer,  
 Dodra Kavar Division,  
 H.P.PWD Dodra Kavar

Draft Schedule of Quantity approved for Rs. \_\_\_\_\_ only.

SCHEDULE OF QUANTITY						Job no. 27
						ESTIMATED COST :- 497701
						EARNEST MONEY:- 9954
						TIME:- Two months.
Name of work:- Balance work C/O Rest house Building at Kavar tehsil Dodra Kavar District Shimla H.P (SH:- C/O Form Work)						
(SH:- C/O Form Work)						
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Centering and shuttering including strutting, propping etc. and removal of form work for :Foundations, footings, bases for columns etc. for mass concrete.	3.84	375.00	Rupees Three Hundred & Seventy Five Only	sqm.	1440
2	Centering and shuttering including strutting, propping etc. and removal of form for walls ( any thickness) including attached pilasters, buttersses, plinth and string coueses etc.	234.48	670.00	Rupees Six Hundred & Seventy Only	Sqm.	157102
3	Centering and shuttering including strutting, propping etc. aand removal for form for suspended floor roofs landings balconies and access platform.	179.76	631.00	Rupees Six Hundred & Thirty One Only	Sqm.	113429
4	Centering and shuttering including strutting, propping etc. and removal of form for columns, pillars,piers,aboutments,posts and struts circular.	7.32	544.00	Rupees Five Hundred & Fourty Four Only	Sqm.	3982
5	Centering and shuttering including strutting, propping etc. and removal of form for Lintel,beams,plinth beams,girders,bressumers and cantilevers.	136.09	537.00	Rupees Five Hundred & Thirty Seven Only	Sqm.	73081
6	Centering and shuttering including strutting, propping etc. and removal of form :for stairs, excluding landings) except spiral stair cases.	11.87	654.00	Rupees Six Hundred & Fifty Four Only	Sqm.	7763
7	Centering and shuttering including strutting, propping etc. and removal of form Edgws of slabs and breaks in floors and Walls Under 20cm (twenty centimeter) wide	145.26	229.00	Rupees Two Hundred & Twenty Nine Only	Rmt.	33265
8	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) within all leads, lifta of materials and othrtr incidentals.	4.31	11500.00	Rupees Eleven Thousand Five Hundred Only	cum	49565
9	Reinforced cement concrete work in Colimns pillars, posts and struts etc.	0.45	11500.00	Rupees Eleven Thousand Five Hundred Only	cum	5175

**SCHEDULE OF QUANTITY**

Job no. 28

ESTIMATED COST :-

499733

EARNEST MONEY:-

9995

TIME:-

Two months.

Name of work:- Balance work C/O Rest house Building at Kavar tehsil Dodra Kavar District Shimla H.P

(SH:- P/L RCC 1:1:5:3 ) for slab (job no.2)

Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size).within all leads, lift of materials and othrtr incidentals.	43.46	11500.00	Rupees Eleven Thousand Five Hundred Only	cum	499733
	Total					499733
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

Conditions:-

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

  
Executive Engineer  
B&R Division  
HP.PWD Dodra Kavar.



<b>SCHEDULE OF QUANTITY</b>						Job no. 29
						ESTIMATED COST :- 499733
						EARNEST MONEY:- 9995
						TIME:- Two months.
Name of work:- Balance work C/O Rest house Building at Kavar tehsil Dodra Kavar District Shimla H.P						
(SH:- P/L RCC 1:1.5:3 ) for slab (job no.3)						
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size).within all leads, lift of materials and othrtr incidentals.	43.46	11500.00	Rupees Eleven Thousand Five Hundred Only	cum	499733
	<b>Total</b>					499733
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

Conditions:-


- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

  
 Executive Engineer  
 B&R Division  
 HP.PWD Dodra Kavar.

<b>SCHEDULE OF QUANTITY</b>						Job no. 30
						ESTIMATED COST :- 499950
						EARNEST MONEY:- 9999
						TIME:- Two months.
Name of work:- Balance work C/O Rest house Building at Kavar tehsil Dodra Kavar District Shimla H.P						
(SH:- P/L steel work (job no.4)						
Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and medium tensile steel bars. luding all leads and leafs as per the direction of Engineer in Charge .	4864.75	102.77	Rupees One Hundred & Two - Paise Seventy Seven Only	KG	499950
	Total					499950
	(Quoted rate in figure) (+/-)	(.....%)				
	(Quoted rate in Words) (+/-)					

Conditions:-

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

  
 Executive Engineer  
 B&R Division  
 HP.PWD Dodra Kavar.

Schedule of Qty						
Name of Work:-C/o Govt Sr.Sec School Kavar(SH:- C/o Steel work for porch in GSS School at Kavar)				ESTIMATED COST		483435
				EARNEST MONEY		9669
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate		
				In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Steel work welded in built up Sections and framed work, including cutting, hoisting, fixing in position and applying a coat of red lead paint in grating framed guard bars ladder, railing, brackets and similar work including all lead and lift as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In -Charge.	2687.99	Kg	179.85	Rupees One Hundred & Seventy Nine - Paise Eighty Five Only	483435
Total						483435

**Condition:-**

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at  
2 his own risk and cost.

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kavar



JOB NO:- 39

Schedule of Qty						
Name of Work :- A/R & M/o road village Jiskoon km 0/00 to 8/00 (SH:- Hiring of JCB removal of slips and maintenance of road km 0/00 to 8/00 and other various link roads)				ESTIMATED COST		480000
				EARNEST MONEY		9600
				TIME LIMIT:		Two Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	384	Per Hour	1250	Rupees One Thousand Two Hundred & Fifty Only	480000
Total						480000

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/-. )

Quoted rate Words ( +/-. )

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar

**SCHEDULE OF QUANTITY**

Job no. 338

ESTIMATED COST :- 481047

EARNEST MONEY:- 9621

TIME:- Two months.

Name of work:- C/O link road from Jarkot to Jilari Dangrighad road km 0/00 to 3/500

(SH:- Providing and laying Kharanja stone soling in essential reaches at RD 0/480 to 0/720 )

Sr. No.	Description	Qty	Rate	Rate In words	Unit	Amount
1	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification.	884.40	2.08	Rupees Two - Paise Eight Only	cum	1840
2	Consolidation of sub grade with roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	884.40	1.35	Rupees One - Paise Thirty Five Only	cum	1194
3	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread thickness(finished work including materials and labour)	203.41	2350.00	Rupees Two Thousand Three Hundred & Fifty Only	cum	478014
	Total					481047
	(Quoted rate in figure) (+/-)			(.....%)		
	(Quoted rate in Words) (+/-)					

Conditions:-

- 1 The rates Should be quoted for all heights including all lead and lifts
- 2 The contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

  
Executive Engineer  
B&R Division

HP.PWD Dodra Kwar.