

**Himachal Pradesh
Public works Department**

Notice inviting Tender

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **04-12-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **03-12-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 02-12-2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.


Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	Construction of Sianj Saroa via Japloh Katwandhi Batoli road km. 0/00 to 3/00 (SH:- Providing and laying stone solling at RD 0/075 to 0/195 and 0/824 to 0/854) Under SCDP	155872	3200	Two Months
2	Construction of sianj Via Japloh Katwandhi Batoli road km. 0/00 to 3/00 (SH:- Providing and laying CC Pavement at RD 0/075 to 0/195 and 0/824 to 0/854) Under SCDP	405846	8200	Two Months
3	C/o Leyoti to Gudahari road km. 0/00 to 2/300 (SH:- P/L G-II & G-III at RD 0/400 to 0/950) Under OTMNP	464056	9300	Two Months
4	C/o Leyoti to Gudahari road km. 0/00 to 2/300 (SH:- P/L G-II & G-III at RD 0/950 to 1/205 and 1/355 to 1/649) Under OTMNP	463226	9300	Two Months
5	Construction of Sianj Saroa via Jhaploh Katwandi Batoli road Km 0/00 to 3/00 (SH:- construction of PCC R/wall at RD 0/670 to 0/699) Under SCDP	489581	9800	Two Months
6	Construction of Sianj Saroa via Jhaploh Katwandi Batoli road Km 0/00 to 3/00 (SH:- ROFD at RD 0/370 to 0/440, 0/670 to 0/715 and 0/800 to 0/835) Under SCDP	158095	3200	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.

4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10 -2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in-Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.


Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

No. PW-GHR-Tender/NIT/2024


8695-8714

Dated

21-11-2024


Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.
4. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.


Executive Engineer,
Gohar Division (B&R),
HPPWD. Gohar.

BILL OF QUANTITY

Name of work :- Construction of Sianj Saroa Via Japloh Katwandhi Batoli road km 0/00 to 3/000 (SH:- Providing and laying Stone soling at Rd 0/075 to 0/195 and 0/824 to 0/854) Under SCDP						Estimated cost Rs. - 1,55,872/-	
						Earnest Money cost Rs. 3200/-	
						Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	75.60	Per Cubic meter				
	Total:-						
	Quoted rate in figure						
	Quoted rate in words						


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD Gohar.

BILL OF QUANTITY

Name of work :- Construction of Sianj Saroa Via Japloh Katwandhi Batoli road km 0/00 to 3/000 (SH:- Providing and laying CC Pavement at Rd 0/075 to 0/195 and 0/824 to 0/854) Under SCDP	Estimated cost	4,05,846.00
	Earnest Money cost Rs. 8200/-	
	Time - Two Month	

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
2	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) :4 graded stone aggregate 20 mm nominal size) with in all leads .lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	63.00	Per Cubic meter			
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer
Gohar Division (S&R)
HP.PWD Gohar.

BILL OF QUANTITY


of Work:- C/o Leyoti to ^{Gudaheri} road km. 0/00 to 2/300 (SH:- P/L G-II & G-III at RD. 0/400 to 0/950) Under MNP.

Estimated cost Rs. - 464056.00

Earnest Money cost Rs. - 9300.00

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	49.50	Per Cubic metre	2655.50		
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	123.75	Per cubic metre	2687.75		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer,
 Gohar Division (B&R)
 HP.PWD Gohar.

BILL OF QUANTITY

Cudabani

Work:- C/o Leyoti to ~~Bani~~ road km. 0/00 to 2/300 (SH:- P/L G-II & G-III at RD. 0/950 to 1/205 and 1/355 to 1/649) Under OTMNP.

Estimated cost Rs. - 463226.00

Earnest Money cost Rs. - 9300.00

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	49.41	Per Cubic metre	2655.50		
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	123.53	Per cubic metre	2687.75		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

92
Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

Name of work :- Construction of Sianj Saroa via Jhaploh Katwandi Batoli road Km. 0/00 to 3/000. (SH:- Construction of PCC R/Wall at Rd 0/670 to 0/699) Under SCDP

Estimated cost Rs. - 4,89,581/-

Earnest Money cost Rs.9800/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	43.07	Per Cubic meter	322.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	92.87	Per Cubic meter	4793.45		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	16.68	Per Cubic meter	1306.55		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	22.00	Each	397.75		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

Name of work :- Construction of Slanj Saroa via Jhaploh Katwandi Batoli road km 0/00 to 3/000 (SH:- ROFD at RD 0/370 to 0/440, 0/670 to 0/715 and 0/800 to 0/835) Under SCDP

Estimated cost Rs. - 1,58,095/-

Earnest Money cost Rs. 3200/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 41.79 cubic metre @ Rs. 300.00 per cubic metre amount Rs.12,537/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	835.82	Per Cubic meter	189.15		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.