



Office of
Executive Engineer B&R Division HP.PWD., Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 06.12.2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 03.12.2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 04.05.2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Junior Engineer & Work Inspector residence at Bhararu in Joginder Nagar Distt. Mandi (H.P.)(SH:- Geotechnical Investigation for safe Bearing Capacity).	Rs. 1,50,300/-	Rs. 3000/-	Rs. 350/-	Class "D"	One month
2	Construction of link road to Ashapuri Mata Mandir in GP Ner Gharwasra km. 0/0 to 1/500 (SH:- Providing and Laying Kharanja sone Soling & Cement Concrete pavement at km. 0/100 to 0/233)(head of account MMGSY)	Rs. 4,21,071/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
3	Construction of link road Chakka to Dabdail via Ali Pabo in GP Dhar km. 5/00 to 10/0 (SH:- Formation cutting at km. 7/150 to 7/345 head of account MMGSY).	Rs. 4,01,962/-	Rs. 8,000/-	Rs. 350/-	Class "D"	Three months
4	Construction of link road Tracknerest to Panchangna GP Har Gunain km. 0/0 to 1/500 (SH:- Providing and laying kharanja stone soling & Cement Concrete pavement at km. 0/00 to 0/133 head of account MMGSY).	Rs. 4,21,071/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
5	Construction of link road Village Gadyara to Antola km. 0/0 to 2/0 in GP Kolang (SH:- Providing and laying vented causeway in km. 0/650 to 0/720 under Head MMGSY).	Rs. 4,25,823/-	Rs. 8,500/-	Rs. 350/-	Class "D"	Three months
6	Construction of link road village Charlotti and Surgani Mata Mandir km. 0/0 to 1/500 in GP Kuthera (SH:- Providing and laying kharanja stone soling & Cement Concrete pavement from km. 0/315 to 0/395 & 0/520 to 0/570 under Head MMGSY).	Rs. 4,24,007/-	Rs. 8,500/-	Rs. 350/-	Class "D"	Three months
7	Construction of link road Harizan Basti Gram to Sajh Jarl km. 0/0 to 3/0 in GP Kuthera (SH:- Providing and laying cement concrete pavement at km. 0/0 to 0/040 & 0/225 to 0/345 under Head MMGSY).	Rs. 4,20,412/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
8	Construction of link road Burhala Bhadyara to Panjatter in GP Burhala Bhadyara km. 0/00 to 1/200 (SH:- Formation Cutting at km. 0/105 to 0/314 head of account MMGSY).	Rs. 4,21,830/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
9	Construction of link road Bhatwari to Badan km. 0/0 to 3/0 in GP Ropa Padhar (SH:- Formation Cutting from km. 0/615 to 0/854 under Head MMGSY).	Rs. 4,22,175/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
10	Construction of link road Ladwan to Chatarbhujia Mata Mandir in GP Pipli km. 0/00 to 3/0 (SH:- Formation cutting at km. 0/870 to 1/095 head of account MMGSY).	Rs. 4,22,844/-	Rs. 8,500/-	Rs. 350/-	Class "D"	Three months
11	Construction of link road Shanan to Amba Ra Gahra km. 0/0 to 3/0 (SH:- Formation cutting from km. 0/825 to 1/105 under Head MMGSY).	Rs. 4,21,448/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
12	Construction of link road Nagan to Jarl & Nagan to Aba ra Gahra from km. 0/120 to 0/248 under Head MMGSY).	Rs. 4,22,188/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
13	Construction of link Yora Tikru Triveni to Sainthal Prain i/c valley bridge km. 0/0 1/00 in GP Dhelu (SH:- Providing and laying wearing grade-II & Cement concrete pavement from km. 0/200 to 0/337 under Head MMGSY).	Rs. 4,24,272/-	Rs. 8,500/-	Rs. 350/-	Class "D"	Three months

14	Construction of link road Khaprotu km. 0/0 to 2/0 in GP Bhararu (SH:- Providing & laying wearing grade-II cement concrete pavement from km. 0/0 to 0/142 under Head MMGSY).	Rs. 4,22,267/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
15	Construction of link road village Sarwaldi to Harizan Basti Batdhar in GP Nauhli (SH:- Providing and Laying kharanja stone soling & cement concrete pavement from km. 0/00 to 0/080 & C/O breast/protection wall at RD 0/315 to 0/330 under Head MMGSY).	Rs. 3,93,529/-	Rs. 7,900/-	Rs. 350/-	Class "D"	Three months
16	Repair & Maintenance of link road to Harizan Basti Pohli km. 0/0 to 1/500 (SH:- Construction of V-Shape drain at various location between km. 0/0 to 0/750 under Head Repair & maintenance of road under SCSP).	Rs. 4,95,941/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three months
17	R/O Restoration of rain damages on Joginder Nagar Arthi Shanan road km. 0/0 to 3/0 in GP Har Gunain under Deposit SID:SDF/2024/321 (SH:- Construction of retaining wall at km. RD 0/750 to 0/755).	Rs. 87,735/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
18	R/O Restoration of rain damages on Nagan Jarl Bhajera road km. 0/0 to 2/00 under Deposit SID:SDF/2024/324 (SH:- Construction of retaining wall at km. RD. 0/0 to 0/004).	Rs. 66,042/-	Rs. 1,300/-	Rs. 350/-	Class "D"	Two months
19	R/O Restoration of rain damages on Bhujru Nallah to Harizan Basti Bhalendra road km. 0/0 to 1/500 under Deposit SID:SDF/2024/323 (SH:- Construction of breast wall at km. RD 0/300 to 0/307).	Rs. 84,609/-	Rs. 1,7000/-	Rs. 350/-	Class "D"	Three months
20	R/O Restoration of rain damages on Harizan Basti Banogi road km. 0/0 to 2/500 under Deposit SID:SDF/2024/330 (SH:- Construction of breast wall at km. RD 1/265 to 1/272).	Rs. 85,112/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
21	R/O Restoration of rain damages on Shil Nallah to Joun road km. 0/0 to 2/00 under deposit SID:SDF/2024/325 (SH:- Construction of breast wall at km. RD 1/780 to 1/787).	Rs. 87,043/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
22	R/O Restoration of rain damages on Uperla Andrahlu to Uperli Nauhli road km. 0/0 to 4/500 under Deposit SID:SDF/2024/322 (SH:-Construction of retaining wall at RD 2/765 to 1/771).	Rs. 1,06,189/-	Rs. 2,100/-	Rs. 350/-	Class "D"	Three months
23	Construction & M/T on Jahmehar Banoun Ropri Chakrog Traimbli Drubbal road under MMGSY (Sub Head:- Formation Cutting in Km. 3/255 to 3/630)	Rs. 4,86,893/-	Rs. 9,700/-	Rs. 350/-	Class "D"	Three months
24	Construction of Drubbal of Drubbal to Harizan Basti Basoti km. 0/00 to 1/500 under SCSP (SH:- Providing and laying Cement Concrete Pavement at km. 0/195 to 0/241 & 0/55 to 0/615).	Rs. 3,02,199/-	Rs. 6,000/-	Rs. 350/-	Class "D"	Three months
25	Restoration of Rain Damages on Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Basahi Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli road (MDR-57) km. 0/00 to 80/00 (SH:- Construction of breast wall at km. 46/630 to 46/650).	Rs. 2,82,729/-	Rs. 5,700/-	Rs. 350/-	Class "D"	Three months
26	Restoration of rain damages on Makreri Khil Chatri road km. 0/00 to 1/600 (SH:- Construction of Pusta for Restaining Wall at km. 0/840 to 0/850).	Rs. 4,79,949/-	Rs. 9,600/-	Rs. 350/-	Class "D"	Three months
27	Construction of link road to Harizan basti Pohli Km. 0/0 to 1/500 under SCSP (Sub Head:- Construction of RCC 900 mm dia hume pipe culvert along with both side wing walls at Km. 0/450)	Rs. 2,36,669 /-	Rs. 4,700/-	Rs. 350/-	Class "D"	Three months
28	Construction & M/T on link road to H.B. village Chanehar under SCSP (Sub Head:- Providing and laying wearing grade-II and cement concrete pavement from Km. 0/0 to 0/210)	Rs. 4,77,803 /-	Rs. 9,600/-	Rs. 350/-	Class "D"	Three months
29	Construction of link road to village Ghator in GP Outpur under Deposit SID: BSP/2021/404 (SH:- Providing and laying C.conc. 1:4:8 & interlocking concrete block pavement at km. RD 1/660 to 1/696).	Rs. 1,68,272/-	Rs. 3,400/-	Rs. 350/-	Class "D"	Three months
30	Construction of& Maintenance of road from Lower Kothi to Basoa Rihra in G.P. Bhararoo Km. 0/0 to 1/500 under SCSP (SH:- P/L wearing grade-II & cement concrete pavement at Km. 0/765 to 0/900)	Rs. 4,30,135/-	Rs. 8,600/-	Rs. 350/-	Class "D"	Three months
31	Construction of Mela Ground at Joginder Nagar District Mandi (HP) (SH:- Construction of retaining wall, plastering and painting work etc.)	Rs. 1,21,650/-	Rs. 2,400/-	Rs. 350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.

4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2024-25-

15994-16043

Dated:-

14/11/2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job-1

Schedule of Quantity

Estimated Cost:- 150300.00

Earnest Money:- 3000.00

Time:- One Month

Name of work:- Construction of Junior Engineer & Workl Inspector residence at Bhararu in Jogindernagar District Mandi (H.P). (Sub Head: **Geotechnical Investigation for Safe Bearing Capacity.**)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 3 nos. depth upto 6 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00			Per Running meter	
				Total:-		

Executive Engineer,

B & R Division

HP. PWD, Joginder Nagar

Job-2

E No. 297

406

SCHEDULE OF QUANTITY

Name of Work : Construction of link road to Ashapuri mata Mandir in GP Ner Gharwasra km.0/0 to 1/500 (Sub Head:- Providing and laying kharanja stone Soling & cement concrete pavement at km 0/100 to 0/233 head of account MMGSY)			Estimate Cost: Earnest Money: Time Limit :		4,21,071.00 8,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.37	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.37	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-3

E No. 295

409

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Chakka to Dabdail via Ali Pabo in GP Dhar km 5/00 to 10/0 (SH:Foramtion cutting at km 7/150 to 7/345 head of account MMGSY)			Estimate Cost: Earnest Money: Time Limit :		4,01,962.00 8,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1704.89	Per cubic metre			
		Total				

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Tracknerst to Panchangna GP Har Gunain km.0/0 to 1/500 (Sub Head:- Providing and laying kharanja stone Soling & cement concrete pavement at km 0/00 to 0/133 head of account MMGSY)			Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			
				Figures	Words		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.37	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	52.37	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD,
 Joghinder Nagar

Job-4 E.No-296

410

506-5

E.No - 306

412

SCHEDULE OF QUANTITY

Name of Work : Construction of link road village Gadyara to Antola km.0/0 to 2/0 in GP Kolang Head:-Providing & laying vented causeway in km.0/650 & 0/720 under Head MMGSY)				(Sub	Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words		Figures	Rate	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	54.90	Per cubic metre						
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	10.20	Per cubic metre						
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	37.92	Per cubic metre						
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	6.64	Per cubic metre						

5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.00	Per running metre			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-6

SCHEDULE OF QUANTITY

Name of Work : Construction of link road village Charloti and Surgani Mata Mandir km.0/0 to 1/500 in GP Kuthera (Sub Head:-Providing & laying kharanja stone soling & cement concrete pavement from km.0/315 to 0/395 & 0/520 to 0/570 under Head MMGSY)					Estimate Cost: Earnest Money: Time Limit :		4,24,007.00 8,500.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	51.19	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	51.19	Per Cubic metre				
Total							

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Harizan Basti Bani Gram to Sajh Jarl km.0/0 to 3/0 in GP Kuthera (Sub Head:-Providing & laying cement concrete pavement from km.0/0 to 0/040 & 0/225 to 0/345 under Head MMGSY)				Estimate Cost: Earnest Money: Time Limit :			4,20,412.00 8,400.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	63.00	Per Cubic metre				
	Total						

~~Executive Engineer~~
 B & R Division HP.PWD,
 Jogginder Nagar

(E No. 30)

507-8

445

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Burhala Bhadyara to Panjalter in GP Burhala Bhadyara km 0/00 to 1/200 (SH:Foramation cutting at km 0/105 to 0/314 head of account MMGSY)				Estimate Cost: Earnest Money: Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1974.12	Per cubic metre			
	Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-9 SCHEDULE OF QUANTITY

Name of Work: Construction of link road Bhatwari to Badan km.0/0 to 3/0 in GP Ropa Padhar (Sub Head:- Formation cutting from km.0/615 to 0/854 under Head MMGSY)			Estimate Cost: Earnest Money: Time Limit :		4,22,175.00 8,400.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1795.88	Per cubic metre		
Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-10

418

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Ladwan to Chatarbhuja Mata Mandir in GP Pipili km 0/00 to 3/0
(SH:Foramation cutting at km 0/870 to 1/095 head of account MMGSY)

Estimate Cost: 4,22,844.00
Earnest Money: 8,500.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT
				Figures	Words	P	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1901.96	Per cubic metre				
Total							

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

706-11

419

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Shanan to Amba Ra Gahra km.0/0 to 3/0 in GP Dhar (Sub Head:- Formation cutting from km.0/825 to 1/105 under Head MMGSY)				Estimate Cost: 4,21,448.00 Earnest Money: 8,400.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1747.44	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

506-12

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Nagan to Jarl & Nagan to Aba ra Gahra km.0/0 to 3/0 in GP Dhar (Sub Head:-Formation cutting of Nagan to Jarl from km.0/510 to 0/623 & Nagan to Amba ra Gahra from km.0/120 to 0/248 under Head MMGSY)				Estimate Cost: Earnest Money: Time Limit :			4,22,188.00 8,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT	
				Figures	Words		Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1688.55	Per cubic metre					
Total								

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Yora Tikru Triveni to Sainthal Prain i/c valley bridge km.0/0 to 1/00 in GP Dhelu (Sub Head:- Providing & laying wearing grade-II & cement concrete pavement from km.0/200 to 0/337 under Head MMGSY)				Estimate Cost: Earnest Money: Time Limit :			One Month
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.37	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	53.95	Per Cubic metre				
	Total						

Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

JOB - 13 E No. 310

421

E No. 309

Job-14

422

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Khaprothu km.0/0 to 2/0 in GP. Bhararu (Sub Head:-Providing & laying wearing grade-II & cement concrete pavement from km.0/0 to 0/142 under Head MMGSY)				Estimate Cost: Earnest Money: Time Limit :			One Month
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.31	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.19	Per Cubic metre				
	Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

706-15

SCHEDULE OF QUANTITY

Name of Work : Construction of link road village Sarwaldi to Harizan Basti Batdhar in GP Nauhli (Sub Head:- Providing & laying kharanja stone soling & cement concrete pavement from km.0/0 to 0/080 & C/O breast/protection wall at RD 0/315 to 0/330 under Head MMGSY)					Estimate Cost: Earnest Money: Time Limit :		3,93,529.00 7,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.28	Per Cubic metre					
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.52	Per Cubic metre					
3	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.98	Per cubic metre					

4	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.65	Per cubic metre			
5	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Each			
Total						

Executive Engineer,
B&R Division, H.P.P.W.D
Joginder Nagar

Eno.299

206-16

SCHEDULE OF QUANTITY

Name of Work : Repair & maintenance of link road to Harizan Basti Pohli km. 0/0 to 1/500 (Sub Head:- Construction of V-shape drain at various location between Km. 0/0 to 0/750 under Head Repair & maintenance of road under SCSP)				Estimate Cost: Earnest Money: Time Limit :		
				4,95,941.00 9,900.00 Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	AMOUNT Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	163.80	Per cubic metre			

2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	67.60	Per cubic metre			
Total						

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

Job-17

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Joginder Nagar Arthi Shanan road km 0/0 to 3/0 in GP. Har Gunain under Deposit SID: SDF/2024/321 (Sub Head:-Construction of retaining wall at Km. RD 0/750 to 0/755)				Estimate Cost: Earnest Money: Time Limit :		
Description of work				Rate		AMOUNT Rs. P
Sr. No.	No. or Qty.		Unit	Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.		5.75	Per cubic metre		
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.		15.85	Per cubic metre		
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.		7.35	Per cubic metre		

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

E.No. 293

Job-18

402

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Nagan Jarl Bhajera road km 0/0 to 2/00 under Deposit SID: SDF/2024/324 retaining wall at Km. RD 0/0 to 0/004)			Estimate Cost: Earnest Money: Time Limit :			66,042.00 1,300.00 7 Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.56	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate is inclusive all taxes levy by the government time to time excluding GST.	11.72	Per cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.92	Per cubic metre				

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

503-19

403

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Bhujru Nallah to Harizan Basti Bhalendra road km 0/0 to 1/500 under Deposit SID: SDF/2024/323 (Sub Head:-Construction of breast wall at Km. RD 0/300 to 0/307)				Estimate Cost: Earnest Money: Time Limit :		84,609.00 1,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.39	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-20

404

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Harizan Basti Banogi road km 0/0 to 2/500 under Deposit SID: SDF/2024/330 (Sub Head:-Construction of breast wall at Km. RD 1/265 to 1/272))				Estimate Cost: Earnest Money: Time Limit :		85,112.00 1,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.10	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.25	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-21

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Shil Nallah to Joun road km 0/0 to 2/00 under Deposit SID: SDF/2024/325 (Sub Head:-Construction of breast wall at Km. RD 1/780 to 1/787)					Estimate Cost: 87,043.00 Earnest Money: 1,700.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.10	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.25	Per cubic metre			

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jodhpur-Nagar

Job-22 E No. 302

425

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Uperla Andrahlu to Uperli Nauhli road km 0/0 to 4/500 under Deposit SID: SDF/2024/322 (Sub Head:-Construction of retaining wall at RD 2/765 to 1/771)					Estimate Cost: 1,06,189.00 Earnest Money: 2,100.00 Time Limit : 1732 Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	9.09	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	19.02	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.02	Per cubic metre			

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job No. 23

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T on Jhamechar Banoun Ropra Chakrog Traimbli Drubbal road Formation, Cutting in km 3/255 to 3/630) <i>under mm 537,</i>					Estimate Cost: Earnest Money: Time Limit :			4,86,893.00 9,700.00 Three Months	
Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P				
			Figures	Words					
Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all roads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 18.55 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quantity of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be fully compensated by him at his own cost. The rate is inclusive all taxes levy by the government	2371.04	Per cubic metre							
Total									

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 24

SCHEDULE OF QUANTITY

of Work : Construction of Drubbal to Harizan Basti Basoti Km 0/00 to 1/500 Under S&R.
Providing and Laying Cement Concrete Pavement at km 0/195 to 0/241 & 0/555 to 0/615)

of Work : Construction of Drubbal to Harizan Basti Basoti Km 0/00 to 1/500 under SCSB.				Estimate Cost: 3,02,199.00	
Providing and Laying Cement Concrete Pavement at km 0/195 to 0/241 & 0/555 to 0/615)				Earnest Money: 6,000.00	
				Time Limit :	
Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical cause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	42.43	Per Cubic metre			
Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job 25

SCHEDULE OF QUANTITY

of Work : Restoration of Rain Damages on Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli of Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli Road (MDR-57) km 0/00 to 80/00 (SH: ruction of <u>Brest</u> wall at km 46/630 to 46/650)				Estimate Cost: 2,82,729.00 Earnest Money: 5,700.00 Time Limit : Three Months	
Description of work				Rate	AMOUNT
				Figures	Words
				No. or Qty.	Unit
Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (here blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments or grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate inclusive all taxes levy by the government time to time excluding GST.				22.60	Per cubic metre
earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of mumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in- charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, dewatering out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.				27.10	Per cubic metre

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre			
providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and A.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	38.00	Each			
Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

Job -26

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain amages on Makiri Khil Chatri Road km 0/00 to 1/600 : Construction of Pusta for Retaining wall ar km 0/840 to 0/850)				Estimate Cost: 4,79,949.00 Earnest Money: 9,600.00 Time Limit :			
Description of work	No. or Qty.	Unit	Rate		AMOUNT		
			Figures	Words	Rs.	P	
Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines (grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	26.90	Per cubic metre					
Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	73.60	Per cubic metre					
Total							

Executive Engineer
B & R Division HP.PWD,
Jalandhar Nagar

Job - 27

SCHEDULE OF QUANTITY

Name of Work : Construction of link road to Harizan Basti Pohli km. 0/0 to 1/500 under SCSP (Sub Head:- Construction of RCC 900mm dia RCC Hume Pipe culvert along with both side wing walls at km 0/450)				Estimate Cost: 2,36,669.00 Earnest Money: 4,700.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	44.18	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre			
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	19.99	Per cubic metre			
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.72	Per cubic metre			
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

E.N. 300

Job-29

SCHEDULE OF QUANTITY

Name of Work : Construction of link road to village Ghator in GP Outpur under DepositSID: BSP/2021/404 (Sub Head:-Providing & laying C.conc.1:4:8 & interlocking concrete block pavement at Km. RD 1/660 to 1/696)					Estimate Cost: Earnest Money: Time Limit :			1,68,272.00 3,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit		Rate		Words	AMOUNT	
					Figures			Rs.	P
1	Providing and laying cement concrete 1:4:8 (One cement isto four sand isto eight aggregate) graded crushed/broken stone aggregate 40mm (fourty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.90	Per cubic metre						
2	Providing and laying reinforced cement concrete in super structure as per drawing and technical specifications clauses 800, 1205.4 & 1205.5. Reinforced cement concrete M-20 (1:2:4) (one cement : two sand : four graded stone aggregate 20mm (twenty millimetre) nominal size) upto any height complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	0.65	Per cubic metre						
3	Providing and Laying Interlocking Concrete Block Pavements having thickness 60 mm (sixty millimeter) as per drawings and Technical Specification Clause 1504. and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is inclusive all taxes levy by the government time to time excluding GST.	88.20	Per Square metre						
		Total							


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-28

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on Link road to HB. Village Chanehar under SCSP (Sub head:- Providing & laying wearing grade-II and cement concrete pavement from Km.0/0 to 0/2.00)				Estimate Cost: Earnest Money: Time Limit :			One Month
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.42	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	67.25	Per Cubic metre				
	Total						

 Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Ekl0,260

426

SCHEDULE OF QUANTITY

Name of Work : Construction & Maintenance of road from Lower Kothi to Basoa Rihra in G.P. Bhararoo Km. 0/0 to 1/500. under SCSP (SH:-P/L wearing grade-II & cement concrete pavement at km.0/765 to 0/900)			Estimate Cost: Earnest Money: Time Limit :			41,30,135 / -- 8,600 / -- One Month	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.90	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	53.16	Per Cubic metre				
	Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of work : Construction of Mela Ground at Joginder Nagar Distt. Mandi (HP) (SH: Construction of retaining wall, plastering and painting work etc.)				Estimate Cost: Earnest Money: Time Limit :			1,21,650.00 2,400.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	15mm (Fifteen millimeter) cement plaster in single coat on the Rough side in cement mortar 1:4 (one Cement : four Sand). of brick/concrete/stone walls for plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	191.70	Per Square Metre				
2	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces(two coats)to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	191.70	Per square metre				
3	Painting on Steel work with two or more coat applied @ 0.90 litre/ 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.80 litre/ 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacturewith Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	159.75	Per Cubic metre				

4	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time excluding GST.	5.10	Per cubic metre		
5	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty milimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.84	Per cubic metre		
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each		
	Total				


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar