

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed Percentage rates tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **11.11.2024 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **12.00 PM** & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **08.11.2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1.	R R D Talyahar Panjethi road km.0/00 to 1/225. (SH:- C/O R/wall at RD. 0/890 to 0/900).	Rs 1,95,447	Rs 4,000	Rs. 350	One Month
2.	C/O Banyara to Kutli road km. 0/00 to 2/300. (SH:- wire cret R/wall at RD 2/090 to 2/100.80).	Rs 1,26,613	Rs 2,600	Rs. 350	One Month
3.	A/R & M/O to the road from Saigaloo to Nalhog km. 0/00 to 6/400. (SH:- P/L Stone soiling, Grading-III, bitumen carpet, repair of pot holes) Job No. 1	Rs 4,59,048	Rs 9,200	Rs. 350	One Month
4.	A/R & M/O to the road from Saigaloo to Nalhog km. 0/00 to 6/400. (SH:- P/L Stone soiling, Grading-III, bitumen carpet, repair of pot holes) Job No. 2	Rs 4,50,266	Rs 9,100	Rs. 350	One Month
5.	C/O Link road Dolra Balh to Pump House Dwada road km. 0/00 to 3/00 (SH - 5/7 mtr wide road in km. 0/137 to 0/170).	Rs 2,25,441	Rs 4,600	Rs. 350	One Month
6.	C/O Neran Gheru Dolra balh road km. 0/00 to 5/300. (SH:- C/O B/wall at RD 4/180 to 4/188.40) Protect house sh. Roshan lal	Rs 3,15,588	Rs 6,400	Rs. 350	One Month
7.	Construction of 25 00 mtrs span RCC Box girder bridge over Amodi khad at Rd 1/70 on Sikkan Mutt to Kasan via Morgaloo road km 0/00 to 3/500 Under NABARD (SH:- Soil investigation thereof)	Rs 2,55,000	Rs 5,100	Rs 350	One Month
8.	R R D Damages on Tarna road km 0/00 to 1/600. (SH:- C/O R/wall at RD 1/040 to 1/053).	Rs 3,79,053	Rs 7,600	Rs. 350	One Month
9.	A/R & M/O Residential building under Mandi Division No-II at Jail road Mandi Distt. Mandi (H.P) (SH:- Providing and laying interlocking paver tile work etc) (Block-A) Job No.1	Rs 2,50,898	Rs 5,100	Rs. 350	One Month
10.	A/R & M/O Residential building under Mandi Division No-II at Jail road Mandi Distt. Mandi (H.P) (SH:- Providing and laying interlocking paver tile work etc) (Block-A) Job No.2	Rs 2,50,898	Rs 5,100	Rs. 350	One Month
11.	Special repair of Old Lapprocy building of zonal Hospital Mandi at Ragunath ka Padhar Tehsil sadar Distt. Mandi (H P) (SH:- Construction of boundary wall, steel work & Painting work etc) Job No.2	Rs 2,91,069	Rs 5,900	Rs. 350	One Month
12.	Special repair of Old lapprocy building of Zonal Hospital Mandi at Ragunath ka Padhar Tehsil Sadar Distt. Mandi (H P) (SH:- Construction of boundary wall, steel work & painting work etc) Job No.1	Rs 3,60,389	Rs 7,300	Rs. 350	One Month
13.	R R D on Sandhapattan Bharol Kun Ka Tar road km. 70/00 to 85/00. (SH:- C/O B/wall at RD. 79/800 to 79/815).	Rs 3,67,614	Rs 7,400	Rs. 350	One Month
14.	Beautification and landscaping of Rachhera Dev Temple complex in Tehsil Kotli, District mandi (H.P) (SH:- C/O Retaining wall in front of proposed gate)	Rs 3,99,096	Rs 8,000	Rs. 350	One Month
15.	Construction of NH-70 to Village Satahan road km. 0/00 to 1/645. (SH:- Filling on road for improvement of Gradient at km. 0/155 to 0/240).	Rs 2,98,978	Rs 6,000	Rs. 350	One Month
16.	A/R and M/O on Rada Nallah Dhandal road km 0/00 to 2/300 (SH:- Providing and laying WBM Grade-III for correction layer and Repair of Pot holes between in km. 0/00 to 1/500).	Rs 4,95,081	Rs 2,000	Rs. 350	One Month
17.	A/R & M/O Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- P/L G-III and repair of pot holes Km. 0/00 to 1/500).	Rs 2,99,140	Rs 6,000	Rs. 350	One Month

Certificated that tender of above works are being called of emergent nature in exigency of public interest.

GENERAL CONDITIONS: -

- The Contractors/ Bidders must submit copy of their Permanent Income Tax Account Number/ GST Number/ EPF No. along with the application for tender.
- The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
- The Contractors/Firms should attach copy of the Registration/ Renewal with the application.
- The contractor/ bidder should quote his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
- Conditional and telegraphic/email tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
- The offer shall remain valid up to 75 days.
- The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The contractors whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to compete in tendering for four months.
- The contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
- The rates beyond the limit of over + 5%, will be rejected and the rates quoted below 10 %, the Additional Performance security will have to borne for unbalanced bid.
- The participants should have the work done of similar nature & sufficient machinery & T & P alongwith proof.

13. The intending bidders who want to purchase tender form for any through job and are unable to visit the office physically must sent his/her authority letter with the person to whom the particular job is to be sold.
14. The tender form will not be sold to those bidders who have more than three pending works (any Head) for the last six months or more.
15. The Executive Engineer reserves the right to accept/rejected any tender/applications or all tenders without assigning any reasons.
16. In the jobs pertaining to Hiring of JCB /Tipper at will be discretionary power of Engineer-in-charge to deploy/engage JCB as & when required. The contractor will be no authority to force Engineer-in-charge to engage/deploy his machinery when not needed.
17. Moreover, in the jobs pertaining to hiring of JCB/Tipper it will be responsibility of contractor to open the road as soon as possible but not later than 4 hours.
18. For job No. 8 & 9 having bituminous macadam the contractor must be having HMP in his possession or he should provide certificate that he will provide supply of bituminous macadam from authorised HMP.

No.PW-MDII-CB NIT (off line) /2024-

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A. E, S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

Dated: -

01 / 11
2024

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

Name of work :- R.R.D Talyahar Pajethi road Km. 0/00 to 1/225.
(SH:- C/O R/wall at RD. 0/890 to 0/900).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 1,95,447/-
Earnest Money Rs. 4,000/-
Time :- One month

	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	17.30	609.90	Rupees Six Hundred Nine and Paise Ninety Only	Per Cubic Metre	10,551.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction, entire satisfaction of Engineer-in-charge.	30.60	5541.50	Rupees Five Thousand Five Hundred Forty One and Paise Fifty Only	Per Cubic Metre	1,69,570.00
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	11.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only	Each	4,270.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	6.60	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	11,056.00
	Total					1,95,447.00



Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Name of work:- C/O Baryara to Kuthi road Km.0/00 to 2/300
(SH:- wire cret R/wall at RD 2/090 to 2/100.80)

%age Rate of SCHEDULE OF QUANTITY

Estimated cost Rs. 1,26,613/-
Earnest cost Rs. 2,600/-
Time:- One Month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in ordinary rock using mechanical means including loading of truck and carrying of excavation materials to embankment site with a lift upto 1.5 mtr. and upto any lead as per Technical Specification clause 1603.2 including carriage of materials with in all leads, lifts and other incidentals.	14.58	198.35	Ruppes One Hundred Ninety Eight and Paise Thirty Five Only	Per Cubic Metre	2,892
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and technical specification clause 1301 (Excluding fo wire crate) (Wire crate will be supplied by department free of cost) including carriage of materials with in all leads, lifts and other incidentals.	38.02	3254.10	Ruppes Three Thousand Two Hundred Fifty Four and Paise Ten Only	Per Cubic Metre	1,23,721
Total						1,26,613


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.


239

DRAFT SCHEDULE OF QUANTITY
Link :- A/R & M/O to the road from Saigaloo to Nalhog Km. 0/00 to 6/400.
(SH:- P/L Stone soling, Grading-III, bitumen carpet, Repair of pot holes), Job No.1

Estimated Cost Rs. 4,59,048/-
 Earnest Money Rs 9,200/-
 Time :- One month.

Description of items.		Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comb including spreading watering and rolling of binding material moorum or earth etc. complete as per HPPWD. specification.100mm spread thickness (finished work including materials and labours) including carriage of materials with in all leads, lifts and other incidentals.	4 25	2075.10	Rupees Two Thousand Seventy Five and Paise Ten Only	Per Cubic Metre	8,819.00
2	Providing, laying, spreading and compacting stone aggregates of 53mm to 22.4 mm (Fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred kn) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/ Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	26 59	3311.95	Rupees Three Thousand Three Hundred Eleven and Paise Ninety Five Only	Per Cubic metre	88,065
3	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 Kg/ sqm (Zero point seven zero to one point zero kilogram per square metre) using mechanical means as per Technical Specification Clause 502 including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	865 55	75.80	Rupees Seventy Five and Paise Eighty Only	Per square metre	65,609.00
4	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 Kg. per sqm (Zero point two five to zero point three zero kilogram per square metre) on the prepared granular bituminous surface treated with primer cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	642.00	22.10	Rupees Twenty Two and Paise Ten Only	Per square metre	14,188.00
5	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 by Manual/ Mechanical Means Bitumen (S-90)/ VG-10 grade including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	642.00	245.10	Rupees Two Hundred Forty Five and Paise Ten Only	Per square metre	1,57,354.00
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By manual/mechanical means including carriage of materials with in all leads, lifts and other incidentals.	642.00	80.10	Rupees Eighty and Paise Ten Only	Per square metre	51,424.00

7	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904 2. 503 and 508 1 including carriage of materials with in all leads, lifts and other incidentals	211 89	347 30	Rupees Three Hundred Forty Seven and Paise Thirty Only	Per square metre	73,589
Total						4,59,048.00


 Executive Engineer,
 Mandi Division No-II,
 HP PWD, Mandi


%age Rate of SCHEDULE OF QUANTITY

Name of work :- A/R & M/O to the road from Saigaloo to Nalhog Km. 0/00 to 6/400.
(SH:- P/L Stone soiling, Grading-III, bitumen carpet, Repair of pot holes), Job No.1

Estimated Cost Rs. 4,50,266/-
 Earnest Money Rs. 91,00/-

Time :- One month

Description of items.		Quantity	Rates		Unit	Amount
	2	3	4 Figure	5 Words	6	7
1	Providing, laying, spreading and compacting stone aggregates of 53mm to 22.4 mm (Fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred kN) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/ Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	26.60	3311.95	Rupees Three Thousand Three Hundred Eleven and Paise Ninety Five Only	Per Cubic metre	88,098
2	Providing and applying primer coat with Bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 Kg/ sqm (Zero point seven zero to one point zero kilogram per square metre) using mechanical means as per Technical Specification Clause 502 including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	865.55	75.80	Rupees Seventy Five and Paise Eighty Only	Per square metre	65,609.00
3	Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. per sqm (Zero point two five to zero point three zero kilogram per square metre) on the prepared granular bituminous surface treated with primer cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	642.00	22.10	Rupees Twenty Two and Paise Ten Only	Per square metre	14,188.00
4	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred kN) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 by Manual/ Mechanical Means Bitumen (S-90)/ VG-10 grade including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	642.00	245.10	Rupees Two Hundred Forty Five and Paise Ten Only	Per square metre	1,57,354.00
5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By manual/mechanical means including carriage of materials with in all leads, lifts and other incidentals.	642.00	80.10	Rupees Eighty and Paise Ten Only	Per square metre	51,424.00
6	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1. including carriage of materials with in all leads, lifts and other incidentals.	211.90	347.30	Rupees Three Hundred Forty Seven and Paise Thirty Only	Per square metre	73,593
Total						4,50,266.00



 Executive Engineer
 Mandi Division No.-II
 H.P.P.W.D. Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work:- C/O Link road Dolra Balh to Pump house Dwada road Km. 0/00 to 3/00
(SH:-5/7 mtr wide road in Km. 0/137 to 0/170)

Estimated cost Rs 2,25,441/-
Earnest Money Rs 4,600/-
Time:- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by all means in all kinds of soil such as pick work, jumper work, blasting work both in soft and hard rock with chiseling/wedging out rock (where blasting is prohibited) and other intermediate classification of soil including cutting and trimming of side slopes and disposal of unserviceable material by mechanical transport and stacking the serviceable/ useful material on road berms as per technical specification clause 1603.1, 1603.2 or directed by the Engineer-in-charge. The recovery of 49.66 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 14,898/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. The work shall be executed in workman like manner and avoids any damages to the private/ Govt. property in the vicinity of work site, if damage access to any property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	817.23	275.86	Rupees Two Hundred Seventy Five and Paise Eighty Six Only	Per Cubic Metre	2,25,441.00
Total						2,25,441.00



Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- C/O Neran Gheru Dolra bali road Km. 0/00 to 5/300
(SH:- C/O B/wall at RD 4180 to 4/188.40)

Estimated Cost Rs. 3,15,588/-
Earnest Money Rs 6,400/-
Time :- One month

1	Description of items.	3	Rates		Unit	Amount
			4 Figure	5 Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	16.80	609.90	Rupees Six Hundred Nine and Paise Ninety Only	Per Cubic Metre	10,246.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	53.84	5541.50	Rupees Five Thousand Five Hundred Forty One and Paise Fifty Only	Per Cubic Metre	2,98,354
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (hundred millimetre) dia AC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	18.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only	Per Cubic Metre	6,988.00
Total						3,15,588.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.




Percentage Rate SCHEDULE OF QUANTITY

Name of work:- Construction of 25.00 mtrs span RCC Box girder bridge over Arnodi Khad at Rd 1/170 on Sikkam Mutt to Kasan via Morgaloo road Km 0/00 to 3/500 Under NABARD (SH:- Soil investigation thereof)

Estimated Cost Rs.2,55,000/-
Earnest Money Rs. 5,100/-
Time :- One month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Engagement of Consultant for soil investigation of diversion of road from Tarna road to Sukodi bridge including 2 nos bore holes upto maximum depth of 15.00 metre and approval from competent authority hauling / carriage of materials through all modes of transportation as per direction of Engineer-in-Charge, with in all leads and lift of materials and other incidentals.The investigation report should be submitted as per relevant IRC code.	30.00	8,500.00	Rupees Eight Thousand Five Hundred Only	Per running metre	2,55,000.00
					Total	2,55,000.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.


%age Rate of SCHEDULE OF QUANTITY

Name of work:- R.R. Damages on Tarra road km 0/00 to 1/600. (SH:- C/O R/wall at RD 1/040 to 1/053.)

Estimated cost Rs. 3,79,053/-
Earnest Money Rs. 7,600/-
Time:- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m (fifty metre) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals complete with in all leads, lifts and carriage of material and other incidentals as per direction, entire satisfaction of Engineer-in-charge.	42.90	524.10	Ruppes Five Hundred Twenty Four and Paise Ten Only	Per Cubic metre	22,484.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals complete with in all leads, lifts and carriage of material and other incidentals as per direction, entire satisfaction of Engineer-in-charge.	63.70	5320.75	Ruppes Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic metre	3,38,932.00
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete with in all leads, lifts and carriage of material and other incidentals as per direction, entire satisfaction of Engineer-in-charge.	20.00	358.35	Ruppes Three Hundred Fifty Eight and Paise Thirty Five Only	Each	7,167.00

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in-charge.	6.25	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic metre	10,470.00
					Total	3,79,053.00


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi


%age Rate of SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Residential building under Mandi Division No.-II at Jail road Mandi Distt. Mandi (H.P.). (SH:- Providing and laying interlocking paver tile work etc.) (Block -A) Job No. 1

Estimated cost Rs. 2,50,898/-
Earnest Money Rs. 5,100/-
Time:- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metres), dressing of sides and bottoms and back filling in trenches with excavated suitable materials. Ordinary soil upto 3.00m (three metres) depth complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	19.99	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	11,429.00
2	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm (five millimetre to ten millimetre), in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in charge complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	14.90	1629.60	Rupees One Thousand Six Hundred Twenty Nine and Paise Sixty Only	Per Cubic metre	24,281.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm (forty millimetre) nominal size) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	9.93	5691.45	Rupees Five Thousand Six Hundred Ninety One and Paise Forty Five Only	Per Cubic metre	56,516.00
4	Providing and laying 60mm (sixty millimetre) thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (fifty millimetre) thick compacted bed of coarse sand, filling the joints with line sand etc. complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	99.34	1568.75	Rupees One Thousand Five Hundred Sixty Eight and Paise Seventy Five Only	Per Square metre	1,55,840.00

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20mm (twenty millimetre) nominal size) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in-Charge.	0.44	6437.00	Rupess Six Thousand Four Hundred Thirty Seven Only	Per Cubic metre	2,832.00
					Total	2,50,898.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY


name of work :- A/R & M/O Residential building under Mandi Division No.-II at Jail road Mandi Distt. Mandi (H.P.). (SH:- Providing and laying interlocking paver tile work etc.) (Block -A) Job No. 2

Estimated cost Rs. 2,50,898/-
Earnest Money Rs. 5,100/-

Time:- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metres), dressing of sides and bottoms and back filling in trenches with excavated suitable materials. Ordinary soil upto 3.00m (three metres) depth complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	19.99	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	11,429.00
2	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm (five millimetre to ten millimetre), in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in charge complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	14.90	1629.60	Rupees One Thousand Six Hundred Twenty Nine and Paise Sixty Only	Per Cubic metre	24,281.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm (forty millimetre) nominal size) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	9.93	5691.45	Rupees Five Thousand Six Hundred Ninety One and Paise Forty Five Only	Per Cubic metre	56,516.00
4	Providing and laying 60mm (sixty millimetre) thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (fifty millimetre) thick compacted bed of coarse sand, filling the joints with line sand etc. complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	99.34	1568.75	Rupees One Thousand Five Hundred Sixty Eight and Paise Seventy Five Only	Per Square metre	1,55,840.00

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20mm (twenty millimetre) nominal size) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	0.44	6437.00	Rupees Six Thousand Four Hundred Thirty Seven Only	Per Cubic metre	2,832.00
					Total	2,50,898.00


 Executive Engineer,
 Mandi Division No-II,
 HP PWD, Mandi.


%age Rate of SCHEDULE OF QUANTITY

Name of work :- Special repair of Old Lapprocy building of Zonal Hospital Mandi at Rangunath Ka Padhar Tehsil
Sadar Distt. Mandi (H.P.).(SH:- Construction of Boundary wall, steel work & Painting work etc.)
Job No. 2

Estimated cost Rs. 2,91,069/-
Earnest Money Rs. 5,900/-
Time:- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	15mm (fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix : With cement mortar 1:4 (1 cement : 4 fine sand) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	243.60	222.05	Rupees Two Hundred Twenty Two and Paise Five Only	Per Square Metre	54,091.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20mm (twenty millimetre) nominal size) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	9.13	7107.10	Rupees Seven Thousand One Hundred Seven and Paise Ten Only	Per Cubic Metre	64,888.00
3	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven litter per ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty kilonram per ten square metre) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	243.60	144.10	Rupees One Hundred Forty Four and Paise Ten Only	Per Square Metre	35,103.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	1002.03	119.95	Rupees One Hundred Nineteen and Paise Ninety Five Only	Per Kilogram	1,20,193.00

5	1.20metres (one point twenty metre) high fencing with 1.80 m (one point eighty metre) deodar/kail/sal ballies posts 300mm (three hundred millimetre) girth (minimum) 2.50m (two point fifty metre) metre centre to centre with six horizontal lines and two diagonals of galvanised steel bar bed wire (IS:278-1962 Type-I) weighing 9.38 KG (nine point thirty eight kilogram) per 100 metre (one hundred metre) minimum strained and fixed to posts with G.I. staples including coal carrying of ballies complete and fixed posts, struts and straining bolts shall be paid for seperately) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	108.00	155.50	Rupees One Hundred Fifty Five and Paise Fifty Only	Per Running metre	16,794.00
					Total	2,91,069.00


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Special repair of Old Lapprocy building of Zonal Hospital Mandi at Ragnunath Ka Padhar Tehsil Sadar Distt. Mandi (H.P.), (SH:- Construction of Boundary wall, steel work & Painting work etc.)
Job No. 1

Estimated cost Rs. 3,60,389/-
Earnest Money Rs. 7,300/-
Time:- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any leads, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m (fifty metre). all kinds of soil complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	20.25	180.95	Rupees One Hundred Eighty and Paise Ninety Five Only	Per Cubic Metre	3,664.00
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	117.29	437.30	Rupees Four Hundred Thirty Seven and Paise Thirty Only	Per Square Metre	51,291.00
3	Providing and laying cement concrete 1:5:10 (1 cement: 5 coarse sand): 10graded stone aggregate 40mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	22.50	5146.05	Rupees Five Thousand One Hundred Forty Six and Paise Five Only	Per Cubic Metre	1,15,786.00
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in- Charge.	28.33	6694.25	Rupees Six Thousand Six Hundred Ninety Four and Paise Twenty Five Only	Per Cubic Metre	1,89,648.00
	Total					3,60,389.00


Executive Engineer,
Mandi Division No-II,
PPWD Mandi

%age Rate of SCHEDULE OF QUANTITY

ck :- R.R.D on Sandhapattan Bharol Kun Ka Tar Kotli road Km. 70/600 to 85/000.
(SH:- C/O B/wall at RD. 79/800 to 79/815).

Estimated Cost Rs. 3,67,614/-
Earnest Money Rs. 7,400/-
Time :- One month

1	2	3	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	27.45	262.60	Rupees Two Hundred Sixty Two and Paise Sixty Only	Per Cubic Metre	7,208.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	4.50	576.60	Rupees Five Hundred Seventy Six and Paise Sixty Only	Per Cubic Metre	2,595.00
3	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) including carriage of materials with in all leads, lifts and other incidentals.	55.20	6271.10	Rupees Six Thousand Two Hundred Seventy One and Paise Ten Only	Per Cubic Metre	3,46,165.00
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	30.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only	Each	11,646.00
Total						3,67,614.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY
Name of work :- Beautification and landscaping of Rachhera Dev Temple complex in Tehsil Kotli, District Mandi H.P.
(SH:- C/O Retaining wall in front of proposed gate)

Estimated Cost Rs. 3,99,096/-
 Earnest Money Rs. 8000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	22.40	576.60	Rupees Five Hundred Seventy Six and Paise Sixty Only	Per Cubic Metre	12,916.00
2	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) including carriage of materials with in all leads, lifts and other incidentals.	58.40	5871.10	Rupees Five Thousand Eight Hundred Seventy One and Paise Ten Only	Per Cubic Metre	3,42,872.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	17.92	1810.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	32,438.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	28.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only	Each	10,870.00
Total						3,99,096.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Construction of NH-70 to Village Satahan road Km. 0/00 to 1/645.
(SH:- Filling on road for improvement of Gradient at Km. 0/155 to 0/240).

Estimated Cost Rs. 2,98,978/-
 Earnest Money Rs. 6000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals.	15.45	4235.55	Rupees one thousand three hundred twenty six and paise five only.	Per Cubic Metre	65,439.00
2	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	46.91	2122.20	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	99,552.00
3	Construction of Embankment with approved material obtained from borrow pits with any lift, transporting to site spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with any lead as per technical specification Clause 301.5 including carriage of materials with in all leads, lifts and other incidentals.	444.40	301.50	Rupees Three Hundred One and Paise Fifty Only	Per Cubic Metre	1,33,987.00
	Total					2,98,978.00



 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Percentage Rate SCHEDULE OF QUANTITY

Name of work :- A/R and M/O on Rada Nallah Dhandal road Km 0/00 to 2/300 (SH:- Providing and Laying WBM Grade-III for correction layer and Repair of Pot holes between in km.0/00 to 1/500)

Estimated Cost Rs. 4,95,081/-
Earnest Money Rs. 2000/-
Time:- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of 53mm to 22.4 mm (Fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred Kn) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/ Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	10.02	3203.00	Rupees Three Thousand Two Hundred Three Only	Per Cubic metre	32,094
2	Providing and applying tack coat with Bitumen emulsion (VG-10) using emulsion distributor at the rate of 0.25 to 0.30 Kg. (zero point two five to zero point three zero kilogram) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 including carriage of materials with in all leads, lifts and other incidentals.	1335.99	22.50	Rupees Twenty Two and Paise Fifty Only	Per square metre	30,060.00
3	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen VG-10/ S-90 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred Kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	1335.99	245.60	Rupees Two Hundred Forty Five and Paise Sixty Only	Per square metre	3,28,119
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 by manual means including carriage of materials with in all leads, lifts and other incidentals.	1335.99	78.45	Rupees Seventy Eight and Paise Forty Five Only	Per square metre	1,04,808
				Total		4,95,081.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- A/R & M/O Ganpati Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- P/L G-III and repair of pot holes Km. 0/00 to 1/500).

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. 2,99,140/-
Earnest Money Rs. 6,000/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred kN) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 . including carriage of materials with in all leads, lifts and other incidentals.	3	3250.60	Rupees Three Thousand Two Hundred Fifty and Paise Sixty Only	Per cubic metre	11,702.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1. including carriage of materials with in all leads, lifts and other incidentals.	787.50	365.00	Rupees Three Hundred Sixty Five Only	Per square metre	2,87,438.00
Total						2,99,140.00

Draft amount approved for Rs- 2,99,140/- only.

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi