



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
12835-43 DATED 13-11-24, ARE URGENT NATURE
AND PUBLIC INTEREST.**

**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in
"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **28.11.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **27.11.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **26.11.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Kolkar to Kalyar Basti Road (SH: Cutting of earth work at RD 0/690 to 0/885 P/L WBM G-I at RD 0/690 to 0/885)	Rs.2,25,036/-	Rs.4,500/-	Rs.350/-	Two Months
2	C/O Barot Nalhota Road km 0/00 to 15/500 (SH: Laying G-II, Prime coat, Tack Coat and Bituminous Concrete (25 mm thick) on Portion from Nalhota to Baragran at RD 15/00 to 15/370)	Rs.4,99,705/-	Rs.10,000/-	Rs.350/-	Two Months
3	C/O Mahila Mandal Bhawan Lower Chobin (SH: C/O Room 1 st Floor Prepainted Sheet Roofing, Distemping etc.)	Rs.4,94,791/-	Rs.9,900/-	Rs.350/-	Two Months
4	C/O Link road Chadhiar to Doli Khurd km 0/00 to 2/300 (SH: P/L C.C. Pavement & WBM G-II at km 0/105 to 0/125, 0/680 to 0/715 and 0/900 to 0/950) SCDP	Rs.3,40,649/-	Rs.6,900/-	Rs.350/-	Two Months
5	C/O Dharer Sansal Via Panjala Road km 0/00 to 4/00 (SH: Dismantling and C/O damaged 2.00 mtr. span RCC Slab Culvert at RD 1/480 & C/O approach U-Shape Drain B/w 1/480 to 1/510)	Rs.1,56,645/-	Rs.3,200/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.
For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/-

12835-43

Dated:- 13.11.2024

- Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.
-

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.	268.80	Per Cubic metre			
5	Providing and Laying, spreading and compacting stone aggregates size 90mm to 45 mm (Ninety millimeter to forty five millimeter) grading-II (100 mm Consolidated thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, Crushable type such as Moorum or Gravel for grading-I (@ 0.30 cum per ten square meter and binding material at the rate of 0.08 cum (Zero point zero eight cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading I as per MORD technical specification clause no 405 complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect	61.43	Per Cubic metre			
Total						

Executive Engineer
Bailnath Division
H.P.W.D., Bailnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(2)

Name of work :- C/O Barot Nahota Road km 0/00 to 15/500 .
(Sh:-Laying G-II , Prime coat ,Tack Coat and Bituminous Concrete (25 mm thick) on Portion from Nahota to Baragran at RD 15/00 to 15/370)

Estimate Cost: 4,99,705.00
Earnest Money: 10,000.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Laying, spreading and compacting stone aggregates size 63mm to 45 mm (Sixty three millimeter to forty five millimeter) grading-II(75 mm Consolidated compacted thickness withness) to water bound macadam specification including spreading in uniform compacted thickness withness using template, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, Crushable type such as Moorum or Gravel for grading II & III @ 0.22 cum (zero point two two cubic meter) per ten square meter and binding material at the rate of 0.06 cum (Zero point zero Six Cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD technical specification clause no 405 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the government.	84.64	Per Cubic metre			
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero point eight five Kilogram) per Square metres using mechanical means as per MORD technical specification clause 502, and as per directions of Engineer - in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1128.50	Per Square metre			
3	Providing and applying tack coat with Bitumen emulsion using (RS-1) emulsion pressure distributor at the rate of 0.275 kg (at rate of zero point two seven five kilogram) per Square metre on the prepared bituminous surface and cleaned with hydraulic broom as per M.O.R.D. technical specifications section No. 503 .The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1128.50	Per Square metre			
4	Providing and laying 25 mm (twenty five millimeter) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 (Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects as per the direction and entire satisfaction of Engineer-In Charge. The rate is inclusive all taxes levy by the government time to time excluding G.S.T.	28.21	Per Cubic Meter			

Executive Engineer

Baljnath Division
H.P.R.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Mahila Mandal Bhawan Lower Chobin.
(SH:- C/O Room 1st Floor Pre-painted Sheet Roofing, Distemping Etc.)

Estimate Cost: 4,94,791.00
Earnest Money: 9,900.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Brick work using common burnt clay building bricks in foundation and plinth in cement mortar 1:6 (one cement : six sand) second class bricks. Extra for brick work in super-structure above plinth level upto floor two level (second class bricks). The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.93	Cum.			
2	Providing woodwork in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position 2nd class deodar wood. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.29	Cum.			
3	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws 40mm thick 2nd class deodar wood. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.64	Sqm			
4	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1476.00	kg			
5	Providing and fixing pre-painted sheet roofing of kolar metal single skin trapezoidal sheeting 0.45mm (sixty millimetre) thickness having 1060mm (one thousand sixty millimetre) cover width over all width 1126mm (one thousand one hundred twenty six millimetre) , 28mm (twenty eight millimetre) crest depth at 353mm (three hundred fifty three millimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	73.80	Per square metre			
6	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick pre-painted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/e fixing with pre-painted iron J or L hooks, bolts & nuts 6mm dia & pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Rmt			
7	Providing and fixing 15 cm. wide 45 cm. overall semicircular plain G.I. sheet/gutter with iron brackets 40x3mm size bolts and nuts and washers etc. Including making necessary connections with rain water pipe complete as per design 0.63mm thick sheet. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Rmt			
8	15mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering above floor two level to floor three level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand). The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	135.63	Sqm			

9	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finish with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc completed. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.91	Sqm				
10	Disctempering (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droopings and other foreign matter and also including preparing the surface even and sand pappered smooth on walls. Priming coat with distemper primer. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	135.63	Sqm				
11	Painting two coats(excluding coat) on previously painted wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand pappering & stoping. With enamel paint other than white complete in all respect as per design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.27	Sqm				

Executive Engineer
Bajinath Division
H.P.P.W.D. Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

(4)

Name of Work : C/O Link road Chadhiar to Doli Khurd km 0/00 to 2/300
(SH:-P/L C. C Pavement & W B M G-II at km 0/105 to 0/125 , 0/680 to 0/715 and 0/900 to 0/950) *scor*

Estimate Cost: 3,40,649.00/-
Earnest Money: 6900.00/-
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.40	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	48.03	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

56

Name of work : C/O Dharer Sansal Via Panjala Road km 0/00 to 4/00 (Sh:- Dismantling and C/O damaged 2.00 mtr span RCC Slab Culvert at RD 1/480 & C/O approach U-shape Drain B/w 1/480 to 1/510 .)							Estimate Cost: 1,56,645.00/- Earnest Money: 3200.00/- Time Limit : Two Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P			
				Figures	Words				
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	4.39	Cum.						
2	Extra for scrapping, cleaning and straightening of reinforcement from RCC work as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	135.00	Kg						
3	Supplying, fitting, and placing HYSD bar reinforcement in super structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.60	M/T						
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause ,800 and 1206.3 RCC M-25 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.06	Cum						
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.93	Per Cubic metre						
6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point five zero meter) in width or 10 sqm), (ten square meter) including dressing of sides and rammimg of bottoms, lift upto 1.5 m, (one point five zero meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of any distance. All kinds of soil with in all leads by any mode of trasportation and other incidental , as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	12.60	cum						

7	<p>Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggs- 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.</p>	6.47	Per Cum				
---	---	------	---------	--	--	--	--

Executive Engineer
Bajina Division
H.P.W.D., Bajinath
2