

**Himachal Pradesh
Public Works Department.**

Through mail

No. PW/HD/CB/T-I/2024-25
To

4090-91

Dated: - 08/11/2024

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - **Publication of tender Notice.**

Sir,

Enclosed please find herewith tender notice of work as given in the Inviting Tender along with Draft bill of quantities for uploading on department website notification No. Pr. Secy (PW) to the Govt. of HP letter No. PBW(B)A (3)1/82020 dated Sh the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and in interest.

Encl: As above


**Executive Engineer,
HPPWD Division, Una,
Distt. Una HP).**

Copy along with copy of press note is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.


**Executive Engineer,
HPPWD Division, Una,
Distt. Una HP).**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. or behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 16.11.2024 up to 12.00 (Non).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 16.11.2024 up to 3.00 PM
3. Date of receipt of tenders: - 18.11.2024 up to 10.30 AM
4. Date of opening of tenders: - 18.11.2024 at 11.00 AM


Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	R/O & R/D on link road Singan to HP Boundary Km 0/00 to 1/300 (SH: C/o Cross Drainage at RD 0/380)	4,64,189/-	9300/-	Two months	350/-	Class- C & D
2	A/R & M/O on link road Jaijon Morh to Saloh Chowk Km 0/0 to 1/500 (SH: C/o U-shape drain at RD 0/450 to 0/520 RHS)	4,90,473/-	9800/-	Two months	350/-	Class- C & D
3	A/R & M/o link road to Lower Manuwal to Upper Mannual Km 0/0 to 1/200, Polian Janani road Km 0/0 to 6/00 & link road to co-operative Society Haroli via GSSS Haroli Km 0/0 to 2/225 (SH: Repair of pot holes at various RDs)	4,95,909/-	9900/-	One month	350/-	Class- C & D
4	C/o link road from Panodoga barrier Panjavar road to SC community. Ward No.6 GP Upper Panjavar Km 0/0 to 0/700 (SH: C/o CC pavement Km 0/0 to 0/096) under MMSY	4,98,173	10000/-	Two months	350/-	Class- C & D
5	C/o Old Saloh Bhadouri road Km 0/0 to 9/615 (SH: C/o CC pavement at RD 6/530 to 6/607) Deposit work	4,97,574/-	10000/-	Two months	350/-	Class- C & D
6	C/o Harijan Basti Khad to Khas Khad (SH :- C/o Edge wall with V-shape drain RD 0/0 to 0/100-BHS & CC overlay at RD 0/00 to 0/088) Deposit work	4,97,940/-	10000/-	Two months	350/-	Class- C & D
7	Upgradation of Panjavar Bathri road from Km 28/00 to 34/000 (SH: Preparation of DPR , Filling Weight Deflectometer Test using FWD equipment and CBR Test)	3,63,0000/-	7300/-	Two months	350/-	Class- C & D
8	C/o link road from House of Champa Devi Km 0/0 to 1/200 (SH: C/o R/wall at RD 1/169 to 1/200 RHS) Deposit work	4,85,195	9700/-	Two months	350/-	Class- C & D
9	A/R & M/o on Ajouli Santokhgarh Polian Jaijon road Km 0/00 to, 17/400 (SH: Writing letters & painting on bridges at RD 4/781, 5/410 & 6/050 i/c parapets)	4,97,118/-	10000/-	One month	350/-	Class- C & D
10	Construction/Renovations of Shamshanghat/Moksh Dham in village Gondpur Jai Chand (SH: P/L 60mm thick paver block on approach road to Moksh Dham) Deposit work	4,94,405/-	9900/-	Two months	350/-	Class- C & D
11	Upgradation of Panjavar Bathri road from Km 18/00 to 23/000 (SH: Preparation of DPR , Filling Weight Deflectometer Test using FWD equipment and CBR Test)	3,02,500/-	6000/-	Two months	350/-	Class- C & D
12	C/o link road Saloh Nursery to Harijan Basti Saloh km 0/0 to 1/200 (SH:- P/L paver blocks on both side of road at RD 0/700 to 0/766) Deposit Work	4,85,999/-	9700/-	Two months	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -


1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh.


Certificate

Certified that tenders for the works called vide this office letter No.PW/HD/CB/T-1/2024- 4090-91 dated 08/11/2024 are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
HPPWD Division, Una,
Distt Una HP).

54

DRAFT SCHEDULE OF QUANTITY

Name of work :Restoration of rain damage on link road Singan to HP Boundary Km 0/00 to 1/300 (SH: C/O cross drainage at RD 0/380)									
S. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost	Earnest Money	Time limit	AMOUNT
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	116.40	Per cubic metre	160.00	Rupees One hundred sixty only			Two months	18624
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement stone aggregate 40mm (forty Millimeter) nominal size in or under water/ broken complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	125.22	Per cubic metre	3250.00	Rupees three thousand two hundred fifty only				406965
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	55.00	Each	160.00	Rupees One hundred sixty only				8800
4	Providing and laying non-pressure NP-2 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : two fine sand) including testing of joints etc. complete 900mm dia RCC pipe including carriage of materials within all leads and lifts. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.50	Per Running metre	4000.00	Rupees four thousand only				10000

5	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	36.00	Per cubic metre	550.00	Rupees Five thousand five hundred fifty only	19800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)©(17/2/0212 dated 7.8.2018				Total:	464189
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					

DMT approved for Rs. 41,641,891/-
 CRUPTERS FOR INC SIXTY FOUR THOUSAND
 ONE HUNDRED EIGHTY NINE ONLY


 Executive Engineer
 Haroli Division
 HP.PWD., Haroli

Q-2

DRAFT SCHEDULE OF QUANTITY									
Name of work :A/R & M/O on link road Jaijon Morh to Saloh Chowk Km 0/00 to 1/500 C/O U- shape drain at RD 0/450 to 0/520- RHS)				(SH:					
					Estimated Cost	490473			
					Earnest Money	9800/-			
					Time limit	Two months			
S. No.	Description of work	Quantity	Unit	RATE		AMOUNT			
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	132.30	Per cubic metre	160.00	Rupees One hundred sixty only	21168			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg(Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	92.40	Per cubic metre	3800.00	Rupees three thousand eight hundred only	351120			
3	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five)design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.63	Per cubic metre	5500.00	Rupees Five thousand five hundred only	30965			

4	Supplying fitting and placing HYSD bar in reinforcement in foundation complete as per drawing and technical specification clause—1002, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	0.98	Per Tonne	89000.00	Rupees eighty nine thousand only	87220
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)©(17)2/0212 dated 7.8.2018				Total:	490473
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					

PW-T approved for Rs 490473/-
 [Rupees four lac ninety thousand four
 Hundred seventy three] only


 Executive Engineer
 Haroli Division
 HP.PWD., Haroli

DRAFT SCHEDULE OF QUANTITY						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	49.18	Per cubic metre	1350.00	Rupees One thousand three hundred fifty only	66393
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty,malkhana toll taxes,GST, labour cess or taxes imposed by the Government	655.75	Per square metre	55.00	Rupees Fifty five only	36066
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification, clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1311.50	Per square metre	300.00	Rupees Three hundred only	393450
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018				Total:	495909
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Approved for Rs 495,909/-
 Pm-Lac Ninety Five Thousand Nine
 Hundred and Fifty only

Executive Engineer
 Haroli Division
 HPPWD

DRAFT SCHEDULE OF QUANTITY						
Name of work: C/O link road from Pandoga Barrier Panjawar road to SC Community, ward No 6 G.P. Upper Panjawar Km 0/00 to 0/700 (SH:-C/O C.C. pavement Km 0/00 to 0/096)) -under MMSY					Estimated Cost	498173
					Earnest Money	10000/-
					Time limit	Two month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	17.28	Per cubic metre	160.00	Rupees One hundred sixty only	2765
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg(Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.92	Per cubic metre	3800.00	Rupees three thousand eight hundred only	98496
3	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC , and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.84	Per Cubic metre	1050.00	Rupees One thousand fifty only	29232

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana , toll tax, GST, labour cess or other taxes imposed by the Government..	27.84	Per cubic metre	3250.00	Rupees three thousand two hundred fifty only	90480
5	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five)design mix to obtain the minimum crushing strength of 25 N/mm ² (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty, malikana , toll tax, GST, labour cess or other taxes imposed by the Government.	50.40	Per cubic metre	5500.00	Rupees Five thousand five hundred only	277200
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)/17/20212 dated 7.8.2018				Total:	498173
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

PHIT approved for Rs 498173/-
 [Rupees Four Lac Ninety Eight Thousand
 One Hundred Seventy Three] only

Executive Engineer
 Haroli Division
 HPPWD

DRAFT SCHEDULE OF QUANTITY									
Name of work : C/O Old Saloh Bhadouri road Km 0/00 to 9/615 (SH: C/O C.C. pavement at RD 6/530 to 6/607)- Deposit work									
Job No-4									
Estimated Cost 497574/-									
Earnest Money 10000/-									
Time limit Two months									
AMOUNT									
RATE In									
Figures									
Words									
Rupees Seven thousand one hundred eighty only									
497574									
Total: 497574									
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)/©(17)20212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									

[NOT approved for Rs 497574]
 [Rupees four lac Ninety seven Thousand five hundred seventy four] only

Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

DRAFT SCHEDULE OF QUANTITY

Name of work :C/O Harijan Basti Khad to Khas Khad (SH: C/O edge wall with V-shape drain RD 0/00 to 0/100-BHS & C.C. overlay at RD 0/00 to 0/088)- Deposit work				Estimated Cost		497940/-
				Earnest Money		10000/-
				Time limit		Two months
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	52.50	Per cubic metre	160.00	Rupees One hundred sixty only	8400
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg(Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	71.80	Per cubic metre	3800.00	Rupees three thousand eight hundred only	272840
3	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five)design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	39.40	Per cubic metre	5500.00	Rupees Five thousand five hundred only	216700
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@ (17/2/0212 dated 7.8.2018				Total:		497940
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer,
H.P.P.W.D. Division Haraji
Distt. Una (H.P.)

PMIT approved for Rs. 497940/-
(Rupees Four Lacs Ninety Seven Thousand Nine Hundred Forty) only

Draft Schedule of Quantity

Estimated cost : 363000
Earnest Money : 7300
Time Limit : Two Month

Name of Work : Upgradation of Panjawan Bathri road from km-28/000 to km-34/000. (SH: Preparation of Detailed Project Report , Falling Weight Deflectometer Test using FWD equipment and CBR Test).

S. No.	Description of item	Quantity	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation of detailed project report which include the following provision as given below:- a) Topography survey by digital total station with two second accuracy, showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, schools, Habitants villages etc. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the b) Draw cross-sections at 15m (fifteen meter) intervals, L-section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable. c) Preparation of survey plan showing all provision and preparation of detailed project report as per MORD Guidelines. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	6 000	Per Kilometre	30000.00	Rupees Thirty Thousand only	180000
2	Falling Weight Deflectometer (FWD) test for Pavement Design of IRC:115-2014. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	6 000	Per Kilometre	20000.00	Rupees Twenty Thousand only	120000
3	CBR-Value & Pavement design of crust as per IRC:37-2012/ SP:72-2015. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	18 00	Each	3500.00	Rupees Three Thousand Five Hundred only	63000
Total =						363000

Conditions: 1. 75 % payment will be released after submission DPR complete in all respect in Divisional level.
2. 25% payment will be released after approved by Chief Engineer Hamirpur.

Executive Engineer,
Haroli Division,
H.P. PWD, Haroli.

EMT approved for Rs 3,63,000/-
Orders Three lac Sixty Three Thousand
Only

DRAFT SCHEDULE OF QUANTITY									
Name of work : C/O link road from House of Champa Devi Km 0/00 to 1/200 (SH: C/O retaining wall at RD 1/169 to 1/200-RHS)- D/work							Estimated Cost	485195/-	
							Earnest Money	9700/-	
							Time limit	Two months	
S. No.	Description of work	Quantity	Unit	RATE In		Figures	AMOUNT		
							Words	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octori, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	33.48	Per cubic metre	160.00	Rupees One hundred sixty only				5357
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	141.59	Per cubic metre	3250.00	Rupees Three thousand two hundred fifty only				460168
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octori, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	65.00	Each	150.00	Rupees One hundred fifty only				9750

4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	19.84	Per cubic metre	500.00	Rupees Five hundred fifty only	9920
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)20212 dated 7.8.2018				Total:	485195
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

DMT approved for Rs. 4,85,195/-
 Carped from lac Eighty five thousand on
 Hundred Five Only

Executive Engineer
 Haroli Division
 HP.PWD., Haroli

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 497118/-
Earnest Money 10000/-
Time limit One month

Name of work:- A/R & M/O on Ajouli Santoshgarh Polian Jaigon road Km 0/00 to 17/400
(SH:-Writing letters and painting on bridges at RD 4/781, 5/410 & 6/050 i/c parapets)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	3386.00	Per cubic metre	132.00	Rupees one hundred thirty two only	446952
2	Writing letter of figures on any surface with black japan paint including stops, commas, hyphen extra including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	33895.90	Per letter per centimetre height	1.48	Rupees one and paise forty eight only	50166
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total	497118
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					

Price approved for Rs 497118/-
[Rupees four lakh Ninety seven thousand One Hundred Eighteen] only

Executive Engineer
Haroli Division
HPPWD

DRAFT SCHEDULE OF QUANTITY

Name of work :Construction / Renovation of Shamshanghat / Mokash Dham in village Gondpur Jai Chand , G.P Gondpur Jai Chand (SH: P/L 60mmthick paver block on approach road to Mokash Dham)- Deposit work				Estimated Cost		494405/-
				Earnest Money		9900/-
				Time limit		Two months
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST ,labour cess or other taxes imposed by the Government.	5.00	Per cubic metre	150.00	Rupees One hundred sixty only	800
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	18.90	Per cubic metre	250.00	Rupees two hundred fifty only	4725
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	48.00	Per cubic metre	3250.00	Rupees Three thousand two hundred fifty only	156000

4	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	33.60	Per Cubic metre	1050.00	Rupees One thousand fifty only	35280
5	Providing and fixing heavy duty precast cement concrete interlocking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	336.00	Per square metre	800.00	Rupees eight hundred only	268800
6	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.40	Per cubic metre	4500.00	Rupees Four thousand five hundred only	28800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)/20212 dated 7.8.2018				Total:	494405
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP.PWD.,Haroli

Draft Schedule of Quantity

Estimated cost : 302500
 Earnest Money : 6000
 Time Limit : Two Month

Name of Work : Upgradation of Panjawan Bathri road from km-18/000 to km-23/000. (SH: Preparation of Detailed Project Report , Falling Weight Deflectometer Test using FWD equipment and CBR Test).

S. No.	Description of item	Quantity	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation of detailed project report which include the following provision as given below:- a) Topography survey by digital total station with two second accuracy, showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, schools, Hadditants villages etc. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes b) Draw cross-sections at 15m (fifteen meter) intervals, L-section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable. c) Preparation of survey plan showing all provision and preparation of detailed project report as per MORD Guidelines. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	5.000	Per Kilometre	30000	Rupees Thirty Thousand only	150000
2	Falling Weight Deflectometer (FWD) test for Pavement Design of IRC:115-2014. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	5.000	Per Kilometre	20000	Rupees Twenty Thousand only	100000
3	CBR-Value & Pavement design of crust as per IRC:37-2012/ SP:72-2015. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	15.00	Each	3500	Rupees Three Thousand Five Hundred only	52500
Total =						302500

Conditions: 1. 75 % payment will be released after submission DPR complete in all respect in Divisional level.
 2. 25% payment will be released after approved by Chief Engineer Hamirpur.

Executive Engineer,
 Haroli Division,
 H.P. PWD, Haroli.

212

DRAFT SCHEDULE OF QUANTITY									
Name of work: C/O link road Saloh Nursery to Harijan Basti Saloh Km 0/00 to 1/200 (SH:- P/L paver block on both side of road at RD 0/700 to 0/766) - Deposit work									
S. No.	Description of work	Quantity	Unit	Figures	RATE In		Estimated Cost	485999	Two month
					Words	Amount			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	87.12	Per cubic metre	160.00	Rupees One hundred sixty only	13939	9700/-		
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.80	Per cubic metre	1050.00	Rupees One thousand fifty only	20790			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.40	Per cubic metre	3250.00	Rupees three thousand two hundred fifty only	85800			
4	Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size 60mm thickness and pattern, finishing and sweeping extra sand (Laying in Checked tiles) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	264.00	Per square metre	1120.00	Rupees one thousand one hundred twenty only	295680.00			

