



**Office of the Executive Engineer, Division Kalpa (B&R)  
HP.PWD; Kalpa District Kinnaur Himachal Pradesh**

Phone No. 01786-226027 Web: www.hppwd.gov.in Email: hp-kin@nic.in Fax No. 01786-226027

No:- PW/KNR-E-Tender/2024/-4535-37

Dated:- 11/11/2024

To

The Executive Engineer (IT Cell),  
HP.PWD. Shimla-2.

**Subject:-**

**Publication of Tender Notice (OFFLINE )**

Enclosed please find herewith the Tender of works costing below 5.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity  
& Certificate.

Executive Engineer,  
Kalpa Division,  
HP.PWD; Kalpa.



**Copy forwarded for information to:-**

1. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.

Executive Engineer,  
Kalpa Division,  
HP. PWD; Kalpa.

## CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2024/-..4.522-52.....dated ....11/11/2024.... from Sr. No. 1 to 10 are of urgent nature and public interest.

  
**Executive Engineer,  
Kalpa Division,  
HP.PWD; Kalpa.**  


### HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP.PWD; Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **19-11-2024 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M. on 18-11-2024** No application for issue of tender forms will be received on **18-11-2024 after 4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.


Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Annual repair and maintenance of link road from Hong Dogri to Leo Bridge Km. 0/00 to 5/200. (SH:- Repair of pot holes at various RD's Job No.1)	4,99,033/-	10,000/-	One Month	350/-	D Class
2	Annual repair and maintenance of link road from Hong Dogri to Leo Bridge Km. 0/00 to 5/200. (SH:- Repair of pot holes at various RD's Job No. 02)	3,59,752/-	7500/-	One Month	350/-	D Class
3	Annual repair and maintenance of Peo Kalpa C.P. road Km. 0/00 to 4/040. (SH:- Repair of pot holes from Km. 0/00 to 2/00)	4,95,357/-	10,000/-	One Month	350/-	D Class
4	Annual repair and maintenance of Peo Kalpa C.P. road Km. 0/00 to 4/040. (SH:- Repair of pot holes from Km. 2/00 to 4/040)	2,77,385/-	6000/-	One Month	350/-	D Class
5	Annual repair and maintenance of various roads in Kalpa section under Kalpa Sub-Division (SH:- Repair of pot hole at various roads Job No.-1)	4,97,684/-	10,000/-	One Month	350/-	D Class
6	Annual repair and maintenance of various roads in Kalpa section under Kalpa Sub-Division (SH:- Repair of pot hole at various roads Job No.-2)	4,94,983/-	10,000/-	One Month	350/-	D Class
7	Annual repair and maintenance of various roads under R/Peo Sub-Division (SH:- Providing and laying of hot applied thermoplastic road marking paint.	4,94,275/-	10,000/-	One Month	350/-	D Class

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
8	Annual repair and maintenance of various roads in Kalpa section under Kalpa Sub-Division (SH:- Supplying and stacking of Hume Pipe 600mm diameter)	1,66,583/-	4000/-	One Month	350/-	D Class
9	Annual repair and maintenance of Spillover Labrang Kanam road Km. 0/00 to 11/500. (SH:- Repair of pot holes at various RD's Job No.-01)	4,97,225/-	10,000/-	One Month	350/-	D Class
10	Annual repair and maintenance of Spillover Labrang Kanam road Km. 0/00 to 11/500. (SH:- Repair of pot holes at various RD's Job No.-02)	4,98,631/-	10,000/-	One Month	350/-	D Class

**Terms and conditions:-**

**Following documents should accompany the application for tenders:-**

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each item in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.

  
Executive Engineer,  
Kalpa Division,  
HP. PWD; Kalpa.

No.:- PW/KNR-E-Tender/NIT/2024- 4538-52

Dated:- 11/11/2024

**Copy forwarded for information to:-**

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.

  
Executive Engineer,  
Kalpa Division,  
HP. PWD; Kalpa.



①

## SCHEDULE OF QUANTITY

**Name of work:-** Annual repair and maintenance of link road from Hong Dogri to Leo Bridge Km 0/00 to 5/200  
**(SH:-** Repair of pot holes at various Rd's Job No.-01).  
**Estimated Cost :-** 4,99,033/-  
**Earnest Money :-** 10,000/-  
**Time :-** One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	830.250			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.68			Per Cubic meter	
	<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

2

## SCHEDULE OF QUANTITY

**Name of work:-** Annual repair and maintenance of link road from Hong Dogri to Leo Bridge Km 0/00 to 5/200

(SH:- Repair of pot holes at various Rd's Job No.-02).

Estimated Cost :- 3,59,752/-  
 Earnest Money :- 7,500/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2,503 and 508.1 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	598.50			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	13.47			Per Cubic meter	
	<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

(3)

**SCHEDULE OF QUANTITY**

Estimated Cost :- 4,95,357/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Annual repair and maintenance of Peo Kalpa C.P Road Km 0/00 to 4/040  
**(SH:-** Repair of pot holes from Km. 0/00 to 2/00).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2,503 and 508.1 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1860.00			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.98			Per Cubic meter	
	<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

29

## SCHEDULE OF QUANTITY

**Name of work:-** Annual repair and maintenance of Peo Kalpa C.P Road Km 0/00 to 4/040  
**(SH:-** Repair of pot holes from Km. 2/00 to 4/040).

Estimated Cost :- 2,77,385/-  
 Earnest Money :- 6,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	992.00			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.44			Per Cubic meter	
	<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.



5

## SCHEDULE OF QUANTITY

Estimated Cost :- 4,97,684/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Annual repair and maintenance of various roads in Kalpa Section under Kalpa Sub-Division  
 (SH:- Repair of pot hole at various roads Job No.-1).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	828.00			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.63			Per Cubic meter	
<b>Total:-</b>						

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

## SCHEDULE OF QUANTITY

**Name of work:-** Annual repair and maintenance of various roads in Kalpa Section under Kalpa Sub-Division  
**(SH:-** Repair of pot hole at various roads Job No.-2).  
**Estimated Cost :-** 4,94,983/-  
**Earnest Money :-** 10,000/-  
**Time :-** One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	823.50			Per Square meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.53			Per Cubic meter	
	<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY


Estimated Cost :- 4,94,275/-

Earnest Money :- 10,000/-

Time :- One Month

Name of work:- Annual repair and maintenance of various roads under R/Peo Sub-Division  
(SH:- Prividing and laying of hot applied thermoplastic road marking paint).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete with applicable specifications,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	425.00			Per Square meter	
	Total:-					

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD,Kalpa.

8

## SCHEDULE OF QUANTITY

**Name of work:-** Annual repair and maintenance of on various roads in Kalpa Section under Kalpa Sub-Division (SH:- ).  
(SH:-Supplying and stacking of Hume Pipe 600 mm diameter).

Estimated Cost :- 1,66,583 /-  
Earnest Money :- 4,000 /-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and stacking of 600 mm (Six hundred millimeter) daimeter Reinforced Cement Concrete Pipe NP2 as per Class Indian Standards vide IS Code 458:2003,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	35.00			Per Running meter	
	<b>Total:-</b>					

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.



**SCHEDULE OF QUANTITY**

**Name of work:-** Annual repair and maintenance of Spillover Labrang Kanam road Km. 0/00 to 11/500  
(SH:- Repair of pot holes at various Rd's Job No.-01).

Estimated Cost :- 4,97,225/-  
Earnest Money :- 10,000/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	954.00			Per Square meter	
	<b>Total:-</b>					

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Annual repair and maintenance of Spillover Labrang Kanam road Km. 0/00 to 11/500  
(SH:- Repair of pot holes at various Rd's Job No.-02).

Estimated Cost :- 4,98,631/-  
Earnest Money :- 10,000/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2,503 and 508.1 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	956.18			Per Square meter	
	Total:-					

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.