



OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-
To

5043

Dated:- 11


11
2024

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice
Inviting Tender for the loading on departmental web-site before 11.11.2024 per
notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No.
PBW(B)A(3)1/2020 dated 16 July, 2021. Certified that the works mentioned in the
Tender Notice are urgent in nature.

Encl:- As above.


**Executive Engineer,
B&R Division,
HP PWD Karsog**



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&I Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **23.11.2024 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 21.11.2024** for which the application should reach in this office **upto 1.00 PM 21.11.2024**.


The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/O ((repair of) restoration of rain damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- Removal of slips at various RDs) SDF/2024/68	1,88,964/-	3,800/-	Two months	350/-
2	Restoration of rain damages on Karsog to Kunhoo road Km. 0/00 to 10/00 (SH:- removal of slips at various RDs) NDF/2024/89	1,96,999/-	4,000/-	Two months	350/-
3	R/O ((repair of) restoration on Karsog Kanda road Km. 0/00 to 12/500 (SH:- Removal of slips at various RDs) NDF/2024/65	1,98,146/-	4,000/-	Two months	350/-
4	Restoration of rain damages on Megli Kot to Kukahan via Samphall road Km. 0/00 to 2/00 (SH:- Removal of slips at various RDs) NDF/2024/90	99,156/-	2,000/-	Two months	350/-
5	Balance work of repair and maintenance of Old Building Civil Hospital Karsog Tehsil Karsog Distt. Mandi H.P. (SH:- P/L preprinted sheet)	4,96,676/-	10,000/-	Three months	350/-
6	Construction of Chithadhartu to Nag Sunani road Km. 0/00 to 1/400 (P/L granular Sub-base (GSB) in Km. 0/700 to 1/050)	4,99,385/-	10,000/-	One month	350/-
7	Construction of Chithadhartu to Nag Sunani road Km. 0/00 to 1/400 (P/L granular Sub-base (GSB) in Km. 1/050 to 1/400)	4,99,385/-	10,000/-	One month	350/-


TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.

7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog


Dated:-


11/11/2024

No. PW-E-Tender-NIT/23

5044-51

1. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
2. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
3. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
4. All the Assistant Engineers, working under this Division.
5. Copy to Drawing & Account Branch.
6. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Estimated Cost 188964
Earnest Money 3800
Time Two Months

Name of Work:- RO (Repair of) Restoration of rain damages on Mamall Mehandl road Km. 0/00 to 19/00 (SH:- Removal of slips at various RD's) SDF/2024/68

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide slips in all kind of soil including excavation of saturated soil, boulder & rocky portion requiring wherever blasting and loading in tipper and disposal of unserviceable materials upto a distance of 1000 mtrs. and stacking of all useful/serviceable materials and neatly dressing the surface etc. as per technical specification 302.3 and 1611 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1574.70	Per Cubic Metre	120.00	188964.00	Rupees One Lakh Eighty Eight Thousand Nine Hundred Sixty Four and Paise Zero Only
Total in Figures					188964.00	
Quoted Rate in Figures			Select	#VALUE!	0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 196999
Earnest Money 4000
Time Two Months

Name of Work:- Restoration of rain damages on Karsog to Kuhnau road Km. 0/00 to 10/00 (SH:- Removal of slips at various RD's) NDF/2024/89

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide slips in all kind of soil including excavation of saturated soil, boulder & rocky portion requiring wherver blasting and loading in tipper and disposal of unseviceable materials upto a distance of 1000 mtrs. and stacking of all usefull/serviceable materials and neatly dressing the surface etc. as per technical sepciciation 302.3 and 1611 or as per direction of Engineer-in-Charge including carnage of material within all leads, lifts and other incidentals.	1641.66	Per Cubic Metre	120.00	196999.00	Rupees One Lakh Ninety Six Thousand Nine Hundred Ninety Nine and Paise Zero Only
Total in Figures					196999.00	
Quoted Rate in Figures			Select	#VALUE!	0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
GPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 198146
Earnest Money 4000
Time Two Months

Name of Work:- R/O (Repair of) Restoration of rain damages on Karsog Kanda road Km. 0/00 to 12/500 (SH:- Removal of slips at various RD's) NDF/2024/65

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide slips in all kind of soil including excavation of saturated soil, boulder & rocky portion requiring wherever blasting and loading in tipper and disposal of unserviceable materials upto a distance of 1000 mtrs. and stacking of all useful/serviceable materials and neatly dressing the surface etc. as per technical specification 302.3 and 1611 or as per direction of Engineer-in-Charge including carnage of material within all leads, lifts and other incidentals.	1651.22	Per Cubic Metre	120.00	198146.00	Rupees One Lakh Ninety Eight Thousand One Hundred Forty Six and Paise Zero Only
Total in Figures					198146.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words				#VALUE!		

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99156
Earnest Money 2000
Time Two Months

Name of Work:- Restoration of rain damages on Megli Kot to Kukahan via Samphall road Km. 0/00 to 2/00 (SH:- Removal of slips at various RD's) NDF/2024/90

Sub-Head and items of works.

Sr.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	826.30	Per Cubic Metre	120.00	99156.00	Rupees Ninety Nine Thousand One Hundred Fifty Six and Paise Zero Only
Total in Figures		Select	#VALUE!	99156.00	
Quoted Rate in Figures				0.00	
Quoted Rate in Words					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost:-
Earnest Money:-
Time:-

496676
10000
Three Month

Name of Work:- Balance work of Repair and maintenance of old building civil hospital Karsog Tehsil Karsog Distt. Mandi H.P (Sh:- P/L preprinted sheet)						
Sr. No.	Description Of Item	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in RS. P	Total Amount with all taxes including GST in Words
1	Providing and fixing 0.60mm thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preprinted iron J or L hooks, bolts and nuts 6mm dia metre with preprinted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge.	177.66	Sqm	2352.20	417892.00	
2	Providing and fixing 15 cm wide, 45 cm overall semicircular plain G.S. sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete.					
2.1	0.63 mm thick with zinc coating not less than 275 gm/m²	91.45	Rmtrs.	861.50	78784.00	
Total in Figures					496676.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				#NAME?		

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 499385
 Earnest Money 10000
 Time One Month

Name of Work:- Construction of road Chitadhartu to Nag Sunani road km. 0/00 to 1/400(SH:- P/L granular sub-base (GSB) in Km 0/700 to 1/050).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST In Words
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	184.67	Per Cubic Metre	2704.20	499385.00	Rupees Four Lakhs Ninety Nine Thousand Three Hundred Eighty Five and Paise Zero Only
Total in Figures					499385.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				#VALUE!		

Executive Engineer,
 Karsog Division,
 APPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 499385
Earnest Money 10000
Time One Month

Name of Work:- Construction of Chitadhartu to Nag Sunani road km. 0/00 to 1/400(SH:- P/L granular sub-base (GSB) in Km 1/050 to 1/400).

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST In Words
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	184.67	Per Cubic Metre	2704.20	499385.00	Rupees Four Lakhs Ninety Nine Thousand Three Hundred Eighty Five and Paise Zero Only
Total in Figures					499385.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words				#VALUE!		

Executive Engineer,
Karsog Division,
HPPWD, Karsog.