



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.THG/CB/TENDER/Tender Notice/2024

4659-61

Dated:-

11/11/2024

To

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.

Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 20.11.2024 upto 12:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 21.11.2024 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 22.11.2024 upto 10:30 AM |
| 4 | Date of opening of Tender | 22.11.2024 upto 11:00 AM |

Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	O/R of Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (SH:- C/O R/Wall in PCC M-15 at R.D.170/248 to 170/251	481541	9700	350/-	2 Months
2	2	O/R of Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (SH:- C/O R/Wall in PCC M-15 at R.D.170/251 to 170/253	321027	6500	350/-	2 Months
3	3	R/R Damages on Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (S.H:- Clearance of hillside choked drain between 177/000 to 188/000)	494000	10000	350/-	1 Month
4	4	A/R & M/O Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at various R.D.)	198000	4000	350/-	2 Months
5	5	Consultancy service for preparation and infrastructure map of NH-05 for Construction of Theog Bypass from Km174/040 to 176/400 (Devrighet to Premghat) on NH-22 (New NH-05) in the State of Himachal Pradesh	70800	1500	350/-	1 Months
6	6	C/O NH Office Building at theog & Narkanda Teh- Theog Distt.- Shimla (HP)	220000	4400	350/-	1 Month
7	7	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper at various RD .)	481400	10000	350/-	1 Month
8	8	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Excavator Cum loader for removal of nosw/slips at various RD	480700	10000	350/-	2 Month
9	9	O/R of Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:- Removal of Slips between 51/170 to 51/200, 51/310 to 51/343,51/380 to 51/407, 51/440 to 51/476, 51/530 to 51/561 and 51/627 to 51/662)	380440	7700	350/-	1Month

10	10	R/R Damages on Theog Kotkhai Hatkoti Road NH- 705 k.m. 0/0 to 69/00 (SH:- Welding of nut and bolts of single side double W-Beam metal crash barrier at K.M 30/0 to 49/00	495110	9900	350	1 Month
----	----	--	--------	------	-----	---------

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.
- 12 Works should be completed by the contractor within the stipulated period.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog
Dated 11/11/2024

No/PW/NH/CB/Tender/2024

4651-58

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Superintending Engineer NH Circle HP PWD Shimla . It is therefore requested to kindly issue the certificate the tender of above emergent nature in public interest.
- 4 All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog



NATIONAL HIGHWAY (NH-05)
HIMACHAL PRADESH PUBLIC WORKS DE-
PARTMENT DIVISION THEOG

Certificate

Certified that the tenders of works as called
vide this office NIT No/PW/NH/CB/Tender/2023- 4651-58 Dated
11/11/2024 are urgent nature and public interest.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Cost:-

481541

Earnest Money:-

9700

Time:- 2 Month.

Name of work :- O/R of Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (SH:- C/O R/Wall in PCC M-15 at R.D.170/248 to 170/251

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	38.70	Per Cum.	340.10	Rupees Three Hundred Forty and Paise Ten Only	13162.00
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	57.96	Per Cum.	7657.40	Rupees Seven Thousand Six Hundred Fifty Seven and Paise	443823.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	13.50	Per Rmt.	279.25	Rupees Two Hundred Seventy Nine and Paise Twenty Five Only	3770.00
4	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	8.10	Per Cum.	2566.15	Rupees Two Thousand Five Hundred Sixty Six and Paise Fifteen Only	20786.00
Total						481541.00
		(Quoted Rates in Figures)(+/-)		(.....%)		
		(Quoted Rates in words)(+/-)				

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:-

321027

Earnest Money:-

6500

Time:- 2 Month.

Name of work :- O/R of Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (SH:- C/O R/Wall in PCC M-15 at R.D.170/251 to 170/253

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	25.80	Per Cum.	340.10	Rupees Three Hundred Forty and Paise Ten Only	8775.00
2	Providing and laying Plain Cement Concrete in M15 Grade (Minimum 5.5 bags of cement per cum of concrete) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	38.64	Per Cum.	7657.40	Rupees Seven Thousand Six Hundred Fifty Seven and Paise Forty Only	295882.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	9.00	Per Rmt.	279.25	Rupees Two Hundred Seventy Nine and Paise Twenty Five Only	2513.00
4	Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	5.40	Per Cum.	2566.15	Rupees Two Thousand Five Hundred Sixty Six and Paise Fifteen Only	13857.00
Total						321027.00

(Quoted Rates in Figures)(+/ -)

(.....%)

(Quoted Rates in words)(+/ -)

Conditions

1 Rates shall be Quoted for all heights including all leads and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	494000
				Earnest Money	Rs:-	Rs:-10000 only.
				Time.	1 Month.	
R/R Damages on Kalka Shimla Wangtoo Road (NH-705) from Km 167/000 to 236/000 (S.H:- Clearance of hillside choked drain between 177/000 to 188/000)						
Sr. No	Description of item	Quantity	Unit	Rate	Rate in words	Amount
1	Removal of earth from the choked hill side drain and disposing it on the valley side manually	3800	Rmt	130	Rupees One Hundred Thirty Only	494000
	Total					494000
				(Quoted Rates in Figures)/(+/-)	(.....%)	
				(Quoted Rates in words)/(+/-)	(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theeg.

SCHEDULE OF QUANTITY				
			Estimated Rs:-	198000.00
			Cost:	
			Earnest Rs:-	4000
			Money	
			Time. 2 Month.	

Name of work :- A/R & M/O Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at various R.D.)					
--	--	--	--	--	--

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsability of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	180	hour	1100.00	Rupees one thousand one hundred only	198000.00
	Total					198000.00
	Total					
	(Quoted Rates in Figures)(+/-)			(.....%)		
	(Quoted Rates in words)(+/-)			(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

**Executive Engineer,
NH Division HPPWD,
Theog.**

SCHEDULE OF QUANTITY

			Estimated Cost:	Rs:-	70800.00
			Earnest Money	Rs:-	1500.00
			Time.	1 Month.	

NAME OF WORK :- Consultancy service for preparation and infrastructure map of NH-05 for Construction of Theog Bypass from Km174/040 to 176/400 (Devrighet to Premghat) on NH-22 (New NH-05) in the State of Himachal Pradesh

Sr. No.	Description of Item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Preparation and submission of Road side Infrastructure map of NH-05 (Construction of Theog Bypass from Km174/040 to 176/400 (Devrighet to Premghat) on NH-22 (New NH-05) in the State of Himachal Pradesh) showing the existing road way width, acquired width of road, marking all the existing structures on the road i.e all cross-drainage work, retaining walls, breast walls, and all other existing structures along the road side. Acquired width of the road should clearly be marked on the map duly authenticated by revenue department and to be verified width of the latest record of land acquisition Collector, Winterfield Shimla. The Maps should be submitted in triplicate Volumes not more than 10 Km width A1 laminated sheets in hard copy and KML File in Soft Copy. The Maps should be signed from the Revenue Department i.e Patwari, Kanungo and Tehsildar in the Scale 1:100.	2.36	Per K.M	30000.00		70800.0
	Total					70800.00
(Quoted Rates in Figures)(+/-)		(.....%)				
Conditions (Quoted Rates in words)(+/-)		(.....%)				

1 Rates shall be Quoted for all heights including all leads and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

DRAFT SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	220000
				Earnest Money	Rs:-	Rs:-4400 only.
				Time.	1 Month.	
Name of work:- C/O NH Office Building at theog & Narkanda Teh- Theog Distt.- Shimla (HP)						
Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Providing and fixing Fire extinguisher ISI mark (Stored pressure type) capacity 9.00 Kg (Nine Kilogram) duly ISI marked confirming to ISI : 15683 : 2006, with IS 14609, ISI marked ABC powder complete with squeeze grip release valve, discharge pipe locked arrangement pressure gauge, operation manual bracked with two screw and sleeve within all leads, lifts of material and other incidentals.	20	No.	11000	Rupees one thousand one hundred only	220000
	Total					220000
				(Quoted Rates in Figures)(+/-%)		
				(Quoted Rates in words)(+/-%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.**
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost**


**Executive Engineer,
NH Division HPPWD,
Theog.**

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	481400.00
				Earnest Money	Rs:-	10,000 only.
				Time.	1 Month.	
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper at various RD						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	83	Days	5800	Rupees Five Thousand Eight Hundred Only	481400
	Total					481400
				(Quoted Rates in Figures)(+/-)	(.....%)	
				(Quoted Rates in words)(+/-)	(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.


SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Rs:-	480700.00	
				Cost:		
				Earnest Rs:-	10000.00	
				Money		
				Time.	2 Month.	
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Excavator Cum loader for removal of Snow/slips at various RD .)						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of Snow / slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	437	hour	1100.00	Rupees one thousand one hundred only	480700.00
	Total					480700.00

	(Quoted Rates in Figures)(+/-)	(.....%)
	(Quoted Rates in words)(+/-)	(.....%)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

			Estimated	Rs:-	380440
			Cost:		
			Earnest	Rs:-	7700.00
			Money		
			Time.	1 Month.	

Name of work :-	Time.	Month.
O/R of Theog-Katkhai-Hatkoti Road (NH-705) from Km 0/00 to 69/00 (SH:-Removal of Slips between 51/170 to 51/200, 51/310 to 51/343,51/380 to 51/407, 51/440 to 51/476, 51/530 to 51/561 and 51/627 to 51/662)		

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Removal of landslide /unserviceable soil in all type of rock, including hard rock and opening of catchpits for choked culverts including cutting by a hydraulic excavator , loading and disposal upto10 km lead as per MORTH specification 2019 clause 3000 . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	1505.50	Per Cum.	252.70	Rupees Two Hundred Fifty Two and Paise Seventy Only	380440
	Total					380440
					(.....%)	
	Conditions				(Quoted Rates in words)(+/-)	

Conditions

1 Rates shall be Quoted for all heights including all leads and lifts.

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estt. Cost:- Rs:- 4,95,110= only

Earnest Money:- 9900.00 only

Time:- One Month.

Name of work :- R/R Damages on Theog Kotkhai Hatkoti road NH-705k.m. 0/0 to 69/00 (S.H:- Welding of nuts and bolts of Single side Double W- beam metal cresh barrier at k.m. 30/00 to 49/00).

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Welding of nuts and bolts of Single side Double W- beam metal cresh barrier at k.m. 30/00 to 49/00). including all require equipment complete including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	45010.00	Per Centimet re.	11.00	Rupees Eleven Only	495110
	Total					495110
	(Quoted Rates in Figures)(+-)				(.....%)	
	(Quoted Rates in words)(+-)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost
- 3 Cement Shall be procured HP state CIVIL Supply corporation.

Executive Engineer,
NH Division HPPWD,
Theog.