

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2024-25- 5810-12

Dated:- 12-11-2024

To

✓
The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.


Subject :-

Regarding publication of Tender Notice on departmental
website to be opened on 23.11.2024.

Enclosed please find herewith the tender notice alongwith schedule of quantity for
uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A
(3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in
public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.
2. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 23.11.2024 up to 2:00 PM and shall be opened on 23.11.2024 the same day at 2:30 PM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 22.11.2024 for which the applications should reach in this office up to 4.00 PM on 21.11.2024. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	A/R & M/O on Jagatpur Parduni road km.0/0 to 5/0. (SH:- Providing and laying Grating at 2/955 to 2/995).	Rs. 1,17,275/-	Rs. 2500/-	Three months	350/-	C & D Class
2	Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300. (SH:- Providing and laying WBM (Soling) grading-I in km. 0/0 to 0/450). Under DMFT.	Rs. 3,37,046/-	Rs. 7000/-	Two months	350/-	C & D Class
3	Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300. (SH:- Providing and laying WBM (Soling) grading-I in km. 0/450 to 0/900). Under DMFT.	Rs. 3,37,046/-	Rs. 7000/-	Two months	350/-	C & D Class
4	Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300. (SH:- Providing and laying WBM (Soling) grading-I in km. 0/900 to 1/300). Under DMFT.	Rs. 2,99,593/-	Rs. 6000/-	Two months	350/-	C & D Class
5	Restoration of rain damages to various roads under Bangran Section of Sub Division No. II HPPWD Paonta Sahib. (SH:-Hiring of JCB and tractor with trolley for removal of slips, Dressing of berms and cleaning of side drains, restoration of rain	Rs. 99,520/-	Rs. 2000/-	Two months	350/-	C & D Class


	cuts and filling of pot holes on various roads).					
6	Restoration of rain damages to various roads under Bhagani Section of Sub Division No. II HPPWD Paonta Sahib. (SH:-Hiring of JCB and tractor with trolley for removal of slips, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes on various roads).	Rs. 99,520/-	Rs. 2000/-	Two months	350/-	C & D Class
7	Restoration of rain damages on Rampurghat Nawada Manpur Deora road km. 0/0 to 8/415. (SH:- Construction of Retaining wall at RD.5/045 to 5/055)	Rs. 94,386/-	Rs. 2000/-	Two months	350/-	C & D Class
8.	Strengthening of link road from Rampurghat Nawada Manpur Deora Guruwala Singhpora road km. 0/0 to 8/400. (SH:- Hiring of JCB and Tractor with Trolley for filling of pot holes and road side katcha berms with granular material in km.0/0 to 1/500). Under DMFT).	Rs. 99,660/-	Rs. 2000/-	Two months	350/-	C & D Class
9.	Strengthening of link road from Rampurghat Nawada Manpur Deora Guruwala Singhpora road km. 0/0 to 8/400 (SH:- Hiring of JCB and Tractor with Trolley for filling of pot holes and road side katcha berms with granular material in km. 1/600 to 3/0). Under DMFT).	Rs. 99,660/-	Rs. 2000/-	Two months	350/-	C & D Class
10	A/R & M/O to link road Village Melion km. 0/0 to 1/0. (SH:- Construction of U-shape drain at RD. 0/530 to 0/600,V-Shape drain at RD. 0/600 to 0/875 & 250 mm dia pipe for crossing). Left side.	Rs. 4,05,500/-	Rs. 8200/-	Three months	350/-	C & D Class
11	A/R & M/O to link road Village Melion km. 0/0 to 1/0. (SH:- Construction of U-shape drain at RD. 0/527 to 0/600,V-Shape drain at RD. 0/600 to 0/875 & 250 mm dia pipe for crossing). Right side.	Rs. 4,18,360/-	Rs. 8500/-	Three months	350/-	C & D Class
12	Renovation of residential PWD Colony at Paonta Sahib H.P. (SH:- P/L Cement Concrete 1:4:8, C.C. flooring 1:2:4, PVC (D-Plast) pipe, grading roof treatment C.C 1:2:4 in existing building type-II qtr.Allotted to Sh. Ramesh Chand Beldar & Type -III qtr. Allotted to Sh.Sunil J.E. in existing PWD Colony.	Rs. 1,46,186/-	Rs. 3000/-	Three months	350/-	C & D Class

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis for bitumen work.



Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

Dated:- 12-11-2024

No.PWP/CB-Tender Notice/2024-25 5813-62

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.



Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib



Job No - 1

Draft Schedule of Quantity					
Name of work:- Restoration of rain damages on Jagatpur Parduni road Km 0/0 to 5/0. (SH):- Providing and laying Grating at RD 2/955 to 2/995)					
S.No	Sub heads and items of work	Qty	Unit	Rate in	
				Figures	Words
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting fixing in position and applying a priming coat of approved steel primer all all complete, including haulage of materials with in all leads, lifts and carriage of materials and as per the direction of the Engineer-in Charge.	1103.76	Per Kilogramme	106.25	Rs One hundred six and paise twenty five only
Total				117275	

Estimated cost:- 117275/- only
Earnest Money:- 2500/- only
Time:- Three Months



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-2

Name of work :- Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300 (SH:- Providing and laying WBM (Soling) grading - I in km 0/0 to 0/450) under DMFT.

SCHEDULE OF QUANTITY

Estimated cost :- Rs :- 3,37,046/-
Earnest Money:- Rs:- 7,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Preparation of sub grade by dressing to camber (earth work) for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD, Specifications, including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1582.88	Per Square metre	2.20	Rs. Two and paise twenty only	3482.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade completed as per HP.PWD specifications including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1582.88	Per Square metre	3.50	Rs. Three and paise fifty only	5540.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading - I as per Technical Specification Clause 405 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	158.29	Per cubic metre	2072.30	Rs. Two thousand seventy two and paise thirty only	328024.00
	Total:					337046.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No- 3

Name of work :- Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300 (SH:- Providing and laying WBM (Soling) grading - I in km 0/450 to 0/900) under DMFT.

Estimated cost :- Rs :- 3,37,046/-
Earnest Money:- Rs:- 7,000/-
Time:- Two Months.


Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Preparation of sub grade by dressing to camber (earth work) for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD. Specifications, including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1582.88	Per Square metre	2.20	Rs. Two and paise twenty only	3482.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade completed as per HP.PWD specifications including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1582.88	Per Square metre	3.50	Rs. Three and paise fifty only	5540.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading - I as per Technical Specification Clause 405 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	158.29	Per cubic metre	2072.30	Rs. Two thousand seventy two and paise thirty only	328024.00
Total:						337046.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-



Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No-4

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Sainwala to Majri Pahaduwalla Km. 0/0 to 1/300 (SH:- Providing and laying WBM (Soling) grading - I in km 0/900 to 1/300) under DMFT.

Estimated cost :- Rs :- 2,99,593/-
Earnest Money:- Rs:- 6,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Preparation of sub grade by dressing to camber (earth work) for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD. Specifications, including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1407.00	Per Square metre	2.20	Rs. Two and paise twenty only	3095.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and reolling the sub grade completed as per HP.PWD specifications including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1407.00	Per Square metre	3.50	Rs. Three and paise fifty only	4925.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading - I as per Technical Specification Clause 405 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	140.70	Per cubic metre	2072.30	Rs. Two thousand seventy two and paise thirty only	291573.00
Total:						299593.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No-5 63

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to various roads under Bangran Section of Sub Division No.II HPPWD Paonta Sahib. (SH:- Hiring of JCB and Tractor with trolley for removal of slips, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes on various roads.)				Estimated Cost:- 99520/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in	
					Words	Amount
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	64.00 hours	Per hour	1055.00	Rs. One thousand fifty five and zero paise only	67520.00
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	10.00 Days	Per day	3200.00	Rs. Three thousand two hundred and zero paise only.	32000.00
					G.Total	99520.00


Executive Engineer,
S. & R Division H.P. P.W.,
Paonta Sahib (H.P.) 173021

Job No-6 64

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to various roads under Bhagani Section of Sub Division No.II HPPWD Paonta Sahib. (SH:- Hiring of JCB and Tractor with trolley for removal of slips, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes on various roads.)						Estimated Cost:- 99520/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	64.00 hours	Per hour	1055.00	Rs. One thousand fifty five and zero paisa only	67520.00	
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	10.00 Days	Per day	3200.00	Rs. Three thousand two hundred and zero paisa only.	32000.00	
					G.Total	99520.00	

Executive Engineer,
4.4 & Division H.P. P.W.D.
Paonta Sahib (H.P.) 17307

Job No-7

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Rampurghat nawda Manpur Deora road km 0/0 to 8/415 (SH:- Construction of Retaining wall at RD 5/045 to 5/055)

Estimated cost :- Rs :94,386/-
Earnist Money:- Rs:- 2,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	8.30	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	1577.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	17.16	Per cubic metre	5180.00	Rs. five thousand one hundred eighty & paise Nil only	88889.00
3	Providing weap holes in plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structure with slope of 1 V:20 H towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	14.00	Each	280.00	Rs. Two hundred eighty & paise Nil only	3920.00
	Total :-					94386.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No-8

DRAFT SCHEDULE OF QUANTITY

Name of work :- Strengthening of link road from Rampurghat Nawada Manpur Deora Guruwala Singhpura road Km 0/0 to 8/400. (SH:- Hiring of JCB and tractor with trolley for filling of pot holes and road side katcha berms with granular material in Km 0/0 to 1/500.) (under DMFT)							Estimated Cost:- 99660/- Only. Earnest Money:- 2000 /- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	52.00 hours	Per hour	1055.00	Rs. One thousand fifty five only	54860.00		
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	14.00 Days	Per day	3200.00	Rs. Three thousand and two hundred only.	44800.00		
G.Total						99660.00		

Executive Engineer,
R. & R Division H.P. P. & J.
Poonia Sahib (H.P.) 193078

Job No-9

BILL OF MATERIALS SCHEDULE OF QUANTITY

Name of work :- Strengthening of link road from Rampurghat Nawada Manpur Deora Guruwala Singhpura road Km 0/0 to 8/400. (SH)- Hiring of JCB and tractor with trolley for filling of pot holes and road side katcha berms with granular material in Km 1/600 to 3/0 .) (under DMFT)									
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	Time Limit: - Two Months.		
				Figures	Words				
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	52.00 hours	Per hour	1055.00	Rs. One thousand fifty five only	54860.00			
2	Hiring of tractor with trolley l/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	14.00 Days	Per day	3200.00	Rs. Three thousand and two hundred only.	44800.00			
							G.Total		
						99660.00			


Executive Engineer,
S. & R. Division H.P. P.W.D.,
Rajendra Sahib (H.P.) 17695

Job No. 10.

Draft Schedule of Quantity						Estimated cost:-405500/- only
Name of work:- <i>A/R & m/o</i> Restoration of rain damages to link road Village Melion Km 0/0 to 1/0.(SH:- Construction of U-Shape drain at RD 0/530 to 0/600, V Shape drain at RD 0/600 to 0/875 & 250mm dia pipe for crossing).Left Side.						Earnest Money:- 8200/- only
Time:- Three Months						
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in	Amount
					Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	117.83	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	22388
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size)including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	0.40	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	1982
3	Providing and laying concrete 1:3:6 (One cement: three sand: six graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (Mechanical mix) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	53.36	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	289470
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	1.91	Per cubic metre	6120.30	Rs Six thousand one hundred twenty and paise thirty only	11690
5	Providing and laying 250 mm dia non pressure NP2 class (light duty) R.C.C pipes with fixing collar with cement mortar 1:2 (one cement : two sand) including testing of joints etc.including all leads lifts and carriage of materials, as per the direction of Engineer-In charge.	110.00	Per running metre	727.00	Rs Seven hundred twenty seven and paise eighty only	79970
					Total	405500


Executive Engineer,
Paonta(B&R)Division,
JP PWD Paonta Sahi

Job No. 11

Draft Schedule of Quantity

Name of work:- Restoration of rain damages to link road Village Melion Km 0/0 to 1/0, (SH:- Construction of U-Shape drain at RD 0/527 to 0/600, V Shape drain at RD 0/600 to 0/875 & 250mm dia pipe for crossing), Right Side.

Estimated cost:-418360/- only

Earnest Money:-8500/- only

Time:- Three Months

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	90.74	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	17240	
2	Providing and laying concrete 1:3:6 (One cement: three sand: six graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (Mechanical mix) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	60.54	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	328420	
3	Providing and laying 250 mm dia non pressure NP2 class (light duty) R.C.C pipes with fixing collar with cement mortar 1:2 (one cement : two sand) including testing of joints etc.including all leads lifts and carriage of materials, as per the direction of Engineer-In charge.	100.00	Per running metre	727.00	Rs Seven hundred twenty seven and paise eighty only	72700	
					Total	418360	

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job 12.

SCHEDULE OF QUANTITY

Name of work:- Renovation of residential PWD Colony at Paonta Sahib (H.P.) (S.H.- P/L Cement Concrete 1:4:8, C.C. flooring 1:2:4, PVC (D-Plast) pipe, grading roof treatment C.C. 1:2:4 in existing building of type-II qtr. Allotted to Sh. Ramesh Beldar & type-III qtr. allotted to Sh. Sunil J.E in existing PWD Colony)

Estimated cost :- Rs :- 1,46,186/-
Earnest Money:- Rs:- 3000/-
Time:- Three Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m for all kind of soil within all leads and lifts as per entire including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	13.42	Per cubic metre	171.40	Rupees one hundred seventy one and paise forty only.	2300.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	13.66	Per cubic metre	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only.	67688.00
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes 75mm conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (i) Single socketed pipes including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	30.00	Per metre	299.96	Rupees Two hundred ninety nine and paise ninety six only.	8999.00
4	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 75 mm bend including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	9.00	Each	241.50	Rupees Two hundred forty one and paise fifty only.	2174.00
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	51.27	Per square metre	378.65	Rupees Three hundred seventy eight and paise sixty five only.	19413.00
6	Providing & laying chicken mesh over roofing mixed with cement concrete roof treatment complete in all respect, including all leads, lifts, carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	75.45	Per square metre	231.00	Rupees Two hundred thirty one and paise Nil only.	17429.00
7	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size including all leads, lifts, carriage of materials & to the entire satisfaction of the Engineer-in-Charge.	4.62	Per cubic metre	6100.15	Rupees Six thousand one hundred and paise	28183.00
Total:-						146186.00

Quoted rate in Figure (+/-) (..... %)

Quoted rate in words (+/-) (..... %)

Condition :-

- The Rates should be quoted for all heights including all leads and lifts.
- The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer,
Paonta (B&R) Division,
HP.PWD, Paonta Sahib.