




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS,
AS CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-
24/- 14127-35 DATED 05-12-24 ARE URGENT
NATURE AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



**Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public Works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in**

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **21.12.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **20.12.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **19.12.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	A/R & M/O on Barot Nalohta road Km 0/00 to 15/225 (SH: C/O R/wall at RD 3/620 to 3/630)	Rs.2,07,608/-	Rs.4,200/-	Rs.350/-	Two Months
2	Special Repair of Rest House Baijnath (SH: Painting, Distemping, Aluminium door Shutter etc.)	Rs.2,72,485/-	Rs.5,500/-	Rs.350/-	Two Months
3	C/O Boundary Wall Divisional Store Baijnath (SH: C/O Boundary Wall)	Rs.4,99,583/-	Rs.10,000/-	Rs.350/-	Two Months
4	Balance work of Rain Shelter at Bhullana (SH: Providing and Fixing Sitting Bench, Railing & Gate)	Rs.43,312/-	Rs.900/-	Rs.350/-	One Month
5	C/O Bridge over Binwa Khad at Balh Raina Bari Road (SH: C/O R/Wall/Approaches at RD 0/724 to 0/741 & 0/741 to 0/755.50)	Rs.4,83,404/-	Rs.9,700/-	Rs.350/-	Two Months
6	C/O Link Road from Danpathar to Babal Mehal road Km 1/00 to 1/450 (MNP) (SH: P/L G-II & C.C. Pavement at km 0/00 to 0/100)	Rs.3,21,212/-	Rs.6,500/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/-

14127 -35

Dated:-05.12.2024

- Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: A/R & M/O on Barot Nalohia road km 0/00 to 15/225.
(Sh:- C/O R/wall at RD 3/620 to 3/630).

Estimate Cost: 2,07,608.00/-
Earnest Money: 4,200.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.90	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	38.30	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.80	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.00	Each			
Total						


Engineer
Division
H.P.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(2) (A)

Name of work :- Special Repair of Rest House Baijnath
(SH:- Painting, Distemping, Aluminium door Shutter Etc)

Estimate Cost: 2,72,485 .00
Earnest Money: 5,500.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	554.82	Per square metre			
2	Wall painting with acrylic exterior emulsion paint of approved brand and manufacture to give an even shade as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	16.42	Sqm			
3	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1274.15	Per square metre			
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	301.80	sqm			
5	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approval make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868.) Minimum anodic coating of grade AC 15) fixed with rawplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junction, at top- bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-in-Charge. For doors windows and ventilations and glazed partitions frames as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.30	Per rmt			

6	Providing and fixing factory made shutters of Pre laminated particle board flat pressed three layer graded wood particle board with one side decorative finish and other side balancing lamination conforming to IS: 12823 Grade I Type II, of approved design, and edges sealed with water resistant paint and lipped with aluminium 'U' type edge beading all-round the shutter, including fixing with angle cleat, grip strip, cadmiu plated steel screws, including fixing of aluminium hinges 100x63x4 mm etc. complete as per architectural drawing and direction of Engineer-In-Charge (Cost of 'U' beading and hinges will be paid for separately).	15.41	Per square metre			
7	Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary plain glass 4mm thick The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.78	Sqm			
8	Providing and fixing G.I. pipes complete with G.I. Fittings including trenching and refilling etc. :20 mm (Twenty Millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Rmt			
9	Providing and Fixing Composite End Seal Compression Fitting of approved brand ISI Mark as per IS-15450-2004 for Cold Water Supply Reducer 2025 * 1216 as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			
10	Providing and fixing 32mm (Thirty two milimetres) nominal size diameters M.I. union for wash basin sink, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each			
11	Providing and fixing composite end seal compression fittings Female elbows 1216 X 15 mm (fifteen millimeter) thread Size as per IS-15450-2004 for cold water supply e.g. tees, elbows, reducers, connectors, couplers and clamps with jointing testing and fittings complete including cutting and making good the walls etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each			
12	Providing and fixing female socket including entire carriage of materials within all leads and lifts as per directions of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			
13	Providing and fixing 10 mm nipple including entire carriage of materials within all leads and lifts as per directions of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			
14	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm (one point six seven ltr per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point two zero kilogram per ten square meter), Clause 13.46.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	97.82	sqm			

15	Providing and fixing Exhaust fan complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
16	Providing and fixing water purifier complete in all respect of kent or equivalent as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
17	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete. 125mm (one hundred twenty five millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.00	Each				
18	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :250x16 mm (two fifty into sixteen millimetre) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
19	Providing and fixing anodized aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.00	Each				
20	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :200x10 mm (two hundred into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
21	Providing and fixing aluminium hanger for cloths, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete two hundred into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
22	Providing and fixing Door Closer anodized colour and shade with bolts and nuts screws etc. complete and technical specifications including carriage of materials within all leads and lifts and other incidental The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				

Executive Engineer
 Bajinath Division
 H.P.P.W.D., Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

(36)

Name of Work: - C/O Boundary wall Divisional store Baijnath .
(SH:C/O Boundary wall .)

Estimate Cost: 4,99,583.00
Earnest Money: 10,000 .00
Time Limit :Two Months

SCHEDULE OF WORKS						
Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (fifty metre).All kinds of soil.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	48.06	cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:6:12 (one cement : six coarse twelve sand) : ten graded stone aggregate 40 mm (forty millimeter) nominal size The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	5.34	cum			
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm (twenty millimeter) nominal size upto plinth level with :Cement mortar 1:6 (one cement : six coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	33.82	cum			
4	Second class Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven Point Five) in superstructure above plinth level up to floor all level in all shapes and sizes in :Cement mortar 1:6 (one cement : six coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	27.95	cum			
5	Second class Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven Point Five) in foundations and plinth in :cement mortar 1:4 (one cement : four coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	9.76	sqm			

③(b)

6	20 mm (twenty millimeter) cement plaster of mix :1:6 (one cement: six coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	132.00	sqm				
7	Steel work welded in built up sections, trusses and frame work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. Clause 10.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	425.31	kg				
8	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm (one point six seven ltr per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point two zero kilogram per ten square meter). Clause 13.46.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	175.00	sqm				

Executive Engineer
Baibajinath Division,
H.F.H.P.P.W.D. Baibajinath, H.P.
2

Estimate Cost: 43,312.00
Earnest Money: 900.00
Time Limit: One Month

Description of work

Executive Engineer
Bajinath Division,
H.P.P.W.D. Bajinath (H.P.)

DNI/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Bridge over Binwa Khad at Balh Raina Bari Road
(Sh:- C/O R/W all / Approach at RD 0/724 to 0/741 and 0/741 to 0/755.50).

Estimate Cost: 4,83,404.00/-
Earnest Money: 9,700.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	27.10	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	89.58	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	19.56	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. Including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	44.00	Each			
Total						

Executive Engineer
Bajinath Division,
H.P.P.W.D. Bajinath (H.P.)

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Link Road from Daupather to Babal Mehal road km 1/00 to 1/450 (MNP)
(SH:-P/L G-II & C. C Pavement at km 0/00 TO 0/100)

Estimate Cost: 3,21,212.00/-
Earnest Money: 6,500.00/-
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.14	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	45.75	Per Cubic metre			
Total						

Executive Engineer
Bajinath Division,
H.P.R.W.D. Bajinath (H.P.)