




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2024-25/-
14811-19 DATED 11-12-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



**Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in**

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **26.12.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **24.12.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **23.12.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Construction of Raina Bari Balh Road Km 0/00 to 1/500 (SH: Construction of 1.00mtr span RCC Slab culvert at RD 0/524 & Edge wall (Approach wall)	Rs.2,65,614/-	Rs.5,400/-	Rs.350/-	Two Months
2	Construction of Raina Bari Balh Road Km 0/00 to 1/500 (SH: Construction of 1.00 mtr. Span RCC Slab Culvert at RD 0/494, 0/756 & various Edge wall (Approach wall)	Rs.4,88,664/-	Rs.9,800/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD.,Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/- **14811** — **19**

Dated:-11.12.2024

- Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD.,Baijnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

① ④

Name of Work: - Construction of Raina Bari Balh Road km 0/00 to 1/500

(SH:- Construction of 1.00 mtr span RCC slab culvert at RD 0/524 & Edge wall (Approach wall)

Estimate Cost: 2,65,614.00

Earnest Money: 5,400.00

Time Limit: Two Month

SL No.	Description of work	No. or Qty.	Unit	Rate to be entered by the		AMOUNT	
				Figures	Words	Rs.	P.
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. (Ordinary rock and hard rock) as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	37.56	Cum				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (P.C.C M-10-1:3:6 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.25	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	18.47	Cum				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.84	Cum				
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.69	Cum				
6	Supplying, fitting, and placing HYSD bar reinforcement in structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	320.50	Kg				

7	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	12.18	Per Cum			
8	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.36	Per Cum			
9	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.00	Each			

Executive Engineer
 Baijnath Division
 HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(2) (a)

Name of Work: - Construction of Raina Bari Balh Road km 0/00 to 1/500

(SH:- Construction of 1.00 mtr span RCC slab culvert at RD 0/494 , 0/756 & various Edge wall (Approach wall)

Estimate Cost: -4,88,664.00

Earnest Money:9,800.00

Time Limit : Two Month

SL No.	Description of work	No. or Qty.	Unit	Rate to be entered by the		AMOUNT Rs. P	
				Figures	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.(Ordinary rock and hard rock) as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	72.50	Cum				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (P.C.C M-10-1:3:6 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.50	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	36.94	Cum				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.68	Cum				
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800,1205.4 and 1205.5 RCC M-25 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.38	Cum				

(2) (b)

6	Supplying, fitting, and placing HYSD bar reinforcement in structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	641.00	Kg			
7	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidentals complete in all respect. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	16.63	Per Cum			
8	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.02	Per Cum			
9	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.00	Each			

Executive Engineer
Bajjnath Division,
H.P.P.W.D. Bajjnath (H.P.)