



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2024-

7120-7219

Dated : 04/12/24

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 11.12.2024 up to 04:00 PM
2. Date and time of issue of tender form : 11.12.2024 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 12.12.2024 11:00 AM
4. Date and time of opening of tender : 12.12.2024 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1	C/O Barach to Bahaldhar road km 0/0 to 2/0 (SH:- C/O 900 mm dia HPC at RD 0/135, 0/270 & 0/585) under MPN 5054-04-337-02.	458620.00	9200.00	350.00	Three months	Class D or above
2	R/R damages on Chopal Chowkia road km 0/0 to 10/0 (SH: Hiring of JCB for removal of Land slide/debris etc. on various RDs.)	153000.00	3100.00	350.00	One month	Class D or above
3	C/o link road from Sheetal Nallah to Karali km 0/0 to 0/750 (SH:- C/O Stone soling at RD 0/0 to 0/315) under MNP 5054-04-337-02	499143.00	10000.00	350.00	Three months	Class D or above
4	C/O link road from Alashna to Kharog km 0/0 to 1/0 (SH: Laying, Spreading and compacting stone aggregate WBM-G-I (Correction Layer) at various RDs and C/O HPC at RD. 0/630) under SCDP 5054-04-789-01-SOON	490859.00	9900.00	350.00	Three months	Class D or above
5	C/o Link road from Salashu Nallah to Sadhan km 0/0 to 0/700 (SH:- Cutting 5/7 mtr wide road at RD. 0/100 to 0/230) MNP 5054-04-337-02	495003.00	9900.00	350.00	One month	Class D or above
6	A/R & M/O to Nanhar to Malkot road km 0/0 to 4/650 (SH: C/o wire crate B/Wall at RD. 3/210 to 3/232.50)	482970.00	9700.00	350.00	One month	Class D or above
7	R/R damages on Chopal to Kumbra road km 0/0 to 18/200 (SH: C/O R/Wall at RD. 15/900 to 15/915)	499313.00	10000.00	350.00	Three months	Class D or above

8.	C/o link road from Kelvi to Lohana km 0/0 to 5/0 (SH: C/o Stone soling at RD. 3/510 to 3/860) under SCDP 5054-04-789-02	497963.00	10000.00	350.00	Three months	Class D or above
9.	Restoration of rain damages on various roads under Pulbahal Section under Chopal Sub-Division (SH: Hiring of JCB for removal of slips/debris at various reaches.)	183600.00	3700.00	350.00	One month	Class D or above
10.	Restoration of rain damages on various roads under Chambi Section under Chopal Sub-Division (SH: Hiring of JCB for removal of slips/ debris at various reaches.)	153000.00	3100.00	350.00	One month	Class D or above
11.	A/R & M/O Nanhar to Malkot road km. 0/0 to 4/650 (SH: C/o wire crated B/wall at R.D. 2/600 to 2/622.50)	269152.00	5500.00	350.00	One month	Class D or above
12.	R/R damages on Marog to Matal road km. 0/0 to 18/500 (SH: C/o wire crated R/wall at R.D. 17/740 to 17/755 and 18/120 to 18/135).	492517.00	9900.00	350.00	Three months	Class D or above
13.	R/R damages on Badlog to Jhina road km. 0/0 to 15/0 (SH: C/o B/wall at R.D. 4/700 to 4/720).	382188.00	8000.00	350.00	Two months	Class D or above
14.	R/R damages on Dhabas to Baghar road km. 0/0 to 9/0 (SH: C/o R/wall at R.D. 6/495 to 6/510).	474478.00	9600.00	350.00	Three months	Class D or above
15.	A/R & M/O Nanhar to Malkot road km. 0/0 to 4/650 (SH: C/o R/wall at R.D. 4/642.50 to 4/650)	470836.00	10000.00	350.00	Two months	Class D or above
16.	R/R damages on Chambi Badlog Jhina road km. 0/0 to 16/0 (SH: Hiring of JCB for removal of land slide/debris etc. on various RDs.).	102000.00	2100.00	350.00	One month	Class D or above.
17.	C/o link road from Manjholi to Lohan Dhar road km. 0/0 to 0/915 (SH: C/o Cutting 5/7 mtr wide at R.D. 0/250 to 0/555) under MNP 5054-04-337-02.	489735.00	10000.00	350.00	One month	Class D or above
18.	C/o Katli to Koftu road km. 0/0 to 3/0 (SH: Cutting 5/7 mtr wide road at R.D. 0/945 to 1/120) under MNP 5054-04-337-02.	481949.00	10000.00	350.00	One month	Class D or above


TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. Any Ambiguous/Conditional/Telegraphic tender(s) and the application received without earnest money or tenders submitted by fax/ mail/ whatsapp/ any other un-verified media shall not be entertained.
3. The contractors/firms should possess the following documents (photo copy to be self-attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders along-with application of tender form for the intended job.
 - b. Scanned Copy of the G.S.T. Certificate issued by the GST department, along-with an affidavit certifying the full knowledge of latest status of the GST no. stating whether it is in operative/active condition or not, at the time of submission of bid. The said certificate should invariably mention that the firm/contractor participating in the bid has nil pendency of GST-3B Return filing or dues towards the GST department upto the date of submission of bid.
 - c. A scanned copy of PAN (Permanent Account Number) issued by the Income Tax Department.
 - d. A scanned copy of EPF issued from the competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s) thereof.
5. Only two number of tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall have to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Labour cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will have to be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.

10. The tender form shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience. Though, the contractor/firm having past adequate experience shall be preferred.
12. The contractor who has failed to start/complete the work already allotted in his favour within the stipulated period shall not be issued tender forms.
13. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
14. Proxy applications will not be entertained.
15. The contractor shall have all required machinery such as Truck/Tipper, Mixer, Water Tank Vibrator, Paver etc. and shall provide the proof of machinery or owner's legal tie-up/arrangement which is a pre-requisite, illustrating that the party can deploy the relevant equipment and machinery.
16. If the date given above falls on a holiday, the tender documents shall be sold/opened on the succeeding working day.
17. TDS of GST and Income Tax will be deducted as per rates fixed by the Government.
18. The rates beyond +5% over will be rejected, even if in cumulative tender and besides this, the additional performance security will have to be borne @ 20% and 30% for unbalanced bid in case the rates are lower than 10%, but upto 20% and lower than 20%, but upto 30% respectively. The tender beyond 30% will also be accepted, however, with APS as applicable.
19. The contractor shall be responsible for rectifying defects noticed within 6 months from the date of completion of the work and the portion of security deposit shall be refunded after expiry of this period.
20. All kind of materials shall be arranged by the contractor/firm on their own from the authorised firm/principal manufacturer as envisaged under Schedule-'F', and procurement of cement from nearby go-down of Civil Supply against the permit/approval/award letter and consumption foresight attested by the AE concerned.
21. In the Jobs pertaining to hiring of JCB/Tipper, it will be the discretionary power of engineer-in-charge to deploy/engage the machinery as and when required. The contractor will be no authority to force the engineer-in-charge to engage/deploy his machinery when not needed.


CERTIFICATE

It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-

1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division,
HPPWD Chopal.

SCHEDULED OF QUANTITY.

①

Estimated Cost	Rs. 458620
Earnest Money	Rs. 9200
Time Allowed	One Month

Name of work C/O Barach to Bahaldhar road km 0/00 to 2/00

(SH : HPC 900mm dia at RD 0/135 to 0/270 & 0/585) under MNP 5354-04-337-02

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mts as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.76	195.00	Rupees one hundred ninety five and paise zero only	Per cubic metre	6778
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	119.43	210.00	Rupees two hundred ten and paise zero only	Per cubic metre	25080
3	Providing and laying plain cement concrete 1:6:12 (1 cement : 6 sand : 12 graded stone aggregate 40 mm nominal size mixing by mechanical concrete mixture 0.40/0.28 & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202 and 1203 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol 1 and as per direction of Engineer in Charge at site in all leads and lifts	14.55	4233.56	Rupees four thousand two hundred thirty three and paise fifty six only	Per cubic metre	61598
4	Providing and laying plain cement concrete 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20 mm nominal dia mixing by mechanical concrete mixing 0.40/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202 and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.19	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	Per cubic metre	142077
5	Providing and laying reinforcement cement concrete hume pipe 900mm dia np2 for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work back filling, concrete and masonry works in head walls and parapets clause 1106 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol 1 and as per direction of Engineer in Charge at site in all leads and lifts.	22.50	3882.55	Rupees three thousand eight hundred eighty two and paise fifty five only	Per running metre	87357

	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.23	5200.00	Rupees five thousand two hundred and paise zero only	Per cubic metre	115596
7	Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00	200.00	Rupees two hundred and paise zero only	Per running metre	1800
8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 Rubble stone laid 1:3 flagged stone flooring 20mm thick including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.35	739.00	Rupees seven hundred thirty nine and paise zero only	Per square metre	5432
9	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.58	950.00	Rupees nine hundred fifty and paise zero only	Per cubic metre	12901
	Quoted rate in figure.				Total	458620
	Quoted rate in words					


 Executive Engineer
 Capital Division (B & P)
 R.F.W.D. Chennai

DNT / SCHEDULED OF QUANTITY.

2

Estimated Cost	Rs. 153000
Earnest Money	Rs. 3100000
Time Allowed	10 Days

Name of work R/R damage on Chopal Chowkia road km 0/00 to 10/00

(SH : Hiring of JCB for removal of Land slide/debris etc. on various Rds)

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	150.00	1020.00	Rupees one thousand twenty and paise zero only	Per Hour	153000
	Quoted rate in figure				Total	153000
	Quoted rate in words.					

Conditions :-

- 1 All the P.O.L charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

DNT No 186 for the year 2024-25 duly approved for Rs. 153000/- only.

[Signature]
Executive Engineer
Chopal Division (B & R)

[Signature]

[Signature]
Assistant Engineer
B & R Sub Division
HPPWD Chopal

SCHEDULED OF QUANTITY.

(3)

Estimated Cost	Rs. 499143
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O Link road from Sheetal Nallah to Karali road km 0/00 to 0/750

(SH : C/O Stone Soling at RD 0/00 to 0/315) under MNP Sp54-04-33 7-02

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	248.33	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	52149
2	Stone soling properly hand packed filling interies with kharaia stone and consolidation with power road roller to the required gradient and camber including spreading watering and rolling of widding materials moorum or earth etc including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	248.33	1800.00	Rupees one thousands eight hundred and paisa zero only	Per cubic metre.	446994
	Quoted rate in figure.				Total	499143
	Quoted rate in words.					


Engineer
 Supply Division (B & S)
 B.P.W.D., Chennai

SCHEDULED OF QUANTITY.

(4)

Name of Work :- Construction of Link road from Alasna to Khrog KM 0/00 to 1/00. (SH:- Laying, spreading and compacting stone aggregate WBM-G-1 (Correction Layer) at various RDs., and C/O HPC at RD 0/630.) *under SCOP 5054-04-789-04 500N.*

Estimated Cost Rs. 490859/-

Earnest Money Rs. 99000/-

Time 30 Days

Sr No	Description Of Items	Quantity	In Figure	Rate		Unit	Amount
				In word			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains for all kinds of soil and ordinary rocks including dressing of sides and ramming of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	66.83	236.65	Rs. Two Hundred Thirty six point Six Five Only		cum	15815
2	Providing and laying in position cement concrete of 1:4:8 (one cement : four coarse sand : Eight graded stone aggregate) 20mm (forty millimetre) nominal size graded stone aggregate for all works including the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.30	4942.10	Rs. Four Thousand Nine Hundred Forty two Point Ten Only		cum	16309
3	Providing and laying in position cement concrete of 1:5:10 (one cement : five coarse sand : Ten graded stone aggregate) 20mm (forty millimetre) nominal size graded stone aggregate for all works including the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.22	4544.20	Four Thousand Five Hundred Forty four point Twenty only		cum	255475

4	Providing and laying in position cement concrete of 1:3:6 (one cement : Three coarse sand : Six graded stone aggregate) 20mm (forty millimetre) nominal size graded stone aggregate for all works including the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.3	5708	Rs. Five Thousand Seven Hundred Eight Only	cum	64500
5	Providing and laying reinforcement cement concrete pipe NP2 for culvert on first class bending of granular materials in single row including fixing collar with cement and masonry works in head walls and parapets clause 1108 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	7.50	3633.10	Rs. Three Thousand Six Hundred Thirty Three point Ten only	Root	27248
6	Providing weep holes in brick/ stone masonry/plain, reinforced concrete abutment, wing wall, return walls with 100mm dia PVC pipe extending through full width of the structure with slope of 1:20 towards drawing face complete as per technical specifications clause 614, 709, 1204.3.7 i/c carriage of material in all leads and lifts.	32.20	388.56	Rs. Three Hundred Eighty Eight point Fifty Six Only	Nos.	12512
7	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.	39.60	2500.00	Rs. Two Thousand Five Hundred Only	Cum	99000
G. Total						490859


 Engineer
 Regional Division (B & R)
 B.M.V.D. Odisha

SCHEDULED OF QUANTITY.

5

Estimated Cost	Rs. 495003
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O Link road from Salashu Nallah to Sadhan road km 0/00 to 0/700 (SH : Cutting 5/7 metre wide at RD 0/100 to 0/230) under MNP 5254-64-337-02						
Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in earth work in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification for Rural Roads clause 1600 and 300, 8.3 (ii)(iv)(v) to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, trimming, filling of uneven ness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. At least 266.34 Cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis if fails recovery @ Rs. 300/- (Rupees three hundred) per cum will be made. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2118.26	233.68	Rupees two hundred thirty three and paise sixty eight only	Per cubic metre.	495003
					Total	495003
	Quoted rate in figure.					
	Quoted rate in words.					

211
Executive Engineer,
B&R Division Hapur
Hapur

SCHEDULED OF QUANTITY.

Name of Work :- A/R & M/O on Nanahar to Malkot road KM 0/00 to 4/650. (SH-11/O CC B/Wall at RD 3/210 to 3/232.50).

Sr No	Description Of Items	Quantity	In Figure	Estimated Cost		Unit	Amount
				Earnest Money	Time		
							Rs. 482976/-
							Rs. 95000/-
							30 Days
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains for all kinds of soil and ordinary rocks including dressing of sides and ramming of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	286.43	210.00	Rs. Two Hundred Ten Only		Cum	60150
2	Providing and laying in position cement concrete of 1:4:8 (one cement : four coarse sand : Eight graded stone aggregate) 20mm (forty millimetre) nominal size graded stone aggregate for all works including the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	79.65	5200.00	Rs. Five Thousand Two Hundred Only		Cum	414180
3	Providing weep holes in brick/ stone masonry/plain, reinforced concrete abutment, wing wall, return walls with 100mm dia PVC pipe extending through full width of the structure with slope of 1:20 towards drawing face complete as per technical specifications clause 614, 709, 1204.3.7 i/c carriage of material in all leads and lifts.	43.20	200.00	Rs. Two Hundred Only		Cum	8640
G. Total							482970


 Executive Engineer
 Shopian Division (B & R)
 P. W. D. Chaudhary

SCHEDULED OF QUANTITY.

7


Estimated Cost	Rs. 499313
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : R/R damage on Chopal to Kumbra road km 0/00 to 18/200

(SH : C/O R/wall at RD 15/900 to 15/915.)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.25	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	11813
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33.75	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	175500
3	Providing weep holes in brick masonry plain/reinforced concrete abutment wing wall retaining wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (v) 20 (h) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.50	200.00	Rupees two hundred and paisa zero only	Per running metre.	4500
4	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and IS:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	93.75	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	271875

5	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	37.50	950.00	Rupees nine hundred fifty and paise zero only	Per cubic metre.	35625
					Total	499313
	Quoted rate in figure.					
	Quoted rate in words.					


 Executive Engineer,
 S&R Division Hyderabad
 Chopped

SCHEDULED OF QUANTITY.

Name of Work :- Construction of Link road from Kelvi to Lohana KM 0/00 to 5/00. (SH/C/O Stone Soling at RD 3/510 to 3/860. under SCDP 5254-04-789-01 800 N

Sr No	Description Of Items	Quantity	In Figure	Estimated Cost		Unit	Amount
				Earnest Money	Time		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains for all kinds of soil and ordinary rocks including dressing of sides and ramming of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	183.75	210.00	Rs. Two Hundred Ten Only		cum	38588
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP, PWD specification. 150 mm spread thickness (finished work including materials and labour)	183.75	2500.00	Rs. Nine Hundred Fifty Only		Cum	459375
G. Total							497963


 Engineer
 Regional Division (B & R)
 B & R, W. D. Chaurasi

(827)

(9)

DRAFT SCHEDULED OF QUANTITY.

Name of work:- Restoration of rain damage on Pulbatal Section under Chopal Sub- Division (SH :- Hiring of JCB for removal of slips /debris at various reaches.)

Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Unit	Amount	Estimated Cost
							Rs. 183600/-
1	Hiring of excavator-cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of Engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in charge and as per HPPWD specification of 1990 vol.1	180.00 hrs	1020.00	Rupees One Thousand and Twenty Only	Per Hour	183600	Rs. 2700/-
G. Total							183600

(Rupees One Lack eighty three thousand six hundred Only)

CONDITIONS :-

- 1 All the POL charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/ major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt. / Private property during course of work shall have to be made by the contractor.

Recommended for approval please.

Assistant Engineer

B&R Sub Division Chopal

HP. PWD Chopal Shimla

Executive Engineer

B&R Division Chopal

HP. PWD Chopal Shimla

NOT NO 827 for the year 2024-25
 duly approved for Rs. 183600/-
 only

(Signature)
 Executive Engineer,
 Chopal Division (B & R)
 H.P.P.W.D. Chopal

829

10

DRAFT SCHEDULED OF QUANTITY.

Name of work :- Restoration of rain damage on Chambi Section under Chopal Sub- Division (SH :- Hiring of JCB for removal of slips / debris at various reaches.)

Sr No	Description of Items	Quantity	Rate	Rate (in words)	Unit	Amount	Estimated Cost
							Rs. 153000/-
1	Hiring of excavator-cum-loader for removal of slips, dressing of berms etomimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of Engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in charge and as per HPPWD specification of 1990 vol.1	150.00 hrs	1020.00	Rupees One Thousand and Twenty Only	Per Hour	153000	Rs. 31,000/-
G. Total							153000

(Rupees One Lack fifty three thousand Only)

CONDITIONS :-

- 1 All the POL charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/ major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt. / Private property during course of work shall have to be made by the contractor.

Recommended for approval please.

DNIT No 829 for the year 2024-25
only approved for Rs. 153000/-


Assistant Engineer
B&R Sub Division Chopal
HP. PWD Chopal Shimla


Executive Engineer
B&R Division Chopal
HP. PWD Chopal Shimla

SCHEDULED OF QUANTITY.

11

Estimated Cost	Rs. 269152
Earnest Money	Rs. 5500
Time Allowed	One Month

Name of work : A/R & M/O on Nanhar to Malkot road km 0/00 to 4/650
(SH : C/O wire crate B/wall at RD 2/600 to 2/622.50)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	151.65	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	31847
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	79.65	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	230985
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (v):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.60	200.00	Rupees two hundred and paisa zero only	Per running metre.	6320
					Total	269152
	Quoted rate in figure.					
	Quoted rate in words.					

21
Chief Engineer
Road Division
B.P.N.D. Circle

DRAFT SCHEDULED OF QUANTITY.

(12)

Estimated Cost Rs. 492517/-
Earnest Money Rs. 4900/-
Time Allowed One Month

Name of work : R/R damages on Marog to Matai road km. 0/0 to 18/500 (SH: C/o wire crated R/wall at R.D. 17740 to 17755 and 18/120 to 18/135).

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation work by mechanical means (hydraulic excavator)/manual means in foundation trenches or drains for all kinds of soil and ordinary rocks including dressing of sides and rinning of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	45.00	210.00	(Rupees two hundred and ten) only.	Per cubic metre.	9450.00
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS : 280 and IS : 4826 in 100x100mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders not less than 25kg each as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	140.63	2900.00	(Rupees two thousand nine hundred) only	Per cubic metre.	407827.00
3	Stone filling with boulders behind retaining wall including carriage of all labour, material and equipment to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	79.20	950.00	(Rupees nine hundred fifty) only.	Per cubic metre.	75240.00
Total						492517.00

1. Page rates in figure :-
2. Page rates in word :-

DIT No. — for the year 2024-25 duly approved
for B. 492517/- only.

[Signature]
Sd/-
Engineer
Public Division (B & R)
B.P.V.D. Group

DRAFT/SCHEDULED OF QUANTITY.

(13)

Name of work : R/R damages on Badlog to Jhina road km 0/00 to 15/00.

(SH: C/O B/wall at RD 4/700 to 4/720.)

Estimated Cost	Rs. 382188
Ec. nest Money	Rs. 8000
Time Allowed	One Month

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	93.75	210.00	Rupees two hundred ten and paiza zero only	Per cubic metre.	19688
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	125.00	2900.00	Rupees two thousand nine hundred and paiza zero only	Per cubic metre.	362500
	Quoted rate in figure.				Total	382188
	Quoted rate in words.					

Note : Recovery of stone utilized at site will be effected @ Rs 300 per cum.

Schedule of Quantity
Approved for E 382188

21/4
~~EXECUTIVE ENGINEER,~~
B&R Division HPPWD
~~Chapal~~

533

DRAFT/SCHEDULED OF QUANTITY.

(14)

Estimated Cost	Rs. 474478
Earnest Money	Rs. 9500
Time Allowed	One Month

Name of work : R/R Damages on Dhabas to Baghar road km 0/00 to 9/00

(SH : C/O R/wall at RD 6/495 to 6/510)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	57.66	210.00	Rupees two hundred ten and paise zero only	Per cubic metre.	12109
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	164.06	2600.00	Rupees two thousand six hundred and paise zero only	Per cubic metre.	426556
3	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	37.70	950.00	Rupees nine hundred fifty and paise zero only	Per cubic metre.	35813
	Quoted rate in figure.				Total	474478
	Quoted rate in words.					

Note : Recovery of stone utilized at site will be effected @ Rs 300 per cum.

DAU 17 Approved for Rs 474478

Executive Engineer
B&R Division HPPWD
Chopal

SCHEDULED OF QUANTITY.

(15)

Estimated Cost	Rs. 470836
Earnest Money	Rs. 10000.
Time Allowed	One Month

Name of work : R/R damage on Nanhar to Malkot road km 0/00 to 4/650
(SH : C/O R/wall at RD 4/642.50 to 4/650 .)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.45	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	8915
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	79.88	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	415376
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	66.00	200.00	Rupees two hundred and paisa zero only	Per running metre.	13200
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.10	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	33345
	Quoted rate in figure.				Total	470836
	Quoted rate in words.					

(Signature)
 Regional Engineer
 Regional Division (B & D)
 B.P.O., D. District

SCHEDULED OF QUANTITY.

16

Estimated Cost	Rs. 102000
Earnest Money	Rs. 21000
Time Allowed	10 Days one month

Name of work R/R damages on Chambi Bading Jhina road km 0/00 to 16/00

(SH : Hiring of JCB for removal of Land slide/debris etc. on various Rds)

No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	100.00	1020.00	Rupees one thousand twenty and paise zero only	Per Hour	102000
	Quoted rate in figure				Total	102000
	Quoted rate in words					

Conditions :-

1. All the P.O.L charges shall be borne by the contractor.
2. All the repair of machineries shall be done by the contractor.
3. For any minor/major repair or any accident contractor shall be responsible.
4. Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

UNIT No. 189 for the year 2024-25 duly approved
172 Rs. 102000/- only.

[Signature]
Executive Engineer
Chopal Division (B & R)
B & R, W. D. Chopal

[Signature]
Assistant Engineer
B & R Sub Division
HPPWD Chopal

SCHEDULED OF QUANTITY.

(17)

Estimated Cost	Rs. 489735
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O Link road from Manjholi to Lohan Dhar road km 0/00 to 0/915.

(SH : C/O Cutting 5/7 mtr wide at RD 0/250 to 0/555) under MNP ss54-04-337-02

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
	Excavation in earth work in hilly area all heights and depths, in all kinds of soil including saturated soil comprising of pick work jumper work soft blast and hard blast and their intermediate classification of soil including dewatering where ever required setting out true to the required line grade sides slopes trimming bottom and levels as shown in the drawings and as per the direction of Engineer in Charge at site according to HPPWD specification 1990 VOL.1 and sorting out useful material and stacking the same in all leads and lifts in acquired width of road and transportation of the un-useful material of filling in roadways camber embankments for grade improvements and disposal of all useful materials of required width of the road or on approved dumping site through all modes of transportation including head load animals load or mechanical means along with is leveling fine dressing and carriage of all labour machineries materials tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour . All useful materials such as stone shingles aggregate and slates shall be sorted out and stacked along road sides which shall not be less the one third blasting work one sixth of blasting work and one tenth of jumper work it fails. At least 218.05 cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis @ Rs.300 per cum will be made any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. including all leads and lifts as per the direction of Engineer in Charge.	2255.70	217.11	Rupees two hundred seventeen and eleven paisa only	Per cubic metre.	489735
					Total	489735
	Quoted rate in figure.					
	Quoted rate in words.					


A.P.B. D. Chugh
 Chief Division (B & A)

SCHEDULED OF QUANTITY.

18

Estimated Cost	Rs. 481949
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O Katli to Kufu road km 0/00 to 3/00

(SH : Cutting 5/7 mtr wide at RD 0/945 to 1/120) under MNP 5054.04-337-02

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
	Excavation in earth work in hilly area all heights and depths, in all kinds of soil including saturated soil comprising of pick work jumper work soft blast and hard blast and their intermediate classification of soil including dewatering where ever required setting out true to the required line grade sides slopes trimming bottom and levels as shown in the drawings and as per the direction of Engineer in Charge at site according to HPPWD specification 1990 VOL.1 and sorting out useful material and stacking the same in all leads and lifts in acquired width of road and transportation of the un-useful material of filling in roadways camber embankments for grade improvements and disposal of all useful materials of required width of the road or on approved dumping site through all modes of transportation including head load animals load or mechanical means along with is leveling fine dressing and carriage of all labour machineries materials tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour. All useful materials such as stone shingles aggregate and slates shall be sorted out and stacked along road sides which shall not be less the one third blasting work one sixth of blasting work and one tenth of jumper work it fails. At least 130.25 cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis @ Rs.300 per cum will be made any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases, including all leads and lifts as per the direction of Engineer in Charge.	2605.13	185.00	Rupees one hundred eighty five and paisa zero only	Per cubic metre	481949
	Quoted rate in figure.				Total	481949
	Quoted rate in words.					

Chief Engineer
Road Division (B & P)
A. H. B. D. Choudhary