



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2024-25-

To

10338-390

Dated:-

7-12-2024

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2024-25/0335-390 dated..7-12-24.. is emergent nature and in Public interest.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.



Tel.01899-299219.

eepwd-chowari@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

Date of issued/sale of tender form against
Cash payment (nonrefundable).

13.12.2024

Date of opening of Tender:-

16.12.2024

The tender shall be received upto 11.00 AM on **16.12.2024** and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **16.12.2024**

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	C/o Ambulance road from main road to Samluna Ghattu via IPH colony km 0/00 to 1/200(Sh:- P/L C.C 1:4:8 and C.C Pavement work at rd.0/231 to 0/300).	447114.00	8990.00	Rs. 350/-	Three Month	Class-D & C
2	C/o Link road from Bad-Draman to Banoli road km 0/00 to 3/500(Sh:- C/o 900 mm dia hume pipe culvert at Rd 2/452 with wing wall)	499716.00	10000.00	Rs. 350/-	Three Month	Class-D & C
3	C/o Link road from Bad-Draman to Banoli road km 0/00 to 3/500(Sh:- C/o 900 mm dia hume pipe culvert at Rd 1/905 with wing wall)	499294.00	9994.00	Rs. 350/-	Three Month	Class-D & C
4	Restoration of rain damage on Chowari Mandhiar baloh fagot road km 0/00 to 13/330(Sh:- C/O R/wall at rd 4/060 to 4/075)	388801.00	7776.00	Rs. 350/-	Three Month	Class-D & C

5	Restoration of rain damage on Bounkhari Mour to Nagali road km 6/00 to 12/00 (Sh:- C/o r/wall at rd 11/430 to 11/437.50)	415220.00	8305.00	Rs. 350/-	Three Month	Class-D & C
6	C/o Fogla to Banoi road km 0/00 to 3/200(Sh:- C/o hume pipe culvert at rd 1/225)	488402.00	9768.00	Rs. 350/-	Three Month	Class-D & C
7	Improvement of formation cutting on Fogla to Banoi road Km 0/0 to 3/200 (Improvement of Grade and improvement of deficiencies at various RDs	488949.00	9780.00	Rs. 350/-	Three Month	Class-D & C
8	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti road Km 25/00 to 40/810 (SH: - C/o R/wall in PCC at Km 28/141 to 28/145 and C/o parapets).	496512.00	9930.00	Rs. 350/-	Three Month	Class-D & C
9	A/R & M/O various road under HPPWD, Sub division, Sihunta (SH: - Painting and lettering/writing of sign board, Kilometer stone culvert etc.).	481461.00	9629.00	Rs. 350/-	Three Month	Class-D & C
10	Repair of music department & physical education department building at Govt. Degree collage at Chowari in tensile Bhattiyat Distt. Chamba (SH:- P/L Painting work & Sanitary installation)	390135.00	7803.00	Rs. 350/-	Three Month	Class-D & C
11	Restoration of rain damage on Chowari to Mandhiar Baloh Fagot road Km 0/0 to 13/330 (SH: - C/o R/wall with Pustha at Rd 6/170 to 6/178).	463965.00	9280.00	Rs. 350/-	Three Month	Class-D & C
12	Restoration of rain damage on Nanikhed to Samlue road Km 0/0 to 30/585 (SH: - C/o CC R/wall at Rd 26/465 to 26/483).	496386.00	9973.00	Rs. 350/-	Three Month	Class-D & C
13	Construction of Fogla to Banoi road Km 0/0 to 3/200 (SH:- C/o 900 mm dia HP Culvert with wing walls at Rd 1/630).	491264.00	9974.00	Rs. 350/-	Three Month	Class-D & C
14	C/o link road Thulel to Anai road km 0/00 to 2/40(Sh:-C/o 900 mm dia hume pipe culvert at rd 1/360 with wing wall)	487750.00	9755.00	Rs. 350/-	Three Month	Class-D & C
15	C/o link road Thulel to Anai road km 0/00 to 2/40(Sh:-C/o 900 mm dia hume pipe culvert at rd 1/660 with wing wall)	492297.00	9846.00	Rs. 350/-	Three Month	Class-D & C
16	C/o link road from Garrnota (Badela) Pukharu via Padwal road km 0/00 to 6/180(Sh:- C/o 900 mm dia hume pipe culvert at rd 1/685 with wing wall)	485199.00	9704.00	Rs. 350/-	Three Month	Class-D & C
17	C/o link road Dugred to Naloh km 0/00 to 6/300(Sh:- C/o r/wall at rd 0/330 to 0/342.80)	366428.00	7328.00	Rs. 350/-	Three Month	Class-D & C

18	C/o link road from Garnota (Bhadela) Pukharu via Padwal road km 0/00 to 6/180(Sh:- C/o 900 mm dia hume pipe culvert at rd 1/825 with wing wall)	481171.00	9624.00	Rs. 350/-	Three Month	Class-D & C
19	C/o kiyod Malwan road km 0/00 to 3/300 (Sh:- C/o r/wall at rd 2/990 to 2/998 & 3/075 to 3/081)	496399.00	9928.00	Rs. 350/-	Three Month	Class-D & C
20	C/o Kiyod Malwan road km 0/00 to 3/300 (Sh:- C/o wire crate b/wall with pusta at rd 3/189 to 3/218))	494409.00	9888.00	Rs. 350/-	Three Month	Class-D & C
21	Periodical maintenance of various roads under Balera section under Sub-division Kakira (Sh:- Providing and laying hot applied thermoplastic compound 2.5mm thick line on various roads in Balera Section	299000.00	6000.00	Rs. 350/-	Three Month	Class-D & C
22	Periodical maintenance of various roads under Balera section under Sub-division Kakira (Sh:- Providing and laying hot applied thermoplastic compound 2.5mm thick line on various roads in Balera Section	432250.00	8750.00	Rs. 350/-	Three Month	Class-D & C
23	Periodical maintenance of various roads under Dundiyara section under Sub-division Kakira (Sh:- Providing and laying hot applied thermoplastic compound 2.5mm thick line on various roads in Dhundiara Section	401050.00	8300.00	Rs. 350/-	Three Month	Class-D & C
24	RESTORATION OF RAIN DAMAGE ON HUNERA TO KAHRI KOTHI ROAD 0/00 TO 5/420(Sh:- Hiring of excavator cum loader removal of slips in km 0/00 to 5/420)	482850.00	9657.00	Rs. 350/-	Three Month	Class-D & C
25	RESTORATION OF RAIN DAMAGE ON CHOWARI MANDHIAR BALOH FAGOT ROAD 0/00 TO 13/300(Sh:- Hiring of excavator cum loader removal of slips in km 2/00 TO 8/00)	471750.00	9435.00	Rs. 350/-	Three Month	Class-D & C
26	RESTORATION OF RAIN DAMAGE ON VARIOUS ROAD UNDER RAIPUR SECTION HPPWD SUB-DIVISION CHOWARI ROAD(Sh:- Hiring of excavator cum loader removal of slips)	468075.00	9362.00	Rs. 350/-	Three Month	Class-D & C
27	RESTORATION OF RAIN DAMAGE ON PARCHORE TO NADDAL ROAD 0/00 TO 3/00(Sh:- Hiring of excavator cum loader removal of slips in km 0/00 to 3/00)	466200	9324.00	Rs. 350/-	Three Month	Class-D & C

28	Restoration OF RAIN DAMAGE ON Ghatasani pull to Bhalog ROAD 0/00 TO 7/360(Sh:- Hiring of excavator cum loader removal of slips in km 0/00 to 7/360)	467850.00	9357.00	Rs. 350/-	Three Month	Class-D & C
29	Restoration OF RAIN DAMAGE ON Patka Dalhousie road km 32/00 to 45/00 ROAD 0/00 TO 7/360(Sh:- Hiring of excavator cum loader removal of slips in km 34/00 to 45/00)	465000.00	9300.00	Rs. 350/-	Three Month	Class-D & C
30	Restoration OF RAIN DAMAGE ON Chowari to jot road km 0/0 to 23/00 (Sh:- Hiring of excavator cum loader removal of slips in km 20/200 to 23/00)	467250.00	9345.00	Rs. 350/-	Three Month	Class-D & C
31	Restoration OF RAIN DAMAGE ON Chowari to jot road km 0/0 to 23/00 (Sh:- Hiring of excavator cum loader removal of slips in km 13/00 to 20/00)	472500.00	9450.00	Rs. 350/-	Three Month	Class-D & C
32	Restoration OF RAIN DAMAGE ON Chowari to jot road km 0/0 to 23/00 (Sh:- Hiring of Tipper for shifting of muck & Hiring excavator cum loader removal of slips in km5/00 to 9/00)	483900.00	9672.00	Rs. 350/-	Three Month	Class-D & C
33	Restoration OF RAIN DAMAGE ON Chalari to Kuther road km 0/00 to 2/045 (Sh:- Hiring of Tipper for shifting of muck & Hiring excavator cum loader removal of slips in km0/00 to 2/00)	458175.00	9164.00	Rs. 350/-	Three Month	Class-D & C
34	Restoration of rain damage on Chowari to jot road km 53/00 to 76/00(Sh:- C/o B/wall in wire crate at rd 58/700 to 58/738)	395242.00	7905.00	Rs. 350/-	Three Month	Class-D & C
35	Restoration of rain damage on Chowari to jot road km 53/00 to 76/00(Sh:- C/o B/wall in wire crate at rd 58/650 to 58/690)	420920.00	8418.00	Rs. 350/-	Three Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

SCHEDULE OF QTY

Estimate cost:-447114/-

Earnest Money:-8942/-

Time limit:-Three Month

NAME OF WORK:- C/O AMBULANCE ROAD FROM MAIN ROAD TO SAMLUNA GHATTU VIA iph colony km 0/00 to 1/200(Sh:- Providing and laying CC 1:4:8 and cc pavement work at rd 0/231 to 0/300)

Sr. No.	Description	Quantity	Unit	Rate (Rs.)		Amount (Rs.)
				In No	In Fig	
1	Providing and Laying cement concrete 1:4:8 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP PWD technical specifications, as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	21.05	Per Cum			
2	Cement Concrete Pavement construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (grade), coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges steel plates including leveling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specifications.	31.57	Per Cum			
Total						

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W. CHOWARI

SCHEDULE OF QTY

Estimate cost:-499716/-
Earnest Money:-9994/-
Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD FROM BAD-DRAWAN TO BANOLI ROAD KM 0/00 TO 3/500(SH:- C/O 900 MM DIA HUME PIPE CULVERT AT RD 2/452 WITH WING WALL)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	68.57			Cum	
2	Providing and laying concere for plain/reinforced cocrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	2.55			Cum	
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced cocrete in open foundations complete as par drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	19.93			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108. (900mm dia hume pipe).as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-In-Charge as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	58.40			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	12.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	6.48			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.W. Chowdhary

SCHEDULE OF QTY

Estimate cost:-499294/-

Earnest Money:-9986/-

Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD FROM BAD-DRAMAN TO BANOU ROAD KM 0/00 TO 3/500(SH:- C/O 900 MM DIA HUME PIPE CULVERT AT RD 1/905 WITH WING WALL)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m desing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	68.57			Cum	
2	Providing and laying concere for plain/reinforced cocrete in open foundations complete as per drawing and technical specification clauses 802, 803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	2.55			Cum	
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced cocrete in open foundations complete as per drawing and technical specification clauses 802, 803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	19.86			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108. (900mm dia hume pipe).as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-In-Charge.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	58.40			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	12.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	6.48			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P. CHOWDHARY

29

SCHEDULE OF QTY

Estimate cost:-388801/-
Earnest Money:-7776/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI MANDHAR BALOH FAGOT ROAD KM 0/00 TO 13/300(Sh:- C/o R/wall at rd 4/060 to 4/075)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m desing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Govenment	31.13			Per Cum	
3	Providing and Laying cement concrete1:5:10 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Govenment.	69.90			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	28.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Govenment.	13.73			Per Cum	
TOTAL						


EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

SCHEDULE OF QTY

Estimate cost:-415220/-
Earnest Money:-8304/-
Time limit:-Three Month

RESTORATION OF RAIN DAMAGE ON BOUNKHARI MOUR TO NAGALI ROAD KM 6/00 TO 12/00(SH:- C/O R/WALL AT RD 11/430 TO 11/437.50)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	27.83			Per Cum	
3	Providing and Laying cement concrete 1:5:10 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	78.00			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	24.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	13.88			Per Cum	
TOTAL						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D. CHOWARI



SCHEDULE OF QTY						Estimate cost:-488402/-	
NAME OF WORK:- CONSTRUCTION OF FOGLA TO BANOI ROAD KM 0/00 TO 3/200(Sh:- C/o 900 mm dia hume pipe culvert at rd 1/225 with wing wall)						Earnest Money:-9768/-	
						Time limit:-Three Month	
S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT	
			In No	In Fig			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	61.07			Cum		
2	Providing and laying concere for plain/reinforced concrete in open foundations complete as par drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Govenment.	22.83			Cum		
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Govenment.	1.33			Cum		
4	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonary work in head walls and parapets clause 1108. (900mm dia hume pipe).as per the direction of Engineer-In-Charge.The rate is including	7.50			Rmt		
5	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-in-Charge.as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	51.00			Cum		

6	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7,as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the	16.00			Each	
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government	7.55			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.R.W. CHOWARI

SCHEDULE OF QTY

Name of work:- Improvement fromation cutting on fogla to banol road km 0/00 to 3/200(Sh:- Improvement of grade and improvement of deficiencies at various RDS)

Estimate cost:-6683677/- 488949/-
Earnest Money:-336747/- 9779/-
Time limit:-Three Month

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Excavation in hilly area in all heights and depths and in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil ,ordinary rock,soft rock ,hard rock chieseling ,wedging out rock (where blasting is prohibited)and their intermediate classification of soil compelet including setting out true to the require lines,grades,width ,cutting and trimming of side slopes and levels as shown on the drawings and as direction of engineer-in-charge at site ,according to the technical specification section 300 and 1600 and sorting out useful material and stacking the same within all leads lifts in acquired width of road and transportation of un-usal materials for filling in roadway camber ,embankment for grade improvements abd disposal of all surplus material to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressig and carriage of machineriess material,tool ,equipment and safety measures and other incidental necessary to complete the work by contractor .Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor ,which shall have to be compensated by him in all cases . The removal of slips during the construction period shall be responsibility of the contractor and nothing extra shall be paid on this account. The rate are including the octroi royalty,Malkana toll tex,sales tax GST or any other taxes imposed ny the Govt.	2047.16			Per Cubic Metre	
TOTAL						

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D. CHOWARI

SCHEDULE OF QTY

Estimate cost:-496512/-
Earnest Money:-9930/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANHI NALLAH TUNUHATTI ROAD KM 25/00 TO 40/810(SH:- C/O R/WALL IN PCC AT KM 28/141 TO 28/145 & C/O PARAPETS)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes	23.76			Per Cum	
2	Providing and laying concere for plain/reinforced cocrete in open foundations complete as par drawing and technical specification clauses 802, 803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	52.80			Per Cum	
3	Providing and Laying cement concrete1:4:8 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	23.40			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	21.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	4.32			Per Cum	
6	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	1.91			Per Cum	
TOTAL						

H. P. W. Bachwari
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W. Bachwari

Estimate cost:-481461/-
Earnest Money:-9629/-
Time limit:-Three Month

STHUNTA

Total :-

Hi. P. 2115

111

SCHEDULE OF QTY

Estimate cost:-390135/-
Earnest Money:-7803/-
Time limit:-Three Month

NAME OF WORK :- Repair of Music Department & Physical Education Department Building at Govt. Degree College Chowari in Tehsil Bhattiyat Distt.

(SH :- P&L Painting work & Sanitary Installation)

S.NO	DESCRIPTION OF ITEM	QTY	Unit	In NO	Rate In Fig	AMOUNT
1	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	0.63	Per cum			
2	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of G.S. Sheet as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	24.38	Per sqm			
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) Second class teak wood as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	0.63	Per cum			
4	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating including fixing with perpainted iron J or L hooks, bolts and nuts 6 mm dia and perpainted G.I. impet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	30.74	Per sqm			
5	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick 4 mm thick glass pane Float glass panes (weight not less than 10 kg per sqm as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	6.72	Per sqm			
6	Applying one coat of Acrylic primer of superior quality on new concrete/masonry/plastered surfaces after and including preparing the surface by thoroughly brushing the surface free from mortar droppings and other foreign matters sand papering the surface smooth complete as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	254.06	Per sqm			

7	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty as required for melling the surface as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	254.06	Per sqm			
8	Painting two coats (excluding priming coats) on new wood and wood based surface under coats with enamel and finished coating with flat oil paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter, sand papering and stopping (with paints other than white) as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	137.38	Per sqm			
9	Finishing wall with weather proof exterior grade emulsion of approved design of superior quality on undecorated wall surface to give an even shade and final finish including thoroughly cleaning the surface to remove all dirt, dust and other foreign matters sand papering the surface smooth complete as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	219.30	Per sqm			
10	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a coat of red lead paint in trusses, trussed purlins and sunshades in building complete as per drawing or as directed by Engineer-in-charge as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	586.00	Per Kg			
11	Providing and placing in position water tank made of sinrex having 1000 litres (five Hundred litres) Capacity with necessary fitting including overflow pipes and ball have cover and locking arrangement including pads of required sizes as required for inlet and outlet of superior quality within all leads and lifts and as per the direction of the engineer-in-Charge and other incidentals as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	1000.00	Per Ltr.			
12	P/F PVC 100 mm dia pipes within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	24.00	Per RMT			
13	Providing and fixing 100 mm (one hundred millimetre) nominal size / diametre PVC floor trap of self cleaning design with including cost of cutting and making goods the walls and floors within all leads and lifts and as per the direction of the engineer-in-Charge and other incidentals as per the direction of Engineer-In-Charge. The rate is including royalty, Malkijana, Toll Tax, GST or other taxes imposed by the Government.	1.00	Each			

14	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	4.00	Each				
15	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- White Vitreous China Wash basin size 550x400 mm single hole basin mixer with a 15 mm CP Brass as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
16	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
17	C.P Brass pillar tap with Capstan head 15mm dia, Swan neck as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
18	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
19	Providing and fixing C.P. Brass waste for wash basin or sink) 32mm dia as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
20	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
21	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				
22	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.as per the direction of Engineer-In-Charge. The rate is including royalty, Malkjana, Toll Tax, GST or other taxes imposed by the Government.	3.00	Each				

23	providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	3.00	Each				
24	Providing and fixing toilet paper holder :as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	1.00	Each				
Total :-							

Abdulkarim
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W. *Abdulkarim*

SCHEDULE OF QTY

Estimate cost:-463965/-
Earnest Money:-9279/-

Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO MANDHIAR BALOH FAGOT ROAD KM 0/00 TO 13/330(Sh:- C/o
R/wall with pushat at rd 6/170 to 6/178)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	30.24			Per Cum	
3	Providing and Laying cement concrete1:5:10 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	86.88			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	20.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	14.40			Per Cum	
TOTAL						

(M. Prakash)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P. WORKS CHOWARI

DNIT

Estimate cost:-496836/-
Earnest Money:-9937/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON NANIKHAD TO SAMLEU ROAD KM 0/00 TO 30/585(SH:- C/O R/WALL AT D 26/465 TO 26/483

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	33.20			Per Cum	
3	Providing and Laying cement concrete 1:5:10 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	91.60			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	28.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	14.20			Per Cum	
TOTAL						

(M. P. W. D.)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D. CHOWARI

SCHEDULE OF QTY

Estimate cost:-471965/-

Earnest Money:-9439/-

Time limit:-Three Month

NAME OF WORK:- CONSTRUCTION OF FOGLA TO BANOI ROAD KM 0/00 TO 3/200(Sh:- C/o 900 mm dia hume pipe culvert at rd 1/630 with wing wall)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	63.60			Cum	
2	Providing and laying concere for plain/reinforced cocrete in open foundations complete as par drawing and technical specification clauses 802,803,1202& 1203 nominal mix (1:4:8) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	2.16				
3	Providing and laying concere for plain/reinforced cocrete in open foundations complete as par drawing and technical specification clauses 802,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	18.30			Cum	
4	Providing cement concert in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	1.20				
5	Providing and laying concere for plain/reinforced cocrete in open foundations complete as par drawing and technical specification clauses 802,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	0.37			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108.(900mm dia hume pipe),as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-in-Charge.as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	51.37			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7.as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	24.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204,3.8as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	8.25			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.W. CHOWARI

142

SCHEDULE OF QTY

Estimate cost:-487784/-
Earnest Money:-9756/-
Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD THULEI TO ANAYI ROAD KM 0/00 TO 2/400(SH:- C/O 900 MM DIA HUME PIPE CULVERT AT RD 1/360 WITH WING WALL)

S.NO	Description of Item	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	62.41			Cum	
2	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	16.05			Cum	
3	Providing cement conceret in sub-structures completed as per drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as per drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	18.85			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108.(900mm dia hume pipe).as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-In-Charge.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	37.36			Cum	
8	Providing weep hole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	16.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	10.56			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P.W. CHOWARI

13

SCHEDULE OF QTY

Estimate cost:-4923331/-
 Earnest Money:-9847/-
 Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD THULEL TO ANAYI ROAD KM 0/00 TO 2/400(SH:- C/O 900 MM DIA HUME PIPE CULVERT AT RD 1/660 WITH WING WALL)

S.NO	Description of item	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	69.87			Cum	
2	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	2.55			Cum	
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	18.85			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108. (900mm dia hume pipe).as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-In-Charge.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	48.23			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7.as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	16.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	32.02			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWABARI DIVISION
 H.P.P. CHOWDHURY

SCHEDULE OF QTY

Estimate cost:-485207/-


Earnest Money:-9704/-

Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD FROM GARNOTA (BHADELA) PUKHARU PADWAL ROAD KM 0/00 TO 6/180(SH:- C/O 900 mm dia hume pipe culvert at rd J/685 with wing wall)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	66.25			Cum	
2	Providing and laying concere for plain/reinforced cocrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	2.55			Cum	
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced cocrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	20.74			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108. (900mm dia hume pipe).as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-in-Charge as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	52.90			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614, 709, 1204, 3, 7 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	18.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	4.20			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.W. CHOWARI

17

SCHEDULE OF QTY

Estimate cost:-366467/-
Earnest Money:-7329/-
Time limit:-Three Month

NAME OF WORK:- C/O LINK ROAD DUGRED TO NALOH ROAD KM 0/00 TO 6/300(SH:- C/O R/WALL AT RD 0/330 TO 0/342.80)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge. The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes	31.62			Per Cum	
2	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	30.34			Per Cum	
3	Providing and Laying cement concrete 1:5:10 and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications. as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	33.54			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the	20.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	8.06			Per Cum	
TOTAL						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W&B CHOWARI


SCHEDULE OF QTY

NAME OF WORK:- C/O LINK ROAD FROM GARNOTA (BHADELA) PUKHARU PADWAL ROAD KM 0/00 TO 6/180(Sh:- C/O 900 mm dia hume pipe culvert at rd 1/825 with wing wall)

Estimate cost:-481171/-
Earnest Money:-9623/-
Time limit:-Three Month

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	68.05			Cum	
2	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	2.55			Cum	
3	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.99			Cum	
4	Providing and laying concere for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:2:4)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	0.37			Cum	
5	Providing cement conceret in sub-structures completed as paer drawing and technical specification clauses 802,804,805,806,807,1202,an 1204 (p.c.c grade m15 nominal mix (1:2.5:5)(item no 5+7)as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	19.05			Cum	
6	Providing and laying reinforced cement concrete pippe N.P.2 for culverts on first class bedding of granular in single road including fixing collar with cement mortar (1:2) but excluding excavation protection work backfilling concrete and masonry work in head walls and parapets clause 1108.(900mm dia hume pipe) as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	7.50			Rmt	

7	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer-in-Charge.as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Govenment.	52.90			Cum	
8	Providing weephole in brick masonry, stone masonry/plain /reinforced concrete abutment wing wall, return wall, with 100 mm dia P.V.C. pipe extending through the full width of the structure drawing and technical specification Clause 614,709, 1204,3,7,as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Govenment.	16.00			Each	
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Govenment.	8.40			Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.W. CHOWARI

19

20

SCHEDULE OF QTY

Estimate cost:-496399/-
Earnest Money:-9928/-
Time limit:-Three Month

0

NAME OF WORK:- C/O KIYOD TO MALWAN ROAD KM 0/00 TO 3/300(SH:- C/O R/WALL AT RD 2/990 TO 2/998 & 3/075 to 3/081

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes	48.12			Per Cum	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	31.68			Per Cum	
3	Providing and laying cement concrete 1:5:10 and curing complete including the cost of formwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP, PWD technical specifications as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	51.60			Per Cum	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	28.00			Per Nos	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	7.65			Per Cum	
TOTAL						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P. D. CHOWARI

SCHEDULE OF QTY

Estimate cost:-494409/-
Earnest Money:-9888/-
Time limit:-Three Month

NAME OF WORK:- C/O KIYOD MALWAN ROAD KM 0/00 TO 3/300(Sh:- C/o wire crate B/wall with pushta at rd 3/189 to 3/218)

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Flg		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavator earth with lift upto 1.5m and lead upto 20m as per technical specification clause 1603.1as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Govenment.	78.3			Per Cum	
2	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	21.75			Per Cum	
3	Providing and laying concere for plain/reinforced concrete in open foundations complete as par drawing and technical specification clauses 802 ,803,1202& 1203 nominal mix (1:3:6) as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	7.98			Per Cum	
4	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I wire conforming to IS:4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra as per drawing and technical specification under clause 1301 as per the direction of Engineer-In-Charge. The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government.	135.94			Per Cum	
Total						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W./CHOWARI


21

SCHEDULE OF QTY

Estimate cost:-299000/-
Earnest Money:-5980/-
Time limit:-Three Month

NAME OF WORK:- PERIODICAL MAINTENANCE OF VARIOUS ROAD UNDER BALERA SECTION SUB-DIVISION KAKIRA(SH:- PROVIDING AND LAYING HOT APPLIED THERMOPLASTIC COMPOUND 2.5MM THICK LINE ON VARIOUS ROADS IN SECTION BALERA

Sr. No.	Description of items	Qty.	Rate		Unit	Amount.
			In No	In Fig		
1	Providing applying and laying tack coat with bitumen emulsion (RS-1) using emulsion distributor as the rate of 0.25 to 0.30 kg per sqm on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per technical specification clause 503 including hauling of material in all leads and lifts as per the direction of Engineer-In-Charge. The rate is including royalty, Malkiana, Toll Tax, GST or other taxes imposed by the Government.	460.00			Per Square metre	
		Total				


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P.W. DECHOWARI

28

SCHEDULE OF QTY

Estimate cost:-432250/-

Earnest Money:-8645/-

Time limit:-Three Month

NAME OF WORK:- PERIODICAL MAINTENANCE OF VARIOUS ROAD UNDER BALERA SECTION SUB-DIVISION
KAKIRA(SH:- PROVIDING AND LAYING HOT APPLIED THERMOPLASTIC COMPOUND 2.5MM THICK LINE ON
VARIOUS ROADS IN SECTION BALERA

Sr. No.	Description of items	Qty.	Rate		Unit	Amount.
			In No	In Fig		
1	Providing applying and laying tack coat with bitumen emulsion (RS-1) using emulsion distributor as the rate of 0.25 to 0.30 kg per sqm on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per technical specification clause 503 including hauling of material in all leads and lifts as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Government	665.00			Per Square metre	
Total						

H.P.P. W.D. Chowari
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D. CHOWARI

23


SCHEDULE OF QTY

Estimate cost:-401050/-
 Earnest Money:-8021/-
 Time limit:-Three Month

NAME OF WORK:- PERIODICAL MAINTENANCE OF VARIOUS ROAD UNDER Dundlaira SECTION SUB-DIVISION
 KAKIRA(SH:- PROVIDIONG AND LAYING HOT APPLIED THERMOPLASTIC COMPOUND 2.5MM THICK LINE ON VARIOUS
 ROADS IN SECTION BALERA

Sr. No.	Description of items	Qty.	Rate		Unit	Amount.
			In No	In Fig		
1	Providing applying and laying tack coat with bitumen emulsion (RS-1) using emulsion distributor as the rate of 0.25 to 0.30 kg per sqm on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per technical specification clause 503 including hauling of material in all leads and lifts as per the direction of Engineer-In-Charge.The rate is including royalty,Malkjana,Toll Tax ,GST or other taxes imposed by the Govenment	617.00			Per Square metre	
Total						

EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P.W. CHOWARI



SCHEDULE OF QTY

Estimate cost:-482850/-

Earnest Money:-9657/-

Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON HUNERA TO KAHRI KOTHI ROAD KM 0/00 TO 5/420

SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 0/00 TO 5/420

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	370.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	170.00			Per Hours	
Total						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D CHOWARI

25

SCHEDULE OF QTY						Estimate cost:-471750/-
						Earnest Money:-9435/-
						Time limit:-Three Month
NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI MANDHIAR BALOH FAGOT ROAD KM 0/00 TO 13/330						
SH:- HIRRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 2/00 TO 8/00						
S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	370.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	150.00			Per Hours	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P.W.D CROWARI

26

SCHEDULE OF QTY					
NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON VARIOUS ROAD UNDER RAIPUR SECTION HPPWD SUB-Division Chowah					
SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS					
Estimate cost:-468075/-					
Earnest Money:-9362/-					
Time limit:-Three Month					
S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		AMOUNT
			In No	In Fig	
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	385.00			Per Hours
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	115.00			Per Hours
Total					

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D CHOWARI

27

SCHEDULE OF QTY

Estimate cost:-466200/-

Earnest Money:-9324/-

Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON PARCHORE TO NADAL ROAD KM 0/00 TO 3/00

SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 0/00 TO 3/00

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	222.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	420.00			Per Hours	
Total						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

28

SCHEDULE OF QTY

Estimate cost:-467850/-
Earnest Money:-9357/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON GHATASANI PULL TO BHOLAG ROAD KM 0/00 TO 7/360

SH:- HIRIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 0/00 TO 7/360

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	250.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	370.00			Per Hours	
Total						

H.P.W.D.
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

29

SCHEDULE OF QTY

Estimate cost:-465000/-
Earnest Money:-9300/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 32/00 TO 45/00

SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 32/00 TO 45/00

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malikana toll tax sale tax or any other taxes imposed by the Government.	390.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	100.00			Per Hours	
Total						

H.P.W.D.
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D CHOWARI

20

24

SCHEDULE OF QTY

Estimate cost:-467250/-

Earnest Money:-9345/-

Time limit:-Three Month


NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO JOT ROAD KM 0/00 TO 23/00

SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 20/200 TO 23/00

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	445.00			Per Hours	
Total						

H.P.W.D.
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

SCHEDULE OF QTY					
NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO JOT ROAD KM 0/00 TO 23/00					
SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 13/00 TO 20/00					
Time limit:- Three Month					
Estimate cost:-472500/-					
Earnest Money:-9450/-					
S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT
			In No	In Fig	
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	450.00			Per Hours
Total					


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.P.W.D CHOWARI

32

SCHEDULE OF QTY

Estimate cost:-483600/-
Earnest Money:-9672/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO JOT ROAD KM 0/00 TO 23/00

SH:- HIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 5/00 TO 9/00

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-in-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	376.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer-in-Charge.	160.00			Per Hours	

H. P. W. D. Chowari
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.W.D CHOWARI

33

SCHEDULE OF QTY

Estimate cost:-458175/-
Earnest Money:-9164/-
Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHALARI TO KUTHER ROAD KM 0/00 TO 2/045


SH:- HIRRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIPS IN KM 0/00 TO 2/00

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperity or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	365.00			Per Hours	0.00
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperity or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	135.00			Per Hours	0.00
Total						

H.P.P.W.D Chowari
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

34

SCHEDULE OF QTY						Estimate cost:-395249/-
NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO JOT ROAD KM 53/00 TO 76/00						Earnest Money:-7905/-
Sh:- C/o B/WALL IN WIRE CRATE AT RD 58/700 to 58/738						Time limit:- Three Month
S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shouring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the direction of Engineer-In-Charge. The rate is including royalty,Malkhana,Toll Tax,GST or other taxes imposed by the Government.	64.50			Per Cum	
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I wire conforming to IS:4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra as per drawing and technical specification under clause 1301 as per the direction of Engineer-In-Charge. The rate is including royalty,Malkhana,Toll Tax,GST or other taxes imposed by the Government.	117.19			Per Cum	
Total						


 EXECUTIVE ENGINEER
 CHOWARI DIVISION
 H.P.W.D. CHOWARI

35
36

SCHEDULE OF QTY

Estimate cost:-420920/-

Earnest Money:-8418/-

Time limit:-Three Month

NAME OF WORK:- RESTORATION OF RAIN DAMAGE ON CHOWARI TO JOT ROAD KM 53/00 TO 76/00

Sh:- C/o B/WALL IN WIRE CRATE AT RD 58/650 TO 58/690

S.NO	DESCRIPTION OF ITEM	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material .as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll	67.60			Per Cum	
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I wire conforming to IS:4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra as per drawing and technical specification under clause 1301 as per the direction of Engineer-In-Charge.The rate is including royalty,Malkiana,Toll Tax ,GST or other taxes imposed by the Government.	125.00			Per Cum	
		Total				

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI