

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Dal/TA/Tender /2024-25 **4697-99**  
To

Dated: - **03-12-24**


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

**DA/ As above.**

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:-4697-99 dated,03-12-24 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:-4647-99 dated,03-12-24 is emergent nature and in Public interest.

9.  
  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 1 Date of receipt of application for the tender  
Form a/w requisite documents:-03 12 2024 onward (between 2:00 p.m.to 4:30 p.m.)
- 2 Date of issued/sale of tender form against Cash payment (non refundable).

The tender shall be received up to 3:00 PM on 13.12.2024 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 12.12.2024

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Construction of Link road to village China Km. 0/0 to 0/750 (SH: - Formation Cutting between Km. 0/0 to 0/415).	460522.00	10000.00	350.00	Three Months	D & C
2.	Restoration of rain damage on Chakra to Sherpur road Km. 0/0 to 7/00 (SH: - Construction of Retaining wall in wire crate at RD. 4/520 to 4/533).	484698.00	9700.00	350.00	Three Months	D & C
3	Restoration of rain damage on Chakra to Sherpur road Km. 0/0 to 7/00 (SH: - Construction of Retaining wall in wire crate at RD. 1/150 to 1/160 & 5/210 to 5/220).	422165.00	9000.00	350.00	Three Months	D & C
4	Restoration of rain damage on various roads under Dalhousie Sub Division (SH: - Removal of Slips on Link road to village Ruliyani, Link road Kathlog to Bharera Km. 0/0 to 2/180 & Link road Cantt to Bathri Km. 0/0 to 4/700 at various Roads.).	482524.00	10000.00	350.00	One Month	D & C
5	Restoration of rain damage on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Removal of Slips on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040).	488325.00	10000.00	350.00	One Month	D & C
6	A/R & M/O Devidehra Osal Guniyala road Km. 0/0 to 3/0 (SH: - Providing and Laying Interlocking Paver Block in Km. 0/255 to 0/365).	306005.00	6500.00	350.00	Three Months	D & C

7	Repair & Maintenance of Balance work of Garam Sadak (SH: - Providing and Fixing Steel Railing and Priming, Painting in RD. 0/0 to 0/250).	497751.00	10000.00	350.00	Three Months	D & C
8	AMP on Banikhet Dalhousie Khajjiar road Km. 0/0 to 27/00 (SH: - Providing and applying Hot mix Tharmoplastic edge line in Km. 20/0 to 21/0 , 23/0 to 24/0 & 24/0 to 25/00 = 3.00 Km.).	208410.00	4500.00	350.00	Three Months	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

No. PWD/TA/Tender /2024-25

4700-750

Dated:- 03-12-24

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief , HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie

# Schedule of Qty.

Name of work: - Construction of Link road to village China Km. 0/0 to 0/750 (SH: - Formation Cutting between Km. 0/0 to 0/415).

Estimated Cost: - Rs.	460522.00
Earnest Money :- Rs.	10000.00
Time Limit :-	Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rates is inclusive of the octroi, royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	1845.41			Per Cubic Metre	
					Total: -	

Executive Engineer  
Dahousie Division,  
H.P.P.W.D. Dahousie



# Schedule of Qty.

Estimated Cost: - Rs. 484698.00

Earnest Money :- Rs. 9700.00

Time Limit :- Three Months

Name of work: - Restoration of rain damage on Chakra to Sherpur road Km. 0/0 to 7/00 (SH:- Construction of Retaining wall in wire crate at RD. 4/520 to 4/533).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana toll tax sale tax, GST or other taxes imposed by the Government.	81.51			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilogramme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	168.48			Per Cubic Metre	
Total:-						

Executive Engineer  
Dalhousie Division,  
H/PWD, Dalhousie

## Schedule of Qty.

Estimated Cost :- Rs.	422165.00
Earnest Money :- Rs.	9000.00
Time Limit :-	Three Months

Name of work: -Restoration of rain damage on Chakra to Sherpur road Km. 0/0 to 7/00 (SH:- Construction of Retaining wall in wire crate at RD. 1/150 to 1/160 & 5/210 to 5/220).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana toll tax sale tax, GST or other taxes imposed by the Government.	67.00			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilogramme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkhana, toll tax, sales tax, GST or any other taxes imposed by the Government.	147.60			Per Cubic Metre	
<b>Total:-</b>						

  
 Executive Engineer  
 Dalhousie Division,  
 HPWD, Dalhousie

## Schedule of Qty.

Estimated Cost: - Rs.	482524.00
Earnest Money :- Rs.	10000.00

Time Limit :- One Month


**Name of work: -Restoration of rain damage on various roads under Dalhousie Sub Division (SH: - Removal of Slips on Link road to village Ruliyani, Link road Kathlog to Bharcera Km. 0/0 to 2/180 & Link road Cantt to Bathri Km. 0/0 to 4/700 at various Roads.).**

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	3863.90			Per Cubic Metre	
Total:-						

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

  
 Engineer  
 Dalhousie Division,  
 H.P.W.D. Dalhousie



## Schedule of Qty.

Estimated Cost: - Rs. :-	488325.00
Earnest Money :- Rs. :-	10000.00
Time Limit :-	One Month

Name of work: - Restoration of rain damage on Dalhousie Jandrighat Chamba via Kollari road Km. 0/0 to 11/040 (SH: - Removal of Slips on Dalhousie Jandrighat Chamba via Kollari road Km. 0/0 to 11/040).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	3909.73			Per Cubic Metre	
					Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availability of funds

  
 Executive Engineer  
 Dalhousie Division,  
 HPFWD, Dalhousie

## Schedule of Qty.

Name of work: - A/R & M/O Devidehra Osal Guniyala road Km. 0/0 to 3/0 (SH: - Providing and Laying Interlocking Paver Block in Km. 0/255 to 0/365).

Estimated Cost Rs. :-	306005.00
Earnest Money Rs. :-	6500.00
Time Limit :-	Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying heavy duty precast concrete 80 mm (Eighty millimetre) thick inter locking paver block pavement with vibration technology in PVC/Fibre moulds upto M-40 (Forty) grade conforming to IS 15658:2006 complete as per technical specification clause 1504 and as per the direction of the engineer in-charge. The rates are inclusive cost and carriage by all mode of transportation of materials within all leads, lifts and other incidentals, inclusive of octroi, GST royalty, Malkana, toll tax GST or any other taxes imposed by the Government.	300.30			Per Square Metre	
2	Providing and laying Mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 millimetre (forty millimetre nominal size on ground or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structure including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of wate including removal of slush which may arise at the time of laying concrete complete for all heights / depths including the cost of form work complete in drain as per drawing and M.O.R.D technical specifications section 800, 900 and 1200 or as directed by Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	3.47			Per Cubic Metre	
<b>Total: -</b>						

  
 Engineer  
 Dalhousie Division,  
 H.P.W.D. Dalhousie

## Schedule of Qty.

Name of work: - Repair & Maintenance of Balance work of Garam Sadak (SH: - Providing and Fixing Steel Railing and Priming, Painting in RD. 0/0 to 0/250).

Estimated Cost Rs. :-	497751.00
Earnest Money Rs. :-	10000.00
Time Limit :-	Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and fixing railing for road works fixed with balluster of 75x75mm (seventy five iso seventy five millier) square hollow M.S Pipe (ISG-18) with a clear height of 120cm (one hundred twenty centimeter) center to center joining top hollow rectangular rail of 75x50x3mm (seventy five is to fifty is three millimeter) and other three row having size 50x50x3mm (fifty iso fifty iso three millimeter) hollow square and jointing with electric/gas welding to the existing ballusters, top rail jointing with ballusters through angel iron cleas 50x850x5mm (fifty iso fifty iso five millimeter) complete and ornaments top of channel round shape with applying a priming coat or red lead paint or as per specification and as per the direction of the engineer-in-charge. The rates are inclusive cost and carriage by all mode of transportation of materials within all leads, lifts and other incidentals, inclusive of octroi, GST royalty, Malkana, toll tax GST or any other taxes imposed by the Government.	3467.22			Per Kilo Gram	
2	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint of approved quality Nerolac, Indigo, Burger, Asian, Dulux, etc including brushing to give an even shade including cleaning the surface all dirt,dust and other foreign matter With white ready mixed paint and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, Toll tax sale tax GST and or other taxes imposed by the Government.	252.00			Per Square Metre	
					<b>Total:-</b>	


  
 Executive Engineer  
 Dalhousie Division,  
 H.P.P.W.D. Dalhousie

## Schedule of Qty.

Name of Work:- AMP on Banikhet Dathousie Khajjar road Km. 0/0 to 27/00 (SI:- Providing and applying Hot mix Thermoplastic edge line in Km. 20/0 to 21/0, 23/0 to 24/0 & 24/0 to 25/00 = 3.00 Km.).

Estimated Cost:- Rs.	208410.00
Earnest Money :- Rs.	4500.00
Time Limit :-	Three Months

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. complete in all respects and as per directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	300.00			Per Square Metre	
					<b>Total:-</b>	

  
 Executive Engineer,  
 Dathousie Division,  
 H.P.P.W.D. Dathousie