

**Himachal Pradesh  
Public works Department**

**Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **26-12-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **24-12-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 23-12-2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	C/o of road from main road Ghiddi to Kharloh via Khadabh Km. 0/00 to 4/00 (SH:- C/o PCC wing wall on both side of exsting hume pipe culvert at RD 0/035 & 1/825) Under OTMNP.	359864	7200	Two Months
2	C/o Saroa to kamrunag road km. 0/00 to 4/760 (SH:- F/C 5/7 meter wide in km. 2/340 to 2/670) Under OTMNP	447113	9000	Two Months
3	Restoration of raod damage on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC R/wall at RD. 7/925 to 7/945) Telicome Deposit.	443418	8900	Two Months
4	C/o Kainaid to Chatter road km. 0/00 to 1/00 (SH:- Providing and laying CC Pavement from km. 0/850 to 0/940 ) under SCDP.	353393	7100	Two Months
5	C/o Kainaid to chatter road km. 0/00 to 1/00 (SH:- Providing and laying CC Pavement from km. 0/940 to 1/00 ) Under SCDP.	253850	5100	Two Months

**Certified that tender of above works are being called for emergent nature in exigency of public interest.**

**GENERAL CONDITIONS:-**

- The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
- The Contractors should quote the rates of all the items in the tenders both in figures and words.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
- Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
- As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10 -2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in-Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I

dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.

7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.

No. PW-GHR-Tender/NIT/2024

Dated

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD. Gohar.



# BILL OF QUANTITY

**Name of Work:-** Construction of road from main road Ghiddi to Kharloh via Khadabh Km 0/00 to 4/00 (SH:- C/o PCC wing wall on both sidee of existing hume pipe culvert at RD 0/235 & 1/825 ) Under OTMNP.

**Estimated cost Rs. -** 359864.00

**Earnest Money cost Rs. -** 7200.00

**Time - Two Month**

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	22.56	Per Cubic metre	322.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	69.20	Per cubic metre	4793.45		
3	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.12	Per cubic metre	1306.55		
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	397.75		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar

# BILL OF QUANTITY

e of work :- C/o Saroa to Kamrunag road km. 0/00 to 4/760 (SH:- F/C 5/7 meter wide in km. 2/340 to 570) Under OTMNP

Estimated cost 447113.00

Earnest Money cost Rs. - 9000

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock ( where blasting work is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of the required lines, levels as shown on the drawing and directed by the Engineer-in-charge at site, and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools , equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation as per the directions of the Engineer-in-charge. The recovery of stones, whether useful or not for 214.00 cum @ Rs. 300/- per cubic metre to Rs. 64,200/- only shall be effected on pro rate basis in all circumstances. Any loss to the public and private property, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2006.25	Per Cubic metre	222.86		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer  
Gohar Division (B&R)  
HP.PWD Gohar.

262



**Name of work:-** Restoration of road damage on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC R/wall at RD. 7/925 to 7/945 )Telicome Deposit.

Estimated cost Rs. - 443418.00

Earnest Money cost Rs. - 8900.00

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.20	Per Cubic metre	322.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	83.40	Per cubic metre	4793.45		
3	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.80	Per cubic metre	1306.55		
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	35.00	Each	397.75		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar

## BILL OF QUANTITY

Name of work :- C/o Kainaid to Chatter road km 0/0 to 1/00 (SH:- Providing and laying CC Pavement from km 0/850 to 0/940) Under SCDP

Estimated cost Rs. - 3,53,393/-

Earnest Money cost Rs.7100/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	106.20	Per Cubic meter	322.00		
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	53.10	Per Cubic meter	2061.80		
3	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	35.40	Per Cubic meter	5924.15		
<b>Total:-</b>						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar



(201)

**BILL OF QUANTITY**

Name of work :- C/o Kainaid to Chatter road km 0/0 to 1/00 (SH:- Providing and laying CC Pavement from km 0/940 to 1/00) Under SCDP

Estimated cost Rs. - 2,53,850/-

Earnest Money cost Rs.5100/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	76.28	Per Cubic meter	322.00		
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	38.14	Per Cubic meter	2061.80		
3	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	25.43	Per Cubic meter	5924.15		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar