



**Office of the Executive Engineer, Division Kalpa (B&R)
HP.PWD; Kalpa District Kinnaur Himachal Pradesh**

Phone No. 01786-226027 Web: www.hppwd.gov.in Email: hp-kin@nic.in Fax No. 01786-226027

No:- PW/KNR-E-Tender/2024/- 5813 - 15

Dated:- 12-12-2024

To

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing below 5.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this
office Letter No. PW/KNR/E-Tender/2024/-...5813-15.....dated12-12-2024
from Sr. No. 1 to 23 are of urgent nature and public interest.


**Executive Engineer,
Kalpa Division,
HP.PWD; Kalpa.**

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP.PWD; Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **26-12-2024 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M. on 23-11-2024** No application for issue of tender forms will be received on **23-11-2024** after **4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Annual repair and maintenance of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 0/520 to 0/533).	4,98,028/-	10,000/-	Three Months	350/-	D Class
2	Annual repair and maintenance of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 0/750 to 0/758.50).	4,99,934/-	10,000/-	Three Months	350/-	D Class
3	Annual repair and maintenance of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 0/758.50 to 0/767).	4,99,837/-	10,000/-	Three Months	350/-	D Class
4	Annual repair and maintenance of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 0/767 to 0/775.50).	4,99,593/-	10,000/-	Three Months	350/-	D Class
5	Improving and widening of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 1/885 to 1/896).	4,95,193/-	10,000/-	Three Months	350/-	D Class
6	Improving and widening of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 1/896 to 1/907).	4,95,206/-	10,000/-	Three Months	350/-	D Class
7	Improving and widening of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 2/180 to 2/192.50).	4,85,750/-	10,000/-	Three Months	350/-	D Class

8	Improving and widening of link road from NH-22 to Taitty valley Km. 0/00 to 4/445. (SH:- C/O R/wall in PCC at RD. 2/192.50 to 2/205).	4,87,112/-	10,000/-	Three Months	350/-	D Class
9	Restoration of rain damages on Peo Karchham Shilti road Km. 0/00 to 11/635. (SH:- Hiring of JCB for removal of slips).	4,95,000/-	10,000/-	Three Months	350/-	D Class
10	Balance work for construction of Sub-Jail Building at Reckong Peo in Distt. Kinnaur HP. (SH:- Providing and laying interlocking paver block Job No.1)	4,98,913/-	10,000/-	Three Months	350/-	D Class
11	Balance work for construction of Sub-Jail Building at Reckong Peo in Distt. Kinnaur HP. (SH:- Providing and laying interlocking paver block Job No.2)	4,99,402/-	10,000/-	Three Months	350/-	D Class
12	Balance work for construction of Sub-Jail Building at Reckong Peo in Distt. Kinnaur HP. (SH:- Providing and laying interlocking paver block Job No.3)	4,96,467/-	10,000/-	Three Months	350/-	D Class
13	Balance work for construction of Sub-Jail Building at Reckong Peo in Distt. Kinnaur HP. (SH:- C/O Main gate etc.)	2,24,480/-	5000/-	Three Months	350/-	D Class
14	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in PCC 1:3:6 at RD. 1/615 to 1/620 Job-4).	4,99,071/-	10,000/-	Three Months	350/-	D Class
15	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in PCC 1:3:6 at RD. 1/615 to 1/620 Job-5).	4,99,071/-	10,000/-	Three Months	350/-	D Class
16	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in G.I. wire crate and PCC 1:3:6 at RD. 1/620 to 1/625).	4,97,418/-	10,000/-	Three Months	350/-	D Class
17	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in PCC 1:3:6 at RD. 1/620 to 1/625 Job No.-2).	4,99,071/-	10,000/-	Three Months	350/-	D Class
18	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in PCC 1:3:6 at RD. 1/620 to 1/625 Job No.-3).	4,99,071/-	10,000/-	Three Months	350/-	D Class
19	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in PCC 1:3:6 at RD. 1/620 to 1/625 Job No.-4).	4,98,796/-	10,000/-	Three Months	350/-	D Class

20	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in G.I. wire crate at RD. 2/110 to 2/165).	4,99,105/-	10,000/-	Three Months	350/-	D Class
21	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in G.I. wire crate at RD. 2/200 to 2/258).	4,97,043/-	10,000/-	Three Months	350/-	D Class
22	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in G.I. wire crate at RD. 2/270 to 2/325).	4,97,800/-	10,000/-	Three Months	350/-	D Class
23	Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660. (SH:- C/O R/wall in G.I. wire crate at RD. 2/400 to 2/455).	4,98,102/-	10,000/-	Three Months	350/-	D Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa. ✓

No.:- PW/KNR-E-Tender/NIT/2024/- 5816-25

Dated:- 12-12-2024

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa. ✓

SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,028/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Annual repair and maintenance of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.
(SH:- C/O R/Wall in PCC at RD 0/520 to 0/533)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	0.12			Per Tonne	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	78.00			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	27.00			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	24.00			Each	
	Total:-					

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,934/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Annual repair and maintenance of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.
(SIT:- C/O R/Wall in PCC at RD 0/750 to 0/758.50)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.57			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	79.56			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.97			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
	Total:-					

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,837/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Annual repair and maintenance of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.
(SH:- C/O R/Wall in PCC at RD 0/758.50 to 0/767)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	22.44			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10 (1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	79.56			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	22.95			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
	Total:-					

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Annual repair and maintenance of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.

(SH:- C/O R/Wall in PCC at RD 0/767 to 0/775.50)

Estimated Cost :- 4,99,593/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	21.505			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	79.56			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	22.95			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,193/-
Earnest Money :- 10,000/-
Time :- Three Months

Name of work:- Improvement and widening of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.
(Sft:- C/O R/Wall in PCC at RD 1/885 to 1/896).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.90			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	78.32			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.40			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.00			Each	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,206/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Improvement and widening of link road from NH-22 to Tailly valley Km. 0/00 to 4/445.
 (SH:- C/O R/Wall in PCC at RD 1/896 to 1/907).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.30			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.32			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	24.42			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	44.00			Each	
	Total:-					

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Improvement and widening of link road from NH-22 to Taily valley Km. 0/00 to 4/445.
(SH:- C/O R/Wall in PCC at RD 2/180 to 2/192.50).

Estimated Cost :- 4,85,750/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	25.00			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	77.00			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including Carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	25.50			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	36.00			Each	
	Total:-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Improvement and widening of link road from NH-22 to Tailly valley Km. 0/00 to 4/44.5.
(SH:- C/O R/Wall in PCC at RD 2/192.50 to 2/205)

Estimated Cost :- 4,87,112/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.625			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	77.00			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	28.50			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	36.00			Each	
Total:-						

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

<u>Name of work:-</u>	<u>Restoration of rain damages on Peo Karcham Shilti road Km. 0/00 to 11/635</u> <u>(SH:- Hiring of JCB for removal of slips).</u>

Estimated Cost	:-	4,95,000/-
Earnest Money	:-	10,000/-
Time	:-	Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition Escort Make, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00			Per Hours	
					Total:-	

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,913/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
 (SH:-Providing and laying interlocking paver block Job No.-1)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying heavy duty precast concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curbing rubbing and polishing complet Subbase concrete floor to be paid for :- 80 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	204.00			Per Square meter	
	Total:-					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing and laying interlocking paver block Job No.-2)

Estimated Cost :- 4,99,402/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curbing rubbing and polishing complet Subbase concrete floor to be paid for :- 80 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	204.20			Per Square meter	
Total:-						


Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,96,467/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
(SH:- Providing and laying interlocking paver block Job No.-3)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	P/L heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curbing rubbing and polishing complete Subbase concrete floor to be paid for :- 80 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	203.00			Per Square meter	
Total:-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 2,24,480/-
 Earnest Money :- 5,000/-
 Time :- Three Months

Name of work:- Balance Work for Construction of Sub-Jail Building at Reckong Peo in Distt Kinnaur (HP)
 (SH:- C/O Main gate etc).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying heavy duty precast cement concrete inter locking paver blocks NTC Make vibro compacted upto M-50 grade i/c border or kurb black grey or coloured over subbase of concrete with 25 mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curbing rubbing and polishing complet Subbase concrete floor to be paid for :- 80 mm thick inter locking block, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	55.80			Per Square meter	
2	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.75			Per Cubic meter	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	525.00			Per Kilogram	
	Total:-					

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

14.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
(SH:- C/O R/Wall in PCC 1:3:6 at RD 1/615 to 1/620 Job-4).

Estimated Cost :- 4,99,071/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.750			Per Cubic meter	
2	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	64.00			Each	
Total:-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
(SH:- C/O R/Wall in PCC 1:3:6 at RD 1/615 to 1/620 Job-5).

Estimated Cost :- 4,99,071/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.750			Per Cubic meter	
2	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	64.00			Each	
Total:-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,97,418/-
 Earnest Money :- 10,000/-
 Time :- Three months

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
 (SH:- C/O R/Wall in G.I. wire crate and PCC 1:3:6 at RD 1/620 to 1/625)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed. All kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	75.60			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203. P.C.C. grade M10 Nominal mix 1:3:6 (one cement: three sand: six graded stone aggregate(20 mm(twenty millimeter nominal size)). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	60.750			Per Cubic meter	
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing an technical specification clauses 802, 803, 1202 and 1203. 1:6:12 (One cement: six sand: eight aggregate) (40 mm (Forty millimeter) aggregates) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.15			Per Cubic meter	
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Each	

5	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	28.80			Per Cubic meter
		Total:-			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,071/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
 (SH:- C/O R/Wall in PCC 1:3:6 at RD 1/620 to 1/625 Job No-2).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.750			Per Cubic meter	
2	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	64.00			Each	
Total:-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
(SH:- C/O R/Wall in PCC 1:3:6 at RD 1/620 to 1/625 Job No-3).

Estimated Cost :- 4,99,071/-
Earnest Money :- 10,000/-
Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.750			Per Cubic meter	
2	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	64.00			Each	
Total:-						

Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
 (SI:- C/O R/Wall in PCC 1:3:6 at RD 1/620 to 1/625 Job No-4).

Estimated Cost :- 4,98,796/-
 Earnest Money :- 10,000/-
 Time :- Three Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	78.750			Per Cubic meter	
2	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	63.00			Each	
Total:-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP, PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,105/-

Earnest Money :- 10,000/-

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660

(SH:- C/O R/Wall in G.I. wire crate at RD 2/110 to 2/165)

Time :- Three months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed. All kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	51.40			Per Cubic meter	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04			Per Cubic meter	
			Total:-			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
(SH:- C/O R/Wall in G.I. wire crate at RD 2/200 to 2/258)

Estimated Cost :- 4,97,043/-
 Earnest Money :- 10,000/-
 Time :- Three months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed. All kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all Incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	43.50			Per Cubic meter	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all Incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04			Per Cubic meter	
			Total:-			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
(SH:- C/O R/Wall in G.I. wire crate at RD 2/270 to 2/325)

Estimated Cost :- 4,97,800/-
Earnest Money :- 10,000/-
Time :- Three months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed. All kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	46.40			Per Cubic meter	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04			Per Cubic meter	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,102/-
 Earnest Money :- 10,000/-
 Time :- Three months

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660
 (SH:- C/O R/Wall in G.I. wire crate at RD 2/400 to 2/455)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means including getting out the excavated soil and disposal of surplus excavated soil as directed. All kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	47.56			Per Cubic meter	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04			Per Cubic meter	
			Total:-			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.