

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-MDI(Padhar)E-Tender-NIT/2024-25- 14556-58 Dated:- 11/12/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 24.12.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 23.12.2024 upto 12.00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Sudhar Swar Hurang Road in Km 0/0 to 7/00. (SH:- Construction of 900mm dia RCC Hume pipe culvert alongwith wing wall at R.D. 0/540)	2,31,384.00	4,600/-	350/-	One month
2	Construction of Sudhar Swar Hurang Road in Km 0/0 to 7/00. (SH:- Construction of 900mm dia RCC Hume pipe culvert alongwith wing wall at R.D. 1/120)	2,31,177.00	4,600/-	350/-	One month
3	Improvement of "Black spot" on Banogi Chehar Chaila road Km 0/0 to 5/00. (SH:- Providing and fixing "W" Metal Beam Crash Barrier at R.D. 2/800 to 2/833)	2,66,684.00	5,300/-	350/-	One month
4	Improvement of "Black spot" on Kataula Batheri Arang road Km 0/0 to 15/285. (SH:- Providing and fixing "W" Metal Beam Crash Barrier at R.D. 2/090 to 2/140)	2,02,601.62	4,100/-	350/-	One month
5	Improvement of "Black spot" on Shegli Prasher road Km 0/0 to 5/00. (SH:- Construction of Retaining wall at R.D. 4/350 to 4/360)	3,51,914.70	7,000/-	350/-	One month
6	Restoration of rain damages on Uhl Valley road in Km 0/00 to 10/00. (SH:- Construction of Retaining wall at R.D. 0/916 to 0/920)	1,93,798.37	3,900/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.

3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 231384.00

Earnest Money Rs:- 4600.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Construction of Sudhar Swar Hurang Road in Km. 0/00 to 7/00. (Sub Head:- Construction of 900 mm dia RCC Hume Pipe culvert alongwith wing wall at R.D. 0/540).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	43.39	Per cubic metre	491.80	21339.00	Rupees Twenty One Thousand Three Hundred Thirty Nine Only
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.76	Per cubic metre	4818.20	3662.00	Rupees Three Thousand Six Hundred Sixty Two Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	23.60	Per cubic metre	5300.20	125085.00	Rupees One Lakh Twenty Five Thousand Eighty Five Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.36	Per cubic metre	5515.20	51622.00	Rupees Fifty One Thousand Six Hundred Twenty Two Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	5.00	per running meter	4061.70	20309.00	Rupees Twenty Thousand Three Hundred Nine Only
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	287.30	2298.00	Rupees Two Thousand Two Hundred Ninety Eight Only
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.80	Per cubic metre	1472.70	7069.00	Rupees Seven Thousand Sixty Nine Only
Total in figure :					231384.00	Rupees Two Lakh Thirty One Thousand Three Hundred Eighty Four Only
Total in Words :					Rupees Two Lakh Thirty One Thousand Three Hundred Eighty Four Only	

Executive Engineer,
Mandi Division No. 1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 231177.00
Earnest Money Rs:- 4600.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work : Construction of Sudhar Swar Hurang Road in Km. 0/00 to 7/00. (Sub Head:- Construction of 900 mm dia RCC Hume Pipe culvert alongwith wing wall at R.D. 1/120).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.43	Per cubic metre	491.80	20867.00	Rupees Thousand Eight Hundred Sixty Seven Only
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.76	Per cubic metre	4818.20	3662.00	Rupees Three Thousand Six Hundred Sixty Two Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	23.60	Per cubic metre	5300.20	125085.00	Rupees One Lakh Twenty Five Thousand Eighty Five Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.36	Per cubic metre	5515.20	51622.00	Rupees Fifty Thousand Six Hundred Twenty Two Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	5.00	per running meter	4061.70	20309.00	Rupees Thousand Three Hundred Nine Only
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	287.30	2298.00	Rupees Two Thousand Two Hundred Ninety Eight Only
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.98	Per cubic metre	1472.70	7334.00	Rupees Seven Thousand Three Hundred Thirty Four Only
Total in figure :					231177.00	Rupees Two Lakh Thirty One Thousand One Hundred Seventy Seven Only
Total in Words :		Rupees Two Lakh Thirty One Thousand One Hundred Seventy Seven				

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs :- 266684.00
 Earnest Money Rs :- 5300.00
 Time :- One month

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. Mandi.

Name of work:- Improvement of "Black Spot" on Banogi Chehar Chaila road Km. 0/0 to 5/00. (Sub Head:- Providing and fixing "W" Metal Beam Crash Barrier at RD. 2/806 to 2/835).

Contract No.:

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	4.45	Cubic metre	491.80	2189.00	Rupees Two Thousand One Hundred Eighty Nine Only
2	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : six graded/crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	4.40	Cubic metre	6165.70	27129.00	Rupees Twenty Seven Thousand One Hundred Twenty Nine Only
3	Providing and erecting a "W" Metal Beam Crash Barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam guard rail 70cm (seventy centimetre) above road/ ground level fixed on ISMC series channel vertical posts 150x75x5mm thick (one hundred fifty into seventy five into five millimetre) spaced 1.50 (one point five zero) metre centre to centre 1.80 metre (one point eight zero) high 1.10 metre (one point one zero) below ground/ road level all steel parts and fittings to be galvanised by hot deep process, all fittings to confirm to IS: 1364, metal beam guard rail to be fixed on the vertical posts with a spacer of channel section 150x75x5mm (one hundred fifty into seventy five into five millimetre), 330mm (three hundred thirty millimetre) long complete as per clause 810 within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	66.00	Running metre	3596.45	237366.00	Rupees Two Lakh Thirty Seven Thousand Three Hundred Sixty Six Only

Total in Figure :

					266684.00	Rupees Two Lakh Sixty Six Thousand Six Hundred Eighty Four Only
--	--	--	--	--	-----------	---

Total in Words :

						Rupees Two Lakh Sixty Six Thousand Six Hundred Eighty Four Only
--	--	--	--	--	--	---

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 202601.62
Earnest Money Rs:- 4100.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP. PWD. at Padhar.						
Name of work :- Improvement of black spot Kataula Batheri Arang road Km. 0/0 to 15/285. (Sub Head:- Providing and fixing of "W" Metal Beam Crash Barriers system at R.D. 2/090 to 2/140).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	3.50	Cubic metre	491.80	1721.30	Rupees One Thousand Seven Hundred Twenty One and Paise Thirty Only
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	3.45	Cubic metre	6095.60	21029.82	Rupees Twenty Thousand Twenty Nine and Paise Eighty Two Only
3	Providing and erecting a "W" Metal Beam Crash Barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam guard rail 70cm (seventy centimetre) above road/ ground level fixed on ISMC series channel vertical posts 150x75x5mm thick (one hundred fifty into seventy five into five millimetre) spaced 1.50 (one point five zero) metre centre to centre 1.80 metre (one point eight zero) high 1.10 metre (one point one zero) below ground/ road level all steel parts and fittings to be galvanised by hot deep process, all fittings to conform to IS: 1364, metal beam guard rail to be fixed on the vertical posts with a spacer of channel section 150x75x5mm (one hundred fifty into seventy five into five millimetre), 330mm (three hundred thirty millimetre) long complete as per clause 810 within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	50	Running metre	3597.01	179850.50	Rupees One Lakh Seventy Nine Thousand Eight Hundred Fifty and Paise Fifty Only
Total in figure :					202601.62	Rupees Two Lakh Two Thousand Six Hundred One and Paise Sixty Two Only
Total in Words :		Rupees Two Lakh Two Thousand Six Hundred One and Paise Sixty Two Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs :- 351914.70
 Earnest Money Rs :- 7000.00
 Time :- One month

Tender Inviting Authority: Executive Engineer, Mandi Division No. I HP.PWD. Mandi.
 Name of work:- Improvement of "Black Spot" on Shegli Prasher road Km. 0/0 to 5/00. (Sub Head:- Construction of Retaining wall at RD. 4/350 to 4/360).
 Contract No.:
 Bidder Name:

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	35.15	Cubic metre	491.80	17287.00	Rupees Seventeen Thousand Two Hundred Eighty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	67.23	Per cubic metre	4560.60	306609.14	Rupees Three Lakh Six Thousand Six Hundred Nine and Paise Fourteen Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	273.10	3277.20	Rupees Three Thousand Two Hundred Seventy Seven and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.80	Per cubic metre	1472.70	24741.36	Rupees Twenty Four Thousand Seven Hundred Forty One and Paise Thirty Six Only
Total in Figure :					351914.70	Rupees Three Lakh Fifty One Thousand Nine Hundred Fourteen and Paise Seventy Only
Total in Words :					Rupees Three Lakh Fifty One Thousand Nine Hundred Fourteen and Paise Seventy Only	

Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padihar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 193798.37
 Earnest Money Rs:- 3900.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD at Padhar.	
Name of work :- Restoration of Damages on Uhl Valley road in Km. 0/00 to 10/00. (Sub Head:- Construction of Retaining wall at R.D. 0/916 to 0/920).	
Contract No. :	
Bidder Name :	

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.80	Per cubic metre	491.80	11213.04	Rupees Eleven Thousand Two Hundred Thirteen and Paise Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge	38.43	Per cubic metre	4553.60	174994.85	Rupees One Lakh Seventy Four Thousand Nine Hundred Ninety Four and Paise Eighty Five Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.40	Per cubic metre	1472.70	3534.48	Rupees Three Thousand Five Hundred Thirty Four and Paise Forty Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	270.40	4056.00	Rupees Four Thousand Fifty Six Only
Total in figure :					193798.37	Rupees One Lakh Ninety Three Thousand Seven Hundred Ninety
Total in Words :					Rupees One Lakh Ninety Three Thousand Seven Hundred Ninety Eight and Paise Thirty Seven Only	

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar