

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2024:-
To,

4159-4163

Dated:-

4/12/24


The Executive Engineer (IT Cell),
Nigam Vihar, Shimla.

Subject:

Publication of Tender Notice.

In this connection, it is submitted that the tender notice of the works given in the Notice Inviting Tender for uploading on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2020 dated 16.07.2021 as the work mentioned in the Notice Inviting Tender are urgent nature and Public interest. The Notice Inviting Tender and Schedule of Quantity are enclosed herewith for favour of taking further necessary action please.


DA/As above.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. The Computer Cell Office of the Executive Engineer, (IT Cell), Nigam Vihar Shimla for uploading the NIT on the Departmental website please.

DA/As above.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
.....
SHORT TERM TENDER NOTICE


Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Fatehpur Divn. HPPWD, Fatehpur for the following works on behalf of Governor of Himachal Pradesh from the approved and eligible contractor Enlisted in HPPWD Class (C&D), so as to reach in the office of the Executive Engineer, Fatehpur Divn. HPPWD Fatehpur on or before **13.12.2024** up to **10.30 AM** and will be opened on the same day at **11.00 AM** in the presence of the contractors or their authorized representatives if any. The application for purchase of tender will be received upto **5.00PM** on dated **11.12.2024**. The Tender form can be had from his office against cash payment (Nonrefundable) up to **5.00 PM** on **12.12.2024**.

The Earnest Money in the shape of the NSC/FDR, s Time Deposit Accounts/ Saving Accounts in any of the post office/ Bank in H.P. duly pledged in favour of the Executive Engineer must be accompanied with the tender. Conditional tender, tender received without earnest money will be summarily rejected. The Executive Engineer reserves the right to reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated cost in (Rs.)	E/Money (in Rs.)	Time limit	Cost of Form
1	Repair of Retaining wall near culvert at Chhoti Blehar to Samshan Ghat road in Golwan Village under SDRF (Deposit work) (SH:- Construction of wing wall at RD 0/643 to 0/649 , 0/655 to 0/658 (US) side and 0/645 to 0/648 and 0/655 to 0/658 (DS).	189657/-	3800/-	One Month	350/-
2	Construction of road from Sushil Kumar to Ashok Kumar House Village Chamoli in GP Batrahan (SH:- C/o Cement Concrete pavement at RD 0/030 to 0/168 under MMGPY (Deposit work)	284725/-	5700/-	One Month	350/-
3	Construction of Pucca Path from Khatrehar Pardah road to Jasbir Ashok etc. house Village Khatrehar GP Hatli (SH:- P/L Interlocking Concrete Block pavement at RD 0/0 to 0/052 under SDP (Deposit work)	146372/-	3000/-	One Month	350/-
4	Construction of Kangar to Kandor road KM 0/0 to 1/0 under SCDP (SH:-P/L G-III at RD 0/700 to 0/870.	68061/-	1400/-	One Month	350/-
5	Construction of Moukhar Hussiana road KM 0/0 to 4/350 (SH:- C/o Retaining wall at RD 3/911 to 3/915).	84841/-	1700/-	One Month	350/-
6	A/R & M/O various road under HPPWD Sub-Division Rehan (Section Rehan) (SH:- Repair of Pot Holes at various RDs.	446335/-	9000/-	One Month	350/-

It is certified that the above work are emergent nature and urgently required in the interest of the People of this area. The Tender of these works be called in Short Terms Tender Notice without publishing in the News Paper, however the same should be shown on Departmental website

- Note:- (1)The contractor may produce the copy of the latest enlistment/ renewal and PAN.
(2) The contractor must be registered as a dealer under HPST Act, 1968 and should produce sale tax clearance certificate from the Excise & Taxation department.
(3) The contractor shall produce registration of labour from the competent authority under contract Act, 1970 failing which no tender shall be issued to him.
(4) Special care should be taken to write the rates both in figures and in words, failing which the case likely to be rejected.
(5) Registered under GST No. & EPF.
(6) The tender will not be issued to those contractors who have already two or more works in hand in HPPWD. The contractor will give an affidavit along with application that he has not more than two works in hand in HPPWD for execution, failing which the application for issuing the tender forms shall not be accepted.


Executive Engineer
Fatehpur Divn. HPPWD
Fatehpur.

SCHEDULE OF QUANTITY

Name of work:- Repair of Retaining wall near culvert at Chhoti Balehar to Shamshan Ghat road in Golwan Village
Under SDRF Deposit work (SH):- Construction of wing wall at R.D. 0/643 to 0/649, 0/655 to 0/658 (US) side and 0/645 to 0/648
and 0/655 to 0/658 (DS).
Estimated cost:- Rs.189657/- only
Earnest Money : Rs.3800/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	26.04 Cubic meter.			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.25 cubic meter			Per cubic meter	
3	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	7.92 Cubic meter.			Per cubic meter	
4	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.00 Numbers			Each	


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (N.D.)

SCHEDULE OF QUANTITY

Name of work:- Construction of road from Sushil Kumar to Ashok Kumar house village Chamoli G.P. Batrahan

Estimated cost:- Rs.284726/- only

(SH):- Construction of cement concrete pavement at R.D. 0/030 to 0/140 and Edge wall at R.D. 0/145 to 0/155) Under MMGPY Deposit

Earnest Money : Rs.5700/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation by mechanical means (Hydraulic Excavator)/Manual means over area (exceeding 30 cm. in depth, 1.5m in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth within any leads and lifts as directed by the Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	1.00 Cubic meter.			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	2.50 Cubic meter.			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	49.50 Cubic meter.			Per cubic meter	

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca path from Khatrehad Pardah road to Jasbir, Ashok etc. house village Khatrehad G.P. Hatli. (SH:- Providing and laying Interlocking Concrete Block Pavement at R.D. 0/0 to 0/052.) Under SDP (Deposit work).

Estimated cost:- Rs.146372/- only
Earnest Money : Rs.3000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer –in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.02 Cubic meter.			Per cubic meter	
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	140.40 Square meter			Per Square meter.	

(Signature)
Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Kangar to Kandor road Km. 0/0 to 1/0 Under SCDP (SH:-Providing and laying Grading-III at R.D. 0/700 to 0/870).						Estimated cost:- Rs.68061/- only
						Earnest Money : Rs.1400/- only
						Time limit:- One month
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	38.89 cubic meter			Per cubic meter	



Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Construction of Moukhar Hussiana road km. 0/0 to 4/350 (SH:- Construction of Retaining wall at R.D.3/911 to 3/915).

Estimated cost:- Rs.84841/- only
Earnest Money : Rs.1700/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	7.28 Cubic meter.			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.74 cubic meter			Per cubic meter	
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00 Numbers			Each	
4	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	20.83 Cubic meter.			Per cubic meter	


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various road under HPPWD Sub Division Rehan (Section Rehan) (SH:- Repair of pot holes at various RDs). Estimated cost:- Rs.446335/- only
 Earnest Money : Rs.9000/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.61 cubic meter			Per cubic meter	
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - tren) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1281.000 Square meter			Per square meter	
					Total:-	


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)