

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No. PW/EE/NH/RMP-CB-Tender/2024-25-  
To

5987


Dated:- 30-11-2024

The Executive Engineer (IT)  
Nigam Vihar Shimla-2

Subject:- Publication of tender notice.


Enclosed please find herewith copy of tender notice in respect of tender invited vide this office NIT No. PW/EE/NH/RMP/CB-Tender Notice/2024-25-5947-86 Dated:-30.11.2024 for uploading the same on department website for wide publicity.

DA:- Copy to NIT

  
Executive Engineer,  
NH Division, H.P.PWD,  
Rampur Bushahr.

### Certificate

Certified that the tenders of the works invited vide this office NIT No. PW/EE/NH/RMP/CB-tender/ 2024-25- 5947-86 dated 30.11.2024 is of urgent nature in exigency of public interest.

  
Executive Engineer  
NH Division HPPWD,  
Rampur Bushahr.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Sealed item rate tender(s) on PWD form No.6 &8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors/consultants in HP.PWD MoRT&H in appropriate class to reach in this office on **09.12.2024** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors/ consultants or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **07.12.2024** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without **earnest money** or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.


Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	A/R & M/O on NH-305 Sainj-Luhri Aut road Km 0/ 0 to 53/0(SH:- Patch work with 40mm BC in pot holes at RDs and 1/810 to 2/135)	305757/-	6200/-	One month	6&8	350/-
2	A/R & M/O on NH-305 Sainj-Luhri Aut road Km 0/ 0 to 53/0(SH:- Patch work with 40mm BC in pot holes at RDs 0/220 to 0/310,0/310 to 0/350,1/370 to 1/385,1/400 to 1/440,1/450 to 1/480 and 1/555 to 1/590,1/780 to 1/800)	411647/-	7200/-	One month	6&8	350/-
3	R.R. damages on Sainj Luhri Jalori Banjar Aut road NH-305 Km 0/00 to 97/00(SH: - Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slip between Km 91/00 to 94/00.	492270/-	10000/-	One month	6&8	350/-
4	-do- (SH:- Maintenance of earthen shoulder, hill side drain clearance and removal of land slide slips between Km 88/00 to 91/00	495782/-	10000/-	One month	6&8	350/-
5	-do- (SH;- Maintenance of earthen shoulder hill side drain clearance and removal of land slide slips between Km 83/00 to 87/00	494139/-	10000/-	One month	6&8	350/-
6	-do- (SH:- Maintenance of earthen shoulder, hill side drain clearance and removal of land slide slips between Km 68/00 to 72/00)	494092/-	10000/-	One month	6&8	350/-
7	-do- (SH:- Maintenance of earthen shoulder, hill side drain clearance and removal of land slide slips between Km 63/00 to 67/00	490204/-	10000/-	One month	6&8	350/-
8	R.R damages on NH-05 Km 236/0 to 368/0(SH:- Construction of R/wall in PCC at RD 316/692 to 316/696)	404277/-	8100/-	Two months	6&8	350/-
9	-do- SH:- C/O R/wall in PCC at RD 316/696 to 316/700)	404007/-	8100/-	Two months	6&8	350/-



10	R.R. damages on NH-05 in the State of Himachal Pradesh (SH:-Temporary restoration of abandoned portion of NH-05 Km 322 to 323 near Solding under HPPCL Deposit.	484371/-	9700/-	Two months	6&8	350/-
11	R.R. damages on NH-22 Km 236/0 to 368/0(SH:- Removal of landslides/slips at different stretches Km 284/00 to 285/00	477792/-	9600/-	15 days	6&8	350/-
12	-do- (SH:- Removal of landslides/slips at different stretches Km 236/0 to 246/0)	463196/-	9500/-	15 days	6&8	350/-

### SPECIAL CONDITIONS

1. The material shall be arranged by the contractor/ consultants himself.
2. The detail of documents to be attached with the application is given below.
  - i Latest copy of renewal enlistment/empanelment.
  - ii Copy of Pan Card.
  - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractor/ consultants are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labour cess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
12. The Contractor/consultants will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.
13. GST will be deducted from each bill as per latest instruction of the Government.


  
Executive Engineer,  
NH Division, H.P.PWD,  
Rampur Bushahr.

No.PW/EE/NH/RMP/CB-Tender Notice/2024-25- 5947-86

Dated:-30.11.2024


Copy forwarded for information to the:-

1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (NH) HP.PWD, Shimla-1
3. Superintending Engineer, NH-Circle, HP.PWD, Shimla
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

  
Executive Engineer,  
NH Division, H.P.PWD,  
Rampur Bushahr.


### Schedule of Quantity

Name of work:- A/R & M/O on NH- 305 Sainj Luri Aut Road Km. 0/00 to 53/00 ( SH:- Patch work with 40mm Bc in pot holes at Rds. and 1/810 to 2/135 )			Estimated Cost:-		305757.00	
			Earnest Money:-		6200.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Providing treatment and repair to pot holes/ruts and any depth/ patch repair of all types of bitumen pavement complete as per technical specification Clause 3004.2 and as per direction of Engineer by using paving grade bitumen/ emulsion/ cold ready mix material. The job includes remoyal of all failed material, trimming of completed excavation to providing firm vertical faces, cleaning of surface. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	577.50			Per cubic meter.	
Total Rs:-						

  
 Executive Engineer,  
 N.H.Division,HP.PWD,  
 Rampur Bsr ✓

**Schedule of Quantity**


Name of work:- A/R & M/O on NH- 305 Sainj Luri Aut Road Km. 0/00 to 53/00 ( SH:- Patch work with 40mm Bc in pot holes at Rds. 0/220 to 0/310, 0/310 to 0/350, 1/370 to 1/385, 1/400 to 1/440, 1/450 to 1/480 and 1555 to 1/590, 1/780 to 1/800 )			Estimated Cost:-		411647.00	
			Earnest Money:-		7200.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Providing treatment and repair to pot holes/ruts and any depth/ patch repair of all types of bitumen pavement complete as per technical specification Clause 3004.2 and as per direction of Engineer by using paving grade bitumen/ emulsion/ cold ready mix material. The job includes remoyal of all failed material, trimming of completed excavation to providing firm vertical faces, cleaning of surface. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compansated by him at his own cost.	777.50			Per cubic meter.	
Total Rs:-						

  
 Executive Engineer,  
 N.H.Division,HP.PWD,  
 Rampur Bsr./✓




### Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road ( NH 305) Km. 0/00 to 97/00) ( Sub Head:- Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slips between Km. 91/00 to 94/00)			Estimated Cost:-		492270.00	
			Earnest Money:-		10000.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Maintenance of Earthen shoulder (filling with fresh selected soil Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	3280.35			Per square meter.	
2	Removal of the earth from the chocked hill side drain and disposing it on the velley side manually. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	2125.00			Per running meter.	
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	366.90			Per cubic meter.	
<b>Total Rs:-</b>						

  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road ( NH 305) Km. 0/00 to 97/00) ( Sub Head:- Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slips between Km. 88/00 to 91/00)			Estimated Cost:-		495782.00	
			Earnest Money:-		10000.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Maintenance of Earthen shoulder (filling with fresh selected soil Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	3290.25			Per square meter.	
2	Removal of the earth from the chocked hill side drain and disposing it on the velley side manually. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	2170.00			Per running meter.	
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	365.50			Per cubic meter.	
Total Rs:-						


  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr/



(5)

### Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road ( NH 305) Km. 0/00 to 97/00) ( Sub Head:- Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slips between Km. 83/00 to 87/00)			Estimated Cost:-		494139.00	
			Earnest Money:-		10000.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Maintenance of Earthen shoulder (filling with fresh selected soil Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	3286.10			Per square meter.	
2	Removal of the earth from the chocked hill side drain and disposing it on the valley side manually. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	2150.00			Per running meter.	
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	365.75			Per cubic meter.	
<b>Total Rs:-</b>						

  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr

(6)

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road ( NH 305) Km. 0/00 to 97/00) ( Sub Head:- Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slips between Km. 68/00 to 72/00)			Estimated Cost:-		494092.00	
			Earnest Money:-		10000.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Maintenance of Earthen shoulder (filling with fresh selected soil Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	3284.20			Per square meter.	
2	Removal of the earth from the chocked hill side drain and disposing it on the velley side manually. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	2150.00			Per running meter.	
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	366.10			Per cubic meter.	
	Total Rs:-					

  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr



Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road ( NH 305) Km. 0/00 to 97/00) ( Sub Head:- Maintenance of earthen shoulder, hill side drain clearance and removal of landslide slips between Km. 63/00 to 67/00)			Estimated Cost:-		490204.00	
			Earnest Money:-		10000.00	
			Time:-		One month	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Maintenance of Earthen shoulder (filling with fresh selected soil Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	3282.25			Per square meter.	
2	Removal of the earth from the chocked hill side drain and disposing it on the velley side manually. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	2100.00			Per running meter.	
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	365.20			Per cubic meter.	
	Total Rs:-					

  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr/✓



# SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damges on NH-05 Km 236/00 to 368/00 (SH:- Construction of Retaining wall in PCC at RD 316/692 to 316/696)


Estimate Cost:- 404277.00

Earnest Money:- 8100.00

Time:- 2 Months.

Sr. No.	Sub Head/Item of work	Quantity	Unit	Rate in Figure	Rate in words.	Amount
1	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications in all kinds of soils i.e.pick work,jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	19.08	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls 3 complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	60.56	Per Cubic Metre			
3	Providing & fixing weep holes in plain cement concrete Retaining wall, Breast wall, abutments and return walls with 100 mm (one hundred milimetre) PVC pipe, extended through the full width of the structure with slope of 1 V: 20 H towards draining face complete as per MORT & H specifications clause 2706 and 2200 (latest revision) including hauling of material in all leads and lifts with all modes of transportation and as per direction of the Engineer-in-Charge.	14.80	Per Running Metre			
4	Providing and laying of Filter media with granular materials/ stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2 of MORT & H specifications to a thickness of not less than 600mm (Six hundred milimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls, abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specifications as per MORTH Clause 710.1.4 of IRC 78 & 2200 latest revision with in all leads and lifts through all mode of transportation and as per the entire satisfication and direction of Engineer -in-Charge.	12.84	Per Cubic Metre			

Total=

  
 Executive Engineer  
 NH Division HPPWD,  
 Rampur Bsr.

# SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damges on NH-05 Km 236/00 to 368/00 (SH:- Construction of R.wall in PCC at RD 316/696 to 316/700)


Estimate Cost:- 404007.00

Earnest Money:- 8100.00

Time:- 2 Months.

Sr. No.	Sub Head/Item of work	Quantity	Unit	Rate in Figure	Rate in words.	Amount
1	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications in all kinds of soils i.e.pick work,jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compansated by him at his own cost.	20.52	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls 3 complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	60.56	Per Cubic Metre			
3	Providing & fixing weep holes in plain cement concrete Retaining wall, Breast wall, abutments and return walls with 100 mm (one hundred milimetre) PVC pipe, extended through the full width of the structure with slope of 1 V: 20 H towards draining face complete as per MORT & H specifications clause 2706 and 2200 (latest revision) including hauling of material in all leads and lifts with all modes of transportation and as per direction of the Engineer-in-Charge.	14.80	Per Running Metre			
4	Providing and laying of Filter media with granular materials/ stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2 of MORT & H specifications to a thickness of not less than 600mm (Six hundred milimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls, abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specifications as per MORTH Clause 710.1.4 of IRC 78 & 2200 latest revision with in all leads and lifts through all mode of transportation and as per the entire satisfication and direction of Engineer -in-Charge.	12.16	Per Cubic Metre			

Total=


  
 Executive Engineer  
 NH Division HPPWD,  
 Rampur Bsr.



### SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damages on NH-05 in the state of Himachal Pradesh (SH:- Temporary restoration of abandoned portion of NH-05 Km 322 to 323 near solding under HPPCL Deposit.							Estimate Cost:-	484371.00
							Earnest Money:-	9700.00
							Time:-	2 Months.
Sr. No.	Sub Head/Item of work	Quantity	Unit	Rate in Figure	Rate in words.	Amount		
1	Earthwork in excavation for structures in all depths as per drawing and technical specifications in all kinds of soils i.e. pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.00	Per Cubic Metre					
2	Plain/Reinforced Cement Concrete in open foundation as per drawing and technical specification. PCC 1:3:6 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	30.00	Per Cubic Metre					
3	Plain/Reinforced Cement Concrete in open foundation as per drawing and technical specification. PCC 1:2:4 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	26.09	Per Cubic Metre					
4	Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 1000mm dia.	30.00	Per Running Metre					


Total=

  
 Executive Engineer  
 NH Division HPPWD,  
 Rampur Bsr.




## Schedule of Quantity

Name of work:- R/R damages on NH -05 Km 236/000 to 368/00 (SH:- Removal of landslides /slips at different stretches Km 284/00 to 285/00)				Estimated Cost:-	477792.00	
				Earnest Money:-	9600.00	
				Time:-	15 days	
Sr. No	Descriptions	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1774.20			Per Cubic metre	
	<b>Total:-</b>					

  
 Executive Engineer,  
 N.H. Division HP.PWD,  
 Rampur Bsr.

## Schedule of Quantity

Name of work:- R/R damages on NH -05 Km 236/00 to 368/00 (SH:- Removal of landslides /slips at different stretches Km 236/00 246/00)				Estimated Csot:-	463196.00	
				Earnest Money:-	9500.00	
				Time:-	15 days	
Sr. No	Descriptions	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1720.00			Per Cubic metre	
	<b>Total:-</b>					

  
 Executive Engineer,  
 N.H. Division HP.PWD,  
 Rampur Bsr.