

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 29-01-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable):- 29-01-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 31-01-2025 at 10.30 AM.
4. Date of opening of Tender:- 31-01-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
	C/O & M/T Jhanikar Tal to Thathwani High School ( GP Amman) km 0/00 to 1/00 ( SH:- P/L Cement concrete pavement at RD 0/233 to 0/259 )	96372.00	2000.00	Two Months	Rs. 350/-	Class-D
2	C/O & M/T Jhanikar Tal to Thathwani High School ( GP Amman) km 0/00 to 1/00 ( SH:- P/L Cement Concrete pavement at RD 0/210 to 0/233)	96239.00	2000.00	Two Months	Rs. 350/-	Class-D
3	C/O Ambulance road Mahila Mandal Bhawan to Baba Balak Nath Temple via Rajpootan Basti ( SH:- Steel Reinforcement for covering the drain at RD 0/30 to 0/060 )	95348.00	2000.00	Two Months	Rs. 350/-	Class-D
4	C/O link road Bhuniplu Da Ghat to Ghumarli via Jijwin ( Kud) Dalalar Km 0/00 to 1/300 ( SH:- P/L Cement concrete pavement at RD 1/072.75 to 1/097)	99450.00	2000.00	Two Months	Rs. 350/-	Class-D
5	C/O link road Bhuniplu Da Ghat to Ghumarli via Jijwin (Kud) Dalalar km 0/00 to 1/300 ( SH:- P/L Cement Concrete pavement at RD 1/048.60 to 1/072.75)	98865.00	2000.00	Two Months	Rs. 350/-	Class-D
6	C/O link road Bhuniplu Da Ghat to Ghumarli via Jijwin (Kud) Dalalar km 0/00 to 1/300 ( SH:- P/L Cement Concrete pavement at RD 1/00 to 1/024.30)	99450.00	2000.00	Two Months	Rs. 350/-	Class-D

7	C/O link road Bhumplu Da Ghat to Ghumarli via Jijwin (Kud) Dalalar km 0/00 to 1/300 ( SH:- P/L Cement Concrete pavement at RD 1/024.30 to 1/048.60)	99450.00	2000.00	Two Months	Rs. 350/-	Class-D
8	C/O inauguration / Foundation Pedestal various work under Sub Division Samirpur (HP) (SH:- Providing and laying fixing of inauguration / Foundation Pedestal i/c Granite stone plate.	81000.00	2000.00	Two Months	Rs. 350/-	Class-D
9	C/O Inauguration / Foundation Pedestal various work under Sub Division Bhoranj ( SH:- Providing and laying fixing of inauguration/ Foundation Pedestal i/c Granite stone plate)	81000.00	2000.00	Two Months	Rs. 350/-	Class-D
10	A/R & M/O HPPWD Rest House at Samipur Distt Hamirpur (HP) ( SH:- P/F curtain, wall mixer & stop cock etc) ( Set No-I & II)	99172.00	2000.00	Two Months	Rs. 350/-	Class-D
11	A/R & M/O HPPWD Rest House at Samipur Distt Hamirpur (HP) (SH:- P/F Furniture , Digital looking mirror & wash basin etc) (Set No-I & II)	99181.00	2000.00	Two Months	Rs. 350/-	Class-D
12	A/R & M/O HPPWD Rest House at Samirpur Distt Hamirpur (HP) ( SH:- P/F flush door shutters, window shutters, P/F & supply furniture & other sanitary items) Set No-I and II )	99963.00	2000.00	Two Months	Rs. 350/-	Class-D
13	Restoration of rain damages on Dasmal to lagmanwin via Bhounkhar km 0/00 to 5/00 ( SH:- C/O B/wall at RD 3/570 to 3/576)	96542.00	2000.00	Two Months	Rs. 350/-	Class-D
14	C/O Path from Ravi Kumar House towards Pawan Kumar House GP Badehar (SH:- P/L Cement concrete Pavement at RD 0/288 to 0/326) ( Deposit work)	99145.00	2000.00	Two Months	Rs. 350/-	Class-D
15	C/O path from Pawan Kumar House towards Janj Ghar Ward NO. 1 GP Badehar ( SH:- P/L Cement Concrete Pavement at RD 0/250 to 0/287.50)( Deposit work)	99024.00	2000.00	Two Months	Rs. 350/-	Class-D
16	A/R & M/O various road under Bhoranj Division ( SH:- Supply of stationary article etc. for use in Division office)	96590.00	2000.00	Two Months	Rs. 350/-	Class-D
17	A/R & M/O various road under Bhoranj Division ( SH:- Supply of stationary article etc. for use in Division office)	98430.00	2000.00	Two Months	Rs. 350/-	Class-D



Class-

18	A/R & M/O Una Aghar Mandi road Km 67/00 to 79/00 ( SH:- Providing and installation of Crash Barrier at RD 67/00 to 73/00)	93600.00	2000.00	Two Months	Rs. 350/-	Class-D
19	A/R & M/O Una Aghar Mandi road Km 67/00 to 79/00 ( SH:- Providing and installation of Crash Barrier at RD 73/00 to 75/00 )	93600.00	2000.00	Two Months	Rs. 350/-	Class-D
20	A/R & M/O various road under Bhoranj Sub Division HPPWD Bhoranj Section Patta. ( SH:- Supplying and stacking of aggregate 10mm to 12mm, 53mm to 22mm and sand)	98800.00	2000.00	Two Months	Rs. 350/-	Class-D
21	A/R & M/O various road under Bhoranj Sub Division HPPWD Bhoranj Section Patta. ( SH:- Supplying and stacking of aggregate 10mm to 12mm, Sand and moulder bricks)	98300.00	2000.00	Two Months	Rs. 350/-	Class-D
22	A/R & M/O various road in under Sub Division Bhoranj ( SH:- Supplying and stacking of aggregate 10mm to 12mm and sand ( Bhoranj Section)	98500.00	2000.00	Two Months	Rs. 350/-	Class-D
23	Restoration of rain damages on Lajhyani-Dhamrol road. ( Dressing and cutting , filling road side Berms/ shoulder at RD 0/00 to 5/200 )	99196.00	2000.00	Two Months	Rs. 350/-	Class-D
24	Restoration of rain damages on Bhareri to Chamboh via Forest Rest House ( SH:- Dressing and cutting, filling road side Berms/shoulder at RD 0/00 to 3/00 )	99196.00	2000.00	Two Months	Rs. 350/-	Class-D
25	Restoration of rain damages of Dhirar to Dadu via Baroh road ( SH:- Dressing and cutting, filling road side Berms/ shoulders at RD 0/00 to 4/00 )	99196.00	2000.00	Two Months	Rs. 350/-	Class-D
26	R/R damages on Una Aghar Mandi road Km 67/00 to 79/00 ( SH:- C/O R/wall at RD 76/450 to 76/458)	97876.00	2000.00	Two Months	Rs. 350/-	Class-D
27	R/R damages on Bassi Manoh road ( SH:- C/O R/wall at RD 0/570 to 0/578.50)	96750.00	2000.00	Two Months	Rs. 350/-	Class-D
28	C/O link road from Bhareri Badehar road to Watan Singh House ( SH:- P/L interlocking paverblock pavement at RD 0/00 to 0/015 )( Deposit work)	97113.00	2000.00	Two Months	Rs. 350/-	Class-D
29	C/O link road from Bhareri Badehar road to Wattan Singh House ( SH:- P/L interlocking paverblock pavement at RD 0/015 to 0/030 )( Deposit work)	97113.00	2000.00	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of

undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

**TERMS AND CONDITIONS:-**

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

**Certified that the above work is of emergent nature in exigency of Public interest.**

Executive Engineer  
Bhoranj Division  
HPPWD Bhoranj  
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2024-

16584-16624

Dated:- 22-01-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8<sup>th</sup> Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,  
Bhoranj Division,  
HPPWD, Bhoranj.

# SCHEDULE OF QUANTITY

WORK:- C/O & M/T Jhanikar Tal to Thathwani High School (GP Amman) km 0/00 to 1/00. (SH:- PIL Cement Concrete Pavement at RD 0/233 to

Estimated Cost  
Earnest Money  
Time

Rs 96372-  
Rs. 2000/-  
2Months

Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1 Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.15	Per Square Meter			
2 Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.06	Per cubic Meter			
3 Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.06	Per cubic metre			
4 Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm (twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.05	Per Cubic Meter			
<b>Total</b>					

**Terms and Condition:-**

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H&P W D Bhoranj



OF WORK:- C/O & MT Jhankar Tal to Thantwani High School (GP Amman) Km.0/00 to 10/00.(SH:- P/L Cement Concrete Pavement at RD 0/210 to 33.)

## SCHEDULE OF QUANTITY

Estimated Cost Rs 96239/-  
Earnest Money Rs. 2000/-  
Time 24 months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres as per the direction of the Engineer-in-charge including entire carriage of material within all leads and tils and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.13	Per Square Meter			
2	Construction of granular sub base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at O/M.C. carriage of mixed material by tippers to work site, for all leads & tils, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value: 30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and tils and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.05	Per cubic Meter			
3	Providing concrete for plant reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and tils and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.05	Per cubic metre			
4	Providing and laying mechanically mixed cement concrete (M-20 (M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain reinforcement concrete in open foundation complete including cost of form work, steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and tils and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.04	Per Cubic Meter			
<b>Total</b>						

**Terms and Conditions:-**

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D. Bhoranj

# SCHEDULE OF QUANTITY

OF WORK:- C/O Ambulance Road Mahila Mandal Bhawan to Baba Balaknath Temple via Rajpootan Basti (SH:- Steel Reinforcement for Covering the Drain  
RD. 0/00 to 0/060 )

Estimated Cost  
Earnest Money  
Time

Rs 95,348/-  
Rs. 2000/-  
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates In Words	Amount
1	Centering and shuttering including strutting, propping etc. and removal of form work for as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	36.00	Per square meter			
2	Mild steel/Tor steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild steel and Medium Tensile steel bars as per direction of Engineer- In-Charge, including entire carriage of materials in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	862.58	Per kilogramme			
	<b>Total</b>					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D. Bhoranj

# SCHEDULE OF QUANTITY

(ME OF WORK :- CO link road Bhimpla Da Ghat to Ghumarli via Jyvan (kud) Dalalar km. 0/00 to 1/300 (SH:- P/L Cement Concrete Pavement at RD Estimated Cost Rs. 99450/-  
172.75 to 1099.7) Earnest Money Rs. 20000/-  
2Months

No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Reinforced concrete for plain reinforced concrete in P.C.C. grade M-10 (M-ten) (nominal mix 1:3:6 (one part cement, three parts sand, six parts stone aggregate) 20mm (twenty millimeters) nominal size in max. 50mm (two inch) size as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per cubic meter			
2	Forming and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 (one and a half) sand) 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per Cubic Meter			
Total						

**Terms and Condition:-**

1. Work shall be executed as per PWD specification

Executive Engineer  
Bhoranj Division  
HQ PWD Bhoranj



WORK:- C/O link road Elumupla Da Ghat to Giumarti via Jiywin (kud) Dalalar km. 0/00 to 1/300 (SH:- P/L Cement Concrete Pavement at RD Estimated Cost Rs 58265/-  
to 1/072.75.) Earnest Money Rs. 2000/-

## SCHEDULE OF QUANTITY

No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
					Time	2Months
1	Providing concrete for planthie, interroad concrete in P.C.C. grade M:10/M: ten nominal mix 1:3:6 (one part cement, three sand, six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.45	Per cubic meter			
2	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement: 1.5 concrete) 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.45	Per Cubic Meter			
<b>Total</b>						

**Terms and Conditions:-**

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
4P PWD Bhorani

## SCHEDULE OF QUANTITY

OF WORK:- C/O link road Bhunipulu Da Chat to Ghumarti via Jiywin (kud) Dalalar km. 0/00 to 1/300 (SH:- P/L Cement Concrete Pavement at RD

Estimated Cost  
Rs. 99450/-  
Earnest Money  
Rs. 2000/-  
Time  
2Months

Description of items	Quantity	Unit	Rate	Rate in words	Amount
1 Providing concrete for plain reinforced concrete in P.C.C. grade M-10(M-ten) nominal mix 1:3:6 (one cement, three sand, six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per cubic meter			
2 Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) 3 graded stone aggregate 20 mm nominal size as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per Cubic Meter			
<b>Total</b>					

**Terms and Conditions:-**

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D. Bhoranj

## SCHEDULE OF QUANTITY

WORK: C.O link road Ethumpla Da Chat to Chumhari via Jiywin (Kud) Dalalar km. 0/00 to 1/300 (SH:- P/L Cement Concrete Pavement at RD Estimated Cost Rs 99450/-  
1038.60) Earnest Money Rs. 2000/-  
Time 24months

Description of Items	Quantity	Unit	Rate	Rate in words	Amount
Providing and laying in position specified grade of reinforced concrete in P.C.C. grade M-10(M-ten) nominal mix 1:3:6 (one part cement, three parts six graded crushed stone aggregate) 20mm, twenty millimeters) nominal size in concrete foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of toll, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per cubic meter			
Providing and laying in position specified grade of reinforced cement concrete, including the cost of cementing, spreading, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 cubic parts six graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of toll, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.50	Per Cubic Meter			
<b>Total</b>					

Terms and Condition:-

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D Bhoranj

## SCHEDULE OF QUANTITY

NAME OF WORK :- C/O Inauguration Foundation Pedestal Various work under Sub- Division Samitpur (SH:- Providing and Laying fixing of Inauguration Foundation Pedestal i/c Granite stone plate.)

Estimated Cost  
Earnest Money  
Time  
Rs 81,000/-  
2000/-  
3Months

S/No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plaque as per approved drawing specification including 2 black Granite stone including letter writing complete. Construction of pedestal in modular bricks in cm 1:4:1 cement :4 sand) including coping in cement mortar 1:3 (1 cement :3 sand ) on top side face including painting / distemper with Terra Kota colour including including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, safe tax or other taxes imposed by the Government.	3.00	Each			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
HR PWD Bhoranj



## SCHEDULE OF QUANTITY

NAME OF WORK : C/O Inauguration of foundation Pedestal Various work under Sub- Division Bhoranj (SH:- Providing and Laying fixing of Inauguration of foundation Pedestal i.e. Granite stone plate.)

Estimated Cost  
Earnest Money  
Time  
Rs 81,000/-  
2000/-  
3Months  
Amount

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plaque as per approved drawing specification including 2" black Granite stone including letter writing complete. Construction of pedestal in modular bricks in cm 1 4/1 cement 4 sand) including coping in cement mortar 1 3 (1 cement 3 sand ) on top side face including painting / distemper with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all roads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahan, toll tax, sale tax or other taxes imposed by the Government.	3.00	Each			
	<b>Total</b>					
	<b>Terms and Condition:-</b>					

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D Bhoregaon

NAME OF WORK:- AIR & MO HP PWD Rest House at Samipur Dist. Hamirpur(P.) (SH:- P/F curtains, wall mixer & stop cock etc.) (Set no. I & II.)

## SCHEDULE OF QUANTITY

Sr.No	Description of Items	Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rs 99172/- Rs. 2000/- 2 month
1	Providing and fixing of curtain door including curtain roads, clamp and ornamental side hooks complete with satisfaction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00	Per Running meter			
2	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved 15 mm nominal dia as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
3	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS 8931, 15 mm nominal bore including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each			
4	Providing and fixing C.P. Towel rail complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws size 600x20mm as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
P.W.D. Bhoranj

## SCHEDULE OF QUANTITY

NAME OF WORK: A/R & M/O HP PWD Rest House at Samipur Distt. Hamirpur(H.P.) (SH:- P/F Furniture, Digital looking mirror & Wash basin etc.) (Set no. Estimated Cost Earnest Money Time

Rs. 5918/-  
Rs. 2000/-  
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	P/F and supplying entire tape M11 (42X21) including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
2	P/F and supplying wooden study chair including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each			
3	Providing and fixing digital looking mirror for complete set as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
4	Providing and fixing G.I Pipes complete with G.I fittings and clamps, i/c making good the walls etc. (concealed) pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall 15 mm dia nominal bore as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.00	Per Rmtr.			
5	Providing and fixing hindware/paryware wash basin with pedestal of catalogue no. Qubex COT1 with C.I brackets including paintings and brackets, cutting good the walls wherever required as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
6	Providing and fixing C.P Soap dish Holder of Catalogue No Jaquar AON-1131N as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
<b>Total</b>						
<b>Terms and Conditions:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
A/R PWD Bhoranj

## SCHEDULE OF QUANTITY

NAME OF WORK : AR & MO HP PWD Rest House at Samipur Dist: Hamirpur(H.P.) (SH:- PF flush door shutters, window shutters, p/f & Supply furniture & other sanitary items.) (Set no.1 and II)

Estimated Cost  
Earnest Money  
Rs. 99963/-  
Rs. 2000/-  
2 month

Sr.No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing ISI marked flush door shutters conforming to IS-2202 (Part I) non-decorative type core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.62	Per Square meter			
2	Providing and fixing paneled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-Charge 35 mm thick shutters including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.24	Per square metre			
3	Providing and fixing white vitreous china pedestal type water closet(V.C. pan) single piece of catalogue no. Aquiline C16901 made up of hardware with parryware with seat and lid conforming to IS:7231, with all fittings and fixtures complete including cutting, making good the walls and floors wherever required as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
4	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 5.5 mm thick glass panes as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.24	per square meter			
5	Providing and fixing curtain rods and doors and all accessories as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.00	Per Running Meter			
6	Providing and fixing C.P. Soap dish Holder of Catalogue No. Jaquar ACN-1131N as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government, as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
HP PWD Bhoranj



## SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of Rain Damages on Dasmal to Lammamwin via Bhounhar Km 0100 to 5100(SH:-C/O BWall at RD 31570 to 31576).

Estimated Cost  
Earnest Money  
Time  
Rs 96,542/-  
Rs 2000/-  
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling, wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.56	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement, five sand, ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe De-plastrified/ vedus pipe having pressure 4kg per centimeter square, (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V) 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhounhar Division  
HP PWD Bhounhar

Notes: Cf. WORK - C/O path from Bawa Kumar House towards, Bawa Kumar House G.P. Badshah (SH - P/L Cement Concrete Payment at RD 01288 to 01326) (for road work)

## SCHEDULE OF QUANTITY

Sr. No.	Description of Items	Quantity	Unit	Rate	Estimated Cost	Rs. 53145/-
					Earnest Money	Rs. 2000/-
					Time	2Months
					Rate in words	Amount
1	Providing concrete for (road) reinforced concrete in P.C.C. grade M-10/M-ten nominal (no. 13.6) (one cement - three sand - six graded crushed stone aggregate) 20mm twenty millimeters nominal size in concrete (including 1% for wastage and 1% for 1% nominal size) 1200 x 1200 x 1200 in for the duration of the 10 years including 1% for 1% nominal size of material within all bags, and 1% and other materials. The rates are inclusive of all royalty, Malwara, toll tax, sale tax or other taxes imposed by the Government.	7.90	Per cubic meter			
2	Providing and laying in position specified grade of reinforced cement concrete, including the cost of opening, shuttering, binding and reinforcement - All work up to depth level 11.53 (1 cement - 1.5 coarse sand) 3 graded stone aggregate 20 mm nominal size as per direction of Engineer-in-Charge including entire carriage of material within all bags, and 1% and other materials. The rates are inclusive of all royalty, Malwara, toll tax, sale tax or other taxes imposed by the Government.	2.63	Per Cubic Meter			
Total						

Terms and Conditions:-

\* Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D. Bhoranj

# SCHEDULE OF QUANTITY

NAHE CV WORK - C/C path from power house towards jang ghar road no 1 G.P. Baidhar (SH - PTL Cement Concrete Pavement at RD 0/250 to 0/287.50) (chopped work)

Sr No Description of Items

1 Providing concrete for foot reinforcement concrete in P.C.C. grade M 10/M 10 nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) (Twenty millimeters) nominal size in concrete reinforcement concrete in per drawings and technical specifications Clause E02, E03, 1202 & 1203 for per the thickness of the thickness in change including entire carriage of material within all roads and the and other incidentals. The rates are inclusive of all royalty, Rajasthan toll tax sale tax or other taxes imposed by the Government.

2 Providing and laying of position specified grade of reinforced cement concrete, including the cost of centering, shuttering, bracing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) is per direction of Engineer-in-Charge including entire carriage of material within all roads and its and other incidentals. The rates are inclusive of all royalty, Rajasthan toll tax sale tax or other taxes imposed by the Government.

Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rate in words	Rs 99028/- Rs. 2000/- Months Amount
8.01	Per cubic meter				
8.58	Per Cubic Meter				
Total					

Terms and Condition:-

\* Work shall be executed as per FWD specification

Executive Engineer  
Bhorani Division  
C/O PWD Bhorani

## SCHEDULE OF QUANTITY

NAME OF WORK: AR & MO Various road under Bhoranj Division. (SH- Supply of stationary article etc. for use in Division office)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rates in Words	Amount
1	Providing and supplying Diary Register complete in all respect within all lead and lift.	20.00	Each	540.00			
2	Providing and supplying Dispatch Register complete in all respect within all lead and lift.	20.00	Each	540.00			
3	Providing and supplying M.A.S. Register complete in all respect within all lead and lift.	8.00	Each	760.00			
4	Providing and supplying Attendance Register complete in all respect within all lead and lift.	15.00	Each	360.00			
5	Providing and supplying Peon Book complete in all respect within all lead and lift.	15.00	Each	360.00			
6	Providing and supplying GST/Income Tax Register complete in all respect within all lead and lift.	5.00	Each	770.00			
7	Providing and supplying Agreement Register complete in all respect within all lead and lift.	8.00	Each	710.00			
8	Providing and supplying Tender Sale Register complete in all respect within all lead and lift.	10.00	Each	700.00			
9	Providing and supplying Tender Open Register complete in all respect within all lead and lift.	10.00	Each	700.00			
10	Providing and supplying T&P Register complete in all respect within all lead and lift.	10.00	Each	670.00			
11	Providing and supplying Deposit Register complete in all respect within all lead and lift.	8.00	Each	870.00			
12	Providing and supplying Register-64 complete in all respect within all lead and lift.	8.00	Each	870.00			
13	Providing and supplying Contractor's Bill Register complete in all respect within all lead and lift.	8.00	Each	770.00			
14	Providing and supplying Work abstract Pad complete in all respect within all lead and lift.	20.00	Each	390.00			
<b>Total</b>							
<b>Terms and Condition:-</b>							

### TERM AND CONDITIONS :-

- Nothing shall be paid for rejected work/material
- GST, income tax and security etc. as admissible shall be deducted from each running bill.
- 1% labour cess will be deducted from the bill.
- The contractor shall have to obtain EPR/ESIS registration before commencement of work
- The rates are inclusive GST and carriage etc.

Executive Engineer  
Bhoranj Division  
(H.E.P.W.D. Bhoranj)



## SCHEDULE OF QUANTITY

NAME OF WORK:- AIR & MO VARIOUS road under Bhornal Division (SH:- Supply of stationary article etc. for use in Division office)

Estimated Cost  
Earnest Money  
Time

Rs 98,430/-  
Rs.2000/-  
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and supplying Schedule Docket Pad complete in all respect within all lead and lift.	20.00	Each			
2	Providing and supplying Store Chalan Book complete in all respect within all lead and lift.	20.00	Each			
3	Providing and supplying Rest House Permit Book complete in all respect within all lead and lift.	20.00	Each			
4	Providing and supplying Rest House Visitor Book complete in all respect within all lead and lift.	8.00	Each			
5	Providing and supplying G R Book complete in all respect within all lead and lift.	10.00	Each			
6	Providing and supplying Store Indent Book (Triplicate) complete in all respect within all lead and lift.	20.00	Each			
7	Providing and supplying Hand Receipt Pad complete in all respect within all lead and lift.	10.00	Each			
8	Providing and supplying 1" & Final Bill Form Pad complete in all respect within all lead and lift.	20.00	Each			
9	Providing and supplying Transfer Entry order pad complete in all respect within all lead and lift.	20.00	Each			
10	Providing and supplying Running Account Bill Form complete in all respect within all lead and lift.	1000.00	Each			
11	Providing and supplying P.M.G.S.Y. Quality Control Register (Part-I & Part II) complete in all respect within all lead and lift.	10.00	Each			
12	Providing and supplying P.M.G.S.Y. Hindrance Register complete in all respect within all lead and lift.	10.00	Each			
13	Providing and supplying P.M.G.S.Y. Measurement Book (Part-I & Part II) complete in all respect within all lead and lift.	10.00	Each			
14	Providing and supplying Site Order Book complete in all respect within all lead and lift.	5.00	Each			
Total						
Terms and Condition:-						

### TERM AND CONDITIONS :-

- Nothing shall be paid for rejected work/material
- GST, income tax and security etc. as admissible shall be deducted from each running bill.
- 1% labour cess will be deducted from the bill.
- The contractor shall have to obtain EPF/ESIS registration before commencement of work
- The rates are inclusive GST and carriage etc.

Executive Engineer  
Bhornal Division  
MF PWD Bhornal

## SCHEDULE OF QUANTITY

NAME OF WORK:- A.R. S.M.O. Una-Aghar Mandi road km. 67/00 to 79/00.  
(S.M. :- Providing and installation of crash barrier at RD 67/00 to 79/00.)

Estimated Cost  
Earnest Money  
Time  
Rates in Words  
Rs. 93600/-  
Rs. 2000/-  
2 Months  
Amount

Sr. No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain reinforced concrete in P.C.C. grade M. 100M. (on nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (four millimeters) nominal size bc. (bottom layer) 150mm (one and a half inch) crash barrier. comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimetre) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. (two metre) to centre. 1.50 mtr. Height 1.010 metre below ground level and steel posts or flanges to be galvanized by hot dip process, all fitting to conform to IS 1367. Metal beam rail to be fixed on the vertical posts with a space of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Mahan, toll tax, side tax or other taxes imposed by the Government.	24.00	Per running metre			
<b>Total</b>						

**Terms and Conditions:-**

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
UP PWD Bhorani  


NAME OF WORK:- AIR & M/O Una-Aghar- Mandi road km. 67/00 to 79/00.  
 (S.H :- Providing and installation of crash barrier at RD 73/00 to 75/00.)

## SCHEDULE OF QUANTITY

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	Rs 93600/-
					Earnest Money Time	Rs.2000/- 2 Months
1	Providing concrete for plant reinforced concrete in P.C.C. grade M-10(M-ten) nominal mix 1:3:6 (one cement, three sand, six graded crushed stone aggregate) 40mm(forty millimeters) nominal size /ic erecting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitting to be galvanised by hot dip process, all fitting to conform to IS 1367, metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and this and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.00	Per running metre			
<b>Total</b>						

**Terms and Condition:-**

1. Work shall be executed as per PWD specification.

  
 Executive Engineer  
 Bhoranj Division  
 PWD Bhoranj

## SCHEDULE OF QUANTITY

NAME OF WORK: AR & MIO various road in under Sub Division Bhoranj, (SH:- Supplying and stacking of aggregate 10 mm to 12 mm, 3mm to 2mm and Sand 1, (Patta Section)

Estimated Cost  
Earnest Money  
Rs. 98,800/-  
Rs. 2000/-  
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Supplying and stacking at site of work, stone metal broken/crushed stone aggregate for water bound macadam road 10 mm to 12 mm nominal size of M.O.T specification as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Per Cum			
2	Supplying & stacking at site of work, approved coarse sand free from disintegrated pieces deleterious and organic matter as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Per Cum			
2	Supplying and stacking at site of work, stone metal broken/crushed stone aggregate for water bound macadam road 53 mm to 22 mm nominal size of M.O.T specification as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	50.00	Per Cum			
	<b>Total</b>					
	<b>Terms and Condition:-</b>					

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
R.P. PWD Bhoranj



## SCHEDULE OF QUANTITY

NAME OF WORK:-AIR & MID various road in under Sub Division Bhoranj (SH:-Supplying and stacking of aggregate 10 mm to 12 mm, 43mm to 22 mm and Moulder Bricks ). (Patta Section)

Estimated Cost  
Earnest Money  
Time

Rs 98,300/-  
Rs 2000/-  
2Months

Sr No	Description of items	Quantity	Unit	Rate	Rate in Words	Amount
1	Supplying and stacking at site of work stone metal broken/crushed stone aggregate/for water bound macadam road 10 mm to 12 mm nominal size of M.O.T specification as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00	Per Cum			
2	Supplying & stacking at site of work approved coarse sand free from disintegrated pieces deleterious and organic matter as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.00	Per Cum			
3	Supplying & stacking at site of work, moulder bricks fire resistance for laying of foundation stone as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3000.00	Each			
<b>Total</b>						
<b>Terms and Conditions:-</b>						

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
AIR, PWD Bhoranj

## SCHEDULE OF QUANTITY

**NAME OF WORK:-** AR & M/O various road in under Sub Division Bhoranj (SH:- Supplying and stocking of aggregate 10 mm to 12 mm and Sand ).  
**(Bhoranj Section)**

**Estimated Cost** Rs 98,500/-  
**Earnest Money** Rs.2000/-

Sr No	Description of items	Quantity	Unit	Rate	Time	
					Rates in Words	Amount
1	Supplying and stocking at site of work stone metal broken/crushed stone aggregate/for water bound macadam road 10 mm to 12 mm nominal size of M O T specification as per direction of Engineer-in-Charge including entire carriage of material within all leads and pits and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	45.00	Per Cum			
2	Supplying & stocking at site of work approved course sand free from disintegrated pieces deleterious and organic matter as per direction of Engineer-in-Charge including entire carriage of material within all leads and pits and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	25.00	Per Cum			
	<b>Total</b>					
	<b>Terms and Condition:-</b>					

1 Work shall be executed as per PWD specification.

Executive Engineer  
 Bhoranj Division  
 H R PWD Bhoranj

# SCHEDULE OF QUANTITY

OF WORK:- Restoration of Rain damages on Lalhyani-Dhamrol road,  
Diversion and Cutting, filling road side Berms/shoulders at RD 0/100 to 5/200.)

Estimated Cost  
Earnest Money  
Time  
Rs 99196/-  
Rs. 2000/-  
2Months

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 as per direction of Engineer in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of oil, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1189.40	Per square metre			
Total						

Terms and Conditions:-

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.E. PWD Bhoranj

# SCHEDULE OF QUANTITY

OF WORK : Restoration of Rain damages on Bharoni to Chambh via forest rest house.  
 At: Dressing and Cutting, filling road side Eremeshoulders at RD 000 to 300.

Estimated Cost  
 Earnest Money  
 Time  
 Rs 59196/-  
 Rs. 2000/-  
 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Monitor and maintain shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil and making up loss of material negotiation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 as per direction of Engineer in Charge including entire cartage of material within all heads and its and other work items. The rates are inclusive petrol, royalty, Mahkama, toll tax, sale tax or other taxes imposed by the Government	1189.40	Per square metre			
Total						

Terms and Condition:-

1 Work shall be executed as per PWD specification.

Executive Engineer  
 Bharoni Division  
 HP PWD Bharoni

# SCHEDULE OF QUANTITY

OF WORK - Restoration of Rain damages on Dhivar to Dadoo via Baroh road.  
Dressing and Cutting, filling road side Berms/shoulders at RD 0100 to 4100.]

Estimated Cost  
Earnest Money  
Time  
Rs 99196/-  
Rs. 2000/-  
2Months

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 as per erection of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	1189.40	Per square metre			
Total						

Terms and Condition:-

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
MP PWD Bhorani



NAME OF WORK:- R/R Damages on Una Aghar Mandi road km. 67/00 to 79/00 (SH:- C/O R/Wall at RD 76/450 to 76/458).

## SCHEDULE OF QUANTITY

Estimated Cost  
Earnest Money  
Time  
Rs 97,876/-  
Rs. 2000/-  
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and retaining structures in all type of classification of soil comprising of ordinary soil, ordinary rock hard rock, chiseling, wedging cut or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts include dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	8.30	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand: ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls/breast walls, complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.28	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/plant reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe. De- plastered/vectus pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (N): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.31 as per direction of Engineer-in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge: i) Granular material including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.12	Per Cubic Meter			
<b>Total</b>						
<b>Terms and Conditions:-</b>						

1. Work shall be executed as per PWD specification

Executive Engineer  
Bhorani Division  
H.P.W.D Bhorani

WORK: RR Damages on Russi Manoh Road (SH- C/O RWail at RD 0570 to 0578.50.)

## SCHEDULE OF QUANTITY

Description of Items	Quantity	Unit	Rate	Estimated Cost	Rs 96750/-
				Earnest Money Time Rates in Words	Rs. 2000/- 2 month Amount
1. 1:200 work on excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and projects executed in all types of classification of soil comprising of ordinary soil, ordinary rock, heavy rock, etc. (including cutting and of rock where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any beds and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise and during dewatering as per the direction of the Engineer-in-Charge including entire carriage of material within all beds and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.53	Per Cubic Meter			
2. Providing and laying mechanically mixed cement concrete 1:5:10 (one cementive sand ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all beds and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	19.98	Per Cubic Meter			
3. Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls, and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe. De-plasticized wetted wetted pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V: 20H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7 as per direction of Engineer-in-Charge including entire carriage of material within all beds and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each			
4. Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204 3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all beds and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all beds and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.69	Per Cubic Meter			
<b>Total</b>					
<b>Terms and Conditions:</b>					

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
UP PWD Bhoranj

## SCHEDULE OF QUANTITY

**NAME OF WORK :-** C/O link road from Bhareni badahar road to watan singh house.  
**At :-** P.L. interlocking paverblock pavement at RD 0/100 to 0/0151.(Deposit work)

**Estimated Cost** Rs. 97113/-  
**Earnest Money** Rs. 2000/-  
**Time** 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and fits including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.15	Per Cubic Meter			
2	Providing concrete for plan/ reinforced concrete in P.C.C. grade M <sub>40</sub> (M-ten nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size including shuttering in open foundations complete as per drawings and technical specifications Clause 602, 603, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.58	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) 3 graded stone aggregate 20 mm nominal size/as per direction of Engineer-in-Charge including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.24	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M <sub>40</sub> (M-ten) grade including border or curb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm( eighty millimeters) thick inter locking blocks (MTC Tile) and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and fits including entire carriage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.75	Per square meter			
<b>Total</b>						

**Terms and Conditions:-**

1. Work shall be executed as per PWD specification.

Executive Engineer  
 Bhorani Division  
 PWD Bhorani



## SCHEDULE OF QUANTITY

Rs. C & Q link road from Bharoni Badhar road to wafian singh house.  
 Setting paverblock pavement at RD 0.015 to 0.030 (Deposit work)

Sl. No.	Description of Items	Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rates in Words	Amount
1	Excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all types of classification of soil, comprising of ordinary soil, ordinary rock, and rock, ensuring working out of rock (where blasting is prohibited) as per drawings and construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any depth and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.15	Per Cubic Meter				
2	Providing concrete for plain reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement, three sand, six graded crushed stone aggregate) 40mm (forty millimeters) nominal size including shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.58	Per cubic metre				
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) 3 graded stone aggregate 20 mm nominal size as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.24	Per Cubic Meter				
4	Providing and laying heavy duty precast concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade including border or curb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm (eighty millimeters) thick interlocking blocks (NTC Tile) and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.75	Per square meter				
<b>Total</b>							

**Terms and Conditions:-**

1. Work shall be executed as per PWD specification.

Executive Engineer  
 Bharoni Division  
 HP PWD Bharoni