HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-SRDD-CB-CTR-NIT-2024-25- 18971-19000 Dated:- 31-01-2025

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Scanned with OKEN Scanner

HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **11-02-2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **10.02.2025 up to 5:00 PM** and the application for issue of tender form shall be received on **10.02.2025 up to 2:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be dept open for 75 days. **The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons.** If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	R/R damages on Totu Tara Devi road Km. 0/00 to 4/105 (SH: C/O R/Wall at Rd. 1/781.70 to 1/785.05).	98478/-	2000/-	One Month	Rs.350/-
2	A/R & M/O to Shoghi Mehli road Km. 0/00 to 12/375 (SH: Providing & fixing crash barrier W-Beam high intensity reflector in Km. 0/00 to 12/375) Job No.1.	99592/-	2000/-	One month	Rs.350/-
3	A/R & M/O to Shoghi Mehli road Km. 0/00 to 12/375 (SH: Providing & fixing crash barrier W-Beam high intensity reflector in Km. 0/00 to 12/375) Job No.2.	99592/-	2000/-	One month	Rs.350/-
4	R/R damges on Ghanahatti Kalihatti Arki road in Km. 0/00 to 8/060 (SH: Hiring of JCB for removal of slips, dressing of shoulders & catch pits/pot holes etc. in Km. 0/00 to 8/060).	96360/-	2000/-	One month	Rs.350/-
5	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F sliding door bolts & W.S. & S.I. fitting etc.).	99905/-	2000/-	One month	Rs.350/-
6	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F PVC antistatic venyl flooring in ADA room etc.).	99530/-	2000/-	One month	Rs.350/-
7	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F aluminium work door & windows to CBI (J) gallery and consumer Judge gallery etc.).	98430/-	2000/-	One Month	Rs.350/-
8	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F sliding door bolts, tower bolt handles & minor work to CBI (J) gallery and consumer Judge gallery etc.).	99724/-	2000/-	One Month	Rs.350/-
9	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F aluminium work door & windows to CBI (J) gallery and consumer Judge gallery etc.).	99260/-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

10	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F aluminium work for shutter in CBI (J) gallery and consumer Judge gallery etc.).	99512/-	2000/-	One Month	Rs.350/-
11	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F aluminum work and 4mm thick (ACP Sheet) etc.	99182/-	2000/-	One Month	Rs.350/-
12	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F PVC antistatic venyl flooring & brick work in ADA room etc.).	99290/-	2000/-	One month	Rs.350/-
13	A/R & M/O to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F aluminium work in CBI (J) gallery and consumer Judge gallery etc.).	99971/-	2000/-	One month	Rs.350/-
14	A/R & M/O to Printing Press building at Ghora Chowki Shimla (SH: Providing PGI sheet in roofing in type –V Qtr.).	65071/-	2000/-	One month	Rs.350/-
15	C/O Type-II Qtr. Building at Jalog, Sub-Tehsil Jalog, Distt. Shimla, H.P. (SH: Conducting of Geological investigation of sub soil at site. (Pit No. 1).	87600/-	2000/-	One Month	Rs.350/-
16	C/O Type-II Qtr. Building at Jalog, Sub-Tehsil Jalog, Distt. Shimla, H.P. (SH: Conducting of Geological investigation of sub soil at site. (Pit No. 2).	87600/-	2000/-	One Month	Rs.350/-
17	Improvement of black spot on link road to village Khatnol Km. 0/00 to 10/00 (SH: Providing W metal beam crash barrier at Rd. 3/876 to 3/888).	52185/-	2000/-	One Month	Rs.350/-
18	Improvement of black spot on link road to village Khatnol Km. 0/00 to 10/00 (SH: Providing W metal beam crash barrier at Rd. 3/888 to 3/910).	95068/-	2000/-	One Month	Rs.350/-
19	Improvement of black spot on link road to village Khatnol Km. 0/00 to 10/00 (SH: Providing W metal beam crash barrier at Rd. 4/016 to 4/038).	95068/-	2000/-	One Month	Rs.350/-
20	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/413 to 2/421.20 (PCC) under BASP.	98742/-	2000/-	One Month	Rs.350/-
21	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/355 to 2/363.30 (PCC) under BASP.	99481/-	2000/-	One Month	Rs.350/-
22	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/305 to 2/313.30 (PCC) under BASP.	99721/-	2000/-	One Month	Rs.350/-
23	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/448.20 to 2/456.50 (PCC) under BASP.	99911/-	2000/-	One Month	Rs.350/-
24	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/405 to 2/413 (PCC) under BASP.	96594/-	2000/-	One Month	Rs.350/-
25	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/113.20 to 2/121.50 (PCC) under BASP.	99441/-	2000/-	One Month	Rs.350/-
26	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/105 to 2/113.20 (PCC) under BASP.	98840/-	2000/-	One Month	Rs.350/-
27	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/440 to 2/448.20 (PCC) under BASP.	98932/-	2000/-	One Month	Rs.350/-
28	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/121.50 to 2/129.90 (PCC) under BASP.	99929/-	2000/-	One Month	Rs.350/-
29	C/O Gadheri Devridhar Bhararu road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rds. 2/313.30 to 2/321.60 (PCC) under BASP.	99961/-	2000/-	One Month	Rs.350/-
30	R/R damages on Mandyalu road Km. 0/00 to 2/820 (SH: Trimming of grass, Maintenance of earthen shoulder, Maintenance of drain, in Km. 0/00 to 1/410) Job No.1.	97935/-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

31	R/R damages on Mandyalu road Km. 0/00 to 2/820 (SH: Trimming of grass, Maintenance of earthen shoulder, Maintenance of drain, in Km.1/410 to 2/820) Job No.2.	97935/-	2000/-	One Month	Rs.350/-
32	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/740 to 0/743).	99235/-	2000/-	One Month	Rs.350/-
33	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/743 to 0/746).	99538/-	2000/-	One Month	Rs.350/-
34	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/655.20 to 0/658.60).	99854/-	2000/-	One Month	Rs.350/-
35	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/658.60 to 0/662).	99741/-	2000/-	One Month	Rs.350/-
36	A/R & M/O Palkari Makri road Km. 0/00 to 1/600 (SH: C/O R/Wall at Rd. 0/063 to 0/066).	98501/-	2000/-	One Month	Rs.350/-
37	A/R & M/O Palkari Makri road Km. 0/00 to 1/600 (SH: C/O R/Wall at Rd. 0/066 to 0/068.90).	95257/-	2000/-	One Month	Rs.350/-
38	A/R & M/O Palkari Makri road Km. 0/00 to 1/600 (SH: C/O R/Wall at Rd. 0/060 to 0/063).	98501/-	2000/-	One Month	Rs.350/-
39	A/R & M/O Palkari Makri road Km. 0/00 to 1/600 (SH: C/O R/Wall at Rd. 0/060 to 0/063).Balance work	95945/-	2000/-	One Month	Rs.350/-
40	A/R & M/O Palkari Makri road Km. 0/00 to 1/600 (SH: C/O R/Wall at Rd. 0/063 to 0/066) Balance work.	95945/-	2000/-	One Month	Rs.350/-
41	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/645 to 0/648.40).	99679/-	2000/-	One Month	Rs.350/-
42	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/648.40 to 0/651.80).	99679/-	2000/-	One Month	Rs.350/-
43	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/651.80 to 0/655.20).	99764/-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

(i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.

(ii) Special care would be taken to write the percentage rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhami.

Certificate

Certified that the tenders called vide this notice inviting tender for 43 (forty three) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 98,478.00	
Name Of Work :- Restoration of Rain Damages on Totu Tara devi road km. 0/00 to 4/105 (SH:- C/O R/wall at Rd .1/781.70 to 1/785.05)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	10.62	Per cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3786
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 20 mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.99	Per cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	89253
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	11.70	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2223
4	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.82	Per cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3216
	Total Rs.						**98478**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Annual Repair & Maintenance to Shoghi Mehli road km. 0/00 to 12/375 (SH:- Providing and fixing Crash Barrier W - Beam high intensity reflector in km. 0/00 to 12/375) Job No. 1

Estimated Cost:- 99.592.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing on Crash Barricade W - Beam high intensity prismatic reflector trapezoid type metal body size 150mm x 80mm with 6.5 mm steel/ zinc plated bolt, fixed with distance of 1 metre. Three sides (left, right and front) laminated with plastic body (Yellow/ white/ red colours etc) as directed by the Engineer in Charge.	236.00	Nos	422.00	Rupees Four Hundred Twenty Two Only	Each	99592
	Total Rs.						**99592**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						
	CONDITION:- 1.Rates Should be quoted for all heights including all leads and lits 2.Sample of all the material to be used on work shall be got apporved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are availble as per Indian Standrd in the market should confirm to bureau of indian standars.						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity							Estimated Cost:- 99.592.00
Name of Work :- Annual Repair & Maintenance to Shoghi Mehli road km. 0/00 to 12/375 (SH:- Providing and fixing Crash Barrier W - Beam high intensity reflector in km. 0/00 to 12/375) Job No. 2							Earnest Money:- 2000.00 Time:- One Months.
S.No	**Description of Work**	**No.of Qty.**		**Rate**		**Unit**	**Amount**
				In figures	**In words**		
1	2	3	4	5	6	7	8
1	Providing and fixing on Crash Barricade W - Beam high intensity prismatic reflector trapezoid type metal body size 150mm x 80mm with 6.5 mm steel/ zinc plated bolt, fixed with distance of 1 metre. Three sides (left, right and front) laminated with plastic body (Yellow/ white/ red colours etc) as directed by the Engineer in Charge.	236.00	Nos	422.00	Rupees Four Hundred Twenty Two Only	Each	99592
	Total Rs.						99592
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						
	CONDITION:- 1.Rates Should be quoted for all heights including all leads and lits 2.Sample of all the material to be used on work shall be got apporved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are availble as per Indian Standrd in the market should confirm to bureau of indian standars.						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ghanahatti Kalihatti Arki Road in Km. 0/00 to 8/060 (Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulders & catch pits / pot hole etc, in km. 0/00 to 8/060)

Estimated Cost: - Rs 96360 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Hiring of Excavator-cum-Loader for removal of slips including cost of fuel oil lubricants wages of operational staff any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor & including all leads and lifts & work shall be executed as per the direction of Engineer -in-Charge.	88.00 Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	96360.00
0					Total:	96360.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing Sliding door bolts & W.S & S.I Fitting etc)

Estimated Cost:- 99,905.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections, appropriate 'L' sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with cast fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and joined mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and cast fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 30 micron) including carriage of material within all leads and lifts	45.78	Kg.	680.00	Rupees Six Hundred Eighty Only	Per Kilogram	31130
2	Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.50 mm dia wire and 1.4mm wide aperture with matching wood beading including carriage of material within all leads and lifts	4.80	Sqm	550.00	Rupees Five Hundred Fifty Only	Per Square metre	2640
3	Providing and fixing bright finished hydraulic door closer of Godrej make or equivalent with screws etc. complete including carriage of materials in all leads and lifts.	3.00	No.	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Each	5550
4	Providing and fixing 100x68x1.90 mm size M.S pressed butt hinges bright finished with necessary screws etc. complete including carriage of materials within all leads and lifts.	15.00	No.	70.00	Rupees Seventy Only	Each	1050
5	Providing and fixing aluminium sliding door bolts (Barrel type) anodized transparent or dyed to required shade and colour with bolts and nuts etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:-**250 X 16 mm**	4.00	No.	250.00	Rupees Two Hundred Fifty Only	Each	1000
6	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. : **200mm x 10mm.**	12.00	No.	90.00	Rupees Ninety Only	Each	1080

Scanned with OKEN Scanner

7	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :**150mm.**	8.00	No.	70.00	Rupees Seventy Only	Each	560
8	Providing & fixing 100 mm bright finished brass hanging type door floor stopper with necessary screws, etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	No.	65.00	Rupees Sixty Five Only	Each	260
9	Providing and fixing Chlorinated Polyvinyl Chioride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fitting, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 15 mm nominal outer dia pipes	15.00	Rmt.	350.00	Rupees Three Hundred Fifty Only	Per running metre	5250
10	Providing and fixing 15mm dia C.P. Brass bib cock of approved quality including carriage of materials within all leads and lifts.	18.00	No.	950.00	Rupees Nine Hundred Fifty Only	Each	17100
11	Providing and fixing 455x 610mm rectangular C.I. cover (light duty) the weight of the cover to be not less than 4.50 kg. including carriage of materials within all leads and lifts.	15.00	No.	850.00	Rupees Eight Hundred Fifty Only	Each	12750
12	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth.Cement Mortar 1:6 (1Cement:6 Sand) including entire carriage of materials in all leads and lifts.	35.50	Sqm	270.00	Rupees Two Hundred Seventy Only	Per Square metre	9585
13	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportion within all leads and lifts and as per direction of Engineer-in- Charge.110 mm dia.	8.00	No.	300.00	Rupees Three Hundred Only	Each	2400
14	Providing and fixing **110 mm (one hundred fifty milimeter)** PVC collars ISI marked including fixing with approved adhesive etc. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportion within all leads and lifts and as per direction of Engineer-in-Charge .	10.00	No.	225.00	Rupees Two Hundred Twenty Five Only	Each	2250

Scanned with OKEN Scanner

15	Providing and fixing 110 mm (one hundred ten millimetre) dia PVC door bend with oval access door insertion rubber washer 3 mm Three millimetre) thick bolts and nuts ISI market complete including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	8.00	No.	350.00	Rupees Three Hundred Fifty Only	Each	2800
16	Providing and fixing PVC plain tee ISI marked including fixing with approved adhesive etc.complete. Including carriage of materials within all leads and lifts. 110mm dia	6.00	No.	400.00	Rupees Four Hundred Only	Each	2400
17	Providing and fixing degree bend ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts 110mm dia	6.00	No.	350.00	Rupees Three Hundred Fifty Only	Each	2100
	Total Rs.						**99905**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,530.00	
Name Of Work :- Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing PVC antistatic venyl flooring in ADA Room etc.)						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing 2.00mm thick (L.G) PVC antistatic venyl flooring plain or coloured, carbed or mosaic/ metalled finish laid with approved adhesive on sub - floor (damp proofing treatment to be paid for separately)	94.79	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square metre	99530
	Total Rs.						**99530**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :-Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing aluminium work Door & windows to CBI (J) gallery and consumer Judge gallery etc)

Estimated Cost:- 98,430.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	144.75	Kg	680.00	Rupees Six Hundred Eighty Only	Per Killogram	98430
	Total Rs.						**98430**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,724.00	
Name Of Work :- Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing sliding door bolts, tower bolt handles & minoer work to CBI (J) gallery and consumer Judge gallery etc)						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.50 mm dia wire and 1.4mm wide aperture with matching wood beading including carriage of material within all leads and lifts	1.78	Sqm	550.00	Rupees Five Hundred Fifty Only	Per Square metre	979
2	Providing and fixing bright finished hydraulic door closer of Godraj make or equivalent with screws etc. complete including carriage of materials in all leads and lifts.	3.00	No	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Each	5550
3	Providing and fixing 100x58x1.90 mm size M.S pressed butt hinges bgight finished with necessary screws etc. complete including carriage of materials within all leads and lifts.	33.00	No	70.00	Rupees Seventy Only	Each	2310
4	Providing and fixing aluminium sliding door bolts (Barrel type) anodized transparent or dyed to required shade and colour with bolts and nuts etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:-**250 X 16 mm**	3.00	No	250.00	Rupees Two Hundred Fifty Only	Each	750
5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. : 150x10mm size	24.00	No	90.00	Rupees Ninety Only	Each	2160
5.1	200mm x 10mm.	6.00	No	120.00	Rupees One Hundred Twenty Only	Each	720

Scanned with OKEN Scanner

6	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :**125mm**	24.00	No	70.00	Rupees Seventy Only	Each	1680
6.1	150 mm size	6.00	No	90.00	Rupees Ninety Only	Each	540
7	Providing & fixing 100 mm bright finished brass hanging type door floor stopper with necessary screws, etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	3.00	No	65.00	Rupees Sixty Five Only	Each	195
8	Providing and fixing bright finished hard drawn hooks and eyes as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	12.00	No	55.00	Rupees Fifty Five Only	Each	660
9	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item)	34.22	Sqm	1170.00	Rupees One Thousand One Hundred Seventy Only	Per Square metre	40041
10	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	63.97	Kg	690.00	Rupees Six Hundred Ninety Only	Per Kilogram	44139
	Total Rs.						**99724**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 99,260.00

Earnest Money:- 2,000.00

Time:- One Months.

Name Of Work :-Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing aluminium work Door & windows to CBI (J) gallery and consumer Judge gallery etc)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	145.97	Kg	680.00	Rupees Six Hundred Eighty Only	Per Killogram	99260
	Total Rs.						**99260**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,512.00	
Name Of Work :- Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing aluminium work For shutter in CBI (J) gallery and consumer Judge gallery etc)						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	144.22	Kg	690.00	Rupees Six Hundred Ninety Only	Per Killogram	99512
	Total Rs.						**99512**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,182.00	
Name Of Work :- Annual Repair & Maintenace to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing Aluminum work, and 4mm thick (ACP sheet) etc.						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	**Description of Work**	**No.of Qty.**		**Rate**		**Unit**	**Amount**
				In figures	**In words**		
1	2	3	4	5	6	7	8
1	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	117.39	Kg	690.00	Rupees Six Hundred Ninety Only	Per Kilogram	80999
2	Providing & fixing 4 mm thick laminated Aluminium Composite panell (ACP SHEETS) in panelling fixied in aluminum doors, windows sutters and partition frames with C.P brass / stainless steel screws etc. complete as per architectural drawings and direction of Engineer in Charge.	15.95	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	18183
	Total Rs.						**99182**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,290.00	
Name Of Work :-Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing PVC antistatic venyl flooring & Brick work in ADA Room etc.)						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing 2.00mm thick (L.G) PVC antistatic venyl flooring plain or coloured, carbed or mosaic/ metalled finish laid with approved adhesive on sub - floor (damp proofing treatment to be paid for separately)	18.205	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square Metre	19115
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure in Cement mortar 1:4 (1 cement: 4 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	35.50	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square Metre	37275
3	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:- 110mm dia.	66.00	Rmt.	650.00	Rupees Six Hundred Fifty Only	Per running metre	42900
	Total Rs.						**99290**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,971.00	
Name Of Work :-Annual Repair & Maintenance to District Court Complex at Chakker Distt. Shimla (SH:- Providing and Fixing aluminium work in CBI (J) gallery and consumer Judge gallery etc)						Earnest Money:- 2,000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	109.18	Kg	680.00	Rupees Six Hundred Eighty Only	Per Killogram	74242
2	Providing and fixing plain/ coloured polycarbonate transparent sheet 1.20 mm thick in roofing and lining with self drilling screws along with washers etc. complete with all accessories as required to complete the work in all leads and lifts as per direction of Engineer in Charge.	11.66	Sqm	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Square	20405
3	Providing & fixing 4 mm thick laminated Aluminium Composite panell (ACP SHEETS) in panelling fixied in aluminum doors, windows sutters and partition frames with C.P brass / stainless steel screws etc. complete as per architectural drawings and direction of Engineer in Charge.	4.67	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square	5324
	Total Rs.						**99971**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Annual Repair & Maintenance to Printing press building at Ghora Chowki Shimla (SH:- Providing PGI sheet in roofing in Type -V Qtr.)

Estimated Cost:- 65,071.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Steel work welded in built up sections/ framed work, including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. As per required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in charges.	109.44	Kg.	105.00	Rupees One Hundred Five Only	Per Killogram	11491
2	Providing and fixing precoated 0.50mm thick PGI sheet ceiling/ lining of approved quality with butt jointing and wood screws (frame work and cover fillets to be measured and paid for separately) including carriage of materials within all leads and lifts, as per direction of the Engineer in Charge	56.40	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	53580
	Total Rs.						**65071**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work: Construction of Type-II Quarter Building at Jalog, Sub-Tehsil Jalog, Distt. Shimla,H.P. (SH:- Conducting of Geological investigation of sub soil at site.(Pit No.1)				Estimated Cost: 87,600/- only Earnest Money: 2000/-only. Time: - One month			
S. No.	**Description of Work**	**Nos of Qty**		**Rate**		**Unit**	**Amount**
				In Figure	**In word**		
1	**2**	**3**	**4**	**5**	**6**	**7**	**8**
1	Sub soil investigation in all type of soil/strata by drilling bore holes of NX size 75mm dia for investigation of soil rock conditions at site of work. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials with in all leads and lifts and as per directions of the Engineer-in-Charge.	12.00	Rmt	7300.00	Rupees Seven Thousand Three Hundred Only/-	Per Running Metre	87600.00
					Total		**87600.00**
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HP.PWD. Dhami

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work: Construction of Type-II Quarter Building at Jalog, Sub-Tehsil Jalog, Distt. Shimla,H.P. (SH:- Conducting of Geological investigation of sub soil at site.(Pit No.2)							Estimated Cost: 87,600/- only Earnest Money: 2000/-only. Time: - One month
S. No.	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Sub soil investigation in all type of soil/strata by drilling bore holes of NX size 75mm dia for investigation of soil rock conditions at site of work. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials with in all leads and lifts and as per directions of the Engineer-in-Charge.	12.00	Rmt	7300.00	Rupees Seven Thousand Three Hundred Only/-	Per Running Metre	₹ 87,600.00
					Total		**₹ 87,600.00**
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HP.PWD. Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Improvement of block spot on link road to village Khatnol km. 0/00 to 10/00 (SH:- Providing W metal beam crash barrier at Rd. 3/876 to 3/888)

Estimated Cost:- 52,185.00

Earnest Money:- 1100.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	0.94	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic Metre	335
2	Providing and erecting "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal rail 70 cm. above road/ground level fixied on ISMC series chanel vertical post 150x75x5 mm spaced 2m center to center, 1.8 m high, 1.1 m below ground/road level, dully imbeded with cement concrete M-10 (1:3:6) of size 0.45x0.45x1.10. All steel part and fitmets to be galvanised by not dip process, all fitting to confirms to IS : 1364 and Is : 1364 metal beam rail to be fixed on the vertcal post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810.	12.00	Rmt.	3890.00	Rupees Three Thousand Eight Hundred Ninety Only	Per running Metre	46680
3	Providing and laying Plain reinforced cement concrete 1:2:4 (one cement: two sand: four graded stone aggregate twenty milimetre nominal size) and curring complete excluding the cost of form work in foundation and plinth and curing complete mechanical mixed and vibrated for compacting reinforced concrete as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials ,labour ,tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	0.94	Cum	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic Metre	5170
	Total Rs.						**52185**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 95,068.00	
Name Of Work :- Improvement of block spot on link road to village Khatnol km. 0/00 to 10/00 (SH:- Providing W metal beam crash barrier at Rd. 3/888 to 3/910)						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	1.62	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic Metre	578
2	Providing and erecting "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal rail 70 cm. above road/ground level fixied on ISMC series chanel vertical post 150x75x5 mm spaced 2m center to center, 1.8 m high, 1.1 m below ground/road level, dully imbeded with cement concrete M-10 (1:3:6) of size 0.45x0.45x1.10. All steel part and fitmets to be galvanised by not dip process, all fitting to confirms to IS : 1364 and Is : 1364 metal beam rail to be fixed on the vertcal post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810.	22.00	Rmt.	3890.00	Rupees Three Thousand Eight Hundred Ninety Only	Per running Metre	85580
3	Providing and laying Plain reinforced cement concrete 1:2:4 (one cement: two sand: four graded stone aggregate twenty milimetre nominal size) and curring complete excluding the cost of form work in foundation and plinth and curing complete mechanical mixed and vibrated for compacting reinforced concrete as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials ,labour ,tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	1.62	Cum	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic Metre	8910
	Total Rs.						**95068**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 95,068.00

Name Of Work :- Improvement of block spot on link road to village Khatnol km. 0/00 to 10/00 (SH:- Providing W metal beam crash barrier at Rd. 4/016 to 4/038)

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	1.62	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic Metre	578
2	Providing and erecting "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal rail 70 cm. above road/ground level fixied on ISMC series chanel vertical post 150x75x5 mm spaced 2m center to center, 1.8 m high, 1.1 m below ground/road level, dully imbeded with cement concrete M-10 (1:3:6) of size 0.45x0.45x1.10. All steel part and fitmets to be galvanised by not dip process, all fitting to confirms to IS : 1364 and Is : 1364 metal beam rail to be fixed on the vertcal post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810.	22.00	Rmt.	3890.00	Rupees Three Thousand Eight Hundred Ninety Only	Per running Metre	85580
3	Providing and laying Plain reinforced cement concrete 1:2:4 (one cement: two sand: four graded stone aggregate twenty milimetre nominal size) and curring complete excluding the cost of form work in foundation and plinth and curing complete mechanical mixed and vibrated for compacting reinforced concrete as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials ,labour ,tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	1.62	Cum	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic Metre	8910
	Total Rs.						**95068**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 98,742.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/413 to 2/421.20 (PCC) Under BASP

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.92	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	979
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.72	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	613
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.86	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	94300
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	15.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2850
	Total Rs.						**98742**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dha...

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99.481.00	
Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/355 to 2/363.30 (PCC) Under BASP						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.73	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	941
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	620
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.09	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	95450
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	13.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2470
	Total Rs.						**99481**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 99,721.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/305 to 2/313.30 (PCC) Under BASP

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.98	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	991
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	620
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.09	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	95450
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	14.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2660
	Total Rs.						**99721**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,911.00	
Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/448.20 to 2/456.50 (PCC) Under BASP						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.98	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	991
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	620
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.09	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	95450
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	15.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2850
	Total Rs.						**99911**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/405 to 2/413 (PCC) Under BASP

Estimated Cost:- 96,594.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.80	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	955
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.68	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	599
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.40	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	92000
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	16.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	3040
	Total Rs.						**96594**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99.441.00	
Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/113.20 to 2/121.50 (PCC) Under BASP						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	5.48	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1091
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	620
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.09	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	95450
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	12.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2280
	Total Rs.						**99441**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhalli

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 98.840.00	
Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/105 to 2/113.20 (PCC) Under BASP						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	5.41	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1077
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.72	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	613
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.86	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	94300
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	15.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2850
	Total Rs.						**98840**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 98,932.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/440 to 2/448.20 (PCC) Under BASP

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.92	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	979
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.72	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	613
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.86	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	94300
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	16.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	3040
	Total Rs.						**98932**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99.929.00	
Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/121.50 to 2/129.90 (PCC) Under BASP						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.03	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	802
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.76	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	627
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.32	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	96600
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	10.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	1900
	Total Rs.						**99929**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 99,961.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :-C/O Gadheri Devridhar Bhararu road km. 0/00 to 3/00 (SH:- C/O B/wall at km. 2/313.30 to 2/321.60 (PCC) Under BASP

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	5.23	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1041
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	620
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.09	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	95450
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	15.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2850
	Total Rs.						**99961**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 97,935.00

Earnest Money:- 2000.00

Time:- One Months.

Name Of Work :- Restoration of Rain damages on Mandyalu road km. 0/00 to 2/820 (SH:- Trimming of Grass, Maintenance of earthen Shoulder,Maintenance of drain, in km, 0/00 to 1/410) Job No. 1

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3525	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15863
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2820.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	67680
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907, including carriage of materils within all leads and lifts and as per the direction of Engineer-In-Charge .	1410.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per running Metre	6345
4	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge.	277.50	Sqm	29.00	Rupees Twenty Nine Only	Per Square metre	8048
	Total Rs.						**97935**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 97,935.00	
Name Of Work :- Restoration of Rain damages on Mandyalu road km. 0/00 to 2/820 (SH:- Trimming of Grass, Maintenance of earthen Shoulder,Maintenance of drain, in km, 1/410 to 2/820) Job No. 2						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3525	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15863
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2820.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	67680
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In-Charge .	1410.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per running Metre	6345
4	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge.	277.50	Sqm	29.00	Rupees Twenty Nine Only	Per Square metre	8048
	Total Rs.						97935
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/740 to 0/743)

Estimated Cost - Rs 99235 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.31	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	539.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge	4.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1711.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	986.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	1515.00
0						**Total:**	**99235.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharampur

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/743 to 0/746)

Estimated Cost: - Rs 99538 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.31	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	539.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1711.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	986.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.16	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1818.00
0						**Total:**	**99538.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/655.20 to 0/658.60)

Estimated Cost: - Rs 99854 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	612.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.48	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1102.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1717.00
0						**Total:**	**99854.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/658.60 to 0/662)

Estimated Cost : - Rs 99741 /- only
Earnest Money : - Rs 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	612.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939 00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484 00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v).20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	986 00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1720 00
0						**Total:**	**99741.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annua Repair & Maintenance of Palkari Makri Road Km. 0/00 to 1/600 (Sh: Construction of R-wall at Rd. 0/063 to 0/066)

Estimated Cost: - Rs 98501 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.27	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	530.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	8.08	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2881.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.70	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90620.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.19	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2685.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1785.00
0						**Total:**	**98501.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annua Repair & Maintenance of Palkari Makri Road Km. 0/00 to 1/600 (Sh: Construction of R-wall at Rd. 0/ 066 to 0/ 068.90)

Estimated Cost: - Rs 95257 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.19	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	511.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	7.81	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2784.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.04	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	87584.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.08	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2593.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1785.00
0						**Total:**	**95257.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annua Repair & Maintenance of Palkari Makri Road Km. 0/00 to 1/600 (Sh: Construction of R-wall at Rd. 0/ 060 to 0/063)

Estimated Cost: - Rs 98501 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.27	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	530.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	8.08	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2881.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.70	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90620.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.19	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2685.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1785.00
0						**Total:**	**98501.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work: -Annual Repair & Maintenance of Palkari Makri Road Km. 0/00 to 1/600 (Sh: Construction of R-wall at Rd. 0/060 to 0/063) Balance work

Estimated Cost: - Rs 95945 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 40 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.71	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90666.00
2	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.05	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3409.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per cubic metre	1870.00
0						**Total:**	**95945.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work: -Annual Repair & Maintenance of Palkari Makri Road Km. 0/00 to 1/600 (Sh: Construction of R-wall at Rd. 0/063 to 0/066) Balance work

Estimated Cost - Rs 95945 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 40 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.71	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90666.00
2	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.05	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3409.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per cubic metre	1870.00
0						Total:	95945.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/645 to 0/648.40)

Estimated Cost: - Rs 99679 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	612.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.45	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	927.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1717.00
						Total:	**99679.00**
0							
	Amount Quoted by the Contractor in Percentage					**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/648.40 to 0/651.80)

Estimated Cost: - Rs 99679 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	612.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.45	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	927.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1717.00
0						**Total:**	**99679.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at R.D. 0/651.80 to 0/655.20)

Estimated Cost - Rs 99764 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate in figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.62	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	612 00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.44	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1939 00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94484 00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.95	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1012 00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1717 00
						Total:	**99764.00**
0							

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner